VEDIC VARIANTS



Exclusively Distributed by

MUNSHIRAM MANOHARLAL PUBLISHERS PVT. LTD.

54, RANI JHANSI ROAD, NEW DELHI-110055

VEDIC VARIANTS

A Study of the Variant Readings in the R. Mantras of the Veda

010669 BY

MAURICE BLOOMFIELD

Late Professor of Sanskril and Comparative Philology in The Johns Hopkins University

AND

FRANKLIN EDGERTON

Salisbury Professor of Sanskrit and Comparative Philology in Yale University

Volume	II
PHONE	rics

•	DRIENTAL	REPI

Oriental Books Reprint Corporation Book Publishers, 54 Rani Jhansi Road, New Delhi-55

First Indian Edition 1979
First published in 1932 by
Linguistic Society of America

Rs. 150

FUBLISHED BY OPIFYTAL BOOKS REPRINT CORPORATION, 54 RAYS SHAYSI ROAD, NEW DELHI 110055 AND PRINTED BY MESHA OFFSET PRESS, EUCHA CHELAN, NEW DELHI 110002

Preface	11
Abbreviations and Symbols	13
Chapter I Introductory, §§1-43	15
Principles of procedure, §§1-5	15
Summary of contents, §§6-19	17
Prakritic influences, §§20–43	20
Chapter II Surd and Sonant Mutes, §§44-79	26
$k \text{ and } g, \S 45-9 \dots \dots \dots \dots \dots$	26
c and j, §§50-7	31
t and d , §58	35
t and d, §§59-68	35
p and b, §69	42
kh and gh, §70	42
th and dh, §§71-8	43
ph and bh, §79	46
Chapter III. Aspirates and Non-aspirates and h, §§80-124	47
k and kh , §81	47
g and kh, §82	47
g(k) and gh, §83	48
c and ch, §84	48
j and jh, §85	48
t and th, §§86-8	48
t and th, §§89-96	50
t and dh, §§97-8	55
d and dh, §§99-110	56
p and ph, §111	63
p and bh, §§112-4	64
Aspirate mutes and h, §§115-124	65
Chapter IV. Interchanges of the Mute Series, §§125-81	70
Gutturals and Palatals, \$6125-34	70
2 Gutturals and Linguals, §135	73
3 Gutturals and Dentals, §§136-47	73
4 Gutturals and Labials, \$6148-53	79
5. Palatals and Dentals, §6154-61	83
6 Palatals and Labials, §162.	86

7 Linguals and Dentals, §§163-70	80
8 Dentals and Labials, §§171-81	90
Chapter V. Interchanges concerning Palatals, §§182-96	90
1 ch and ks, ts, ps, §§183-6	90
2 sy and 5c or s(h) plus sibilant, §§187-9	97
3 ks, ks, and khy, §§190-1	99
4 j and y, §§192-3	100
5 Palatal stops and $\hat{s}(s)$, §§194-5	101
6 Miscellaneous (j and h, h, and bj), §196	103
Chapter VI Labial Mutes, v, and m, §§197-242	104
p(ph) and v , §§198–202	104
p and m , §§203-5	108
b and v, §§206–19	109
$bh \text{ and } v, \S\S 220-2$	114
$v \text{ and } m, \S 223-40.$	115
b and m , §241	124
bh and m, §242	125
Chapter VII Interchange of y , $r(d)$, $l(d)$, v , and h , §§243-73	126
y and r, §244	126
y and l , §245	127
$y \text{ and } v, \S 246-55$	127
y and h , §256	134
r and l, §§257-65	134
r and v, §§266-8	138
r, v and h , §269	140
$l \text{ and } d, \S \$ 270-1$	140
r and d , §272	141
r and d , §272a	142
l, d, and n, §273	143
Chapter VIII The Sibilants, §§274-99	144
ś and s, §§275–87	144
ś and ş, §§288–92	149
ş and s, §§293–4	152
kh, kş, and sıbılants, §§295–7	153
s(s) and h, §§298-9	153
Chapter IX Presence or absence of Nasals, Semi-vowels, Liquids,	1 = =
Sibilants, visarga, and h, §§300-87	155
1 1 tocolide of Endonies of Indiana that are a few and a	155
2 Presence or absence of y, §§313-47	160
3 Presence or absence of r. §§348–57	175

	D or alternate of a \$6359-71	181
4	Presence of absence of 1) 33000 11	189
5	Presence or absence of s, §§372-7	192
	Presence or absence of visarga, §§378-84	199
7	Presence or absence of h, §§385-7	201
Chap	ter X Consonant Groups, §§388-421	
1	Double and single consonants, §§389-405	201
2	Assimilation of two consonants to one double consonant,	000
	§§406-16 .	209
3	Simplification of consonant groups, §§417-21	212
	ter XI Variations between short and long a, §§422-512	216
1.	Final a and ā, §§426-77	217
	(a) absolutely final short a rhythmically lengthened,	
	§§428–49 · · · · · · · · · · · · · · · · · · ·	217
	(b) absolutely final a varying otherwise with \bar{a} , §§450–61	223
	(c) stem-final short a in compounds, etc, lengthened,	
	§§462–8 .	227
	(d) other final a and \bar{a} , §§469–77	230
	Non-final a and \bar{a} , in verb inflection, §§478–82	233
3	Non-final a and \bar{a} , in noun formation, §§483–96	234
	Non-final a and \bar{a} , in noun declension, §§497–507	242
5	Non-final a and \bar{a} , lexical and miscellaneous, §\$508-12	245
Chap	pter XII Variations between long and short i and u , §§513-69	249
	Final short i phonetically lengthened, §§514-21	249
2	Final i in the seam of compounds, phonetically shortened,	
	§§522 -4 .	252
3	Miscellaneous final i and \bar{i} , §525	252
4	. Noun stems in i and \bar{i} , §§526–30	253
	and in verb forms and in dissyllabic bases, §§531-40	256
6	Noun suffixes containing i and \bar{i} , §§541–3	258
	. Miscellaneous 1 and 7, §§544-5	259
	Final short u lengthened, §§546-52	260
	Final ū shortened, §553	262
	u and \bar{u} in noun formation and inflection, §§554–7 .	262
11	. Other u and \bar{u} , §§558–69	264
Cha	pter XIII Qualitative Interchanges of a, i, and u vowels,	
•	§§570–628 .	269
1	1 Short a and 1, §§570-96	269
	In noun formation, §§585-96	275
	2 ā and ī, §§597–98a	279
	3 a and with shift of quantity \$8509_600	901

4. Short a and u, §§601–18	283
5. Other a and u vowels, §§619-21	291
6 Short i and u, §§622-7 .	29
7. \bar{i} and $\bar{u}(u)$, §628	29
Chapter XIV. Vocalic Liquids and Other Vowels, §§629-84	298
1. r and $a(\bar{a})$, §§631–4	29
2 r and z(ī), §§635-40	297
3. $r(\bar{r})$ and $u(\bar{u})$, §§641-4	300
4. l and u, §645	301
5. 7 and 0, §646	302
6 τ and ar, §§647-51	302
7. r and ār, §652	304
8. 7 and 27, ur, ür, §§653-5	304
9. 7 and ra, rā, §§656-65	305
10. τ and ri , ri , §§666–77	308
	311
Chapter XV The i and u Diphthongs and Samprasārana, §§685-	
750	314
1. i and e, §§686-94	314
2 7 and e, §§695-8	317
3 i and a:, §§699-700	319
4. ī and a:, §§701–2	320
5. e and a:, §§703-12	321
6. u and o, §§713-9	326
7. ū and o, §§720-3	329
8 u and au, §724	330
** * * * * * * * * * * * * * * * * * * *	331
	331
	333
22 Sumpression a(a) and su(su); sto , 88.00 as	335
10 aga and 0, and and and, 43	338
22 474 474 474 474 474 474 474 474 474 4	339
Outpool 12,12 Amounted of Surpment of 12,100, 20,100 to	341
1. Apolitical of toward out the comment apro-	341
2 111101119 01 191 1111 1111 1111 1111	344
**	346
To more ferrance (amount) and arrest of the contract of the co	348
O building and mount of the contract of the co	349 351
D. Brown 1111111 V. 201111 1	351 351
Ε in verh forms, δ6794-8	JUL

Change of n to n , §§945–54	443
Final s after non a vowels, before initial t , §§955–8	447
Final s before initial k and p , §§959-67	449
Final r before initial k and p, $\S968$	454
Final s before sibilant (plus vowel), §§969-71	454
Final s before sibilant plus consonant, §§972–80	455
plus surd, §§974-7	456
plus sonant, §§978~80	458
Initial s varying with s, §§981-8	460
Secondary crasis and hiatus, §§989-96	463
Index of Sounds, Sound Groups, and Letters	471
Sanskrit Index	474
Subject Index .	. 480
Index of Mantras	482

PREFACE

This second volume of the Vedic Variants deals primarily with Phonetics; included also are graphic variations, false divisions between words, and rine words. It is the largest volume of the series, and probably the most interesting and important

The general plan and objects of the Vedic Variants have been described in the Preface to Volume I, The Verb (Philadelphia, 1930); which also stated the approximate extent to which each of the coauthors participated in the work. The greater part of the first volume was Bloomfield's In this volume my own share is larger. Nevertheless the first nine chapters owe much to Bloomfield, who prepared a draft of their text on the basis of preliminary studies made by me have preserved as much as possible of Bloomfield's language in these chapters those who know his inimitable style will find traces of it at many points in them To my regret, he never continued this work beyond the ninth chapter In the remainder his participation was nearly or quite limited to the gathering of preliminary list of materials This will be true, also, of all the remaining volumes of the series, to which he contributed only an occasional marginal note, aside from the preliminary lists

Cordial thanks are again due to the Linguistic Society of America and to the American Council of Learned Societies devoted to Humanistic Studies, which by their continued generosity have made possible the publication of this second volume of the series

Dr. Murray B. Emeneau, Sterling Fellow and Research Associate in Yale University, has read the proofs of this volume and made a number of useful suggestions. It gives me great pleasure to announce that Dr Emeneau is collaborating much more extensively in the preparation of Volume III, on Noun Inflection With his able and vigorous cooperation it is now (in April, 1932) nearly completed, and we hope to issue it soon Dr. Emeneau's name will appear, most deservedly, on its covers and title-page as co-author

FRANKLIN EDGERTON

ABBREVIATIONS AND SYMBOLS

These are the same as those used in Volume I, with the addition of VV = Vedic Variants (VV I = the first volume, on The Verb). Most of them, it is believed, are self-explanatory. Vedic texts are referred to by the abbreviations used in the Vedic Concordance. RVRep. = Bloomfield's Rigueda Repetitions.

The asterisk * is used to indicate a variant reading in one text when the mantra occurs in the same text with the reading for which this variant is a substitute, that is, it calls attention to the occurrence of both forms of the variation in the same text

The dagger † is used to call attention to a quotation which needs to be corrected in the Concordance.

CHAPTER I. INTRODUCTORY

PRINCIPLES OF PROCEDURE

§1. An examination of our materials shows that many, perhaps most, of the cases here treated under the general head of 'phonetic variations' are accompanied by, or result in, a lexical or morphological change at the same time. Thus, beginning with RV, the two words $v\bar{a}cam$ and $v\bar{a}jam$ interchange in:

pra vācam (9 35 4a vājam) indur isyati RV. 9. 12 6a, 35. 4a, 'Soma sends forth speech (substance)' Obviously, there is here a change, involving a single sound, from one very familiar Vedic word to another equally familiar, the two having no etymological connexion whatsoever. Tho there is good reason to believe the reading vācam is the primary one (cf. RVRep. 410), the alteration makes good sense and is intentional. Yet when we find this same interchange occurring independently in a considerable number of cases, we cannot doubt that rime and phonetic confusion—both phenomena of sound, rather than sense—hold shares in the transaction, or, more precisely, constitute the prime motive in the shift.

§2. More purely phonetic, yet not devoid of lexical significance, is the following variation, which also involves interchange of c and j.

prāñco agāma (TA. prāñjo 'gāmā) nṛtaye hasāya RV. AV. TA., 'We have gone forward (swiftly) to dancing and mirth.' For some reason prāñco, surely intelligible and fit, has suggested to the Taittirīyaka the more sophisticated, or tenser, reading pra + añjas 'forward swiftly' (añjas, RV) The commentator's prāñjah = prāñcah is negligible, TA. must have been familiar with añjas in the sense of 'swiftly'.

§3. We find, however, a great many phonetic changes which carry a certain word or expression to the danger-line of unintelligibility, without necessarily reaching the point of senseless corruption. In these cases the secondary reading appears inappropriate to its context, or at least, its motive escapes our appreciation. And yet it would be dangerous to deny the resulting lexical change as a real fact of the tradition of a given school. The study of Vedic tradition must not be content with reconstructing or defining the original body of mantras, by detecting and recording secondary fancies, adaptations, and corruptions. These

secondary readings have their own right to exist, they are, as a rule, the genuine readings of their respective schools. It is our duty to sketch the development of the mantras in all the Vedic schools, assigning, where possible, causes for the changes, but rejecting no unexplained or apparently unmotivated change, however it may seem to conflict with what seems to us good mantra sense. Thus:

ud usrıyāh srrate (TB sacate) sūryah sacā RV SV TB. 'The sun sends forth (accompanies, attends) his ruddy rays all together' (The TB comm seems to come around tortuously to the sense of the other schools: utsacata udgatatvena sambaddhān karoti prasāravatītu arthah) The TB reading is inappropriate, but neither the theory of a quasi-Prakritic substitution of a for r. nor that of interchange between surd and sonant (elsewhere a real phonetic change), alters the fact that the TB understood the word as a form of sac, and had lost sight of the root sry, whatever meaning it attached to sac Note, in passing, that the TB reading results in a kind of alliteration. sacate . . sacā the phonetic considerations involved are complicated by the (at least possible) regressively assimilatory influence of the word sacā on the original strate Yet in its final outcome the change is lexical, tho unquestionably related to (and perhaps started by) faulty hearing of sounds Cf. Winternitz in his edition of ApMB, Introduction, xv ff, and xxx.

§4. Clearly, then, such variants are of interest and importance for Vedic phonology Concretely speaking. If we are collecting examples of the quasi-Prakritic shift of r to a, we shall, of course, begin with such a variant as this:

ava sma durhanāyatah (SV. durhrn°) RV SV.

Here the RV. has an obvious Prakritism which the SV 'corrects' by substituting the Sanskritic durhrn'. This does not mean that the SV knows more Sanskrit than the RV; the RV. itself knows the stem durhrn-(1.84.16; 7.59.8) It is, however, a purely phonetic variation On the other hand, in the variant.

etām samkrsya (MS. MS 'kasya or 'kusya) juhudhi MS ApŚ. MŚ, who can decide definitely whether the a or u for r is purely phonetic (Prakritic), or lexical? Böhtlingk in fact assumes an improbable samkusya from the root kus. Be this as it may, if we can discern in the Veda signs of a Prakritic change of r to a, then the substitution of sacate for stjate, lexically different tho the two words be, bears in some fashion and in some degree upon the matter of Vedic Prakritism But it is impossible to draw a hard and fast line between purely phonetic and

lexical shifts Our detailed consideration of the variants tries to do this as far as possible, holding itself very free from imposing upon the materials personal theories and predilections.

§5. Our procedure has been to select all sound interchanges, which could possibly have phonetic interest, and then to gather all variants which show these sound interchanges, irrespective of the contributory influence of lexical and other moments. At the same time we have borne in mind the greater interest and value which, for the purposes of this study, must attach to those variants which are purely phonetic—which show different phonetic forms of what must be regarded as lexically the same word. By this procedure we are enabled to present here a new mass and a new class of materials for the study of Vedic phonetics, which are likely to become a permanent factor in future Vedic grammar

SUMMARY OF CONTENTS

- §6. We begin with interchanges between voiced and voiceless consonants, quite numerous and often suggestive of Prakritic phonetics Next, interchanges between aspirates and non-aspirates, few and mostly lexical in character. Then variations between aspirate stops and h, mostly concerning h and bh, and in fact mostly interchanges between grabh and grah
- §7. Next, interchanges in the articulation-series, numerous and extremely interesting. The little section concerning palatals is important out of all proportion to its size (notably the quasi-Prakritic variations between ks, ts, ps, and ch). The numerous variations of labial stops with m and v are partly graphic (b and v, p and v), partly morphological (suffixes containing m and v), partly lexical, but to a large extent purely phonetic (especially in the variation between b and v, a very familiar phenomenon)
- §8. The variations between semi-vowels and liquids differ widely from one another in character. Those between y and r, l, h are not many nor very significant. Those between y and v are more numerous and to some extent quite curious, pointing to phonetic relations between these two sounds hitherto not sufficiently emphasized. The tendency of the Taittriya school to prefer v to y is paralleled by its preference in some cases of the vowel u to the vowel v. The only other important subdivisions of this section are the variants between r and l (numerous, and almost purely phonetic), and those between d and d, or dh and dh (numerous, but mainly a matter of cut-and-dried school usage).
 - §9. With the sibilants we find a very large number of variants between

and $ru(r\bar{u})$ with r show Prakritic tendencies Prakritism is, of course, concerned in the little group of variants between aya and e, and ava and o.

- §14. Next comes a section on insertion or expulsion of vowels. Most commonly the vowel (generally 1) is secondarily inserted, contrary to the meter, either before or after a liquid (anaptyxis); the insertion is especially common after r and before a sibilant or h. Only superficially do these cases resemble the next and last vocalic section, which concerns the writing of iy and iv for iv and iv, which is shown to be largely an attempt to represent in writing the vocalic pronunciation of iv and iv (as iv and iv).
- §15. Leaving now the behavior of individual sounds, there is a considerable variety of phenomena which concern groups of sounds. We take up first metathesis: of consonants (transposition of a single consonant without change of other sounds, interchange in position of two consonants, adjoining or not adjoining); then metathesis of vowel and adjoining semivowel. This is followed by an interesting group of variants concerning haplology and dittology.
- §16. Next, a large section dealing with differences in the division of words, which may perhaps hardly be called strictly phonetic, but which are interesting and important because they show, more than possibly any other kind of interchange, the extent of the breakdown during Vedic tradition of both sense and sound values The point is reinforced by a miscellaneous collection of 'patch-words', teaching the same general lesson
- §17. A class of rime-words also throws light on the methods of text tradition. On the slender basis of a vaguer kind of assonance, rather than of real phonetic interchange, words which are easily subject to association are substituted one for another. There is no rubric in which the details of causation can be watched and accounted for more profitably.
- §18. Finally, a considerable number of variants may be based on graphic similarities. Doubtless a careful study of Indian paleography would suggest much more than we are able to state in this section. Our selections are of the more obvious and simple kind, they seem, however, to suggest the great age to which graphic corruptions in Vedic tradition may go back.
- §19. The variants exclusively concerned with external sandhi in a narrow sense constitute the last chapter of this volume, a large and important one A summary of its contents will be found in its introductory section

khajāpo 'jopakāśinīh ApMB · bajābojopakāśinī HG Uncertain, because the words concerned are barbarous and obscure.

§22. The variations between surd and sonant aspirates are both much fewer, and less certain in their relation to Prakritism; we may however quote two cases (see §§70, 76-7):

mā nah kaścit prakhān (ApŚ praghān) .. KS ApŚ

svāyām tanū (ApMB†MG†tanūn) rlviye (RV.†rlvye) nādhariārām (ApMB nātha°, MG bādha°) RV. ApMB MG.

§23. Under aspirates and h occur a few forms which might be connected with the later Prakritic tendency to substitute h for aspirate mutes. Dialectic in a broad sense this change certainly is; but see Wackernagel I p. 252f., who holds that h regularly replaced dh and bh in the RV dialect after (or initially before) an unaccented vowel. Cf. Ascoh, KZ 17. 258ff:

asamheyam [perhaps for asamkhycyam?] parābharan JB. asambharyam parā° AV. See §121.

ardhrah sıtıkakşī vārdhrāṇasas te duvyāh (KSA. vārhīnasas te 'dutyāh)
TS KSA So the single ms of KSA; v. Schroeder emends to
vārdhrī"; the form with h for dh is otherwise unknown, but we should
incline to keep the ms reading See §122

kakubham (VSK. TS ApŚ kakuham) rūpam vīsabhasya (KS. rūpam īsa) rocate... VS VSK. TS MS. KS ŚB ApŚ. MŚ. The adjective hakuhā (with regular h according to Wackernagel's law) occurs in RV, where kakubha is not known See §120.

§24. Under Palatals and Dentals (§§154-61, see especially 156, 159) are found some variations between d and j before y, with obvious Prakritic bearings; the second example we are about to quote shows an interesting hyper-Sanskritism in HG:

sahasrıyo dyotatām (TS. TB. dīpyatām, MS °rīyo jyotatām) . VS TS. MS KS \$B TB

ava jyām wa dhanvanah AV. Vait ApMB: ara dyām wa dhanwanah HG §25. On Linguals and Dentals see our discussion below. §163:

avaiasya (SV. avaiasya) visarjane RV. SV. We believe (for reasons set forth §164) that avaia, 'well', is a pure Prakritism, and that, on the evidence of the variants, Prakritic influence in this section of Vedic phonetics has not been sufficiently recognized heretofore

§26. The miscellaneous group of interchanges concerning palatals (Chapter V) contains a number of Prakritic phenomena (cf. Wackernagel I §135) Thus there are the familiar but very interesting cases of ch for ks, ts, ps (§§183-6); in most of our variants lexical considerations enter in, but note the following

- achalābhih (KSA acharā°, MS. alsarā° in pp, in sp matsarā°, VS rkṣalā°) kapiñjalān VS TS MS KSA The same word appears as rcharā in AV 10 9 23 Either MS or VS (or both?) must have hyper-Sanskritic back-formations
- $\S27$. The following may be quoted as a probable example of dialectic khy for k ($\S\S190-1$) Tho the Tait form is none too clear, it seems that the $\S\S$ has a corruption of it
- ıdhmasyeva prakşāyatah (ŚŚ. prakhyā°) TB TA ŚŚ. ApŚ
- §28. There are a number of cases of mutual interchange between y and y (§§192-3), mostly more or less justifiable lexically. Cf Wackernagel I §§188b, 140b. In the following example we have a proper name, and may infer that one or the other form is a dialectic corruption of its rival
- saujāmm (SG. sauyāmm, with both se tarpayām) AG SG—Cf AV. 19 34 2a, jāgītsyas tripañcāšīh (mss, wrongly emended in edition), for which read yāh (or yāś ca) kṛtyās, or yā gṛtsyas, see Whitney's note to Transl, and our §192
- §29. The interchange between v and m may be Prakritic, of Wackernagel I p 197, it is fairly frequent (see particularly §§223-5) That between b and v (§§206-19) is certainly dialectic in a wide sense, whether properly Prakritic or not, of Wackernagel I p 183f
- uc chvañcasva (TA chmañcasva) prihwr mā nı bādhathāh (TA vı bā-dhıthāh) RV AV TA
- yatra bānāh (VS vāṇāh) sampatanti RV SV VS TS AG Both b and v are found in the RV in this word, it is not known which is original.
- §30. The thoro confusion of the sibilants in the Middle Indic dialects makes it plausible to suppose that the extensive confusion of them even in the Vedic texts is of like nature (cf. Wackernagel I p. 225f.) A few examples out of many may be quoted here, for \$ and \$ see especially \$\$274-9
- vn srutayo (AS vnsrutayo, SS vnsru°) yathā pathah SV AS SS And other cases of sru for sru (so that BR even postulate a 'root' sru, 'flow'!) Here's is original and s secondary. The contrary is the case in the next
- śukeşu me (AV sukeşu te) harımanam RV AV TB ApS
- §31. Much less numerous are the variations between \$ and \$, yet they are not rare, and are to some extent at least purely phonetic (see §\$288-90)
- naınad devā āpnuvan pūrvam arşat (VS aršat) VS VSK ĪšāU. The proper form is arşat, VS comm. 76a gatau

§32. There are very few variations between s and \$ (§291):

ye vrkşeşu (KS. raneşu) başpıñjarāh (TS saspi°) VS TS. MS KS Thought of the word sasya doubtless influenced TS, and cf taspa for the other form (a kind of haplology in each case); see §278

§33. The later confusion between kh and a (perhaps scarcely to be called 'Prakritic' in a strict sense; cf Wackernagel I p 136) finds surprisingly little representation here; in fact we have noted only one case, and that an uninterpretable word (§295):

kaşotkaya svaha TA TAA.: khakholkaya sraha MahanU.

§34. There are however a couple of interesting cases of variation between & and kh, which must be similar in character; see §296 felow

§35. Under presence or absence of masals and anustara occur come variations which remind us of Pali-Prakrit sihe for sinhe and the like. altho usually levical considerations enter in (cf §300).

pasne 'aghrnaye svaha TA · pasna aghrnaye (em., mss aprnaye) staha MŠ *āghrni* is regular

§36. Under presence or absence of y we find some interesting cases which remind us of the wide-spread use of an unetymological y between two vowels as a 'hiatus-tilger' (§§338-44). To be sure, the forms are all grammatically or lexically diverse; but a similar phonetic tendency is surely present. It may be added that there are traces of a similar use of v. altho again the variant forms are lexically justifiable (§§358ff.) varsvānaram tia ā (TS. tlāya) jālam agnim RV. SV. VS TS MS. KS

PB SB. The secondary and not very intelligent reading of TS shows a tendency to avoid hiatus by use of the glide-sound v.

\$37. In Pali and Prakrit we find rather free interchange between long or nasalised vowel plus single consonant and short vowel plus double consonant, without much regard for etymology The conditions are best stated by Geiger, Pali §§5, 6 Traces of a similar tendency may be detected among the variants (§§393-8), the again complicated by other considerations

agne samrād işe rūye (ApŚ rayyai) . AŚ ApŚ : ise rāye . . VS MS (See §396) While the two parallel stems rat and rays are of course concerned here, the result resembles the Middle Indic phonetic change referred to

§38 There are also (§§406-16) traces of the Prakritic assumilation of two adjoining consonants, this is especially marked when one of the consonants is a semi-vowel or liquid, or (as in the following instance) the two are semi-vowel and liquid.

abhinne khilye (TB khille) nidadhāti devayum RV. AV TB This is a purely phonetic, Prakritic variant, TB can mean nothing but an equivalent of *khilye* (comm *khilībhūte*).

§39. Of the vocalic sections, the first to claim attention here is that on the interchange of vocalic liquids and other vowels (§§629-45) The Prakritic nature of this change is obvious. These variants are quite numerous, and, especially between r and a, contain not a few genuine phonetic variations.

ava sma durhanāyalah (SV durhrn°) RV SV. The SV restores Sanskritic vocalism, as against the Prakritic form of RV

tejo yasasın sthavıram samıddham (SG samıddham) SG. PG ApMB HG Here SG alone has the 'correct' Sanskrıt form, and even it has a v 1 samıddham (perhaps felt as 'inflamed', with tejas?)

puramdaro gotrabhid (MS °bhrd, TB maghavān) vajrabāhuh VS MS KS TB A hyper-Sanskritism in MS, see §636

tvasirmantas (MS MS. tvasiri°, ApS tvasiu°) tvā sapema VS MS KS SB KS ApS MS

samvatsara stubhih samvidānah (KS °bhis cākļpānah, ApŠ °bhis cākupānah) MS KS ApŠ

§40. Various Prakrit dialects show occasional forms with r_1 or r_2 for Sanskrit r_2 ; and the modern vernacular pronunciation of Sanskrit r_2 as r_3 or (e.g. Marāthī) r_4 should be remembered in this connexion. Among the variants r_4 for r_4 shows a tendency to be associated with labial consonants. Besides trasfirmantas (trasfir) etc., §39, we may quote from §§666-84

trşucyavaso (MS trışu°) juhvo nāgneh RV MS The adverb trşu is the only possible form here, the variant of MS is purely phonetic bhrmim (TB bhrumim) dhamanto apa gā avrnata RV TB The mss of TB seem to be unanimous on bhrumim, an otherwise unknown form.

pruşvā asrubhih VS. MS. asrubhih pruşvām (TS prs°) TS KSA The form prsvā occurs a number of times in Tait texts; it may be called a hyper-Sanskritism for pruşvā

§41. Coming next to the diphthongs, variations between long and short diphthongs (§§703-12, 728-32) naturally remind us of the fact that all long diphthongs are shortened in Middle Indic Among the clearest phonetic variants are:

avārāya kevariam VS pāryāya kawariam TB The usual form is kai sukurīrā svaupašā VS TS KS SB sukarīrā svopašā MS Several mss of MS and its p p read syaupašā

§42. The familiar Prakritic reduction of aya to e and ava to o is paralleled by our §§744 \rightarrow 9, e.g.,

- namah kinsiläya ca Lşayanäya (MS Lşenäya) ca VS TS MS KS. Lşena is otherwise unknown.
- to-to (MS. KS MS tara-tara, TS. ApS to-te) rāyah VS. TS. MS IIS SB ApS. MS
- §43. The insertion of an epenthetic vowel, generally i, between two consonants, usually a liquid and a sibilant or h, is likewise related to Prakrit phonetics (§§751-65):
- tan nah parşad (MS parışad) atı dvışah TS MS. Cl Wnekernagel I p 57

CHAPTER II SURD AND SONANT MUTES

§44. These are treated in the following order k and g, c and j, t and d, t and d, p and b, kh and gh, th and dh (For g and kh see §82; t and dh, §97f.; p and bh, §§112–14) In general the purely phonetic variants are much rarer than those which involve lexical change. They concern, too, for the most part rare words, so that it is often uncertain whether the voiced or voiceless sound is more original, unless the theory of Prakritic influence is sufficient to establish greater probability for the voiceless. It does seem to be true that, especially under purely phonetic variations of k and g, there is a preponderance of the cases in which k appears to be original

k and g

- §45. We shall begin with the forms which clearly involve real lexical changes along with the phonetic changes, and first of all with cases where both readings make good sense. In these the question of priority is often peculiarly delicate, both variants may be assumed to represent the conscious intentions of their schools.
- athāham anukāmınī (MŚ °gāmınī) TS ApŚ MŚ How near these expressions are to one another may be seen from AV 1 34 5cd, yathā mām kāmıny aso yathā man nāpagā asah Yet MŚ (all mss) is no doubt secondary
- grnatā nah svistaye AV lightlan nah svistim (MS KS "tam) VS TS MS KS "Sing for us unto well-being", 'make well being for us' The meter of AV is easier, but the āprī hynin where it occurs is in a state of corruption so great (of Bloomfield, Atharvaveda 54, Keith, HOS 18 clxi) as to throw doubt upon its version of this pāda, easier tho it be The word grnatā is preceded by grnata (other forms of grno" in the other Samhitās), this suggests that grnatā is a secondary corruption, due not wholly and perhaps not primarily to the tendency here considered
- mitrāvarunā šaradāhnām (MS °hnā) cikitnū (MS cikitam, KS jigatnū, AŠ cikitvam) TS MS KS AŠ cikitnū of TS (presumably 'intelligent' tho not quoted in the lexicons) and jigatnū of KS ('swift') are both reasonable See RV 7 65 1, where jigatnu is precisely an epithet of Mitra and Varuna (wrongly Oldenberg, Noten 2 50)

١

- namah krchrebhyah krchrapatibhyak ca vo namah MS KS · namo grisebhyo grisapatibhyak . . . VS TS. See §185
- tato na vicikitsati (VSK ItäU. vijugupsate) VS VSK ItäU.: na tato vijugupsate KU.: na tadā vicikitsati SB BrhU "Then he no more doubts', or, 'then (therefrom) he does not shrink away' Two familiar verb-forms, both appropriate The Kānva recension of BrhU. has jugupsate Cf AV. 13 2 15b
- dhipsyam vā samcakara janebhych MS: yad rādāsyan samjagārā janebhyah TB: aditsan vā samjagara janebhyah TA Cf dāsyann adāsyann uta sam grnāmi (TA and AVPpp uta iā larīsyan) AV. TA: adāsyann agna uta sam grnāmi AV In all these passages sam-gr seems to mean 'devour, eat', tho doubt has been east on this interpretation (see Whitney on AV 6 71. 3 and 6. 119. 1) If 'devour' is right, sam-cakara 'collect' is secondary, tho in the outcome not very far from the original meaning
- §46. We list next cases in which the priority of one reading is emphasized by the fact that the secondary form, the correct enough considered as an individual entity out of its context, fits that context more or less poorly, so that the term corruption begins to be more or less applicable to it. Here belong, first, several interchanges between the roots k_T and gam.
- ukhām (ApŚ garbham) sravantīm agadām akarma (KŚ. aganma) KŚ ApŚ. MŚ 'We have made the leaking ukhā diseaseless.' Tho aganma may serve at a pinch, akarma seems to be the true reading; see VV I p 211.
- urvīm gavyām parisadam no akran AV: ūrvam gavyam parisadanto agman RV KS. The original RV, 'surrounding it they penetrated into the stable of the cows,' is done over in AV., 'they have made for us a wide conclave rich in kine' (Whitney).
- vadhūr jajāna (AV. jigāya, MS KS mimāya) navagaj (ŚG. navakīj) janitrī AV. VŞ TS MS. KS ApMB ŚG See Whitney on AV. 3. 10 4 for a collection of Hindu guesses on the meaning of navagat, the European guesses are scarcely better. ŚG. tries a sort of hyper-Sanskritism, rationalizing a tradition which it did not understand.
- imam logam (TA lokam) mdadhan mo aham rışam RV AV. TA. 'Deposting this clod of earth, may I suffer no injury.' TA lokam (after imam, this follows so naturally!) makes no sense here. The comm in fact interprets it as loştam (= logam), etymologizing monstrously (lokyate drŝyata iti loko loştah!) Some mss and the comm of AV read like TA, however

- pary āgāram (AŚ ākāram) puna:-punah AV. AŚ ŚŚ Only āgāram makes sense; something (a drum?) is being beaten 'about the house', not 'about the form ' The preceding (in AV, preceding but one) pāda is yadi (yadīm, lelim) hanat katham hanat
- ındrāpāsya phaligam ApMB · ındrāyayāsya śepham alīkam . HG
 The correct reading is certainly phaligam
- mano jagāma dūrakam (PB dūragāh) RV. PB The latter is a farreaching recast of RV, where dūrakam belongs with manas, dūragāh (in itself a perfectly good word) can only be construed by violently detaching it to go with the subject of the next pāda tan ma āvartayā punah This, according to the PB comm., who so construes, is Soma (whom the epithet dūragāh does not fit at all)
- rājānah satyam kṛnvānāh (AV gṛhnānāh, but Ppp kṛnvāno) RV AV Whiney, who renders 'apprehending truth', notes that the other reading is better
- tasya rathagṛtsaś (MS °kṛtsnaś, KS °kṛtsaś) ca rathaujāś ca senānīgrāmanyau (TS senānt°) VS TS MS KS ŠB The word ratha° is a proper name, 'chariot-clever', °kṛtsa is probably a corruption of the first stage, leading over to °kṛtsna, which does not fit
- abhūr gṛṣtīnām (AV * v āpīnām mss , R-Wh vaśānām, false emendation withdrawn by Whitney ad loc , ApMB and one ms of HG. āpīnām, HG. āpīnām) abhiśastipā u (HG ApMB °pāvā) AV. (bis) HG ApMB . bhavā hṛṣṭīnām (AV gṛ°, but Ppp hṛ°) abhiśastipāvā (AV °pā u) AV PG. ApMB HG See Whitney on AV 19 24 5, Roth, ZDMG 48 110 The word must mean 'people'; 'heifers' is nonsense (see Sāyana's ludicrous attempt to justify it).
- prānān samkrošaih MS samkrošān prānaih (VS "krošaih prānān) VS TS. samghosān (ms "gosān) prānaih KSA Here what was originally probably a mere corruption in KSA (s for s, loss of r) becomes, if we accept the emendation, a lexical variant
- §47. We come now to cases where the new reading produces a word or combination of words which seem to defy interpretation. At the same time the putatively original forms are themselves apt to be not above suspicion. The cases concern great textual decay, and belong largely to the Yajurveda schools.
- nikīrya tubhyam abhya āsam Vait nikīrya tubhyam madhya ApŚ nigīrya tubhyam madhiah MŚ nigīrya sarvā ādhīh KŚ The passages are unintelligible, kir, 'scatter', does not seem to be recorded in composition with ni, which points, perhaps, to nigīrya 'swallowing down' (note madhvah in MŚ)

- tena samhanu kṛnmasi AV.: tena sann anugṛhnāsi HG The meaning of AV. is uncertain (perhaps corrupt, see Whitney's note). The individually irreproachable words of HG mouth over an uncomprehended text. Cf. §386
- arepasah sacclasah (etc) svasare manyumatlamāš (SV. ApS. °mantaš) cite goh (SV. citā goh, ApS. cidākoh) SV. AV. ApS. MS. cidākoh, with metathesis of voice-quality, as if from a stem *cidāku, is corrupt
- salma yat te goh MS KS.. sagme (TS sanyat) te goh VS TS. ŚB 'What power of (over) the cow is thine', MS. KS, perhaps correctly and originally. In VS ŚB. sagme looks indeed like a Prakritism for śakma But on account of the different cases it is doubtful whether it is felt as having the same meaning (cf however the adjective śagma, from root śak) It seems, rather, vaguely connected with sa and the root gam VS comm, followed by Griffith, sagme yajamāne (!), goh gauh (very simple!). BR read in TS. sampátie with one ms (pp. samyát, te), but the comm, followed by Weber, ISt 13 197, takes samyát as = samyak. So also Keith ('to match thy cow'). BR regard sampátie as = sagme, both meaning 'Einswerden im Handel'; they render 'wenn du auf eine Kuh eingehst' They therefore derive sagma from sa and gam.
- rudra yat te krayî (VS KS. krıvı, VSK. kravı, MS MS giri-) param nāma tasmaı (VS. MS. SB. tasmın) hutam ası VS. VSK. TS. MS. KS SB ApS MS. These various names of Rudra are all equally unintelligible The reading giri- is especially sophisticated, having in mind Rudra's mountain habitat
- idam aham sarpāṇām dandaśākānām grīvā upa grathnāmı (MS mss kṛtsnāmı; Knauer conjectures kṛnatmi) TS ApS MS. 'I now tie up the necks of the stinging serpents' But kṛtsnāmı is not kṛnatmi, and the MS. may have merely a corruption of TS., in spite of Knauer's belief that the mantra was not taken from TS Somewhat the reverse of this is found in pumān enam etc. \$48
- Cf. also jāgrtsyas tripancāšīh etc., §192.
- §48. In the remaining cases the possibility of real lexical change becomes fainter. We believe that we are now dealing with what are essentially nothing but phonetic shifts, if not pure corruptions:
- invakā (MS. °gā) nakṣatram MS KS. This name for the constellation Mṛgaṣūṛṣa is recorded in its g form only here, and in its k form according to BR. (V. 1144) only once more (TB. 1. 5 1. 1). The priority of invaka, 'pervading', is hardly to be questioned, but MS. may have felt the word as a compound of inva plus ga, gā.

- sā prasūr (ŚG suprasūr) dhenukā (HG °gā) bhava AV. ŚG HG ApMB dhenukā is a pet-word to dhenu 'milch cow' In dhenugā there may be a touch of popular etymology, a hint of the stem go, 'cow', but the form is essentially Prakritic
- āšuh kāṣṭhām wāṣaran (read °ram with comm, Ppp, Whitney, and Bloomfield) AV. 2 14 5b All mss gāṣṭhām, kā° is emendation Ppp also (ms) gā° (em Barret, JAOS 30 193.kā°), comin glāṣṭhām pilah (KSA pigah) kṣwiħkā nīlaśīrṣnī te 'ryamne (KSA °mṇah) TS KSA The word is always mka, except here.
- srkāhastā (TS KS srkāvanto, MS srgavanto, one ms srka°) nisaāgiņah VS TS MS KS The stem concerned is always srka 'spear', except in this and the following passage, and in a lexical quotation, perhaps based on these readings

namah srkāyibhyo (TS srkāvibhyo, MS srgāyibhyo) jighānsadbhyah VS TS MS. KS See preceding

vīnāganakıno (ŚB °gıno) devair imam yajamānam samgāyata ŚB ApŚ Also: vīnāganakınah pūrvaih saha sukrdbhī rājabhir imam yajamānam samgāyata ApŚ vīnāganaginah purānair imam yajamānam rājabhih sādhukrdbhih samgāyata ŚB Cf further KŚ 20 3 2 Altho the compound vīnā does not occur outside these passages, its meaning is plain ('master of a band of lute-players'), and it seems that it must contain -ganaka, with suffixal ka Perhaps the g is due to assimilation to the preceding g, or to sophistication from the root gā, 'sing' (so comm on ŚB and KŚ, both of which implausibly understand vīnā-gana as meaning 'a quantity of [various kinds of] lutes'), cf Conc inder gāyatam

puñpikasthalā (KS \dagger puñpiga°) ca kṛtasthalā (VS ŠB kratu°) cāpsarasau VS TS MS. KS. ŠB This name of an Apsaras appears in later literature, always with k

pumān enam tanuta ut kṛnatti RV. pumān enad vayaty ud gṛṇatti AV. See Whitney's note on AV 10 7 43. gṛnatti is doubtless a mere corruption, promoted by confusion with the root gṛath, gṛanth 'tie', which with ud is nearly synonymous with ut-kṛt More or less the reverse of this shift is found above, §47, sdam aham etc

§49. In the following variants there is for the most part little evidence to support the greater originality of either k or g, the words are almost or quite $\delta\pi\alpha\xi$ $\lambda\epsilon\gamma\delta\mu\epsilon\nu\alpha$

vīryam kuhābhyām (KSA gu°) TS KSA. A part of the horse's body For ku° the TS comm says, hastayor madhyasamdhī (cf vışu-kuh) The other form suggests perhaps guhya, 'pudenda'. Neither is recorded lexically.

- pratikramananı kusthabhyam (KS. gu°) TS KSA.: akramananı ku° MS Both otherwise unknown; like the preceding they designate a part of the horse's body. Bhaskara, hastaparardhamani, Keith, 'the two centres of the loins'. Cf. kusthikā, 'dew-claw, spur', etc
- gane kahua MS KS. MS (agne) gahya TS Neither in lexs, and neither interpretable Keith, not plausibly, 'abysmal' (thinking of aāhva)
- salılah salıqah saqaras te na üditya havişo jusana mantu svaha MS KS: lekah salekah sulekas te na adutya ayam jusana viyantu TS ApS All isolated and uninterpretable.
- grāmyamankīradāšakau ApŠ grāmyam mangīradāsakau MS : vyāghram mangīradāsa gauh Vait In Vait read mangīradāsagau, or possibly with Caland, "dāsakau Two preper names, Mañgira or Mankira, and Dasaka (or Daso), are involved
- namo vah kirikebhyo (MS MS namo girikebhyo) devānām hedayebhyah VS TS. MS KS SB. MS In such a formula, of the Satarudriva. either epithet remains doubtful, the girla, of course, suggests 'mountain-born' like girisa etc The possibility of different lexical interpretations may be admitted, but the variation is probably purely phonetic
- uruka urukasya (ApS. uruga 1 ugasya) te väcä vayam sam bhaktena gamemahi (MS °mahy agric grhapate) MS ApS. Neither form is in the lexs: uruga may be felt as uru-ga, 'wide-going' (so Caland). Is urula some bird of good omen?
- vi te bhinaidmi takarīm (KS orim, AVPpp [Roth] tagarim, AV, mehanam) AV TS KS. ApS There is no evidence as to the meaning of takarī (°rı, tag°) except the context and the variant mehanam; and none whatever as to its derivation or original form.

c and i

§50. Prakritic interchanges between the two sounds go in both directions (Pischel, §202) This of itself makes difficult the appraisal of their phonetic aspect in the variants. Moreover all variations produce passably good words of different origin or etymology, so that priority must be determined by sense, or by the established superiority of one or the other text We are unable to discover anything like a concerted movement, either from c to j or vice versa But on the whole we have the impression that the main current is from c to j, and that it is Prakritic in character (prānjo from prānco, ud-az from ud-ac).

§51. Most notable and extensive is the riming interchange between

the forms $v\bar{u}cam$ and $v\bar{u}jam$ Tho not synonyms, they are both familiar in ritualistic language as words of good and useful meaning Their interchange begins in the RV itself

pra vācam (vājam) indur işyati RV (both).

Here there seems reason to regard vācam as prior, see RVRep 410 In the next following cases vācam is also original

- vācaspatir no adya vājam svadatu VSK vācaspatir vācam (VS*†91, \$B*†51116 vājam) nah svadatu VS KS \$B SMB vācaspatir vācam adya svadāti (MS °tu) nah (TB te, Poona ed nah) TS MS KS TB The word vācaspatir, with the preponderance of texts, shows that vājam is secondary
- paritravantah pari vācam (TA vājam) āsate RV. TA N The older vācam refers either to the sound of the soma-drops (Grassmann) or to the hymns of the officiating priests (Ludwig)
- premam vājam vājasāte avantu AV premām vācam višvām avantu višve TS MS KS In all texts the preceding pāda reads marutām manve adhi no (AV me) bruvantu The Maruts seem here to be regarded as singing priests (RV 3 14 1, 5 29, 3, 1, 178, 1), who may well help the vāc of human priests AV is a banal recast
- vācam asme ni yacha devāyuvam VS ŠB vājam asmin ni dhehi devāyuvam MS.. tapojām vācam asme ni yacha devāyuvam TA In MS a specious lectio facilior, tapojām in TA, as well as the inprānām devayā vācas of RV. 5 76 1, prove that the other texts are right
- §52. In the remaining cases it seems likely that vājam is the original word
- sā dīkṣitā sanavo vājam asme (MŚ vācam asmāt) TS MŚ sā samnaddhā sanuhi vājam emam (MG sunuhi bhāgadheyam) AV † MG 'Do thou (O woman), consecrated, win strength (holy speech) for him (from (this),' or the like. bhāgadheyam is a sort of synonym of vājam. In MŚ asmāt refers to the girdle with which the Pratiprasthātr binds the woman as he recites this verse (iti pratiprasthātā yoktrena patnīm samnahyati), vācam is simple but secondary
- undram vājam vi mucyadhvam TS KS TB · indrāya vācam vi mucyadhvam MS MŚ The verb on which the first two words of this quasi-pāda depend is ajījapata, cf ajījapatendram vājam VS ŚB As the interested person is a king, vājam is clearly required, vācam, 'prayer' or 'Sarasvatī', is far-fetched Cf vājanc and vājantyāyar in Conc

asredhanta ıtana vāzam acha RV adroghāvītā vācam acha AV The

poor meter and general corruption of AV. (in which RV. 3 14 6 is somehow involved) make it unintelligible, see Whitney's note Tho $v\bar{a}cam$ would fit fairly well, RV is original at all points

Analogous to these is one variant between vacasā and ojasā,

- sam eta viśvā (AV † viśve) vacasā (SV ojasā) patīm dīvah AV SV —Ppp evidently means to read ojasā, its text, as quoted by Roth, has viśvā oham ā This supports SV, tho the otherwise corrupt Saunakīya text makes as good sense as its rivals 'Go all together to the lord of heaven (the sun) mightily (with prayer).' See, however, above under vācam asme. §51
- §53. There are next a pair of riming variants in which ud-ac, 'draw out' ('schopfen', of liquids) seems to vary with ud-aj. This is the nearest approach to purely phonetic or Prakritic change, tho ud-aj may at a pinch be a fairly good synonym 'drive out' in the sense of 'obtain, acquire'. Thus in RV 1 95 7 uc chukram atham ajate simasmāt, which we take with Geldner, Ved Stud 2 189, to mean 'he draws out (derives) from himself a bright garment'. Otherwise ud-aj is the favorite word for driving cattle (often mythical) from their stable, which comes metaphorically even closer to ud-ac
- aviraghnīr ud ajantv (ApMB acantv) āpah AV. ApMB 'Let them draw forth waters that slay not heroic sons'; cf. vyukṣat krūram ud acantv āpah ApMB 1. 1. 7 Weber, Ind St 5 198, and Whitney on AV. 14. 1 39 go the length of emending ajantv to acantv, which is doubtful practice (cf §3) But probably the mantra was first composed with acantv, despite RV 1 95 7 above
- samudrād udajani vah (ApŚ udacann wa) srucā MS ApŚ Here MS is probably secondary or corrupt, but possibly understands a form of root jan, 'was born out of the ocean'.
- \$54. There are two cases in which derivatives of roots can and jan vary, it seems that they divide the honors of originality.
- canisthad (SV ja°) agne angirah RV SV Little can be done with the anomalous canisthad (Whitney, Grammar, §906b, Oldenberg, Noten, on 8 74 11); less with janisthad, tho the ideas of either 'giving delight' or 'arousing' are well enough.
- sāntro 'sı canodhāh (MS janadhāyāh) VS MS SB Cf tutho 'sı janadhāyāh (PB 'yah) MS KS. PB. MS: stuto 'sı janadhāh TB ApS 'Thou art Savıtar's joy-gıver (creature-nourisher)' The preponderance of texts favors jana-; there is no other criterion; both are reasonable enough
- §55. In two other individual cases the change is clearly from c to j, the in both the forms with j are tolerably defensible

prāñco agāma (TA. prāñjo 'gāmā) nrtaye hasāya RV AV. TA See §2 devebhyas tvā devāyuvam (KS devāvyam) prnacmī (so MS by emendation, mss mostly prnaymī! ApŠ prnajmī) yajñasyāyuşe MS KS ApŠ MŠ prnajmī (all mss of ApŠ) is supported by Dhātup and by anavaprgna RV 1 152 4, which is placed by Wackernagel I p 117 and doubtfully by Whitney (Roots) under prc See however Scheftelowitz, IF 33 136, and Neisser, ZWbch d RV 1 33 (root *parzg) But the matter is uncertain, the forms with g, j may be based on root prc, and due to proportional analogy with other 7th-class roots in j, which have k by internal sandhi in certain forms (e g, bhanāktī bhagna bhanājmī = prnaktī prgna prnajmī)—In this connexion also

upa mā jakşur (1) upa mā manīsā KŠ 13 2 19, where jakşur is either misprint or Prakritic anomaly for cakşur

§56. In several cases the variation between c and j is in the reduplication of roots in k and g, which latter it really concerns, see §45

mitrāvarunā šaradāhnām (MS °hnā) celetnā (MS celettam, KS jugatnā, AŠ celetvam) TS MS KS AŠ

tato na vicilitsati (vijugupsate), etc

dhipsyam vā samcakara janebhyah, etc

§57. The remaining cases are miscellaneous

somah sutah pūyate ajyamānah (SV suta reyate pūyamānah) RV SV Here the original form of root aj (añj), 'adorn', is replaced in SV by rc, 'praise', a lexical change with hyper-Sanskritic tendency tve kratum api vṛñjanti viśve (AV *pṛñcanti bhūri) RV AV (both) SV TS AA ApŚ MŚ 'In thee they all set (mingle) their mind' The combination api aprāk once more AV 10 4 26, and nowhere else For api varj (original) see Bloomfield, JAOS 35 281

agne vyacasva (RV MS yajasva) rodasī urūcī RV AV MS 'O Agni, make sacrifice to (embrace) the wide heaven and earth' AV has a contaminated lectio facilior, cf RV 10 111 2 mahānti cit sam vivyācā rajānsi, and the converse, RV 8 12 24, na yam vivilto rodasī; or 10 112 4, yasya mahimānam ime mahī rodasī nāviviltām

dwas (SV dwah) prşiham adhı tışthanlı cetasā (SV \dagger rohanlı tejasā) RV. SV. With metathesis of c(j) and t

ud usrıyāh srjate (TB sacate) sūryah sacā RV SV TB See §3
anāhanasyam vasanam carışnu (ApMB HG ja°, PG jarışnuh) ŚG
PG ApMB HG As an epithet of a garment, jarışnu would mean
possibly 'much worn' or the like, as an epithet of the subject,

aham (PG), possibly 'attaining or destined for old age'. To us (contrary to the opinions of Kirste and Oldenberg on HG) ja' seems, with the majority of the texts, the original reading, rather than SG carisnu (Oldenberg, 'wallend')

jāmım (KS†camı) mā hinsīr amuyā (MS anu yā) sayānā KS. TB ApS MS· mā jāmım moşīr amuyā sayānām AV—The KS reading (of a single ms) should certainly be corrected to jāmim

gharmas trisug vi rājati (SS rocate) VS SB SS Hardly belongs here, rocate is a perfect synonym of rājati.

yuktās tisro vimījah (comm ribhījah) sūryasya PB: yunajmi tisro vimījah sūryasya te (MS virītah sūryah save [or, savah]) TS ApS MS In PB the comm has two equally fatuous guesses on vibhījah 'dividers' (of the sun) But there is little more sense in vipīcah, apparently 'separators' (of the sun); it seems to be applied collectively to pīthivī, vāyu, and vāc It can hardly mean 'separate, distinct' as BR take it Keith, doubtfully. 'spaces', Caland and Henry, Agnistoma, 128, equally doubtfully, 'épouses'

girā ca (AV virājah) śruṣtih sabharā asan nah RV AV VS TS MS KS SB The AV reading shows far-reaching adaptation to a secondary purpose, as it seems also to include with most of SPP 's mss (and his oral reciters) and the comm śnuṣṭih for śru° Whitney adopts śnu°, which Ppp. also intends with its suniṣṭas (Barret, JAOS 30 207) See §865

purā jatrubhya (TA ApMB jartrbhya, MS cakrbhyā, p p vaktrbhyah) ātrdah (MS °da) RV AV SV MS PB TA KS ApMB The original is obscure enough, but MS is hopelessly corrupt and unintelligible Note its loss of final h (§384)

t and d

§58. We have found practically no variants here; the one recorded involves plausible but secondary change from 1st to 3d person in a verb form $(VV\ I\ p\ 217)$.

vısvāvasum namasā gīrbhir īde (ApMB ītte) RV ApMB

t and d

§59. Here we find, first, a number of cases in which d is substituted for t as what seems to be a purely phonetic, Prakritic change, real lexical difference being scarcely, or only in a very strained way, conceivable:

cılrā elagvā (TB eda°) anumādyāsah RV MS TB The comm on TB

- ignores the word. The etymology of clama (AJP 17, 426) furmishes no opportunity for the change.
- pārācataghnīm (TB "daghnīm) acare surfitibhih RV MS KS TB N pārācataghnīm (se sararatīm), either 'slaying the distant (enemy)', or 'slaying from a distance' TB comm has a labored and worthless explanation. If the text had anything in mind it must have analyzed pāra + acadaghnīm, root dagh, something like 'reaching across' (pāra, 'further bank')
- sa îm păhi va țiiți tarutrah (VaradapU tarudrah) RV AB GB TB. NțpU VaradapU Perhaps vague popular etymology in tarudrah, as if 'tree-cleaving'
- tme 'rātsur ime subhūtam (MS sūdam') al ran TB ApS MS. The latter (quoted by Kunuer from an unpublished part of the text) evidently intends subhūdam, for subhūtam, since it is followed immediately by
- ıma udvüsil ürina (MŠ 1mü uddhäsicürina) ime durbl ütam (MŠ °dam) al ran TB ApS MS - Cf prec
- agotām anapalyatām (vulgate with most miss anapadyatām) AV 4 17 6b Some miss and the comm read anapalyatām, which must be intended, as guaranteed by its juxtaposition with agotām Cf RV 3 54 18 yuyota no anapalyām . pašumān astu gāluh.
- yadā rākhātyau vadatah ApS yadā rāghatī taradah Vait . yad adyārādhyam vadantah MS See §§70, 272a Vait is thoroly Prakritic §60. In the next following cases lexical considerations enter more forcibly, yet the change continues to be from primary t to secondary d.
- tayam hi vām purutamāso (AV. °dam°) akunā AV AS ŠS. Is the epithet (here applied to the poets, hāru, but in juxtaposition to the word akunā) a bungled reminiscence of its application to the Akuns in RV 7 73 1 (purudansā purutamā) ? Roth, ZDMG. 48 107, and Whitney on AV. 7 73 1, consider the AV form, 'having many houses', corrupt
- mã me hārdi tvişā (MS. hārdim dvişā) tadhīh TS MS A replica of RV 8 79 8c mā no hārdi etc , dvişā is lect fac
- sato tah pitaro desma VS sado etc ApS SMB GG In VS 'of what is ours, O Fathers, we will give to you' The others with lect fac, 'a seat, O Fathers' etc, this is facilitated by the quasi-synonym grha in the preceding pāda grhān nah pitaro datta. Cf the next
- mulham sad asya iira it satena (TB sadena) VS MS KS TB The texts all intend sad asya (so MS p p and VS comm), TB comm apparently reads sam asya VS comm. takes satena from a stem

- sata, said to be a sacrificial implement, and says that the stem sat (in sad) = sata, 'chāndasah'. TB sadena, taken by its comm. to mean 'scat', may be a sort of phonetic perseverance, matching sad-asya Cf. prec
- śwā rutasya (VSK śwa rtasya, TS and v l. of MS. śwā rudrasya) bheşajī (MS °jā) VS. VSK. TS MS KS. See §684.
- gāva upāvatāvatam (SV. upa vadāvate) RV. SV. VS. In SV. a form of upa-vad; in the others, of upa-av. SV. is uninterpretable; its verb is singular, but the subject can only be gāvah.
- svasāra āpo abhi gā ulāsaran (SV. udāsaran) RV. SV. In SV. a form of ud-ā-sr (quotable nowhere else) is substituted for the original, uta+asaran.
- ya ātrnatty (ViDh āvrņoty, SamhitopB. ātrnoty) avitathena (VāDh. avidathena) karnau SamhitopB VāDh. ViDh. N. avidathena can at a pinch mean 'unsacrificial' or 'not according to rule', but the use of the hieratic vidatha is very questionable at this stage. The reading is simply Prakritic or corrupt.
- yathāpah pravatā yanti TA. TU. Kaus: yathā yantı prapadah SMB. The latter is secondary; Jorgensen, 'wie die Wege gehen'. In his note he suggests pratipadah, which is not enticing in view of the variant.
- agne län vettha yadı te jälavedah HG. ApMB.. tvam vettha yalı te jälavedah RV VS yadı, 'if', ıs lect fac.
- ā vatso jagatā (AG jāyatām, PG jagadanh) saha AV. AG PG. ApMB. HG. MG. jagadanh (comm 'guards', anugai rahṣakanh) is certainly poor and secondary. The comm. however is probably right in his interpretation, as the next variant interestingly shows:
- isānam jagadam saha PG: īšāno jagalas patm AV. TS KS ApMB. The context is different; the two pādas are hardly variants of each other. PG comm jagadam, anucaram Cf. prec.
- htvā na ūrjam pra patāt patīsthah (AV prapadāt pathīsthah) RV. AV. MG In RV., 'leaving us food may it fly forth, most swift-flying' AV, doubtless intentionally, 'leaving us food, may it set out, being on the road', which seems to make possible sense, the it is secondary (Whitney, however, abandons it and translates the RV. version).
- vanā vananti dhṛṣatā (MS mss °dā; one, dṛṣadā) rujantah RV. TS JB. SB MS The corruption of MS mss is due to thought of dṛṣad, 'mill-stone'. RV 8. 49 (Vāl 1) 4 may have dhṛṣat in this sense. But see Oldenberg, Noten, on this passage
- amocı (AV. amukthā) yakşmād durntād avartyaı (AV. avadyāt) AV TB ApMB avartı 'distress' seems likely to be original

ā sutrāvne (MS KS bhūyışlhadāvne) sumatım āvṛnānah AV MS KS oṣişlhadāvne sumatım gṛnānāh TS See §355

In a couple of cases involving adverbs in d and t the t seems older, they are grouped below, §68, with similar cases in which d is older

- §61. In the next group we find different division of the words, but the change is still from t to d (cf. §65)
- pathā madhumatā bharan (MS madhumad ābharan) VS MS TB Either reading is interpretable, in VS TB madhu° goes with pathā, in MS with the object of ābharan We judge that the former is probably original, cf RV 10 24 6 madhuman me parāyanam madhumat punar āyanam
- yena bhūyas carāty (MG caraty) ayam (AG ca rātryām) AG ApMB MG yena bhūris carā dwam PG The original form is that of ApMB MG, of which AG is a corruption PG changes the verb from 3d to 2d person, carās (VV I p 235), this is connected with the further change that introduces dwam
- tvam no devatātaye (AV deva dātave) RV AV SV—Ppp reads devatātaye, indicating that AV (Ś) is secondary—It makes, however, a sort of crude sense 'do thou, O god, (stir) us (up) unto giving'
- arepasah sacetasah cite goh (citā goh, cidākoh), see §47 Note the metathesis of surd and sonant qualities in the two consonants (t-q, d-k)
- jīvann eva pratī tat te (so Jorgensen for SMB, v 1 pratīdatie) dadhāmī (SMB dadāmī) TA SMB† jīvann eva pratīdatie dadāmī MS. The latter is corrupt
- §62 The cases in which the change is, certainly or presumably, from d to t do not impress one so much with the presence of a purely phonetic movement. They consist either of downright blunders, or of variations in which either reading makes fair sense but the t forms represent a later or easier reading. Thus in the first case the t is a palpable blunder that turns an impeccable passage into a group of unintelligible syllables $ah\bar{a}$ neta (GB netar a-, SS $ah\bar{a}d$ eta) sann ancetanam AV AB GB SS
- ahā ned asann apurogavānı (so divide) JB—This is followed by jajñā (JB Caland, yajñā) neta sann apurogavāsah (JB Caland, ancetanāsah) AV AB GB JB yajñād eta sann apurogavāsah SS Gaastra reads GB as yajñā neta asann apuro, and so in the prec, read in GB netar asann Weber, Ind St 9 306, suggests correctly ned asann for AV etc The true form of the two pādas is ahā ned asann avi, yajñā ned asann apuro, 'lest the days be without distinction, lest the sacrifices be without a leader' So

- Caland, ZDMG 72 24f., who quotes JB. as reading thus, except for the interchange of the two adjectives. AV and SS are hopeless, but GB (as read by Gaastra) makes possible sense
- $\S63$. But in other cases, as indeed in one secondary form of the preceding (that of GB), either reading makes reasonable sense, the for various reasons we believe that the d is older.
- part doṣād udarpithah KS: parītoṣāt tad arpitha ApS. Preceded in KS by yo me 'dya payaso rasah; in ApS. by yan me 'tra payasah It is an expiatory formula after a nocturnal emission Caland adopts part doṣād ('without [part, sc. my] fault') from KS, and reads udarpitah We agree with him that this is the original reading, but consider that he is wrong in emending ApS to accord with it; parītoṣāt, 'thru excessive gratification', tho a slipshod lect. fac, is clearly what ApS intended
- godhāyasam vi dhanasair adardah (TB atardat) RV. AV MS TB. The antique and rare adardah (3d sing imperf intensive of dar) puzzles TB sufficiently to provoke the synonym atardat
- prvyo me hrdo (MS htto, v 1 huto) 'si (MS † bhava) TS MS The latter is simply a lect fac
- sapla rājāno ya udābhışıktāh KS AA · anu sapla rājāno ya utābhışıktāh TB The TB stumbles over udā, 'with water', and eases it up to the colorless adverb uta
- yās ca (AV yā) devīr (SMB devyo, PG devīs) antān (AV antān, PG tantān) abhito 'dadanta (PG SMB tatantha) AV. PG. SMB ApMB. yās ca gnā devyo 'ntān abhito 'tatananta (so em; mss. tatantha) MG. The reading tatantha could only intend a monstrously augmented form atatantha, because of the preceding abhito (note sandhi) Roth, ZDMG 48 108, considers it obvious that tatantha is a corruption for 'dadanta In PG, however, the corruption has become infectious, because there antān is further changed to tantān under the influence of tatantha The comm on PG (see note in Stenzler's translation) treats the muddle of the text as Vedic license Cf VV I p 139f
- yatrādhi sūra udito vibhāti (TS uditau vyeti) RV VS VSK. TS yasminn adhi vitatah sūra eti MS KS Of course RV is original, but vitatah is found also in the AV version, yasyāsau sūro vitato mahitvā
- vidad yadī (MS†yadı, TB ApŚ. yatī) saramā rugnam (MS† saramārunam) adreh RV. VS MS KS TB ApŚ The original yadī (yadı), 'when', is corrupted into a fem pple. yatī (TB comm

- gachanti) suggested by the final $\bar{\imath}$ of $yad\bar{\imath}$, and supported by RV 5 45 7 $yat\bar{\imath}$ saramā Saramā, the messenger, is hardly ever mentioned without the implication that she is a great traveler, cf. RV 10 108, 1, 3, 5, 7, 9, and note $g\bar{a}t$ at the end of 3 31. 6, the stanza here concerned. Caland in his Translation of ApS unwisely abandons $yat\bar{\imath}$ for $yad\bar{\imath}$
- yad vo detā atīpādayām (AŚ °tayāmi) TB AŚ ApŚ. ati-pad and atī-pat are synonyms, 'transgress' TB comm alaranam anyathā-laranam cātipattīh. There is little reason for preferring either, except the somewhat greater evidence for the pad form (two texts confirm each other)
- űrdhvā yasyāmatır bhā (so divide) adıdyutat (VSK. ati dyutat) savīmanı AV. SV. VS VSK. TS MS KS SB AS SS N. The VSK reading, if authentic, is secondary. See VV I p 128
- śvetāya vaidārvāya (PG °darvyāya, ApMB HG °darvāya, MG vaitahavyāya)... AG. ŚG. PG. ApMB HG MG The epithet vaitahavya does not belong to the serpent demon Sveta, and is a secondary misunderstanding.
- $\S64$. In the following cases the t variant produces readings that are increasingly difficult or suspicious, and that tempt more to emendation Even here, however, we cannot be sure that the secondary or false reading was not the established text of the school.
- duras ca visvā avrnod apa svāh RV.: turas cid visvam arnavat tapasvān AV.7 Whitney translates AV · 'may he, quick, rich in fervor, send all ' Since Ppp agrees with RV., it is clear that AVS is secondary But turas is lexically defensible.
- tvam rājāsi pradīvah (VS VSK pratīpat) sutānām RV. VS VSK. TS MS KS N. pratīpat is hardly intelligible; Mahīdhara takes pratīpat sutānām as a compound, ignoring the accents: 'draughts pressed on each initial day of a lunar fortnight.'
- harmasya raghuşyadah (ApŚ. °şyatah, two mss °şyadah) AV ApŚ Caland adopts the AV reading, if ApŚ really intended °taḥ, it simulates a pres pple form from a denominative *raghuşya-.
- agne (Poona ed agre, but comm agne) vikşu pratīdayat (v. 1 °yan; not in Poona ed) TB: agre 11ksu pradīdayat RV. Comm on TB, groggily- pratīdayat, pratyekam eva prāplam āsīt (as 1f prati, 1d, ayat!).
- §65. Here again we find some cases accompanied by false division of words (as in §61):
- salyā tā dharmanas patī ApS: salyād ā dharmanas (SS and mss of MS

- onā) patī (Vait MS pari, SS omits) AS SS Vait MS Caland in his Transl. of Vait understands satyādā as one word (nom dual), which may be right. He also adopts this reading in ApS, which is surely wrong in principle. The secondary, ApS is perfectly clear, and undoubtedly intended just what it reads.
- tad vipro abravīd udal. (SS u tat) AV SS Followed by qandharrah kāmyam racah SS has a lect fac which would be quite acceptable but for its repetitousness (tat, twice).
- bahm schanto vitudasya (AG vi tu tasya, v. l vidurasya) presyāh (MahānU AG presthāh) TAA MahānU AG The AG attempts to rationalize the obscure vitudasya (said by TAA. comm to be a name of Kālāgnirudra), a ἄπ λεγ which it does not understand
- §66. The remarkable case of tevi for devi deserves special emphasis; it is best regarded as merely a hyper-Sanskritism, of §21. disam devy (MS tevy) avatu no ghrtācī TS MS. AS.

In the pada mātrh kva cana vidyate, TA. 1 5 1d, the comm (does not read mādrh, as Cone states, but) interprets mātrh by mādrh, which seems the only possibility.

§67. A few other special cases with problems of their own:

privo (VS MS privo, KSA bidvo) nyañkuh kakkalas (MS kakuthas, TS KSA. kaŝas) te 'numatyar (KSA °yāh) VS TS MS KSA. None of the forms privo etc occurs elsewhere Some animal is meant; remotely possible is connexion with pedu

mayamdam (MS MS mayamtam) chandah VS TS. KS MS SB MS. An otherwise unknown fanciful name of a meter Mahidhara, sukham dadāti; Keith, 'delight-giving' This is probably right-mayamda for mayoda in deference to the prevailing type of nambic dipody compounds with prior member in m See Bloomfield, JAOS 21. 50ff, Wackernagel 2 1, pp 204ff

parişītah kveşyası ApMB. parişīdah kleşyası HG parimīdhah kva gamışyası PG. The true reading is that of PG., with dh, and neither t nor d See Stenzler's translation ('umpisst'). Comm on ApMB gets fairly close in general sense chāndasam dīrghatvam, parişitah paribaddhah

[suṣadam id gavām asti pra khuda AV . susatyam id gavām asyasi pra khudasi ŠŠ The AV mss read exactly as ŠŠ, except that they read gavom and pra sudasi The variant is not genuine, but only due to Roth's false emendation]

§68. In a number of cases adverbs in t or d interchange. In the first two cases the d forms are certainly older, but in some of the others the reverse is the case:

ado (MŚ ato, AV. ado yad) devī (AV. KS devī) prathamānā pṛthag yat (AV. °nā purastāt) AV. KS ApŚ MŚ

adah su madhu madhunābhi yodhīh RV AV SV AA MS. ata ū şu madhu madhunābhi yodhi TS.

ıtı cıd dhı (AV *yadı cın nu) tvā dhanā jayantam RV AV (both) arhā nah santu sarvadā (PG sarvatah) ApS PG HG

dhātar āyantu sarvadā (TA TU sarvatah svāhā) TA TU Kaus samavayantu sarvatah SMB

tato na (KU na tato, SB. BrhU na tadā) vicilitsati (VSK ISāU. KU vijugupsate) VS VSK SB BrhU. IsāU KU See §45 tato is certainly older

parı krośatu sarvatah (HG sarvadā) HG ApMB

p and b

§69. Here occur only a few stray variants

phalgūr (KSA °gur) lohitornī balakṣī (VS pal°, KSA balakṣīs, em by ed to °kṣī) tāh †sārasvatyah VS TS KSA MS balakṣa, of unknown etymology, means 'white, and is clearly intended here. The change to pal°, not otherwise recorded, may be due to contamination with palita, VS comm simply says that pal° means bal° avātiratam brsayasya (TB prathayasya) seṣah RV, TB Bṛsaya, name of a

avaluratam brsayasya (TB prathayasya) sesah RV, TB Brsaya, name of a demon TB comm takes its form also as the name of a demon, it is clearly a corruption of the RV form

khajāpo 'jopakāsinīh ApMB bajābojopakāsinī HG The readings are untrustworthy, and neither form is intelligible

pilvo (pidvo, bidvo) , see §67

There are also a number of cases in which b as reduplicating syllable of bh (in bibharti etc.) varies with p as reduplicating syllable of p (in piparti etc.), they are gathered in §112

kh and gh

§70 Here again are only a few stray variants

mā nah has cit prahhān (ApS praghān) mā pramesmahi KS ApS 'May no one harm us (or the like), may we not be injured ' Probably KS is original, pra-hhān BR (Nachtrage to V), 'durch Graben zu Fall bringen' praghān is felt as coming from root han, tho problematic in form, it appears to ease the meaning Prakritic influence is likely

saghāsı jagatīchandāh TS sakhāsı (ŚŚ adds patrā) jagacchandāh ŚŚ MŚ Cf sakhāsı gāyatram chandah MŚ (Bloomfield, JAOS 16.

3ff.) It seems that sakhā is a sophisticated lect fac, it is clear that saghā (stem saghan, comm 'vulture') is original; preceded in TS. SS. by syeno 'si gāyatiachandāh, and suparno 'si trişlupchandāh (SS inserting patrā both times)

yadā rāghatī varadah (ApŚ rākhātyau vadatah) Vait ApŚ. yad adyārādhyam vadantah MŚ The form rā° appears to be a proper name, not found elsewhere and wholly incomprehensible. BaudhŚ 16. 23 reads rākhandyau (?), and one ms of ApŚ rākhāndau

th and dh

§71. Aside from the interchange of the adverbs atha and adha, or similar adverbs, the material is scanty. It may be partly graphic, since th and dh are practically indistinguishable in some South Indian alphabets. There is no clearly defined phonetic movement in either direction. Yet there seems to us to be, as in the preceding rubries, perhaps a slight tendency to favor dh for th in readings that are obviously secondary, showing the presence of what we have thought to be Prakritic influence.

§72. In the one common case of interchange between the adverbs, chiefly atha $(ath\bar{a})$ and adha $(adh\bar{a})$, we should expect on general grounds to find that the dh forms are generally original. This expectation is realized to this extent, that the SV, with only one exception among the variants, substitutes th forms for RV dh. Yet the AV, relatively late and popular, surprizingly favors adha $(adh\bar{a})$. The RV. in its hieratic parts favors the dh form as we should expect, and in its more popular parts the th forms. The remaining texts in general favor atha, but now and then fall into the archaizing adha

§73. We begin with cases in which RV shows adhā, other texts athā (atha), included is also one case of RV. viśvadhā, SV. viśvathā:

vı bhānum vıśvadhālanat (SV. vıśvathā°) RV. SV

adhā jivrī (AV atha jivrir, mss jirvir; ApMB athā jīvrī) vidatham ā vadāsi (RV vadāthah) RV. AV. ApMB

adhā (SV athā) no vrśvacarşane RV SV

adhā (SV. athā) te sahhye andhaso vi vo made RV SV.

adhā (SV athā) te sumnam īmahe RV AV. SV TS

adhā (TS MS. athā) te syāma varuna priyāsah RV TS MS KS

adhā (TS MS athā) šatakratvo yūyam RV VS TS MS KS ŠB rudrasya maryā adhā (SV athā) svašvāh RV. SV.

\$74. Next, cases in which RV. (almost always in Books 1 and 10) shows the more popular atha (athā), while other texts have the archaining adha (adhā). The latter occurs most frequently in AV. (of course

- secondary, of the similar preference of AV for the archaic kmo- as against karo-, VV I p 116ff), once in SV ($\bar{u}rdhvadh\bar{a}$ for RV $^{\circ}$ $th\bar{a}$), once or twice in other texts
- pra śmaśru (SV śmaśrubhir) dodhuvad ūrdhvathā bhūt (SV, °dhā bhuvat) RV (10) SV
- athā (AV adhā) nah sam yor arapo dadhāta (MS °tana) RV (10) AV VS MS KS N· athāsmabhyam sam etc TS
- athā (AV adhā) prīrn sundairān upehr (AV TA. apīhr, TS† apīta) RV (10) AV. TS TA Add to VV I §370
- athā (AV adhā) mano †vasudeyāya kṛṣva (AV kṛnuṣva) RV (1) AV Despite the grandiloquent adhā, AV is secondary as shown by the meter
- athā (AV adhā, MS KS tato) no vardhayā rayım (RV JB gırah) RV.
 (3) VS TS AV. MS KS JB. SB TB JābU.
- athā (AV adhah, comm adha, but Ppp adhah, Barret, JAOS 40 161) sapatnī yā mama RV (10) AV ApMB · adhā sapatnān māmakān AV.
- atho (AV adhā) vayam bhagavantah syāma RV. (1) AV KŚ ApŚ N athā (AV adhā, comm atha) vayam āditya vrate tava RV. (1) AV. VŚ TS MS KS ŚB N . athādītya vrate vayam tava ArS SMB
- athā (KS adhā) somasya prayatī yuvabhyām (KS yuvā°, v 1 yuva°) RV. (1) TS KS N
- athā (MS adhā) devānām apy etu pāthah RV (2) TS MS.
- §75. Among the remaining cases, it may be noted that AV again prefers the dh form repeatedly, as against other texts with th
- adha syāma surabhayo (ApŚ corruptly, syām asur ubhayor) grheşu AV. KS ApŚ athā svāta surabhayo grhesu MS
- adhā jīvema saradām satām AV · atho jīva saradah satam VSK And others, see Conc under asau jīva
- adhā (HG atha) māsı punar ā yāta no grhān AV HG.
- adhā (MS MS athā) poşasya poşena VS MS KS MS
- adhā vişvāhārapa edhate grhe VS atha visve arapā edhate grhah TS
- athă (VS SB adhā) sapatnān (KS †°nān, TS, twice †°nān, once °nān) indro me VS TS MS KS SB ApS MS
- athā (VS SB adhā) sapatnān ındrāgnī me VS TS MS KS SB ApS MS
- athā jīvah (KS adhā viṣitah) pitum addhi pramuktah (so divide) TS MS KS: athaitam pitum addhi prasūtah VS ŠB
- adhāsyā madhyam edhatām KSA · athāsya madhyam ejatu VS IS athāsyat (TS. MS TB °syā) madhyam edhatām (Vait °tu, AS IS. ejatu, SS ejati) VS TS MS SB TB AS SS. Vait IS.

- ındro marudbhir ştuthā (TS ApMB °dhā) krnotu TS MS KS AS, SS ApMB
- devā no yajāam tuthā (TB ApS tjudhā) nayantu VS TB. ApS See \$157.
- §76. Somewhat like the change of adha to atha is one interchange between the roots $n\bar{a}dh$ and $n\bar{a}th$, since here $n\bar{a}dh$ is clearly prior. But $n\bar{a}dh$ is commonly considered to be in origin a secondary and quasi-Prakritic form of $n\bar{a}th$ (von Bradke, ZDMG 40 678ff, cf. Wackernagel I p. 123):
- svāyām tanū (ApMB† MG† tanūn) rlvvye (RV† rlvye) nādhamānām (ApMB nātha°, but many mss nūdha°, MG bādha°) RV ApMB MG
- §77. For the rest we find no very definite phonetic movement in either direction But it may be significant that the cases in which th seems probably the original—listed in this paragraph—are somewhat more numerous than those in which dh appears older:
- avakro 'vithuro (ApŚ 'vidho', Kauś adds 'ham) bhūyāsam AŚ ApŚ MŚ. Kauś That avithuro (root vyath) 'not staggering' is the original is indicated by the majority reading, and by its closer agreement in meaning with avakro, avidhuro is clearly secondary.
- maiṣām nu gād aparo artham (TB ApŚ ApMB ardham) etam RV. AV VS ŚB TB ApŚ ApMB · mā no nu gād aparo ardham etam TA ApŚ 'Let not another of them go to that goal (side, part).' artha and ardha are here synonyms, cf RV 1 164. 17.
- ābhūr (VS TS ābhur, NīlarU. śwo) asya niṣañgathih (VS °dhih, NīlarU. °tih) VS TS MS. KS NīlarU Comm on VS 'sheath of a sword', but 'quiver' is more plausible since arrows are mentioned in the preceding pāda Hindu lexicons quote niṣañgathi as meaning 'embracing' etc; the other forms are ἄπ λεγ. Probably °dhi is influenced by thought of root dhā (popular etymology), while °ti is a mere corruption
- paridam vāso adhithāh (HG adhidhāh, ApMB adhi dhā) svastaye AV. HG ApMB The original (AV.) form is 2 sing nor mid. of dhā, the personal ending -thāh is mouthed over in the later texts to a sufficiently plausible form of dhā (dhāh), the first part becoming the preposition adhi See VV I p 39
- ākhuh kaśo mānthālas (MS mānthālavas, VSK māndhālas) te pītrnām VS VSK MS. pāāktrah (KSA pāāktah, but all mss of both TS and KSA pāmtra-) kaśo mānthīlavas (KSA † ma°) te pītrnām (KSA † pītr°) TS KSA We may guess that the majority of

- texts preserve the original th, but the forms occur nowhere else Said to mean 'flying fox'
- indrāvathuh (VSK °dhuh, KS * TB ApŚ °lam) kāvyair (TB ApŚ karma ā) dansanāblih RV AV VS VSK. MS KS (both) ŚB TB ApŚ The subject is the Asvins, so that VSK is hardly interpretable. See VV I p 282
- apa snehrlīr (SV snīhtim) nṛmanā adhatta (SV. adhad rāh, KS† nṛmanām adadhrām) RV AV SV KS upa stuhi tam nṛmnām (Poona ed snuhi tam nṛmanām) athadrām TA See §110

§78 In the rest dh seems to be the original:

- apāma edhi mā mṛthā na indra SMB amā ma cdhi mā mṛthā na (AS † ma) indra AS SG anāmayaidhi mā riṣāma indo Kaus The original (AS SG) 'be at home with me, do not desert us (me), Indra' This SMB converts into the unbelievable 'be an off-warder of disease, do not die for us, Indra' At least the comm takes it thus, seeing in mṛthā(h) a 2d sing mid of mṛ (one ms. reads mṛthā), riṣāma of Kaus confirms mṛth as original The variation is somehow connected with the sphere of sa mā mṛta (tam mā mṛthah), which see in §98 On Kaus's reading see §344
- madhavyau stokāv (MS °kā, AV mathavyān stokān) apa tau (AV yān) rarādha AV TS MS Several mss and the comm on AV read madhavyān, which Whitney properly recommends
- adhorāma (HG atho^o) ulumbalah (HG † ulumbarah) ApMB HG adho^o = adhas is obviously correct, HG mechanically recalls the many phrases beginning atho (= atha u), q v in Conc
- dīrghām anu prasitim (KS samṛtim) āyuşe dhām (KS tvā) VS TS KS SB TB. dīrghām anu prasītim samspršethām MS An extensive alteration, yet still showing the change of dh to th (°şe dhām °šethām)

ph and bh

- §79. The instances are few and all concern questionable forms phalāya, and, phallāya KhG·bhalāya svāhā, and, bhallāya svāhā SMB GG The words are addressed to the sun, or to the evening twilight, their meanings are unknown. The form with single l and the variant with ph make it questionable whether bhalla is Prakritic for bhadra (Wackernagel I §195), in spite of the form bhallākşa which is probably so to be explained (Weber, Ind St 288).
- kanātkābhām (AŚ pranākāphā) na ābhara TB AŚ See §151 yā sarasvatī vaišambhalyā (ApŚ °balyā, v l °phalyā and °bhalyā) tasyām me rāsva . TB ApŚ See §114

CHAPTER III ASPIRATES AND NON-ASPIRATES AND H

880. The subdivisions of this chapter are very unequal in size and In most of them we find only stray variants, often concerning obscure words of doubtful belongings Sometimes both forms may be interpreted and defended, but on the whole they suggest that phonetic confusion between aspirates and non-aspirates played no slight rôle in changes of the Vedic tradition Variants of aspirate and non-aspirate mutes in considerable numbers are found only as between t and th, where however graphic confusion is undoubtedly largely to blame, and as between the dental aspirates and non-aspirates. It is here that we find much the largest and most interesting group appear that lexical and morphological considerations enter in to a large extent, vet it will scarcely be doubted that phonetic resemblance accounts at least in some measure for the swollen bulk of the variations between roots $d\bar{a}$ and $dh\bar{a}$, for example, or between verbal endings of different sorts containing t and th—The variation of aspirate mutes with h is appended to this chapter as a special section, §§115ff

L and kh

- §81. Here occur two variants, both concerning very dubious forms. gohya †upagohyo marūkoi (PG mayūkho) manohāh PG. SMB Cf. grhyo etc Names or forms of Agni The mss vary The form mayūkha, 'ray', would fit fairly well, but may be merely a lect fac. The lexicons report marūka in various meanings
- kaşotkāya (MahānU lhakholhāya) svāhā TA TAA MahānU The MahānU form recurs in the Purānas; it is interpreted as kha-kha-ulka (1), 'sky-meteor', i e the sun The other form is ἄπ λεγ, and the comm 's explanation is not worth quoting

a and Lh

- §82. Two variants between the synonymous stems sukha and suga, to which no phonetic significance can be attached. The form sukha is later both times.
- sugam (VS MS ŚB sukham) meşāya meşyai (RV meşye) RV. VS VSK TS MS KS ŚB LŚ
- sugam (VS MS sulham) ca me śayanam ca me VS VSK TS MS KS

g(k) and gh

§83. Only a few variants, one very obscure, one corrupt, of yena mahānaghnyā jaghanam AV. Kauś, where apparently all mss of both texts read so, but the emendation mahānagnyā is obviously required and is assumed by the Conc. and by Whitney

yanasya ghoşad asi TS TB. ApS · goşad ası MS KS. MS TS comm 'wealth', Keith 'substance', remarking that ghoşad is probably a corruption for goşad, which however is itself not clear

yatheyam strī pautram agham na rodāt AG SMB PG ApMB HG yathedam strīpautram aganma rudriyāya MG See §801

tāsām īśāno bhagavah (MS maghavan) VS TS MS KS The words are virtual synonyms

apūpakrd aslake ŠG apūpaghrtāhute ApMB. Addressed to an aslakā, same context, one must be a phonetic corruption of the other 'O cake-making A', or 'O thou that hast cakes and ghee as oblations'

c and ch

§84. Two variants, one an onomatopoetic word

cec-cec chunaka srja PG chad apehr.. ApMB Cf the English 'skat'

karnābhyām (PG godānāc) chubukād (ApMB cu^o) adhı RV AV ApMB PG. A v 1 of AV with its comm. cubukād; one ms of ApMB cibukād, which is the form found in later Sanskrit.

g and gh

§85. A single variant

apām napire jaṣah (KSA jhaṣah) TS KSA. jaṣa is otherwise not unknown (AV), but jhaṣa is regular in the later language. The word is of non-Aryan origin

t and th

§86. These variations are without doubt largely, perhaps mainly, graphic. In every case but one they concern interchange of \$\si\text{t}\$ and \$\si\th\$, which are practically indistinguishable in most alphabets. In nearly every instance the \$th\$ form is proper, or at least more usual. Many of the words, however, are obscure in derivation.

kuşthayā (MS Luştayā) te krīnām MS ApS Regular is kuşthā, designation of a measure; kuştā is not recorded lexically

nadībhyah paunījistham (TB °tam) VS TB Also

namah pungusthebhyo (TS °tebhyo) nisadebhyas ca vo namah TS KS.

namo nisadebhyah punnishebhyas (MS "(ebhya") ca to namal VS MS. The word punn" or paunn" 'fisherman' or 'fowler' eceme usually to be written with "tha, but there is no little fluctuation. Its unknown, perhaps non-Aryan, origin is not illuminated by the proposed worthless etymologies.

ranistum (AB TB AS MS. *thum) asya mā rātista MS KS AB TB.
AS SS † 5 17 9, MS The regular form is conistin, of unknown derivation Knauer (on MS) would emend MS to *thum

- ahorātre ūrvassīve (VS "sthīve) brhadrathamtare ca me yajārum lalpelām (VS † kalpantām) VS MS (Add to VV I \$357) The proper form is ūrv-asthīva, the latter part being a modulation of asthi-vant, knee'.
- śatāpāṣthādya (read with Poona edd oshā gha) riṣū pari no rṛnah!ri TB TA · śarā rūṣlād (p p rū, aṣlāt) dhariṣū rūrnah (read [a-] tarnah?) MS As a missile (helt) is the subject, the true reading contains apāṣtha, 'barb'. The MS is entirely corrupt The Poona ed of both TB and TA, makes the pāda begin with the preceding word ugrā
- anupūrram yatamānā yatı stha (AV stha, TA. yatısta) RV. AV TA yatısta could only be an aorist; but as it retains a double accent (yátı-stá) it is obviously corrupt (suggested by the preceding yatamānā) for yátı sthá, 'as many as ye be'
- rdhag ayā (TS MS KS ayād) rdhag utāšamışthāh (MS KS °şia) VS TS MS KS. ŠB N·dhruvam ayā (AV ayo) dhruvam utāšamışthāh (AV utā šavıştha) RV. AV Here both forms are correct; there is a shift of verbal person, from 2d to 3d (explained VV I p 211). On the corrupt reading of AV. see §234 Cf next
- āşta (MS āşthāh, KS ms † āştāh, em v. Schr. āşta) pratişthām . . . TS. MS KS PG See VV I p 238, and cf. prec.
- vity area canisthayā (SV. panistaye) RV. SV. If the SV. reading is tenable at all (panistaye, 'for praise') it points to a stem in ti, whereas RV (of course original) has a superlative in istha.
- [nir asthausam asmriam GB Vait ApS Quoted in Conc with astarisam from GB and Vait But the Vait reading is a mere misprint, corrected by Garbe p 119; and Gaastra reads asthausam in GB. without report of variant Accordingly we may assume that astausam never existed. The form is from sthu = sthiv 'spit' (cf. sthutvā, ApS)]
- §87. In the preceding sih is the proper or at least the usual spelling We now come to the cases where si seems proper. Both are dubious,

the first belongs to the sphere of the Kuntāpa hymns, whose textual tradition in all versions is of the worst sort, and the second has \it{th} only in the p p of MS

sasim (SS sasthm) sahasrā navatīm ca kaurama AV AS SS The combination sasitm sahasrā is very common, see e.g. Conc. thereunder SS, if its reading has any real standing, has confused sasit with the ordinal stem sasiha

mā no agnım (p p agnıh) nırrtır mā na āştān (p p āşthām) MS mā nu rudro nırrtır mā no astā TA See VV I p 93 The forms are doubtful, read āştām?

§88. The following is the sole variant between t and th not preceded by § Nothing is known about the word hahutha or kakkata except that, as the context shows, it is the name of some animal

privo (prdvo, bidvo) hakkatas (kakuthas) , see §67

t and th

§89. These sounds interchange a good deal in old, historic, morphological elements which are otherwise identical (or nearly so) in form, and frequently identical or similar in meaning. Hence, with variations containing such forms, it is not easy to say to what extent the change was morphological in character, and to what extent it resulted from an error of speech or hearing. No doubt both influences were concerned in most cases. We find, for example, that 2d personal verb forms containing th (indicative) and t (modal) are often interchanged, there is seldom any connexion in which either of them is impossible or even difficult (cf. VV I, especially §§14ff, 116). Again 2d and 3d duals often differ only in this single consonant, t or th, and VV I, especially §§20f, 292ff, 326ff, has shown how easy is the shift between second and third personal forms, often with no further change in the context. There are also cases concerning noun formation, suffixation etc., where this slight phonetic difference is concerned.

§90. We begin with the variations between the verbal endings that and ta, the former properly present indicative, the latter modal (or preterite) They have been listed in VV I p 23f In the majority—listed first—the t form appears to be older, in the last five, at least, the th form

āpura stā SS āpūryā sthā TS AS Add to VV I le tam sma jānīta (VSK. °tha) parame vyoman AV VS VSK TS KS SB MS jānīta 'smainam (TS MS jānītād enam) pa' vy' AV TS MS elam jānātha (TB jānītāt, KS jānīta) pa' vy' VS KS TB

- SB Note especially that VSK jūnītha is apparently a blend of jānīta and jānūtha, tho jūnītha is grammatically better than jānūtha.
- śwā no bhavata (ApŚ °tha) jīvase MS ApŚ
- śuddhāh pūtā bhavata (TA °tha, MG. °ntu) yazīnyāsah RV. TA. MG. aśvā bhavata (AV. TS KS °tha) vāzīnah AV VS. TS. MS KS. ŚB · devā bhavata vā° RV
- tena krīdantīś (ŚG. krīl^o) carata (ŚG °tha) przycna (AV vaśān anu) AV. TS ŚG PG ViDh. vaśān anu in AV is due to infection from RV. 1.82 3, 10 142 7.
- devebhyo bhavata (TB. °tha) suprāyanāh RV AV. VS. MS. KS TB. N. datto asmabhyam (KS dattvāsma°, AŚ dattāyāsma°, SMB dattāsma°) dravneha bhadram AV KS AŚ. SMB. dadhatha no dravnam yac ca bhadram MS
- ye'tra pıtarah.. bhūyāstha AV. ŠŚ. ya etasmın loke ...bhūyāsta TS TB A primary ending on a precative form is absurd, yet all mss. of AV. and ŚŚ. seem to agree on "tha; see Whitney on AV 18 4 86.
- arālāg udabharisata (AV. mss °tha) AV SS The AV. reading, augmented but with °tha, is a monstrosity. Roth's violent emendation, āsannā udabhir yathā, has no standing
- aulaba (HG °va) it tam upā hvayatha (HG. °ta) ApMB HG. Several mss of ApMB read °ta, in such trash as this it makes little difference what is read
- saputrılāyām jāgratha PG. yajamānāya jāgrta ApS. See note in Stenzler's translation of PG. 1. 16. 22
- indrena yujā (TB sayujā) pra mṛnīta (TB. °tha [Bibl Ind pranītha]) satrūn AV. TB Add to VV I §16
- payasvatīh kṛnuthāpa (TS °tāpa) oṣadhīh śwāh (TS. omits śwāh) AV. TS. Followed by
- wrjam ca tatra sumatim ca pinvata (TS °tha) AV. TS. (Add to VV I §18.)

 The clauses are parallel and we should expect the same mood in both; yet both are inconsistent Little weight is to be attached to the Ppp readings, quoted by Roth as having t thruout the stanza, even in pada d (yatrā naro marutah siācathā madhu), where the relative clause should ensure the th form (indicative; see VV I pp 78f.). Contrariwise, the AV. comm. reads pinvatha for °ta, which seems to suggest, perhaps, that originally all the verb forms had th.
- yad āmayatı nış kṛtha (TS MS KS kṛta) RV VS TS MS KS kṛtha, tho a dubious root present, really a back formation from norists like kṛthi, is the older reading, kṛta lect fac

yūyam (MS divo) vrslim varsayathā (MS °tā) purīsinah RV TS MS KS—MS, which borrows divo vrslim from e.g. RV 2 27 15b, is secondary also as regards °tā.

ud īrayathā (MS MŚ °tā, AV KS °ta) marutah samudratah RV AV TS MS KS AŚ. MŚ

§91 About equally often second and third duals containing thand t interchange (listed VV I pp 24f.) Even when the context is to our feeling inconsistent in one or the other reading, as often happens, we should generally resist the temptation to emend, for reasons made clear in VV I (references quoted §89) We begin with passages in which the th forms seem to be the older, in the majority there is little to choose between them

cıtrebhır abhraır upa tış(hatho (MS °to) ravam RV † MS Followed by dyām varşayatho (MS °to) asurasya māyayā RV MS See VV I p 241 yāv (MS KS yā) ātmanvad bibhrto (KS † °tho, AV višatho) yau ca rakşatah (AV. KS † °thah) AV TS MS KS Followed by

yau viśvasya paribhū (KS viśvasyūdhipā) babhūvathuh (TS†°tuh), same texts See VV I p 228 The unanimity of AV. and KS, partly supported by MS, perhaps indicates that the 2d persons are original, we fail to see any ground for Keith's opinion (on TS 4.7.15 3) that the 3d persons are more 'logical'.

tat satyam yad vīram bibhṛthah (MŚ † °tah), and, in same passage, vīram janayışyathah (MŚ °tah),

te mat prātah prajanayişyethe (MS °te),

te mā prajāte prajanayışyathah (MŚ °tah) TB ApŚ MŚ See VV I p 236

ghrtena (Kaus vapayā) dyāvāpṛthivī prornuvāthām (VS TS Ap\$
prornuvāthām, MS MS † prornuvātām) VS VSK TS MS KS ŚB
Kaus Ap\$ MS · also see Conc under svarge (°gena, suvarge)
loke (-na) prornuvāthām etc (only MS °tām; VS VSK. TS KSA
[†samprornuvāthām] SB TB Vait. °thām)

yā rājānam (MS KS °nā) saratham yātha (MS yāta) ugrā TS MS KS juşetām (and, °thām) yajāam iştaye RV (both) Add to VV I §21

kāmam duhālām sha sakvarībhsh AV rāstram duhāthām sha revatībhsh TB. See VVI pp 25, 224

purā grdhrād araruṣah pibālah (TS $^{\circ}$ thah) RV MS TB Here, and in the following cases, it seems fairly clear that the t forms are original

sam (ApMB sam) ūdho romasam hatah (ApMB hathah) RV ApMB See VV I p 24.

hato (SV TB hatho) vṛtrāny āryā (AV TB aprati) RV SV AV TB followed by,

- hato (SV hatho) dāsām satpatī RV SV., and,
- hato (SV. hatho) viśvā apa dvişah RV SV. See VV I pp. 222, 232.
- yajñasya yuktau dhuryā (TB Ap\$ °yāv) abhūtām (MS. °thām) MS. KS†TB Ap\$ And, in the same stanza.
- dw (KS dwe) yyotir ajaram (MS KS uttamam) ärabhetäm (MS. KS.† °thām), same texts abhūthām is certainly wrong, and all texts have a 3d person in the 1st-pāda of the verse. See VV I p 235
- §92. There are further a few anomalous variants concerning other verbal endings containing t and th, or, in the last case, a verbal ending with th varying with a nominal ending with t.
- abhiramyatām (MS. °thām') MS. SG YDh BrhPDh The MS form, if correct (it occurs in an unpublished part of the text), is hopelessly anomalous, see VV I §22
- yās ca (yā) devīr (devyo, devīs) antān (antān, tantūn) abhīto 'dadanta (tatantha), etc., sec. §63
- ubhāv ındrā (ŚB ındro) udıthah sūryas ca VS. ŚB · aya(h)sthūnam (TS °nāv) udıtā (TS MS KS °tau) sūryasya RV TS. MS. KS The old loc sing in °tā is shifted in VS ŚB. to a second person dual verb, udıthah
- §93. In nominal endings, suffixal or quasi-suffixal, this variation has a certain scope, but is complicated by corruptions or other obscurities
- asunītāya (TA °thāya) vodhave AV. TA The AV comm reads °thāya, which is clearly original; °tāya is infected by asunīti; cf. Whitney on AV. 18 2.56
- punar brahmāno (AV. brahmā) vasunītha (AV °nītur, KS * °dhītam, 38. 12b† °nītha, MS °dhīte) yajñath (AV MS KS * agne) AV VS TS. MS KS (bis) SB All forms are rare and dubious KapS (v. Schr. on KS 8 14b) has vasudhītam or °tim (so also v 1 of KS.).
- nurtho (MS oto) yas ca misvanah (AV misvarah) AV. MS TA nurto in MS is a secondary blend of nurtha (old) and nurth (common).
- svastı nah putrak theşu (MG. pathyāk teşu, but v. 1 as RV) yonışu RV AB MG Note metathesis of t and th in MG.; if the reading is correct, it is a blunder due to pathyāsu in the preceding
- ābhur (MS KS ābhūr, NīlarU. śwo) asya nişangathih (VS °dhih, NīlarU °tih) VS TS MS KS NīlarU. The last has a corruption, see §77
- paktā (KSA panthā) sasyam TS KSA Comm. on TS, pālašīlam. KSA corrupt, see Keith on TS 7.5 20 1
- stuto 'sı janadhāh TB ApS (LS. pratīka, stutah): tutho 'sı janadhāyāh

(PB °yah) MS KS PB MS LS Is stuto lect fac for tutho of unknown meaning?

samıddho agnır vrşanāratır (AV °nā rathī, ŠŠ °nā rayır) dwah AV AB AŠ ŠŠ From RV. 3 3 6, 4 15 2, 8 75 1 it is probable that rathī is the true reading

garbhas ca sthātām garbhas carathām RV Conc would read cáratām .(gen pl of cárant), but caráthām (gen pl of carátha) may stand (Oldenberg, Noten)

§94. In a few adverbial forms this variation is primarily morphological, but rather indeterminate phonetic tendencies may have been at work.

atho (MU ato) annenawa jivanti TA TU MU

tato (AV ArS tathā) vişvañ vyakrāmat (AV tathā vyakrāmad visvañ) RV. AV ArS VS TA

atho rājann (AV uta rājñām) utlamam mānavānām AV TB

atho pitā (MS utāyam pitā) mahatām gargarānām AV TS MS KS §95. As regards lexical interchange of t and th, RV 8 13 27 harī indra pratadvasū abhi svara has been suspected of harboring a corruption of prathadvasu, 'increasing wealth' (Yāska, prāpta-vasu, Sāyana, vistīrna-dhana), or pratata-vasu But there is not the slightest reason for any Vedic poet to blunder away from so obvious a form as prathad-vasu The word as it stands may be pra-tad-vasū, '(carrying) forward his (Indra's) wealth', so the two bay steeds, as subject Cf the doubtful kṛtād-vasū (kṛta-tad-vasū with haplology?) in RV 8 31 9; see however Wackernagel, 2 1 pp 64, 319, Oldenberg Noten on the passages

§96. The lexical interchanges are otherwise few, largely corrupt, and partly based on different word divisions

tābhyām (MS KS add vayam) patema sulrītām u lokam (Kauś. pathyāsma sukrtasya lokam) VS TS MS KS ŠB Kauś Dhātup has a root path 'go' doubtless abstracted from the noun path, panthan Possibly Kauś intends pathyā(h) sma In VV I p 110 we have treated its form as a precative It is likely, however, to be a mere corruption as regards the th

hıtvā na ürjam pra patāt patişthah (AV padāt pathişthah) RV AV MG See §60

samsrāvabhāgā (VS SB KS samsrava°, MS °bhāgāh, KS Kaus °bhāgās) stheṣā (Kaus tavṣā) brhantah VS TS MS KS SB Kaus tavṣā is a sophisticated assimilation to brhantah

aktam (MS MS aptubhī, KS *artham) rihānā vyantu (TS TB KhG

viyantu) vayah TS MS KS. (bis) TB MŚ GG. KhG: vyantu vayo 'ktam rihānāh VS. ŚB KŚ aktam rihānāh, 'licking the fat', is certainly original, the KS. aitham rationalizes poorly, or rather is a mere corruption. Indeed von Schroeder on KS 31 11 suggests emending artham to aktam. On MS see §152

atho mātātho pītā TA·hatā mātā hatah pītā SMB: hato hatamātā krimih AV See §386

atho ye kşullakā wa AV hatah krımīnām kşudrakah SMB · atho sthūrā atho kşudrāh TA. See ibid

sarve rādhyāh stha (SS °yās tu) putrāh AB SS

grho hiranyayo mitah (AS gromiohio) AV KS AS Here all AV. mss. and comm read mithah, which makes no sense and is clearly a corruption; RWh read mitah with Ppp and KS AS

parītosāt tad arpitha ApS pari dosād ud arpithah KS. Read in both udarpitah, see §63

upa yajñam asthita (AV. comm astria, MS astu no) vaisiadevī RVKh AV ApS MS.

t and dh

§97. Here we find chiefly forms of the roots vrdh and vrt, which in composition with several prepositions are almost synonymous, but in every variant which occurs one reading or the other is suspicious or corrupt. It happens that the vrt forms are correct or original in every case except the first two, where the reverse is true.

bhīma ā vāvrdhe (SV vāvrte) savah RV. SV.

madanti devir amṛtā ṛtāvṛdhah (Vait °vṛtah) Vait ApŚ MŚ Caland on Vait 13:20 assumes that °vṛtah (all mss) is an error

abhı rāştrāya vartaya (AV vardhaya) RV. AV. The AV is certainly poor, and Ppp has vartaya, see Whitney on 1 29 1. Cf next two yenendro abhıvāyıte (AV. °vrdhe) RV AV In same verse as prec:

same conditions Cf also next

abhi somo avīvītat (AV. °vīdhat) RV AV In next verse to the prec two, same conditions

nnvario yo ny avivrdhah (ApMB °vrlat) HG ApMB. Oldenberg adopts °vrlat for HG

pumānsam vardhatām (†text is right, despite Conc) mayi \$G.: pumān samvarlatām mayi PG. pumān garbhas tavodaie \$MB 'Let them two (Indra and Agni) make a male grow in me', 'let a male be in me' or the like \$G\$ has a 3 dual active verb See §840

Note further the exchange between the old (RV) adjectives rtarrdh

- and dhriawata (not concerning root vrt) in: āvitte (āvinne) dyāvāprihwī rtāvrdhau (dhriavrate), and others, see §§466, 665
- \$98. The remaining cases are sporadic, and again largely suspicious or corrupt
- samvatsarasya dhāyasā (AV VS tejasā) AV VS TS KSA HG Synonyms
- sa mā mṛta (MG vṛtat) AG ApMB MG: cf tam mā mṛdhah ŚG 'Let him not die', or 'do not fail him', and §78, apāma edhi mā mṛthā na indra, etc The MG has a mere corruption, see §225 ābhur (ābhūr, śwo) asya niṣañgadhih (°thih, °tih), see §77
- vn te (PG tau te, HG vndhe) krodham nayāması PG HG ApMB Kırste suggests emending HG to vn te, and this apparently Oldenberg assumes in his translation, vndhe may be somehow felt as from vn-dhā, but is really hopeless
- yebhyo madhu pradhāvatı (AV pradhāv adhı) RV AV TA Comm on AV, followed by SPP ın text and by Whitney in his Translation, reads as RV See Whitney's note and Lanman, ap Whitney, p xen
- śriyai (MG śriye) putrāya vettavai (MG vedhavai) ApMB MG For the MG Knauer suggests veddhavai, Conc vettavai
- nnantı pākam atı (SS †adhı) dhīra etı (SS emi) AS SS ApS adhı is very inferior in sense

d and dh

\$99. This interchange occurs in a considerable and heterogeneous mass of variants, most of which are isolated and either lexical or under suspicion of corruption. The manuscripts certify to the ease of confusion between the sounds by very frequently showing variation between them in the same passage of the same text; of e.g., Whitney on AV 11 1 23 (ansadhrī "drī), to mention only one out of numerous possible examples. In the midst of this miscellaneous mass, however, there looms a large and compact block of variants between the two roots dā and dhā. These two roots, thruout the whole of their inflection and in large part in nominal derivatives, are rime-words, differing (in general) only in the aspiration or lack of it. They are also in large measure synonymous, or so near it that it amounts to the same thing

Roots dā and dhā

§100. They are thus used interchangeably, without betraying any perceptible difference of meaning, in ritual formulas like the following. āyurdā asi ŠŚ. āyurdhā asi TS JB AŚ

āyurdā (MS KS °dhā) agne'si VS TS MS KS. ŚB ŚŚ. PG. cakşurdā (KS °dhā) arī VS KS ŚB

varcodā asī VS ŠB ŠŠ varcodhā asī AV TS MS KS JB TB ApŠ MŠ.

rarcodā (MS °dhā) agne 'si VS TS MS ŚB ŚŚ PG —All these formulas are followed by āyur (calşur, varco) me (mayı) dehi (dhehi), the verbs in the two associated formulas being always consistent

§101. There is, to be sure, one regular difference between these two verbs as regards the cases they govern, tho it is one-sided rather than reciprocal $d\bar{a}$ does not govern the locative of the person, but only the dative. The root $dh\bar{a}$, on the other hand, while it seems (to our feeling at least) most naturally construed with the locative, may also govern the dative. We have noted among the variants only two cases of $d\bar{a}$ with the locative, both of which may reasonably be suspected

tokhām dadhātu (MS dadātu) hastayoh VS TS MS KS SB This is no real exception, first because a dative (tubhyam) in the preceding pāda is connected with the verb, the locative hastayoh being really epexegetic, but also and chiefly because the MS reading is nonsense, since the preverb ā is joined with dā, which could only mean 'take', a meaning that is manifestly impossible here. Cf mā no andhe, \$105

mayı puşlım †puşlıpalır (AV puşlam puşla") dadhātu (AG †dadātu) AV. MS KS TAA MahānU ApS AG SMB. Here the isolated dadātu in the late AG is evidently an error

[mays rucam dhah (KS †dhehs) MS KS Conc dehs for KS]

§102. On the other hand, we find cases like payo me dāh, MS, recurring as payo mayı dhehi ApS, and in the same text (TS) all three possibilities in a formula like āyur me dehi TS 1 5 5 3, āyur me dhehi 1.661, and āyur mayı dhehi 7 5 192 (but, NB, no *āyur mayı dehi).

§103. In very simple formulas of the type presented in this paragraph, there is as a rule no criterion for establishing the greater originality of either reading. Indeed, it is doubtful to what extent they are properly to be considered variants of one another, not infrequently they may very well have originated independently.

rayım me dah (AV dhehr) AV. MS

ojo dehi KS ojo dhatta TS KS ojo mayı dhehi VS TB.. ojo me dah (svāhā) AV VS SB

balam dehi KS balam dhatta TS MS balam mayı dhehi (AV me dāh svāhā) AV VS TB

saho mayı dhehi (AV. me dāh svāhā) AV VS. TB

- prānam dhehi (KS dehi) KS TA ApS. See Conc in the vicinity of these
- vācam dhehi (MS. me dāh) MS TA
- annam me dehi (PB * dhehi) PB (both) LS Kaus, cf note on Kaus 136 4.
- āyur dhehi (KS dehi) KS TA ApŚ. MŚ · āyur me dāh (svāhā) AV VS MS. ŚB TA ApŚ MŚ · āyur mayı dhehi VS TS ŚB āyur me dehi VS TS ŚB ŚŚ. PG : āyur me dhehi VSK TS KS KSA MS TB. ApŚ. āyur me dhattam TB ApŚ
- śrotram dehi (TA dhehi) KS TA śrotram mayı (KSA †mayı, not me) dhehi TS KSA · śrotram me dāh AV MŚ
- calşur dehi (TA dhehî) KS TA calşur me dhehi (KS KSA dehî) VS KS KSA. SB calşur mayı dhehi TS · calşur me dāh (svāhā) AV MS.
- tejo mayı (AS me) dhehi (AS dehi) AV VS TS KS SB TB AS LS SG. ApMB: tejo me dhāh (AS dāh svāhā) TA AS
- varco mayı dhehi VS TS PB SB ApS varco me dāh (TA dhāh) MS MS. TA.: varco me dehi VS TS SB SS PG · varco me dhehi VSK MS KS JB ApS varco asmāsu dhatta (AS dhehi) AV AS
- vīram dhatta (AS vīram me datta, MS °no datta) mtarah AS ApS MS vīrān nah pilaro dhatta ViDh vīrān me milaro (tatāmahā, pratatāmahā) datta Kaus
- ürjam mayi dhehi VS VSK MS KS. PB SB LS. ApS MS ürjam me dhehi (PB LS. dehi) VSK TS KS PB GB TB Vait LS KS hrdispil kratuspig varcodāh (MS °dhā asi) MS AS
- §104. Prose formulas of a somewhat less simple type continue the same style of variations without introducing any additional criteria of textual correctness or priority
- aśvibhyām pradhāpaya (TA °dāpaya) MS TA
- apām osadhīnām garbham dhāh (MS garbham me dāh) TS MS
- adhı datre vocah VS TS SB · adhı dhatre vocah MS KS
- calşurdā varcodā varivodāh TS·varcodhā varvodhāh MS varcodā varvodāh (TA varvodā dravnodāh) VS TS KS SB TA
- bhūs (also, bhuvas, and svas) tvayı dadhāmı (MG te dadāmı) SB BrhU PG HG MG. bhūr bhuvah svah sarvan tvayı dadhāmı (MG svas te dadāmı) SB BrhU PG MG
- anādhrstāh sīdata sahaujaso (TS MS KS sīdatorjasvatīr) mahi ksatram (varcah) ksatriyāya dadhatīh (KS dadatīh) VS TS MS KS SB
- iyam vah sā satyā samdhābhūd (MS samvāg abhūd) yām ındrena samadhadhvam (MS °dadhvam) TS MS eşā vas sā satyā samvāg abhūd

yām indrena samadadhvam KS yām indrena samdhām samadhathāh (comm and some mss samadhatlāh) AV. Where the noun samdhā occurs, it guarantees connexion of the verb with the root dhā, note that in MS KS it is replaced by samrāg; but even so, samadadhvam may perhaps be felt as from root dhā (Wackernagel I p 128).

astrto nāmāham...ātmānam ni dadhe dyāvāpṛthivībhyām gapīthāya (KS. dyāvāpṛthivyor ātmānam pari dade ...) AV, KS

devīr āpo apām napād . . devebhyo devatra dhatta (VS SB. datta, KS dāta) VS TS KS SB . . tam devebhyah śukrapebhyo dāta MS

puşlapale cakşuşe cakşuh smane smānam...dehy asma: MS · puşlipalaye (AŚ °pale) puşliś...asma: punar dhehi (AŚ. dhehi or dehi svāhā) AŚ ApŚ For smane smānam see Bloomfield, AJP 21 324

agnır annādo 'nnapatır. mayı dadhātu (TB yajamānāya dadātu) \$B TB. K\$ Similarly nine other formulas with other gods [udgātar devayajanam me dehi \$B Ap\$ (Conc dhehi for Ap\$)]

§105. The metrical variants bring in a larger number of texts, but offer little new evidence, only the familiar chronological relations of the various texts offer any basis for distinctions of priority, as when, in the first cases to be mentioned, we naturally assume that the RV is original.

rayım devî dadhātu me AV. rāyo devī dadātu nah RV.

purumedhaś (SV °dhāś) cư takave naram dāt (SV. dhāt) RV SV

dakşam dadhāsı (KS dadāsı, v 1 dadhāsı) jīvase RV. MS KS TB. ApS asmabhyam dattām (AV dhattām, but comm dattām) varunas ca manyuh RV AV—Ppp also dattam

vasudeyāya (KS "dheyāya) ndhate vibhāti RV KS In RV vasudeya occurs twice more, but no vasudheya

tato no dehi jīvase RV TB TA · tasya no dhehi jīvase AV SV Kaus tisro dadhur (KS dadur) devatāh samrarānāh VS † (so for Conc RV) 19 81b, MS KS TB The majority are probably original

somāya rājne paridhātavā (HG °dā°) u AV HG ApMB. As Kirste remarks, HG is secondary or corrupt, the first pāda of the verse has paridhatta in all texts

mā no andhe tamasy antar ādāt MS (properly emended by Knauer to ādhāt, cf §101) mā sv (Poona ed mo şv) asmāns tamasy antarādhāh TA mo şvatvam asmāntarādhāt MS † (corrupt)

pratyādāyāpara 15vā AV 10 1 27, read pratyādhāyā°, see Roth, ZDMG 48 681, and Whitney's and Bloomfield's Translations

dhātā dadhātu (TS, Ap\$ ApMB, dadātu) no rayim AV, TS, MS.† K\$ Ap\$, ApMB Kau\$. See \$106 first two variants.

dhātā dadhātu (Ap\$. dadātu) surranasyamānah AV. M\$ KS. Ap\$.

indre a ria indrigam dattam ojah AV.; asmin nara indrigan dhattam ojah TS. Comm. on AV. and Ppp. dhattam.

āņur no dehi fīvase ŠG.: āyuş te (AV. āyur no) višrato dadhat AV. TS TA. Apš. Aš. HG. BDh. Ci. ray in no dehi . . . §106.

rāyns poşari cilituşe (AV. "şī AS. yajarnāne) dadhātu (SS. dadātu) AV. TS. MS. KS AS. SS.

işarı ürjanı yajamanaya dhehi (Vait. datteā, AV. duhrām) AV. VS. TS MS. KS. ŠB. Vait.

lolam asmai vaicmānāva dehi (MU, dhehi) TS, KSA, MU.

trașă răpări dadrati (SB. KS. dadati) sarasrati SB. TB. AS. SS. KS. dadati is a secondary adaptation to dadătu în the next păda.

asme dřeki (SV. dehi) jälaredo riahi šravah RV. SV. VS. TS. MS. KS. krivî (AV řytvá) savarnám adadur (AV. adadhur) vivastale RV. AV. N. The AV. is undoubtedly secondary, but it is perhaps a little strong to call it a 'corruption' (Whitney).

derebhyo (VS. devānām) bhāgadā (TS. "dhā) asat VS. TS. MS. KS. f

pra no (MS. KS. mā) brū'ād bhāgadhān (Apś. °dhām, MS. °dām, KS. dharirdā) devalāsu (KS. °tēbiyah) TS. MS. KS. Apś.

§105. In the preceding there seemed to be some reason for preferring one reading or the other. In the following we find none, or so little as not to be worth noting:

Thôid dedôtu (AV. dedhôtu) dōsuşe AV. AS. SS. AG. SG. X. See next. Vôid riêrā rūryā dadhōtu AV.: dhôtā dedōtu dōsuşe rasūni TS MS ApMB. In variants like this and the preceding, the occurrence of a derivative of the root dhô in the context may be noted. But as an argument for priority it may be a two-edged sword. Does it indicate that the original verb was dhô, or rather that an original dō was attracted to it?

rayin, ro dehi jirase \$\$.: rayim no drehi yajniyarı MS. Ci. ayur no dehi jirase, \$105.

rnedhām açnir dadātu me (SMB dadhātu te) SMB. ApMB.; cf. medhām ta indro dadātu HG, medhām dhātā dadātu (RVKh. Scheftelowitz dadhātu) me RVKh. VS.

tasrioi rio devolt paridhaticha sarre AV.: tasrioi no devolt paridaticha (KS. MŚ. dhatta PG. drattel a) sarre (MŚ.† riste) TS. KS. MŚ. SMB. PG. BDh. Comm. on AV. also datteha. called by Whitney's better reading: of this we are less sure.

tasya no rāsta tasya no dheht (AŚ dāh) AV, AŚ,

jūrann cia prati tat te dadhūmi (SMB dadāmi) TA SMB f. jīrann cia pratidatte dadāmi MS

udno (AV. ed ūdhno, but mss utno etc.; Whitney transl reads udno) divyasya no dhātah (TS, KS deht) AV, TS MS KS Comm. on

AV. dhāta, explaining by dhehi (1) mahi tarcah ksatriyaya dadhatih (KS dadatih, TS tantanah) TS. MS KS.

§107. Leaving now the roots da and dha, we come to other d and dh variations. They are practically all lexical, or else involve dubious and probably corrupt readings But their very frequency, and the frequency of corruptions between the two sounds in the me, certifies to the ease with which they could be confused. We begin with a group in which the variant forms are still fairly close to one another in external form; in the first they are even etymologically equivalent, concerning divergent forms of the desiderative of the root dabh This (originally *dhabh) produces both dhips and dips, of which the first is historically regular, while the second, the analogical in origin (:dabh), is the usual form. nindād vo asmān dipsāc (VS SB. dhipsāc) ca VS. TS. MS. KS SB. TA.

dhipsyam vā samcakara janebhyah MS : aditson vā samjagara janebhyah Here dhips varies with the negative desiderative of da (cf. §§180, 45).

vam te scadharan scadayanti dhenarah RV .: yam te scadaran scadanti gurlayah RV. The second version is inferior in sense and meter; see RVRep on 8 5. 7a and 8. 49. 5c.

sā brahmajāyā vi dunoti rāştram AV.: sā rāştram ava dhūnule brahmajyasva AV Roots du and dhū.

rajani (AV. ed. em. rajjuni) granther danam (AS. dhanam) AV. AS. Vait. The emendation rajiuni is very pat; the passage means 'the tying of a rope', and dhanam, like rajani, is nonsense.

adhi ksami (SV. asmin ksaye) pralaram didhyanah (SV. °ram didyanah) RV. AV. SV. See Whitney on AV. 18 1 1 and Geldner. Guruvūiākaumudī 20. SV, has an obvious lect, fac infected by ideas such as RV. 5. 64 5, sudītibhih . . . sre Lsaye . . . vrdhase, or RV. 5 23. 4, esu ksayesu ... dīdihi Geldner seems to have the right sense (with didhyānah)

yad bankiştham nätividhe (TB "vide) sudünü RV. MS. KS TB. AS Both readings make a sort of sense; TB comm natyaniam labhyam But the compound ati-rid is not really Sanskrit, and is properly wanting in the lexicons However, one ms. of MS. has onde

- undra dartā (SV dhartā) purām ası RV. SV. AV The foolish antonym of SV is disproved by RV. 1 130. 10, 3 45 2, 6, 20 3
- [dhāmno-dhāmno rājan VS TS MS KS ŚB AŚ ŚŚ KŚ LŚ ApŚ MŚ MG. So also mss. on AV 7 83 2, emended by RWh to dāmno-dāmno Whitney, Transl, keeps the emendation, tho even Ppp has dh- But Keith on TS, 'from every rule' (ordinance), which is conservative and possible At any rate there is no variant In the preceding verse also the AV mss have sarvā dhāmām muñcatu, emended by RWh to dāmām, the variant KS 3 8, AŠ. 3 6 24 has dhāmno-dhāmna iha muñcatu]
- §108. A little less close to each other are the roots vid and vrdh, which exchange several times, the 'Prakritic' exchange of r and i also comes in here. In the first two variants vid is clearly original, in the last the precedence is less clear.
- mā no vidad (KS vrdhad) vrjinā (KS TB ApS vrjanā) dveşyā tyā AV KS TB ApS Cf Conc under mā no vidad (vidan)
- hotrāvidah (RV. °vida, TB °vrdha) stomataştāso arkaih RV AV MS TB On hotrāvid cf RV 5 8 3; hotrāvrdh is not recorded
- ındrartublır brahmanā vāvṛdhānah TB Ap\$ · ındra ṛbhublır brahmanā samvıdānah \$\$
 - §109. Remoter lexical variants are the following:
- śyenasyeva dhrajato (MS KS dravato) aūkasam pari RV VS TS MS KS ŚB. dravatah is a banal easing up of the poetic dhraj- with śyena; cf RV 1 165 2
- avocāma kavaye medhyāya RV. VS TS MS pra vedhase Lavaye vedyāya (TB ApŠ. MŠ medhyāya) RV KS TB ApŠ MŠ šruikarnāya Lavaye vedyāya AV KS ApŠ
- āpo asmān (MS mā) mālarah šundhayantu (AV MS KS sūdayantu, TS ApŠ šundhantu) RV. AV VS TS MS KS ŠB AŠ ApŠ sūd° is evidently secondary. Note that in AV 20 136 16d the word šuddham of the vulgate is based on mss readings sudam and šunam (Whitney, Index).
- tam tvā bhrātarah suvrdho (HG suhrdo, AV suvrdhā) vardhamānam AV ApMB HG suvrdhā vardho, 'growing with good growth', is original In iIG. there is a slipshod assimilation in sense to bhrātarah ('brothers, friends')
- spardhante dhiyah (TS. KSA divah) sūrye na (SV sūre na, TS KSA † sūryena) wšah RV SV TS KSA In RV., 'Pious thoughts (prayers) vie for him (Soma) as people (vie for) the sun,' poetic but intelligible, is done over in TS KSA, into 'The people of the

sky vie with the sun (seated on Soma as on a steed)' So at least the TS comm., followed by Keith; this however implies emendation of the accent of divah to diváh (ignored by them). If correct, this concept is otherwise apparently unknown, and it is strange that it supplants the familiar notion of 'conflicting prayers' (Bloomfield, Acts 14th Congress Orientalists 242ff, or Johns Hopkins Circulars 25 1ff) The whole verse is obscure.

§110. The rest are obscure if not corrupt.

- apa snehitīr (KS ms snihit, em v Schroeder; SV. snīhitim) nīmanā adhatta (SV. adhad rāh [so divide], KS † nīmanām adadhrām) RV AV. SV KS · upa stuhi tam nīmam (Poona ed snuhi tam nīmanām) athadrām TA—KapS reads snehitī tīmanām athamdrī In RV 'He, the heroically minded, drove away the enemies ' Cf. 1 74 2 Benfey takes adhad as aorist of dhā, and rāh as 'riches' The TA comm. understands snuhi as bhūmau prasrāvaya (root snu), and glosses athadrām by adhodravanasīlam (v. 1 atho, as if atha = adhas+drā') Why these terrible readings instead of the simple version of RV.?
- anāgaso adham it samkṣayema TB · anāgaso yathā sadam it sam kṣiyema Vait Comm. on TB. adham id, anantaram eva; but no adverb adham is otherwise known. It seems to be a nonce-formation = adhā by proportional analogy, on a pattern such as sadā sadam = adhā adham, note that the TB. comm assigns to it the meaning of sadam, 'always' Cf VV I p 195
- upākriam sasamānam yad asthāt (MS sadhasthāt, v l. sad asthāt) AV. TS. KS MS If sadhasthāt is more than a blunder it must depend on upākriam 'fetched from home' or the like
- vanā vananti dhṛṣatā (MŚ. mss dhṛṣadā and dṛṣadā) rujantah RV. TS. JB ŚB MŚ See §60
- ud vanšam iva yemre RV SV TS KB N· ārdhvam kham wa mentre Mbh
- adhā visitah pitum addhi prasūtah KS adomadam annam addhi pramuktah AV And others, §870 adomadam is obscure, we suspect that it contains adas (pronoun).
- [tayā madantah sadhamādyeşu (RVKh VS. sadhamādeşu) RVKh VS MS KS TB And others; §325 Scheftelowitz prints °mādhyeşu in RVKh; but his ms °mādyeşu.]

p and ph

§111. Only in the synonymous roots gusp and gulph Aspiration in the latter may be somehow connected with sibilation in gusp, but the

relation is obscured by other forms such as guph, gumph (Whitney, Roots), see Bloomfield, Hymns of the AV 338, top, where gushiam SB 3 2 2 20 is a mispi int of that text

mano yad asya guspitam (ApŚ gulphitam) MS ApŚ yad asya guspitam (ApŚ gulphitam) hrdi MS. ApŚ visāne vi sya guspitam (some mss and comm gulphitam) AV

p and bh

§112. These sounds vary chiefly in rime-words of nearly synonymous meanings most commonly the roots pr and bhr, in the meanings 'preserve' and 'support' In AV 3 5 4c, $lam\ prij\bar{q}sam\ bahu\ rocamanah$, we must read $bhrij\bar{q}sam$ with Whitney

manas tanüşu bibhratah (TB * Ap\$ * L\$ pipratah) RV VS TB L\$ Ap\$ Kau\$ Both readings in TB, Ap\$.

utem (ŠŠ uto) āšu mānam piparti (ŠŠ bibharti) AV AB GB ŠŠ One ms of ŠŠ piparti, which should perhaps be read even in that text tam piprhi dašamāsyo 'ntar udare ŠG tam mātā daša māso bibhartu ApMB HG

ea tvā rāṣtrāya subhṛtam bibhartu AV 13 1 1d, Ppp according to Roth pipartu for bi°, which must be secondary if Ppp has subhṛtam as indicated by Roth's silence. This is just the converse of the following, which concerns three pādas of AV 11 5 (1d, 2e, 4d) sa ācāryam tapasā piparti (Ppp bibharti),

sarvān sa devāns tapasā piparti (Ppp bibharti), and

śramena lokāns tapasā piparti (Ppp bibharti), all AV. and Ppp

§113. There are also two interchanges of the partly synonymous roots yup and lubh, the former being original both times, see Bloomfield, AJP 12 414ff ·

samyopayanto duritāni viśvā RV MG samlobhayanto duritā padām AV ayupitā (ApŚ. alubhitā, and once āyupitā by misprint, see Errata to Vol. 2) yonih MS ApŚ MŚ

§114, Finally two miscellaneous cases

agner jıhvāsı suhūr (VSK TS TB subhūr, KS supūr) devebhyah (TS TB devānām) VS VSK TS. KS TB SB SS suhū, 'calling enticingly,' fits jihvā best

yā sarasvatī varšambhalyā (ApŚ °balyā, vv ll °phalyā, °bhalyā)

TB ApŚ The true form, derivation, and meaning of this epithet
are unknown TB comm has a fatuous explanation

ASPIRATE MUTES AND H

§115. That there was in Vedic times, as in Prakrit, a tendency to reduce aspirates to h is indicated e g by Wackernagel 1 §218 Nearly all our cases concern bh and h; and a majority of these, again, the single root grah (grabh) Any rule as to early phonetic interchange between these two forms of the root (Wackernagel, I. c., p 252) is cheerfully neglected. The same school or the same text will use grabh in one place and grah in another, under like conditions. The popular texts, AV and most of the Grhya Sūtras, seem to like grah a little better, but they are not consistent, they are merely moving in the direction of Classical Sanskrit, with which they are in other respects more closely affiliated than the hieratic language. Perhaps the same preference may be discernible in TS and KS RV and other archaizing texts—seemingly including VS, MS, SB, and ApMB—and the RV, sūtras prefer grabh on the whole. But really the one stable factor is inconsistency.

bh and b

§116. We begin with bh and h, which includes grah: grabh and with it nearly all that may have historical significance First, grah and grabh grbhnāmi (AV. HG gṛhnāmi) te saubhagatvāya (ApMB HG supra-jāstvāya) hastam RV. AV AG SG SMB PG HG ApMB MG

jagrhmā (RV jagrbhmā, TB jagrbhnā) te dal. sinam indra hastam RV SV MS TB Svidh In VV I p 252 we have suggested that the form jagrbhnā (comm vayam grhītavantah) may have been a 1st person subjunctive [In the ms of this section Bloomfield wrote. 'If this startling form is more than an old and inexplicable blunder, it seems to contain dissimilation of m to n after the labial aspirate' I myself am now inclined to see in it only a sort of confused blendform, jagrbhmā (in which -mā is the 1st plural ending) of RV is stupidly altered to -nā with thought of the present infix in forms like grbh-nā-ti —F E]

na hy asyā (ApMB asyaı) nāma grbhnāmi RV ApMB : nahı te nāma jagrāha AV

hıranyapāvāh pasum āsu (SV apsu) grbhnate (AV.† grh°) RV. AV SV sanlā (AG. ApMB HG. MG °lā te) hastam agrabhīt (AV SMB MG °hīt) AV. AG SG SMB ApMB HG. MG : devas te savıtā hastam grhnātu AV.

ıdam rādhah pratı grbhnīhy (JB. grhnīhy) añgırah AV. GB. JB \$\$ bhagas te hastam agrabhīt (AV. °hīt) AV \$G. ApMB

- agnış te hastam agrabhīt (SMB °hīt) SMB ApMB. HG
- aryamā (ApMB. °mā te) haslam agrabhīt (SMB °hīt) ŚG SMB ApMB osadhayah prati grbhnīta (TS KS grhnītāgnim etam, MS MŚ grbhnītāgnim etam) VS VSK TS MS KS ŚB MŚ
- nākam grbhņānāh (TS KS grh°) sukrtasya loke VS TS MS KS SB agne brahma grbhnīṣva (MS MŚ grhnīṣva, KS grhīṣva) VS MS KS SB MŚ
- apo devīr (VS SB devā) madhumatīr agrhnan (MS KS agrbhnām, VS SB agrbhnan) VS TS MS KS SB ApS
- āpo devīh pratigrbhņīta (TS KS Apچ°gṛhnīta) bhasmaitat VS TS MS KS ŚB ApŚ MŚ
- devo vah savitā hiranyapānih prati (MS MŠ °pānir upa) grhnātu(VS ŚB pratigrbhnātv , VSK °vah savitā pratigrhnātu .) VS VSK TS MS KS ŚB TB ApŚ MŚ
- adıtıs te (VS MS SB °tış te) bılam grhnātu (VS MS SB grbh°) . VS. TS MS KS SB TA ApS
- tam vo grhnāmy (MS tam te grbhnāmy) uttamam VS TS MS KS SB TA
- prati grhnāmi (MS. TB † AŚ grbh°) mahate vīryāya (MS. KS mahata indriyāya) MS KS TB AŚ—TB. Poona ed text and comm grbh°.
- yasya yonim palirelo grbhāya (HG prati reto grhāņa) ŚG HG vy asya yonim prati reto grhāņa ApMB
- §117. The same variation occurs in the independent but semantically synonymous roots bhr and hr, without other motive than the close similarity in sound. The first two variants in §118 belong also here parāpuro nipuro ye bharanti (MŚ har°) AV VS ŠB AŚ ŚŚ ApŚ MŚ SMB
- rātrīm-rātrīm (VS ŚB* ahar-ahar, AV TS rātrīm-rātrīm) aprayāvam bharantah AV VS TS MS KS ŚB (both) ahar-ahar balim it te harantah AV
- śarma varmedam ā bhara ApMB śarma varmautad ā hara AV viṣnuh sambhriyamānah VS viṣnur upāvahriyamānah TS
- prānāpānābhyām balam āharantī (ApMB ābhar°) SMB ApMB (Other forms, see Conc)
- §118 Next come a number of shifts between the participles -hita (-dhita) and -bhrta (-hrta, cf preceding) Tho quasi-Prakritic as regards both vowel and consonant change, this variation really concerns approximate synonyms Cf also -dhita -bhrta, §175
- hıranye 'smın samāhılāh (HG samābhrlāh) RVKh HG ApMB Scheftelowitz reads 'hrlāh in RVKh

devīr devaih samāhtiāh (TB °bhrtāh) SV TB: devair devīh samāhtiāh RVKh But Scheftelowitz, here also, reads °hrtāh for RVKh'; if this is right the variant belongs in the preceding paragraph alone. gandharvo dhāma vibhrtam guhā sat VS: gan° nāma nihitam guhāsu TA MahānU. And others; §855.

sūryarašmim samābhrtam TS TB. sūryān (p. p. °yāt) šukram samābhrtam MS sūrye santam (KS TA šukram) samāhitam (KS TA °bhrtam) VS. KS ŚB TA.

yad agne pürvam prabhṛtam (AS prahıtam; MS mhıtam) padam hı te TB ApS AS MS

§119. Next we group together a number of cases in which derivatives of the root $bh\bar{u}$ vary with others from $h\bar{u}$ and hu. All are ritualistic epithets compounded with su- or sva-, and in such language these epithets are very nearly interchangeable, one does about as well as another

agner jihvāsi suhūr (subhūr, supūr) devebhyah (devānām), see §114 ekayā ca dašabhiš ca svabhūte (AV cā suhūte) AV VS MS ŠB. TA AS.

SS According to Roth Ppp has cā bhūte, evidently intending cā svabhūte, which is presumably original Vāyu is addressed

ā tvā subhava (AB AS suhava) sūruāva AB KB SB AS SS

samudram na suhavam (AV subhuvas, TB oona ed suhuvam) tasthivānsam AV. TB ApŚ: mahisam nah subhvam tasthivānsam MS— AVPpp reads as MS except subhavas, for which Barret, JAOS 35 46, reads subhuvas. The root hu may be concerned here, despite TB comm (sukhenāhvātum šakyam).

suhutakṛtah stha . . AS : subhūtakṛta stha ApS.: subhūtakṛtah subhūtam nah kṛnuta SS

§120. In two cases—besides the grah grabh variants—the identical word, or a derivative of the same root, appears with bh and h

kakubham (VSK TS ApŚ kakuham) rūpam vrsabhasya (KS rūpam rs°) rocate brhat (VSK brhan) VS VSK. TS MS KS SB (pratikas, ApŚ MŚ)—kakuha occurs already in RV, which does not know kakubha Cf §23

apām gambhan sīda VS SB KS apām gambhīram gacha KS Ap \hat{S} . apām tvā gahman sādayāmi . MS M \hat{S}

§121. Miscellaneous cases

brāhmanebhyo hy anujāātā (TA 'bhyanu") TA MahānU hi (a)bhi asambhavyam (JB asamheyam, perhaps for asamkhyeyam) paiābhavan AV JR

abhi dyumnam (RV. VS sumnam) devabhaktam yanişiha (MS KS devahıtam yanışihya) RV. VS TS. MS. KS ApMB

nābhimrše (MS KS nābhidhrşe) tanvā (TS tanuvā) jarbhurānah (TS MS KS jarhrṣānah) RV VS TS MS KS SB

asmān (MS KS asmān) u devā avatā haveşu (MS KS bhareşv ā) RV. SV VS TS MS KS asmān devāso †'vatā havesu AV

dh and h

§122. Here we find only a few variants They are partly based on familiar phonetic alternates (imperative ending dhi hi, participle hita dhita), partly on lexical changes

nrīnh (MS nrīns) pāhi śrnudhī (SV °hī) girah RV SV VS MS KS SB Cf Wackernagel I p 253

uşnena vāya (ApMB vāyav) udakenehi (SMB GG °naidhi, MG vāyur udakenet) AV AG SMB GG PG ApMB MG ihi edhi, both regulai, the latter obviously secondary

upasthe soma āhrtah (ApMB ādhrtah) RV AV ApMB MG Note archaism in ApMB

ye bhakşayanto na vasüny änrdhuh (TS änrhuh, MS änasuh) AV TS MS Whitney (Roots) rubricates änrhuh under arh The obscurity of the passage makes it impossible to say whether this is right or whether it is a phonetic form of änrdhuh, see Whitney's note on AV 2 35 1 and Keith on TS 3 2 8 3

grdhrah sıtıkakşı vardhranasas te duvyah (KSA ms varhinasas te 'dutyah)
TS KSA Von Schroeder emends to vardhrı', questionably, see
Edgerton, Studies in Honor of Hermann Collitz 28, and above §23

harşamānāso dhṛṣitā (TB °atā) marutvah RV TB N harşamānā hṛṣitāso marutvan AV Three mss of AV dhṛṣitāso, Ppp ms ṛṣamānāso ṛṣadā, for which Barret, JAOS 35 59f, reads dhṛṣatā The form hṛṣit sobviously suggested by the preceding harṣa usrāv (VSK KS usrā) etam dhūrṣāhau (VSK MŠ °vāhau. KS °bādhā)

. VS VSK TS KS ŠB MŠ

gh and h

 $\S 123$. We find only a few cases, which seem on the whole to concern phonetic reduction of gh to h

arghah HG arghyam SS HG arghyam bhoh Kaus arhanīyā āpah ApG See §321, end arh = argh

angharir (SS anharir, all mss) ası bambharih VS TS MS KS PB SS LS The word is obscure, but SS looks like a phonetic reduction

somam le krīnāmy ūrjasvantam payasvantam †vīryāvantam abhımātışāham

(KS vīryāvantam bahvargham sobhamānam) TS KS: somavıkrayın somam te krīnām mahāntam bahvarham bahu sobhamānam MS am ghed agnır vṛdhāvatı RV TS: tam hed agnır vṛdhāvatı MS Particles gha and ha

nīram hı (read avīraghnī?) vīravatah suševā MG: avīraghno (ApMB† °nī) vīravatah (ŚG vīratarah, HG °tamah) suvīrān (HG suševān) AŚ ApŚ ŚG HG ApMB

kh and h

§124. Only one real variant, which concerns an onomatopoetic word imitating the sound of a frog With this cf asambhavyam (JB asamheyam) parābhavan AV JB, where asamheyam may be for asamkhyeyam; see §121

khanvakhā3ı khaımakhā3ı madhye taduri AV: haımahā3 haımahā3 KS Cf haımahā3 ıdam madhv. SS LS. ApS

CHAPTER IV. INTERCHANGES OF THE MUTE SERIES

1. GUTTURALS AND PALATALS

§125. Interchange between gritturals and palatals is of special interest, because both go back to identical IE sounds, namely value or laborelars, with the exception of the voiceless aspirates which are pecilist. The general rule that palatals appear before IE e, ē, i, ī, and y, much disturbed by analogies even in established words and classes of words, is still further rendered unstable by the more sporadic forms that nostly appear among the variants. Especially VSK affects forms like toroid if or torocomi, yaragori for yanajmi (§§127, 131), etc. It may be observed that in these particular forms VSK is historically regular, the variant forms being analogical. But since VSK also replaces juith y before m when j is an IE palatal, which should never appear as g, it is unlikely that it here preserves unchanged a real prehistoric form. Rather we are dealing with a secondary matter of school oddity. Wackernagel, I §§119ff., especially 121ff., deals fully and ably with the leading aspects of the interrelation of these sounds.

k and c

§125. The variants are not numerous. They occur occasionally in the same word, but more often in words which, while not identical, are available for interchange because of greater or less semantic proximity. Thus, first, in two desivatives of the root cd:

acrānori celo obilizatrikalizam (TB. kelo obhirarnobhodkrum) AV. TB. ā το come vucēvaā (TB. Apš. saketrai) RV. SV. MS. TB. AŠ. ŠŠ. Apš.

The exten below is £7.147., and is doubtless due to confusion between calcus and below, both of which are historically regular. TB. communications when the meaning of the Classical below (perhaps from a, 'pile', rather than cit). The form-below of the second instance is too be sure with different meanings) commoner and more primary than-celou, patterned after the prevalent c forms of the root. Cf. Wachernagel I p. 146, and further Oldenberg on RV. 5. 66.4; Neisser, ZWbch. d. RV., s. v. below. Yet the reading subcluma is evidently secondary.

total (TS. total) printing was as disas part VS. TS. MS. KS. SB. total in Exdey, and analogical.

a

- kanīkhunad wa sāpayan TB: canīkhudad yathāsapam AS c- 1s again analogical; for the intensive reduplication see Wackernagel I p. 147.
- yatraıtān (VS. ApMB °nān) veitha nihitān parāke (SMB. parācah) VS AG Kauś SMB ApMB. HG MG. parā(ñ)c- and its extension parāk-a-
- nū cit (SV. nakih) sa dabhyate janah RV. SV. cit'is, of course, in origin the regular neuter to the stem ka-; but equally of course no consciousness of this relationship can have been present at the time when this variation occurred
- atho adhinkartanam (ApMB ocartanam) RV. AV. ApMB Here the two roots are unrelated. ktt 'cut' and ctt 'tie'. In both the initial sound has been generalized (Wackernagel I p 145). The primary reading of this variant was 'cutting off'; the secondary, 'untying'.
- ima udvāsīkārına .TB. ApS · ımā uddhāsicārına ... MS. See §59
 The MS reading is secondary and poor; it is felt as containing root
 car, as against the original kr

§127. In a class by itself is the curious phonetic treatment of an established root-ending c as k before m in VSK, see §125:

ındrasya (MS. MŚ ındrāya) tvā bhāgam somena tanacmı (VSK tanakmı, MS MŚ somenātanacmı) VS VSK KS ŚB· somena tvā tanacmindrāya dadhı TS. TB ApŚ

g and c

§128. An isolated case concerning unrelated words; the majority reading with c is presumably original.

na vai śvelasyādhyācāre (HG °bhyācārena, MG. °bhyācāre, AG śvelaś cābhyāgāre) AG PG. ApMB. MG

k and ch

§128a. An isolated lexical variant.

chavīm (KSA †kavīn) chavyā TS KSA. The latter is doubtless original, assimilation to the next word in TS, resulting in absurd repetition of the same stem.

kh and ch

§129. Two variants contain forms of khid and chid, identified by Haug, ZDMG 7 517, and hesitatingly by Uhlenbeck, Etym Woch Wackernagel however (I §§121, 131), with most scholars the against Brugmann, denies any historic connexion between kh and ch. See his references §131b, end, and cf Guntert, Reimwortbildungen 23, 32

yatah (MS yena) prajā alhıdrā (MS achıdrā) ajāyanta . TS, MS KS alhıdrāh (ApŚ aghorah) prajā abhınpasya KS ApŚ achınnaputrāh (MS °traḥ) prajā aruvīkṣasva VS. MS ŚB

g and j

§130. The distinction between the two kinds of Sanskrit \jmath (Wackernagel I §§120, 136ff) is such that \jmath from IE palatal g should properly never vary with g, whereas \jmath of the velar (labio-velar) series should appear only before IE e, \bar{e} , ι , $\bar{\iota}$, y Nevertheless \jmath from palatal g produces analogically some g forms (Wack §138), and the velar voiced sound at the end of roots before consonantal endings (usually m and v) is regularly treated as \jmath (Wack §130c) The variants regard all historic distinctions of this sort little or not at all

§131. To begin with, VSK as we have remarked (and in one case SV) shows g for j before m (§§125, 127) This applies equally to both kinds of j (root yuj with velar, roots mij and sij with palatal)

mıtrararunayos tva prasastroh prasisa yunajmı (VSK °gmi) . VS

VSK TS MS KS SB TB APS MS

agnım yunajmı (VSK °gmı) savasā ghrtena VS VSK TS MS KS SB KS ApS MS

agnīşomābhyām juştam ni yunajmi (VSK °gmi) VS VSK ŠB vājinam tvā vājedhyāyai (TS sapatnasāham, KS vājin vājayatyāyai) sam mārjmi (VSK °gmi) VS VSK TS KS ŠB

vājinīm tvā vājedhyāyai (TS sapatnasāhīm, KS vājini vājayatyāyai) sam mārjmi (VSK °gmi) VS VSK TS KS Corresponding formulas of other schools all with mārjmi, see Conc under vāji tvā upa trā kāmān mahah sasrjmahe RV AV upa tvā kāma īmahe sasrjmahe SV

§132. Besides the above, derivatives of the roots yij and sij show each a couple of variations between g and j

hınvāno mānuşā yugā (SV. yujā) RV SV

dawyam mānuṣā yugā RV SV. VS TS SB mprāso mānuṣā yugā KS dawam mānuṣā yujā MS The SV form of the first variant may be taken with Benfey as instrumental from root-stem yuj In this case both are phonetically normal, as the RV. has a neuter plural of yuga (cf Wackernagel I §128a, d) In the second case also MS may have an adverbial instrumental

dıştaya rajjusarjam (TB °sargam) VS TB

prajūpate vištasrj (MS *srg, mss mostly srk, one srj) jīvadhanyah MS TB AS † 2 14 12c [also in Cone under idam no deva pratiharya havyam, read AS. 2 14.12d] ApŚ —The $\delta \pi \lambda \epsilon \gamma$. rajju° seems to mean 'rope-maker' (TB comm rajjūnām srastūram), and the vocalism of the radical syllable points to an a-stem. Since a-stems from roots in velar j tend to have g (Wackernagel §128a), the root srj is carried away with the rest; of the familiar nomen actionis sarga. The 'historically correct' sarja, occurring here alone, may therefore be secondary. On srj: srg see Wackernagel I pp. 173f, 329. In the second variant srj before j might stand for srl, of. below, §112, brahman tvam asi viśvasrl (°srl).

- §133. Once an intensive reduplication varies between g and j; cf. the same with k and c, §126, kanikhunad etc:
- nı galgalītı dhārakā VS SB . nı jalgulītı (KSA † mss. jalgalūtı, ed em. jalgalītı) dhānıkā TS KSA
- §134. The rest concern miscellaneous words of independent origin: †prajāyāmasy agratah HG. pragāyāmasy agratah PG ApMB.: pragāyāmy asyāgratah MG. Verb forms of pra-gai and pra-jan, the latter obviously secondary, but found in other places besides HG; see Kirste's note
- sadā yācann aham girā (SV. $yy\bar{a}$) RV SV N. Comm on SV. reads girā with RV Since $jy\bar{a}$ is unaccented, Bensey posits a verb-form ('potential optative') of root n, with loss of final m, for * $jy\bar{a}m = *jny\bar{a}m$. Very dubious
- apa (AV. ava) šveta padā jahi AV. AG. SG. PG ApMB HG: apah (most mss apa) švetapad āgahi (so all mss) MG. See §817.
- punar brahmāno (AV brahmā) vasunītha (°nītir, °dhītam, °dhīte) yajñaiḥ (AV. MS KS * agne) AV. VS TS MS. KS. (bis) SB. See §93.

2 GUTTURALS AND LINGUALS

§135. A single stray variant concerning obscure forms in k and d: tekas ca sasaramaṭañkas ca HG: tekas ca sasaramaṭandas ca ApMB. See §165.

3 GUTTURALS AND DENTALS

§136. The variations between gutturals and dentals are interesting, but none too numerous and for the most part difficult or dubious. To some extent they concern final consonants; in one of these cases the ultimate root concerned has a palatal ending, and the variation is really one of sandhi. The majority of guttural-dental variants are levical in character; often the change is in consonant combinations, again bringing in (this time internal) sandhi or assimilation.

k and t

§137. We begin with lexical variants, where we find first the absolutely equivalent rime-roots stabh and shabh; see Bloomfield, IF 4. 74ff; Guntert, Reimwortbildungen 26ff. Among the variants, RV always has stabh, while AV prefers shabh

jagatā sindhum divy astabhāyat (AV asl.a°) RV. AV

mahān mahī astabhāyad (AV KS † aska°) vi jātah AV TS KS AB. AS yam krandasī avasā tastabhāne (AV avatas caska°) RV AV. VS VSK TS ya ime dyāvāprthivī tastabhāne MS KS AVPpp (Barret, JAOS 35 44f)

vy astabhnā (VS ŚB asla°, MS asla°, KS asta°, TS aslabhnād, TA astabhnād) rodasī visnav (°na, °nur) ete RV. VS VSK TS. MS KS ŚB. TA

dıvam skabhāna KS: dyām stabhāna KS

§138. There are few other cases in which k and t, not final, exchange in a purely lexical or corrupt fishion.

stuhi sūram vajrinam apratīkam (TB. apratītam) MS TR The Bibl.

Ind ed of TB. has apratītam, but comm and Poona ed text correctly, apratītam, 'invincible' MS has a mere blunder.

avānyāns tantūn kırato dhatto anyān TB: prānyā tantūns tirate dhatte anyā AV See Whitney on AV 10 7.42

purā jatrubhya (TA ApMB jartībhya, MS. cakrbhyā, p p vaktībhyah') ātīdah (MS °da) RV AV SV MS PB TA KŚ. ApMB See §57.

ugro (HG. ūrdhvo, MG agne) vrājann (MG 'jam) apa (MG upa) sedha (AV vrāksva) šatrūn (MG. šakram) AV. ApMB HG MG §139. Next a group of cases in which the combination tt varies with kt (and occasionally with other consonants before t), cf. §416, to which all these viriants also belong

n no rāstram unattu payasā svena TB. sam te rāstram anaktu payasā ghriena AV. For n-unattu cf RV 1 164 47, 5 83 8, for samanaktu, RV. 10 88 4, 118 4 The variation is lexical, hardly phonetic

devair nyuptā (KS. nuttā, AV uktā) vyasarpo mahitvā (AV °tvam) AV KS ApŠ MŠ 'Cast forth (KS impelled, AV spoken') by the gods thou (earth) hast spread out greatly (to greatness)' Ppp reads mahitvā, and also srṣṭā for uktā, seemingly an ancient gloss which states in plain language what all the texts really mean

anyām icha prirşadam vyaktām (ApMB. mitām) RV ApMB jāmim icha prirşadam nyaktam (read °tām) AV. Here the assimilated form of ApMB (with samprasārana) is clearly secondary

- sarvān it tān anu vidur vasisthāh RV.: sarvam uktam anutudur tasisthāh BB. A more drastic reconstruction or Verballhornung in JB.
- tha prasatto (AV prasatto, TB. prasapto) in cayat kṛtam nah RV. AV. MS. TB. prasapto (comm prakarṣena samāgatah san, is if from pra-srp with Prakritic a for r) has no standing. AV, tho also secondary, makes fair sense, 'attached'; RV. probably 'gracious', in the sense of the later prasanna
- viviktyai (TB vivityai, read with Poona ed vivityai) liattāram VS TB.
 viviktyai, 'for discernment', is certainly original TB comm.
 višesa-lābhābhimāninyai: but the form of root vid is isolated if vi
 be regarded as the preposition, and anomalous if it be taken as
 reduplication
- dhātuh katkaļah (KSA kakkaļah) TS KS Original form unknown; VS 24 32 has kakkaļa
- avımuktacakra (v. 1 °rā) āsīran PG.: vivrttacakrā āsīnāh HG ApMB.
- §140. There are also several cases of variation between k_s and t_s , reminding us of the fact that both these combinations become ch in the Middle Indic languages, and to some extent in Vedic dialects, see below, §§183ff These variants indeed really belong in that chapter; they manifestly concern the pronunciation of both combinations as something verging on ch In five out of six cases the writing with k_s (thrice in SV., once in AV, once in MS.) is secondary, and in three it is more or less foolish, if not utterly uninterpretable
- vṛṣanam pṛṭsu (SV. pṛkṣu) sāsahim RV. AV. SV. Here only pṛṭsu, 'in battles', can be meant; 'in delights' (root pṛc) is silly.
- yat te ditsu (SV dikşu) prarādhyam RV. SV. The RV. has a nom sg. neut of a desiderative adjective from dā, agreeing with manas SV clearly secondary and poor (Benfey, 'in aller Welt')
- yad ditsasi (SV yac chikşası) stuvate māvate vasu RV. SV. In this case the two forms are practically synonyms; silşeyam and ditseyam together in RV. 8. 14 2; a similar passage RV. 1. 81 2.
- agnim (AV agnih) sruco adhvaresu prayatsu (AV. prayakşu) AV. VS TS MS KS Cf. prayaty adhvare, familiar formula in RV. at the ends of pādas (RVRep. 660) Wackernagel I §156a, note, erroneously suggests that prayatsu may be for prayatsu = prayakşu (pra-yaj), but the form does not really construe The hymn AV 5 27, with its miserable corruptions (Bloomfield, Atharvaveda 54), does not call for any serious treatment of prayakşu (the p p leaves it undivided); it is, like most of the SV readings with kş for ts, a phonetic blunder for prayatsu

- āvitsi (MS āyukşı) sarvā oşadhīh RV VS TS. MS KS Roots ā-vidā-yuj
- prāsmān ava prianāsu pra viksu (TB yutsu) RV TB Here, of course, ks is original, yutsu is suggested by prianāsu
- §141. There is also one isolated anomaly in which kn is substituted for tn, somewhat as in the preceding. Here too kn seems to be a phonetic variant or blunder, based merely on similarity of the sound combinations
- tādītnā (TB † °knā) satrum (TB °ūn) na kılā vıvıtse (TB Conc vıvatse, read vıvıtse with Poona ed text and comm) RV TB tādīknā is repeated in the comm (Poona ed), which glosses tādršān! It seems that it must mean simply tādītnā
- §142. Finally, a few cases of interchange between k and t final All concern the ends of padas. Two concern adverbial forms in -k from $a\bar{n}c$ stems, a third is simply a matter of external sandhi
- anamıtram no adharāt (KS °rāk, VSK me †adharāk) AV VSK KS Equivalent adverbs, one abl of adhara, the other acc neut of adharānc The same pair sonantized, below, §145, ottarād adharād (°rāg) ā purastāt
- tad vipro abravīd udak (SS u tat) AV SS See §65
- brahman (MahānU brahman) tvam ası vıśvasrt (MahānU °srt) TA
 MahānU There is a v. l °srt in TA, and as the next sentence
 begins with t, the variant may be graphic Possibly, however,
 srt may be for srt by dissimilatory influence of the lingual vowel r,
 cf. Wackernagel I §156a, note, and as regards the final treatment
 of this root in general, §149a, α [Delete brahma tvam ası etc in
 Conc]
- samyak (TS MS TAA ApŚ * MŚ sam it, KS * sarit) stavanti sarito na dhenāh RV VS TS MS KS ŚB TAA KŚ ApŚ MŚ See §830 sarasvatī tvā maghavann abhiṣnak (TB ApŚ abhīṣnāt) RV AV VS MS KS ŚB TB ApŚ Altho TB comm fatuously glosses by bhiṣajyatu, abhīṣnāt (abhi+iṣnāmi) is doubtless an independent lexical word, 'inspire', into which the phonetic relation of k t enters as a factor While abhiṣnak is äπ λεγ, the word, as well as the treatment of its final consonant (Wackernagel I §138), is primary

Note also yaśo bhagaś ca mā rışat MG 1 9 27c, where Knauer reports that practically all his mss point to rışak as the true reading, of course it must mean the same as rışat Cf Wackernagel I §260a, β , small print. §277a

Cf also AV. 1 18 2a: nir aranım savılā sāvışal padoh, so the vulgate,

but all mss. sāviṣak, retained by SPP. and approved by Whitney; see Whitney, Grammar 151a, and the preceding variant. According to Whitney, the comm and Ppp both have sāviṣat. The same form occurs in the VSK. version of the following, on the subject of final k:t see most recently Renou, Ehrengabe für Wilhelm Geiger 163n; Oertel, ibid. 137; and our §272a, na me tad etc; our §145; and abhiṣyak for eyat, PG. 3. 1. 3b (VV I p. 242, infra).

tasyām no devah (MS tasyām devah) savītā dharmam (VS.† VSK † TS † SB † dharma) sāvīşat (VSK ° şak) VS VSK TS MS. KS. SB.

The next is an error of the Cone:

[trivrd yad bhuvanasya rathavrt TB ApS . trivrd bhuvanam yad rathavrl. KS Cone , but read rathavrl , text ori jivo-]

kh and t

§143. In the single variant following, PG, has a corruption, due to assimilation to the word sakhyāni in the following, Stenzler on PG 2 11 12 translates the AS reading See his note there, and his critical note

parı satyasya dharmanā (PG sakhyasya dharmanah) AS. PG.

g and d

- §144. Except final, this interchange occurs in only a few stray variants. The first may possibly contain a phonetic confusion or assimilation.
- ā galdā dhamanīnām (ApŚ. galgā dhavanīnām) ApŚ. MŚ N. galgā is undoubtedly secondary (by assimilation to the preceding ga-?); galdā is Rigvedic (8 1. 20), but nevertheless obscure Pischel, VSt 1 84, and KZ 41. 183ff, discusses the word without knowing the full stanza in ApŚ MŚ. After him many others, see Oldenberg, Noten, on 8 1 20 The following word in ApŚ. is also a phonetic corruption for dhamanīnām, see §225 Caland leaves the pāda untranslated.

yad annam admı (PrānāgU. agmır) bahudhā mrūpam (etc., §619) AV.
TA PrānāgU.

na van gāvo mangīrasya (KS mandīrasya) KS Vait. MS. Proper names, of unknown etymology

rudras (MS ugras) tantıcaro veşã TB. ApS MS. GG KhG.

marudbhir ugrā ahrnīyamānāh AV . marudbhī rudrāh samajānatābhi TS. Whitney considers ugrā a corruption for rudrā

āsmīnī (KS. ā sīm) ugrā (MS ā samudrā) acucyavuh TS MS KS. ApS. In an obscure ritual verse, MS doubtless a lect fac §145. In the rest the sounds are final (either absolutely, or before pāda endings); as under k.l (§142), matters of external sandhi seem to some extent involved. But it is hard to isolate or define the extent of that influence; it is complicated by lexical confusions and corruptions. The first case is purely morphological, presenting (before a following sonant) the same two adverbs, adharāt and ${}^{\circ}r\bar{a}k$, which we met in §142, first variant.

ottarād adharād (TB °rāg) ā purastāt RV MS KS TB

nıyudbhır (AV. vıyugbhir) vāyav (AV VSK MS rāya) tha tā ti muñca (SS †muñcah) AV. VS VSK MS SB TA AS SS ApS [Add to VV I §§25 and 156] Also:

prayughhya (TB prayud°) unmattam VS TB. In the first of these two viyughhir is untenable, because the niyutah are technically the span of Vāyu (Brhaddevatā 4. 140) In the second, prayughhyah of VS is hardly translatable (not glossed by Mahīdhara, Griffith, 'for Motives') Comm on TB glosses prayud° by prakarşena yoddhidevehhyah, as if from pra-yudh At TB 3 7. 9 1, Ap\$ 12 3 2 occurs prayutah, which TB comm glosses prakarşena somam misrayantah (adopted by Böhtlingk, 'durcheinander mengend'). This idea fits unmattam 'mad', thus favoring the TB reading But PB 1. 2 5 reads maruto for prayuto in the corresponding passage; Caland gives up prayutah.

nrcakṣāh soma uta suśrug (comm., and Poona ed text, śuśrug) astu TB sucakṣāh soma uta sasrud astu MŠ The latter is not quite certain; the mss record forms which look towards the TB reading. But sasrut occurs several times in RV. TB. obviously contains root δru (comm $\delta rot\bar{a}$); so that apparently g=k must stand for d=t It belongs with our §142, and Wackernagel I §§260a, β , note, 277a. See also our §283.

mayum (also gauram, gavayam, meşam, sarabham) te sug rchatu (KS te kşut) VS MS KS SB Mixed lexical and phonetic (sandhi). KS actually reads kşud, before a following sonant

triśug (AŚ °śrud) gharmo vibhātu me (KS gharmas sadam in me vibhāti) KS TB TA AŚ °śrud here is poor and doubtless corrupt

yamasya dūtas ca vāg vidhāvati MS yamasya dūtah svapād vidhāvasi TA The subject is grdhrah 'vulture'; TA is correct, and MS an unintelligible corruption, in which the sandhi relations of $g(\lambda)$ and d(t) have a share

dadhrg (TA. dadhad) vidhalşyan (AV. °lşan) paryañlhayête (TA °tai, AV. parīñlhayātai) RV. AV TA. Roots drh and dhā

\tilde{n} (for k) and n (?)

§146. One variant concerns an obscure name of a gandharva, of which the original form is uncertain; it is obvious that MS. (secondarily) etymologizes on it, changing it to su-rāc 'beautiful-voiced':

sutān nabhrād . MS MS svān nabhrād . . KS : svāna bhrājānghāre . . . VS TS SB : svāna bhrāt . TA.

amāsi sarvān (AS sarvān) asi pravislah AS. Kaus The original is sarvān (sarvānc 'turned in all directions'); AS, secondary.

Guttural and dental aspirates

§147. The few cases under this heading present little of interestgrame vidhuram (HG vikhuram) ichanti svähä HG ApMB Both in wretched hocus-pocus, from which scarcely any meaning can be extracted

aghadvışlā devajālā AV. Kauś . alharvyuşļā derajūtāh ApŚ The latter is a mere corruption

deva purascara saghyāsam tvā TA ApS: detapuras carasa rdhyāsam tvā MS The former is original 'may I be able to carry thee'. MS has a slipshod substitute

yad aghrıyata (KS °yathās) tad ghrtam (KS adds abhatas) MS KS: yad adhrıyata tad ghrtam abhavat TS — As Keith says, the TS etymology is not too bad for a Brāhmana; but the other is certainly original

4 GUTTURALS AND LABIALS

§148. Wackernagel's treatment of this interchange (I §117b) receives additional illustrations from the variants. They almost all concern k and p, and reveal no new principle. For the peculiar Taittiriya treatment (not mentioned in TPr.) of the final sound of the stems anuslubh and trislubh as k(g) in all case-forms except before vocalic endings, and as word-finals in sandhi except before surds (occasionally however k before p), and before j, d, and dh, see Weber, ISt 13 109, in 2, Keith, HOS 18. p xxxviii. This applies to TB as well as TS., but apparently not to ApS.:

anuşlup (TB anuşluk) pañktya (MŚ pañktaye) TB ApŚ MŚ anuşlup (TS anuşluk) pañktyā saha VS TS MS KSA. trişlub (TS trişlug) graişmī VS TS MS KS. ŚB.

§149. The word, of unstable form, which occurs in the next group refers to some kind of aquatic bird; AV 11. 2. 25 adds $pur\bar{\imath}kaya$ (comm. $pul\bar{\imath}$). It may be noted that most forms contain both p and k somewhere in the word — The original form cannot be determined:

- mitrāya kulīpayān (MS pulīkayān) VS MS
- nākro makarah kulīpayas (TS kulīkayas, MS pulīkayas, KSA pulīrayas) te 'kūpārasya (KSA †kūvarasya) VS TS MS KSA
- kulīkā devajāmībhyah VS devānām patnībhyah pulīkāh MS
- §150. Very varied also are the forms of the following words It is impossible to say what the original form is, unless the solitary occurrence of nicumpuna in RV decides It may be onomatopoetic
- avabhṛtha nīcumpuna (TS TB ApŚ nīcankuna, MS KS MŚ nīcunkuna) VS TS MS KS SB TB LŚ ApŚ N
- nicerur ası nıcumpunah (TS TB nıcaākuna, MS KS nıcuākunah) VS TS MS KS SB TB LS In same passage as preceding, nom changed to voc in TS TB by form-assimilation to the adjoining formula
- §151. Other, isolated cases which concern chiefly textual decay, with more or less obscure phonetic bearings, are the following, lexical considerations enter in faintly with some of them
- kanātkābhām (AŠ pranākāphā) na ābhara TB AŠ Note the dental n in AŠ, despite preceding r Comm on TB, desperately, kanakavad bhāsamānām rūpavatīm kanyām Both forms are hopeless bajābojopakāšinī HG khajāpo 'jopakāšinīh ApMB. Again both are hopeless
- kūtanānām (VS ŚB kukūnanānām, MS pūtanānām) tvā patmann ā dhūnom: VS MS KS ŚB kotanāsu (sc te śukra śukram ā dhūnomi) TS An otherwise unknown, perhaps onomatopoetic, epithet of waters
- sam te (AV * sam u, TA sam u te, KS MŚ sam nah) santv anūpyāh (TA anūkyāh) AV KS TA MŚ anūkyāh might be considered a purely phonetic variant, it should be remembered that Tait texts show a certain preference for at least final gutturals in place of labials (§148) The word is an epithet of waters and must mean about the same as anūpyāh, from anūpa, so comm, anūpadeše bhayā anūkyā āpah Formally, however, anūkya is imaginable from the stem anvaūc ('successive'? or 'going along with', approximately 'helping'?), and it is likely that influence from this sphere has been at work in TA
- pūlyūny (ApMB kulpūny) āvapantikā AV ApMB lājān āvapantikā SG. PG. MG. agnau lājān āvapantī SMB HG kulpūny may conceivably be understood in the light of the Tait preference for gutturals, of the prec and §148
- vanakraksam (SV °praksam) udaprutam RV SV 'Sounding in (vessels

of) wood' The onomatopoetic root kraks also in kraksamāna, arakiakṣin SV *prakṣa has no lexical basis and is doubtless phonetic, tho the comm, followed by Benfey, absurdly derives it from pra-kṣi 'abide'.

ansum (AV ansūn) babhasti (ApS. gabh°) haritebhir āsabhih AV. KS. ApS The ApS stanza is otherwise corrupt, and gabh° is uninter-

pretable Caland gives up the verse

grīvāyām (KS grīvāsu) baddho apīkaksa āsanī (MS. apīpaksa āsan) RV. VS TS MS KS ŚB N Original is apīkakse, a certain part of the body MS (p p apī-paksaḥ) may have been influenced by thought of paksa (cf. Keith on TS 1.7 8 3)

visralopa visradāvasya trāsañ zuhomi TS GB. Vait - visloka visradāvye trā samjuhomi srāhā MS visloka is perhaps a sort of leet, fac, but visialopa is itself not clear, cf. Keith on TS 3 3 8 2

§152 The rest concern cases where lexical rather than phonetic considerations dominate, that is, words of independent origin seem more clearly to be involved

agner (ApŚ detā) akrnvann (RV apunann) ušijo amītyaic (RV. °vah, ApŚ amartyaic) RV. MS ApŚ

yad adya dugdham prthwim asrpta (TB. ApŚ asakta, MŚ abhakta) AB TB AŚ ApŚ MŚ. In MŚ, as in AB ...Ś, the parallel following pāda contains asrpad, in TB. ApŚ, asarad

tha prasatio (AV. prasakto, TB prasapto) vi cayat kriam nah RV AV MS TB See §139

krānā (SV prānā) šišur mahīnām RV, SV. And:

kiānā (SV prānā, AV prānah) sindhūnām kalašān acikradat (RV. avīvašat) RV SV AV The SV. is really inexplicable, AV attempts to rationalize it CI Oldenberg, Proleg 279 On the much discussed krānā see last RVRep 136

devair nyuptā (KS nuttā, AV uktā) vyasarpo mahitvā (AV. *tram) AV KS ApS MS See §139

altam (MS MS aptubhī, KS *artham) rīhānā vyantu (viyantu) vayah
TS MS KS * TB MS GG KhG. And others, see §96 The
stem aptu (certainly secondary here) is said to mean 'small' It is
hard to apply this meaning here, perhaps adverbially, 'daintily'

asmın goşihe karişınih (Kaus onah, MS purişınih) AV MS Kaus The rımıng synonyms karişa and purişa, cf Bloomfield, AJP 16 409ff Different context, hence different gender, in Kaus

krıyanta (TB prıyā ta [so dıvıde]) ā barhıh (TB Conc °hıs, Poona ed °hıh) sīda RV AV KS TB Preceded by ımā brahma brahma-

vāhah (TB†°ha) 'These prayers, O thou to whom prayers are offered, are made (TB, are pleasing to thee), sit upon the barhis' [pra so agne tavotibhih] suvīrābhis †tirate (SV TS tarati) vājabharmabhih (SV TS °karmabhih) RV SV TS KS

sugandhım (AV subandhum) pativedanam AV VS SB ApS sugandhım puştivardhanam (KS rayıpoşanam) RV VS TS MS KS SB TAA Vait, LS N The AV changes sugandhım by adaptation to the meaning of pati-vedanam (pati suggests bandhu)

§153. To the same category as the preceding section belong three cases of variation between the roots pr and qr (qir), which have a special interest because in each of the three derivatives of the root yar are closely associated These words are pivotal for the interpretation of the variants The roots yaz and gr go naturally together (sacrifice and praise), and abhi-ar (as in the third variant) likewise goes with yar because sacrifice gratifies the gods (qūrta = Lat grātus), see e.g. RV 1 15 3, 3 6 10, 10 15 6 On the other hand yaz and pr 'give' are perhaps even more constant companions (istā-nūrta), see Windisch, Festgruss Böhtlingk 115ff, Bloomfield, AJP 17 408ff In the third variant abhipūrtam and pūrtam are clearly secondary, suggested by istam which recalls istapurta In the first variant text-history makes it equally clear that gr is secondary In the second, KS seems to give the best sense, but may be a lectio facilior The fact is that the two roots, riming in sound and ritualistically so close in meaning, easily slip over into one another Aside from the matter of rime, they contain little of phonetic significance

ındro yayvane prnate (AV gr°) ca sıkşatı (AV °te) RV AV TB svıştam agne abhı tat prnāhi (PG prnīhı, KS tad grnīhı) KS TB Ap\$ PG HG

ıştam vītam (AV pūrtam) abhıgūrtam (AV °pūrtam) vaşaţkrtam RV AV VS TS MS KSA [Delete in Conc reference to AV under ıştam vītam]

§153a. The following variants, the concerning independent words each of which is suitable to the context, are interesting phonetically as involving the quasi-Prakritic equivalence of k; and ps (cf. §§182–6)

somasya drapsam (AV bhakṣam) avṛnīta pūṣā (AV śakrah) AV TS MS KS Either a 'drop' or a 'draught' of soma will suit, it is hard to see any reason for preference-

hṛtsu kratum varuno (MS °nam) vikṣv (RV apsv, MS dikṣv) agnim RV, VS †TS †MS KS ŚB †

5 PALATALS AND DENTALS

§154. These variants are mostly lexical in character except before y, the combinations dy and y exchange on a purely phonetic basis. A suggestion of a similar 'palatalization' of t before $\bar{\imath}$ or y seems to occur in the first variants quoted under §156

c and t

- §155. Here occur first a number of variations between the approximately synonymous riming roots car and tar'
- yajñasyāyur anu sam carantı (AS tarantu) TS AS CI yajñayur anusamcarān TB ApS
- na tad (AV namam) rakşānsı na pišācāš carantı (VS °cās tarantı, AV °cāh sahante) RVKh AV VS But Scheftelowitz reads RVKh as VS
- achinnam tantum anu sam tarema (TA carema) AV TA Comm on AV car^o
- śamyāh prataratām (Vant °tā) wa (MŚ pracaratām nha) Vant KŚ. ApŚ MŚ
- §156. The rest are sporadic, and partly corrupt; the first two have interesting phonetic aspects
- sā šamtāt (SV. °tā; TB ApŚ °cī) mayas karad apa sridhah RV. SV. TB. ApŚ The TB ApŚ reading (conceived as an adjective agreeing with Aditi, the subject) is apparently felt as modelled on directional adjectives in -ācī, fem to -āūc (like prācī), so, perhaps, the comm understood it (aniṣṭaśamanaprāpikā satī) But it seems at least possible that palatalization of the original dental was not unrelated to the following 2-vowel Cf next
- arcişātrino nudatam pratīcah AV arcişā šatrūn dahatam pratītya AG Here in the secondary AG we have an essentially phonetic change, the reverse of the preceding
- satyaujasā . TS MS. KS sacetasāu . . . AV. See §305 Here we suspect that AV is secondary, with palatalization of ty to c
- agre (TB agne, Poona ed. agre) yajñasya cetatah (RV. śocatah) RV. KS TB.
- vidyām yām u ca (ŠŠ uta) vidmasi AB ŠŠ
- jagdhā vitrsiir (HG vicastir)...HG ApMB And others, see §634 Oldenberg on HG. assumes vitrsii, 'thirst'
- divo vābhisthām anu yo vicaste MS: devānām visthām (ApS† nisthām) anu yo vitasthe VSK TB. KS ApS

- yat kşurena marcayatā (MG vartayatā) sutejasā (AG PG HG ApMB supeśasā) AV AG PG. HG ApMB MG —AVPpp reads varcayatā (varcas)
- vācam (RV AV vātam) viņnum sarasvatīm RV AV VS TS MS ŠB viņnum vācam sarasvatīm KS vācam is secondarily suggested by sarasvatīm, note that KS places it next to that word AV comm also has vācam
- śraddhe kam indra carato vitarturam (TB vicar°) RV TB The latter is perhaps mechanically assimilated to the preceding car-ato Comm regards it as an intensive formation from root tvar! (viśczena tvarā yathā bhavati tathā)
- yuklās tisro vimījah sūryasya PB yunajmi tisro vipīcah sūryasya te (MŚ vivītah sūryah save, or savah) TS ApŚ MŚ Here j as well as c is involved, cf next See §57

j and t

§157. Besides the last variant quoted, we find several miscellaneous lexical variants, the phonetic aspects are faint

śabalı prajānām śacışihā vratam (ApS śavışihā vrajam) anugeşam svāhā PB ApS vrajam hardly makes sense and is clearly secondary

tato yajñas tāyate visvadānīm KS MS tato yajño jāyate visvadānih TB ApS yajñas tāyate is standard, cf eg RV 7 10 2, 9 102 7, 10 90 15 It is interesting that Knauer reports all mss but one of MS as reading tyāyate, a middle stage leading to the lect fac jāyate

devā no yajāam rtuthā (TB ApŚ rjudhā) nayantu VS TB ApŚ yajāam rtuthā is supported by RV 1 170 5, 8 44 8, but in RV 2 3 7 the two points of view blend in rju yakṣatah yajantāv rtuthā. They are in fact nearly synonymous

sam bāhubhyām dhamatı (etc., §853) sum patatraih (KS yazatraih) RV AV VS TS MS KS TA MahānU ŠvetU

c and d

§158. Four cases, all lexical, three with secondary c for d, in the first ucyale is due to assimilation of sense to the preceding vacas somāya vaca udyatam (SV ucyate) RV SV SV MS KS PB Ap\$ girā-girā ca dal şase (KS cal şase) RV SV VS MS KS PB Ap\$ sadā (MS šacyā) pa syanti sūrayah RV SV AV VS TS MS KS SB NpU and other Up One ms of KS has sadyā!

ajaismādyāsanāma ca (AV °sanāmādya) RV AV ca and adya

3 and d

- §159. Here occurs the purely phonetic variant of dy and jy in the roots dyut, jyut (Wackernagel, I §140a). It is flanked by a pair of hyper-Sanskritic readings in which $jy\bar{a}m$ and jman are displaced by $dy\bar{a}m$, and by another case or two in which similar tendencies have had influence.
- sahasrıyo dyotalām (TS TB dīpyalām, MS °rīyo yyotalām) aprayuchan VS TS MS KS SB TB
- ava zyām wa dhanvanah SV Vait Kaus ApMB: ava dyām wa dhanvinah HG See Edgerton, Studies in Honor of Hermann Collitz 29
- upa mann upa vetase VS TS MS KS. SB: upa dyām upa vetasam AV. Vait Kauś The absurd AV reading involves, like the preceding, a sort of hyper-Sanskritism, see Whitney's note.
- pavamānah so adya nah RV VS · pav° svarjanah (suvar°) MS KS TB ApŠ HG BDh In a secondary lect fac, dy becomes j
- ımam (MS ımam ca, VS TS SS ya ımam) yajñam svadhayā (KS AS °yā ca, MS sudhayā) dadante (AS yajante, SS bhajante) VS. TS MS KS AS SS.
- drwyāya dhartre joṣṭre (MS dhātre deṣṭre) VS TS MS KS ŚB Note the palatal diphthong after d, which is however doubtless secondary
- 'ccairvāji pṛtanāṣāṭ (HG 'sāham, ApMB 'vādi pṛtanāji) RVKh HG ApMB If ApMB is correct (v l 'vāji is recorded) it is a hyper-Sanskritic absurdity, no form of root vad can be concerned here prati sma (AV sma) raksaso daha (AV jahi) RV AV
- notes on HG 2 3 7. Both forms seem uninterpretable Oldenberg on HG, 'visiting those who wake (?)', apparently understanding 'jägrtän
- erum tundānā (TS perum tunjānā) patyeva jāyā AV TS Roots tuj and tud are practically synonyms See Whitney on AV 6 22 3, Keith on TS 3 1 11 8, and cf Oldenberg, Noten on RV. 1 45 4 The AV comm reads tunjānā
- mā na āyuh param avaram mānadonash MS: mā nah param adharam (MS tadhanam) mā rajo 'nash (MS nash) TA MS. See §836

j and dh

§160. Only lexical variants

mātā yad vīram dadhanad dhaniṣṭhā (MS jajanaj janɪṣṭham) RV. VS MS KS TB Cognate verb and noun are both altered in MS to suit a more familiar aspect of the mother function, tho the superlative janiş[ha is not otherwise recorded 'when the mother has borne a most prolific son' Cf the following similar variant oşadhībhyah paśubhyo me dhanāyo (TS paśave no janāya) TS KS ApІMŠ.

athāsya madhyam ejatu VS LS athāsyai (TS MS TB °syā) madhyam edhatām (Vait °tu, AS LS ejatu, SS ejatī) VS TS MS SB TB AS SS Vait adhāsyā madhyam edhatām KSA

y and d

§161. This seems a natural place to append two variants between y and d, in the first of which y seems to be secondary, while the second is dubious (yaso seems to make better sense) The phenomenon may have phonetic meaning, continuing the relations between j and d on the one hand, and between j and y (below, §§192f) on the other

sūyavasınī manave (RV TA manuşe, KS mānuşe) dašasyā (TA° sye, TS MS KS yašasye) RV VS TS MS KS ŠB TA

diśo (TB yaśo) yajñasya dalṣināh (TB °nām) TB AS Note that d is followed by i

6. PALATALS AND LABIALS

§162. Only a few cases, hardly showing phonetic tendencies We do not include here cases like kakup (TS kakue) chandah, where the TS reading represents t in sandhi, since they belong under dentals and labials, §178.

tasyās te sahasrapoşam puşyantyās caramena pasunā krīnāmi TS paramena pasunā krīyase (MS krīyasva) VS MS KS ŚB Corruption in TS, see Keith Yet carama is not far from parama in meaning

vīty arşa canışihayā (SV panışiaye) RV. SV See §86 vāyosāvıtra (MS vāyusavıtıbhyām) āgomugbhyām caruh (MS payah) TS MS KSA

7. LINGUALS AND DENTALS

§163 In the main, the Sanskrit linguals are derived from dentals, influenced by neighboring r, r (l, l) or s, whether actually found or historically assumable (Wackernagel I §§145–7) There are also cases of analogical transfer of lingualization (ibid §148a, cf especially §133, note), and also of linguals due to dissimilation (ibid §156a). In some cases, however, it seems that linguals are due to Prakritic influence Namely dentals are often replaced in Prakrit by linguals, without the

influence of any adjacent sound (Pischel, Gram d. Pht Sprachen §§218-25), some dialects show the reverse tendency Especially n becomes n in almost all Prakrit dialects (Pischel §224). The same spontaneous interchanges between dentals and linguals occur in Sanskrit and Vedic under the influence of popular speech, giving rise to Vedic variants with both sounds Classification of the individual sounds is unnecessary since the entire series is subject to the same tendencies. We include also the nasals n and n, except when n is conditioned by the normal rules for lingualization of n (on which see §§945-54)

§164. We shall begin with cases in which there is no reasonable doubt of the lexical equivalence of the forms with dental and lingual, and in which we hold that the lingualization is spontaneous, that is, dialectic, in the same class with spontaneous lingualization in Prakrit Here first we have three cases of $ava\{a=avata,$ the latter each time in RV We may remark that the derivation of this word from an adverb avar (Bartholomae, IF 3 179, approved by Wackernagel I §146a), leaves avata unexplained and seems to us unlikely.

avatasya (SV. avatasya) visarjane RV. SV.

ışkriāhāvam avaiam RV — nışkriāhāvam avaiam TS Ap\$ gāva upāvaiāvaiam (SV. upa vadāvaie) RV SV. VS.

§165. Next, some demonic names in the Grhya Sūtras, in which no influence of liquid or lingual sibilant, and no dissimilation, are at all imaginable, it is simply a case of lingual for dental spontaneously: tekaś ca sasaramaṭankaś ca HG tekaś ca sasaramaṭankaś ca ApMB manthākako (HG mandākako) ha vah pitā HG ApMB

In the following doubtful word, the lingual of MS KapS may be due to the preceding r.

aıdamıdā yavyudhah KS. aılabıdā (MS °mıdā, KapS īlamıdā) āyuryudhah (TS. yavyudhah; MS vo yudhah) VS TS MS. See §241. Cf also ahar (MS. vahad, v 1 vahad, p p vahat) dıvābhır (MS divyābhır) ūtībhıh VS MS ŠB TA ŠŠ LŠ See §§272, 272a

Next an isolated variant concerning the root or roots pan, pan, which we think can best be explained as spontaneous (dialectic) lingualization, cf. Pischal, Ved St 1 199ff For attempts to explain pan as going back to an IE root containing a liquid, see Wackernagel I §172b, note, d, note

sā me satyāšīr devān gamyāj jusļāj jusļatarā panyāt paņyatarā (KS. panyāt panyatarā) MS KS ApŠ Cf Durga on N 6 8 (Roth's Erlauterungen 76 foot).

§166. These are the only clear cases of 'spontaneous' lingualization.

The curious form padbhis which varies twice with padbhis has been explained in this way, this would be more likely if the lingualization were not restricted entirely to the instribular Some obscure lingualizing influence may be suspected, but nothing so far proposed is very convincing. Cf Bloomfield, AJP 11 350ff, Johns Hopkins Circulars, 1906, 15ff, Oldenberg, ZDMG 63 300ff, Pischel, Ved St 1 228ff uro vā padbhir (Kauś padbhir) āhate (Kauś SMB °ta, but Jorgensen

uro vā padbhir (Kauś padbhir) ähale (Kauś SMB °la, but Jorgenser °le) TS ŚŚ KŚ MŚ Kauś SMB

padbhis (ApŠ padbhis) caturbhir akramīt AV ApŠ One ms at AV 3 7 3 also padbhis, but Ppp pad°

§167. In the case of one word the 'correct' form requires a lingual (final of root ιah), and the dental is due to dissimilation from a preceding lingual, see Wackernagel I §156a, who quotes this form, noting that TS has ditya- $v\bar{a}l$ and turya- $v\bar{a}l$ in the same passage where pastha- $v\bar{a}t$ occurs This proves that dissimilation is responsible for t-

pasthavād (TS °vād) vayah VS TS MS KS ŠB ApŠ

paṣṭhauāt (TS °vāc) ca me paṣṭhauhī ca me (MS omits me, twice) VS TS MS KS

§168. Next come a few cases in which it appears that the lingual is or may be due to the original presence of an r-sound or s, in the first variant the dental occurs in a different verb-form where the conditions causing lingualization were lacking, in the others it may be due to dissimilation, since the preceding syllables contain r

grhā mā bibhīta mā vepadhvam (LS ApS HG vepidhvam) VS LS ApS SG HG vepidhvam is an iş-aorist, vepadhvam present

purovāta (KS °to) jinva rāvaļ (KS rāvat) svāhā MS KS purovāto tarsañ jinvar āvīt svāhā TS ApS And similarly other formulas, heginning tapati etc; all in TS 2 4 7 2, MS 2 4 7, KS 11 9, all containing the sacrificial exclamations rāvaļ etc in the same forms A natural assumption would be that the lingual t in MS is due to an originally preceding vocalic t, as in TS (which divides badly, jinvar-āvīt for jinva-rāvīt), the dental t of KS might be due to dissimilation to the initial r But of §632 The words are mere interjections and any form would pass

vilurida (VS °dra, KS °da) vilohita VS TS KS vyalrda vilohita MS Obscure epithets of Rudra, cf TB ati-lirita The original presence of an r-sound, before or after d, seems indicated by VS and MS The dental of TS may again be due to the r of the preceding syllable, thru dissimilation

§169. Finally we come to lexical variants, tapering off into mere

corruptions First, the ritualistic root id and its derivatives are confused several times with more or less similar but independent formatives the SV substitutes the more banal indh, 'kindle' (Agni is the object both times) for id 'revere':

agnim īdīla (SV ındhīla) martyah RV. SV

yam sīm (SV sam) id anya īdate (SV. indhate) RV SV.

The same id figures along with the similar tid (and adjective vidu) in exchange with other similar forms of different etymologies.

- tigmam anīkam vidītam sahasvat AV tigmam āyudham vidītam (KS "dham īdītam) sahasvat TS MS KS In AV. vidītam 'found', is evidently a poor reading for vīdītam, certainly KS īdītam is equally secondary.
- dhişane vīdū (VS VSK vīdvī, KS vīte, MS MS īdite) satī (MS KS MS omit) vīdayethām (MS. MS īdethām) VS VSK TS MS KS SB ApS MS vīdū or vīdvī 'firm'; vīte 'pleasant', īdite 'revered'. KS is the only one that has an adjective not related to the verb, which we take as proof of its secondariness. KapS has īdite īdauethām

§170. The rest are sporadic

- parı no heti rudrasya vzyyāh (VSK °yāl) RV VSK · pari no hedo tarunasya vzyyāh RV heti and hedas are quasi-synonyms See the list of very similar formulas, RVRep 573
- dwo vābhişhām anu yo iicaste MS. deiūnām iisthām (ApS †nisthām) anu yo vitasthe VSK TB KS ApS See §156
- yajñam (KS yajñiyā) yajñam prati delayadbhyah (KS † SS.† °yadbhyah) VSK TS KS SS KS MS The stem deva-yaj (in sandhi °yad) varies with the denominative participle delayat, virtually a synonym, but probably secondary
- sarasaatyā (AV "yām) adhi manāv (KS mānā, v. 1 manā, AV. manāv, SMB Cone vanāva, Jörgensen manāv) acarkrsuh (KS SMB Jörgensen, acakrsuh, SMB Cone carkrdhi, KS v. 1 acark") AV. KS TB ApŠ MŠ SMB PG The original reading is probably that of most texts (low of manu, 'on behalf of Manu'); but the AV (low of manu) is capable of interpretation ('over a luckstone')

asādhāya sahamānāya vedhase (TB mīdhuse) RV. TB. N.

- ghriam duhānā višvatah prapītāh (TB ApMB prapīnāh, AVPpp pravīnāh) RV AV VS. TB ApMB. See §198
- pītā bhāsvaty aņūpamā TA: pītābhā syāt tanūpamā MahūnU. See §\$38 nāvas carantı svasıca ıyānāh VS TS SB nāvo viyantı susıco na vāņīh MS KS
- mā no agnım (p.p agnıh) nirftir mã na āşlān (p p. āşļhām) MS : mā no rudro nirftir mā no astā TA. See §87

In \$\delta\$ 17 12 1 sarvā vinudya samtrdyah (cf critical note, top of p. 276) is suspicious as regards its linguals

8 DENTALS AND LABIALS

 $\S 171$. Interchanges of dentals and labials is rarely if ever purely phonetic. It is chiefly lexical, concerning in large part words which approach one another in meaning, but are etymologically unrelated. It is, however, noteworthy that a very large proportion of these variants concern the voiced aspirates. Possibly a specially close phonetic relation may exist between dh and bh, we may recall that both exchange with h ($\S \S 115ff$, 122)

dh and bh

§172. We shall begin with these, and first of all with the considerable list of variants between the prepositions abhi and adhi. Both of these vary with other prepositions, but far oftener with each other, chiefly on account of their similarity in sound no doubt, tho in some aspects they are not far apart in meaning too

bhadrād abhı (AV Kauś adhi) šreyah prehı AV TS AB KB AŠ SS ApS MS Kauś.

svapnah svapnādhikarane RVKh.: svapna svapnābhikaranena AV brahmādhiguptah (PG brahmābhi°) svārā kṣarāni (PG surakṣitah syām) svāhā AG PG brahmābhigūrtam svarākṣānah MG See Stenzler's Translation of AG 2 4 14 (p 73, n 2), and the critical note on MG 2 8 6

tayor devā adhısamvasantah ApŚ tasyām dəvā adhı samvasantah TS TB yasyām (v 1 asyām) devā abhı samvısantah MŚ

višvāvasur abhi tan no grņātu RV. TA · vīrebhir adhi tan no grņāno etc MS

samānamūrdhnīr abhı (PG adhi) lokam ekam TS MS KS PG tā ekamūrdhnīr abhı lokam ekam AV

trtīye fdhāmāny abhy (VS dhāmann adhy) arrayanta VS TA Mahān U ıdam (PG ımam) tam adhıtışthāmı (PG MG. abhi°) ŚŚ AG MG PG rtasya nābhāv adhı (AV abhı) sam punāmı (AV punāti) RV AV

na vai švetasyādhyācāre (AG švetaš cābhyāgāre, HG švetasyābhyācārena, MG švetasyābhyācāre) AG PG HG ApMB MG.

mä rudriyāso abhi gur vrdhānah (MS abhi gulbadhānah) MS TA mā no rudrāso adhigur vadhe nu (mss nuh) MS

adhı skanda vīrayasva AV . abhı kranda vīlayasva ŚG rşīnām putro adhırāja eşah (AŚ avırāja eşah, AV abhıśastıpā u, VS ŠB abhīsastīpāvā, TB abhīsastīpā ayam) AV. VS TS MS KS ŠB TB AS SMB N

yamo rājābhitişthati (KS MŚ rājādhi^o) KS. TA ApŚ MŚ.

§173. As the roots skabh and stabh were seen to interchange (§137), so the roots sudh and subh, whose conjugations are parallel, interchange freely, without preference on the part of individual texts except that AV. seems to prefer subh (five times); Whitney's Index Verborum confirms this tendency:

tena mā saha šundhata (AV šumbhantu) RV. AV. See VV I p. 239. tāni brahmā tu (AV ApMB brahmota) šundhati (AV. šumbhati; ApMB šansati) RV AV. ApMB

sumbhantām lokāh pitrsadanāh AV · sundhantām etc. VS. MS KS SB. MS · sundhatām lokah pitrsadanah TS. ApS.

sumbham mukham mā na āyuh pra moṣīh AV.: sunddhi (sundhi) siro māsyāyuh pra moṣīh AG PG ApMB. MG.

āpah šundhantu (AV. višve šumbhantu) mainasah AV. VS KS SB TB antaḥ šubhrāvatā (SV. šundhyāvatā) pathā RV. SV.

§174. An interesting extension of the preceding correspondence appears in one case where $s\bar{u}d$, instead of $\hat{s}udh$, varies with $\hat{s}ubh$; this seems to be rooted in the rather standard relations of $\hat{s}ubh$ and $\hat{s}udh$, the latter being replaced by $s\bar{u}d$.

asūšubhanta (TS. TB asūsudanta) yajniyā rtena TS MS. KS TB.

§175. In the remaining variants between dh and bh lexical similarity, to the point of synonymy, continues to enter in largely. Thus in two cases of the participles dhita and bhrta, which must be appraised in the light of the relations of hita and bhrta, §118:

sa tvā rāsirāya subhriam bibhartu (Ppp. pipartu) AV.: sa no rāsiresu sudhitām dadhātu TB

garbha iva (SV. KU, Poley's ed, iiet) subhrto garbhinībhih (RV. sudhito garbhinīşu) RV, SV KU.

§176. Some of the remaining examples show such a degree of synonymy that we might expect a larger number of variants:

dhartāras (ApMB bhar°) te (MG. te subhage) mekhale mā riṣāma SMB ApMB MG

bhakşīmahi (TS. MS. KS Vait. drukşīmahi) prajām işam RV. SV. TS MS KS. PB Vait.

anādhṛṣṭā apasyo vasānāh VS MS KS SB.: anībhṛṣṭā apasyuro vasānaḥ TS. Both mean 'undefeated'.

sam bāhubhyām dhamati (AV. bharati, TS. TA. namati, KS. namate, MS -bhyām adhamat) sam patatraih (KS. yajatraih) RV. AV. VS TS. MS KS TA. MahānU. ŠvetU.

nıkīrya (MŚ KŚ nıgīrya) tubhyam madhye (MŚ madhvah, Vait. tubhyam abhya āsam, KŚ sarvā ādhīh) KŚ. Vait ApŚ MŚ See §47

avilşobhāya (KS °lşodhāya) paridhīn dadhāmi KS. TB ApS. 'For non-disturbance' 'for non-hunger'. KS makes inferior sense

andha sthāndho vo bhalṣīya VS ŚB KŚ. ambhah (TS ŚŚ ambha) sthāmbho vo bha° TS MS KS ŚŚ ApŚ. MŚ MG andhah '(soma-) juice' ambhah 'waters'

bhansaso (ApMB dhvansaso) vi vṛhāmi te RV AV ApMB Here ApMB is meaningless

Aspirate and non-aspirate dentals and labials

§177. There are a few sporadic cases of bh and d, t, and dh and p vi senābhir dayamāno (SV bha°) vi rādhasā RV SV bhayamāno is absurd, since the word is an epithet of Indra Benfey renders 'furchtbar', which it cannot mean

bhūrnım (MS, v l tūrnım) devāsa tha subriyam dadhuh RV, KS ApŠ MS

dhanamjayam dharunam dhārayışnu RVKh bhūmidinham acyutam pārayışnu AV bhūmidinho 'cyutas' cyāvayışnuh AV Quasi-synonyms 'establishing', 'saving'

§178. Ultimately, the not superficially, here belong the variants of *kakup* (representing stem *kakubh*) and *kakuc*, *kakut*, *kakud*, *kakun*, all by regular sandhi for *kakud*. Of these two stems, which are perfect equivalents the of independent origin, TS and TB use *kakubh* only before vocalic endings (cf. Weber, *IndSt*. 13, 109, Keith, *HOS*. 18, p. xxxviii)

kakup (and, trikakup) chandah VS MS KS SB kakuc (and, trikakuc) chandah TS

kakup (TB kakuc) chanda ihendriyam VS MS KS TB

apām napād āšuheman ya ūrmih kakudmān (MS ūrmih pratūrtih kakubhvān , KS ūrmih pratūrtih kakudmān) TS MS KS. devīr āpo yo va ūrmih pratūrtih kakunmān . VS VSK SB brhaty uşņihā kakup (TS kakut) VS TS MS KSA

d and b

§179. A single variant between dulā and bulā, both obscure; applied to fire-bricks

ambā ca bulā ca MS. MŠ · ambā dulā TS , cf ambāyar svāhā dulāyar svāhā TB 3.1 4 1

Another lexical variant:

abaddham mano .TS KS BDh · adabdham mana (MS. cakşur) ... MS SG.

t and p

- §180. These two sounds interchange in quite a number of cases, usually in words which are near-synonyms, and seldom showing phonetic tendencies
- tiro razānsi asprtah (SV astrtah) RV SV Both mean 'unconquerable'
 The RV version occurs also with accusative asprtam, 8 82 9b
- ye cet pūrva rtasāpah (AV °sātāh) RV AV Cf RV 1 179 2a, ye ced dhe pūrva rtasāpa āsan, which confirms the RV reading, if confirmation were necessary to condemn the unintelligent version of AV ('won by rta', instead of the standard 'tending, loving the rta')
- matsarāsah prasupah (SV ctah) sākam īrate RV SV Epithets of Soma The SV rationalizes desperately a word it does not understand (comm prakarşena sutāh [1], abhişutāh) Benfey, 'zeugend' = pra-su(t), but the comm is right to the extent of connecting SV's word with su 'press' The RV reading is obscure, cf Oldenberg, Noten on 9 69 6 (suggesting a derivative of sup = svap)
- vahnih samiarano (TA sampārano) bhava VS TA Practically synonyms, both 'rescuing'
- devair nyuptā (KS nuttā, AV uktā) vyasarpo mahitvā (AV °tvam) AV KS ApS MS See §139
- yat kşurena marcayatā (MG vartayatā) supešasā (AV MG sutejasā) AV AG PG ApMB HG MG Nearly synonyms See §156 upa (MS utā) no mutrāvarunāv uhāvatam (MS °nā uhāgatam) MS TB
- mitro (VS vipro) babhūva saprathāh RV VS TS MS TA
- sacelasāv (VSK °sā, delete 'MS.' in Cone) arepasau VS VSK ŚB · sacelasau sarelasau TB samokasau sacelasā arepasau MS . samokasāv (KS °sā) arepasau TS KS Kauś The TB. has a lect fac. to match samokasau which immediately precedes sacelasau (comm. ekakarmapravarlakau bhūtvā)
- yo gopā apı (TB ApS gopāyatı) tam huve RV AV TB ApS The denominative verb makes the same sense as the noun with copula 'understood'
- suśevam somapitsaru (TS sumatitsaru) VS TS MS KS ŚB VāDh suśīmam somasatsaru AV—Ppp (Roth) suvešam (intending suśevam) somapitsalam For suśīmam, Whitney 'well-lying', but

It is a mere corruption Whitney and Keith regard the TS reading as the correct one; in that case the reading "pitsaru would contain dissimilation. But it is improbable that the isolated TS, has the original reading. With Mahīdhara, somapi may be taken as 'soma-drinker', and somasa as 'soma-winner' (of pasu-ṣá, priya-sá, both RV.); both would refer to the yajamāna, and the cpd would mean 'having a handle (ready) for the yajamāna' (or perhaps AV. 'having a soma-winning handle').

dhipsyam vā samcakara janebhyah MS aditsan vā samjagara janebhyah TA 'Intending to deccive'. 'not intending to give' Others, §45 āsannişūn hitsvaso mayobhūn RV. AV. TS KSA MS N: āsann eṣām apsuvāho mayobhūn SV The latter is wholly secondary, see §820

rnān no narnam ertsamānah AV nen na rnān mava it samānah TA nem na rnān rnavān īpsamānah MS In AV desid. of ā + rdh; but comm ecchamānah, which suggests that TA intends iccha (phonetic confusion of its and ch) MS has a synonym, likewise with phonetic confusion of ps and ch

tato na (na tato, na tadā) vicilitsati (vijugupsate) VS VSK SB. BrhU KU IšāU See §45. Here the variation between ts and ps is connected with the approach of both of them to the Prakritic ch; see §182

n and m

§181. There are finally some cases of interchange between the dental and labial nasals. Sometimes this concerns the indicative and subjunctive personal endings mi and ni; these concern verbal inflection and may be found recorded in VV I §\$104c, 118, 119, 124; to §119 should be added the following, omitted there:

pratılāmīti (AŠ °nītı, TS KSA TB pra sulāmīti) te pitā VS TS. MS KSA ŠB TB AŠ. ŠŠ. The verbs concerned are obscure, and evidently taken from popular (vulgar) language

The rest are scattering

agdhād eko 'hutād ekah samasanād ekah TS: adhvād eko 'ddhād eko... sanāsanād ekah MŚ. TS, 'eater of what is gathered' (Keith). Knauer takes the MŚ form as sana + a-sana + ad. Both uncertain Assimilation or dissimilation may be concerned

mademendram (MS maden°) yajamānāh svarkāh VS MS KS. SB. TB Von Schroeder emends KS to maden°, without justification; the opt madema is probably the original form The other, with instr.

- sg madena, is however construable, the pada being then made dependent on the verb of the preceding sentence. Assimilation or dissimilation in MS?
- kad va rtam kad anrtam (SV amrtam) RV SV See Benfey's note in his translation of SV, which is obviously secondary
- jīvam (ApMB jīvām) rudanti vi mayanie (AV nayaniy) adhvare (AV. °ram) RV AV. ApMB Clearly a secondary effort in AV. to make an obscure passage 'sensible'
- abhīmam (TS °mām, MS MS v l °mān) mahınā (VS MS v.l °mā) dıvam (MS dıvah) VS TS MS TA ApS MS In the original the subject is Mitra, who encompasses 'this heaven by his greatness', in the secondary VS mahımā (acc to Mahīdhara, Agni's 'greatness') is made the subject
- jāmim (KS †cami) mā hinsīr amuyā (MŚ anu yā) sayānā KS TB MŚ · mā jāmim moṣīr amuyā sayānām AV The MŚ is clearly secondary.
- akṣānām vagnum (MS †vagmum, AV ganam, read gatnum) etc., AV. MS TB TA. See §832
- puteva putram jarase nayemam (MS ma emam) MS KS ApMB. HG. See \$835
- nen na rnān . TA · nem na rnān .. MS See §180 Particles id and $\bar{\imath}m$
- śūro nṛṣātā śavasaś (SV MS śra°) cakānah (SV. ca †kāme) RV. SV. TS MS

CHAPTER V. INTERCHANGES CONCERNING PALATALS

§182. Here we group a rather miscellaneous assortment of interchanges concerning palatal mutes, and the palatal semi-vowel and sibilant, which do not seem to fit well elsewhere. The regular correspondences between palatal mutes and those of other series (§§126-34, 154-61) contain some similar phenomena; and for the palatal sibilant and semi-vowel exchanging with other sibilants and semi-vowels, see the appropriate sections below. Notably the variations between c and c (§156), and still more those between c and c (§159) and c and c (§161), contain matters similar to the shift between c and c (§153a), and c and c (§180, end) belong with the exchange of all these sounds with c as in the next following sections

1 ch varying with ks, ts, ps

§183. These changes are distinctly Prakritic; cf above, §26, and note the references mentioned in the last paragraph The shift occurs in both directions; when ky etc are secondarily substituted for ch, this is to be regarded as hyper-Sanskritism Confusion often occurs in the mss, so that it is sometimes not certain what a particular text really read in a given passage. As examples of pure blunders in mss we may mention etatsamdah for etac chandah MS. 3, p 22, n 3; āvrchata for ārrisata, ibid 1, p. 18, n 7; itsata for ichata Kaus 73, 15, patsah for pacchah Kaus 82, 29 See further BR. s vy kaputsala, ucchādana The pada paritadam paritsatam, AV, Naks, is read parichavam in many AV. mss; see Lanman's note ap. Whitney; and the Berlin ed reads uchantūnnā maruto ahrtena in 3 12 4, with all of R-Wh.'s mss and most of SPP,'s, the SPP, reads (correctly) ukşantūdnā with three mss and comm. (Ppp , Barret JAOS 32 366, has ul şantūnā, emended by Barret to oudna). Finally-altho the list might easily be extended further-for the pada tena yo'smat samrchātai, TA 2 4. 1c, the mss at MS. 4. 14. 17c read twice (247. 1 and 3) corruptly samrtsātām, which von Schroeder emends to the TA reading -Mention may also be made of Bloomfield's generally accepted etymology of RV Lsu, as for *psu (:paśu), IF 25. 185ff., which implies the same phonetic law

\$184. Most of the genuine variants, which are less numerous than one

might expect from the great confusion shown in the mss, concern λs and ch

- vācaspate vāco vīryena sambhrtatamenāyakṣase (TA "yakṣyase, SS "yachase) MS TA SS Tho āyachase, 'procure', is a possible alternative for the other reading, derived from ā-yaj 'obtain by sacrifice', it is doubtless a mere phonetic corruption See VV I p 29
- somī ghoṣena yachatu (SV rakṣatu) RV SV The preposition ā, found in the preceding pāda, goes with the verbs; ā-yam and ā-tah are here synonyms, 'bring hither' SV is of course secondary, with a sort of hyper-Sanskritic change in phonology
- tām pūṣānu yachatu (AV 'pūṣābhī rakṣatu) RV AV anu-yam 'guīde'; abhī-rakṣ 'protect'. Quasi-synonyms, but since the object is the furrow in plowing, AV is obviously slipshod and secondary, again with hyper-Sanskritic phonetics. The RV. original is much more neat and pointed
- achalābhih (KSA acharābhih, MS atsarābhih in pp, matsarābhih in sp, VS rhṣalābhih) hapiñjalān VS MS TS KSA. In AV. 10 9 23 occurs the form rcharā, with v l rtsarā which is supported by Ppp The word is a name for a part of the horse's body, its original form is quite unknown Note that is as well as kṣ and ch occurs Either is or kṣ, or both, must be hyper-Sanskritic See Edgerton, Studies in Honor of Hermann Collitz 29f
 - §185. For ts and ch, besides the variant last quoted, we find:
- namah krchrebhyah krchrapatibhyas ca vo namah MS KS.: namo grtsebhyo grtsapatibhyas ca vo namah VS TS See §45
- In AV 19 34 2a the mss read mostly jāgrtsyas tripaācāših (v 1. yā gr^c; Berlin ed alsakrtyās, certainly wrongly). For this Ppp reads (with slight corruption, Barret, JAOS 44. 262) yāh krcchrās For the true Saunakiya reading see §192
 - §186. For ps and ch we have noted only this.
- 2chanto 'paridākrtān ApMB īpsantah parijākrtān HG. The two words are of course perfect synonyms. One is reminded of the false identification of the two stems 2cha- and īpsa- by Goldschmidt, Gött Nachr 1874, 525, note

2 sy exchanging with s-c or s(h) plus sibilant

§187. In an interesting little group of variants we find a genitive singular noun form in -sya varying with another form, generally the nominative case of the same noun, ending in a subdant or h, the last

syllable of the genitive ending being represented by the first syllable of a different word (several times the conjunction ca, at other times a longer word beginning in a sibilant) All these cases, of course, involve different word divisions, and so belong to our later chapter on False Divisions Either reading may be at times the older

§188. We quote first the cases containing the conjunction ca, varying with -sya

stomo yajñaś ca (TB yajñasya) rādhyo havişmatā (TB °tah) RV TB
The TB awkwardly detaches stomo from the rest of the pāda, and
makes rādhyo agree with Vişnu, with genitives dubiously depending
on it, comm, yajñana tvam ārādhanīyah—Here the nominative is
the original form, in the next two it is secondary to the genitive

na vai śvetasyādhyācāre (AG śvetaś cābhyāgāre, HG śvetasyābhyācārena, MG śvetasyābhyācāre) AG PG ApMB HG MG In AG the epithet śveta is attracted to the noun ahir in the next pāda. Tho the majority reading is undoubtedly original, AG makes good sense, a snake-king is appealed to, to drive out snakes

ubhāv indrā (SB indro) udithah sūryas ca VS SB aya(h)sthūnam (TS °nāv) uditā (TS MS KS °tau) sūryasya RV TS MS KS The Cone unjustly stigmatizes indro of SB as an error, it is a nom. sing, replacing the elliptic dual indrā (=Indra and Sūrya) of VS to match the complementary nom sing sūryas which follows, of Edgerton, KZ 43 110ff

yad uttaradrāv uparas ca khādatah AV yad apsaradrūr uparasya (ApŚ apsararūparasya) khādati KS ApŚ

§189. In the rest the gentive -sya varies with a nominative in h followed by another, usually a longer word beginning in a sibilant, again the movement may be in either direction

dyumattamā supratīlasya sūnoh (AV supratīlah sasūnuh) AV VS TS MS KS SB The AV secondarily alters the construction, making the epithets nominative to agree with the following, instead of genitive to agree with the preceding Agni is meant both times See Whitney on AV 5 27 1

dhiyā martah śaśamate (SV martasya śamatah) RV SV The SV has an unintelligent and far-reaching revision of the whole half-stanza, see VV I p 164

yaso bhagas ca mā vidat (MG rişat, mss mostly rişat) PG MG yaso bhagasya vindatu ArS Conc suggests bhagas ca for ArS No doubt PG is original ('let glory and fortune find me') But ArS makes yaso object, and since bhagas cannot be accusative, changes it to a dependent genitive 'let him find glory of fortune'

viprasya dhārayā kavih RV: viprah sa dhārayā sulah SV. In SV the stem vipra is attracted into agreement with the epithet sulah, for RV kavih, which is a synonym of vipra and which SV contains in the preceding pāda

somah sutasya madhvah RV: somah sutah sa madhumān SV. Like the prec; the genitives are (so naturally!), made to agree with

somah

yunazmı tısro vıprcah süryasya te (MS vıvrtah süryah save, or savah) TS ApS MS. yuklās tısro vımrzah süryasya PB —MS. is clearly corrupt

mānasya patni šaranā syonā AV.: mā nah sapatnah šaraṇah syonā HG The latter is hopelessly corrupt; Oldenberg follows AV in translating

3. Interchanges of ks, ks, and khy

§190. The closely analogous phenomenon of interchange between kh and s, $k\bar{s}$, is treated by Wackernagel I §118 Our variants, however, are concerned with the combination khy in variation with $k\bar{s}$ or $k\bar{s}$ For the most part the forms involved are derived from the root $khy\bar{a}$ 'see', which regularly in MS, and once in KS., is spelled $k\bar{s}\bar{a}$; of von Schroeder, Introduction to MS, p XLIII In fact the mss vary greatly; but von Schroeder has generalized the spelling in his edition This writing is also known to the grammarians

anukhyātre (KS °kšātre) namah KS. GB Vait KŚ The kś of KS. (both mss) is the more remarkable since it is immediately preceded by two parallel forms written -khyā-.

vy akhyan (MS akśan) mahişo divam (AV.* TS mahişah s(u)vah) RV. AV (bis) SV ArS VS TS MS KS SB The mss of MS vary, p p akhyat AVPpp agrees with RV

indra rbhukşā marutah parı khyan (MS ksan) RV VS. TS MS KSA N. All mss of MS here kşyān, p p khyan

anv agnır uşasām agram alhyat (MS MS aksat) AV. VS TS MS. KS SB TB ApS MS. All mss of MS. akşat or akşyat; p p akhyat. But most mss of MS aksat

vikhyāya (MS vikšāya) cal susā tvam VS TS MS. KS SB.

svar abhuvyakhyam (MS MŠ °kšam) jyotur vaišvānaram MS KS MŠ : svar (KhG sur) abhuvyakhyam KS ApŠ. GG KhG

nṛcakṣasam tvā deva soma sucakṣā ava khyeṣam (MS kśeṣam) TS MS duścakṣās te māvakśat (KS text with one ms °kṣat, v l °khyat) MS. KS . tam te duścakṣā māva khyat TS† (so read) Whatever be the

writing of KS, the meaning can only be that of ava-khyā

§191. In the following the reverse condition is found, the readings with lhy are secondary to ks.

yas te agne sumatum marto alsat (AV alhyat, v 1 alsat) RV AV If akhyat is the true reading, it makes quite good sense ('has seen', for the original 'has attained', a more recondite and difficult form)

viśvākṣam (MahānU °khyam) viśvasambhuvam TA MahānU. No doubt viśvākṣam 'having eyes all over', is the original, but viśvākhyam is felt as a synonym, 'all-seeing'

adhmasyeva prakṣāyatah (ŚŚ prakhyā°) TB TA ŚŚ ApŚ Both TB and TA comms derive from root kṣi with intransitive meaning(!), 'of him perishing like fuel (in the fire)', and similarly Caland on ApŚ Better from pra-kṣā (kṣai) 'burning up' In any case the ŚŚ (all mss) form shows phonetic decay; it makes no independent sense

4 j and y exchanging

§192. The interchanges of these sounds are common enough to prove conclusively the genuine phonetic instability between them in the Vedic language, as in Prakrit Cf Wackernagel I §§188b, 140b, and above, our §§156, 159, 161 The change goes in either direction, and often appears in corruptions of the mss, e.g. in AV 3 11 6 several mss read javam for yuvam, and the commevidently had this reading before him. Some of our variants may perhaps fairly be called mere corruptions, and indeed some are eliminated in more recent editions of their respective texts. But when is a corruption a true variant? Note the first case

uto (SS and GB Gaastra, uta) padyābhur yanışthah (AB ja°) AV AB GB SS The Berlin ed of AV also reads janışthah, against all mss There is no doubt that this is the 'correct' form, the word can only mean 'swiftest' But only AB reads so in the mss, while not only AV and its Brāhmana, GB, but the independent SS, have the 'corrupt' reading' Under these circumstances it seems more conservative to keep the reading of the mss, regarding it as a case of dialectic phonology Similarly in the next.

jajñā (yajñā) netasann (read, ned asann, GB Gaastra netar asann) apurogavāsah (avicetanāsah), yajñād eta sann apuro, see §62 Again there is no doubt that yajñā is the 'correct' reading, but j for y occurs persistently in the tradition of various texts

tato ha jajñe (MŠ tato 'ham yajñe) bhuvanasya gopāh (MŠ goptā) TB ApŠ MŠ te·ha jajñe bhu° gopāh PB Here the reverse change has occurred. MŠ, is clearly secondary

- śatam yo nah śarado azītān (SMB Conc azīzāt, comm. azīzanat; PG jīzān) TS SMB PG But Jorgensen reads for SMB. azīzāt; comm azīzād azyāt, aza gatiksepanayoh, gamayatv ity arihah. Three mss of the text read azyāt See VV I p 92f
- saujāmim (SG saujāmim), se tarpajāmi, AG SG Here saujāmim (so v 1 of SG) is doubtless original. It is a n pr
- yajñasya hi stha rtvijā (TB. ApŚ rtviyau) RV SV KS PB AŚ ŚŚ ApŚ yajñasya rtvij- is established from RV 1 1 1 on
- tisro yahvasya (MS MS jihvasya, v l yah°) samidhah parijmanah RV MS ApS MS jihvasya probably corrupt, and certainly secondary
- īśāno m syā (=snyā, TS srjā) drim AV TS MS KS The two forms are synonyms, TS is secondary
- yāgrisyas iripañcāśīh AV 19 34 2a, mss (v l. yā gr°); R-Wh alsahriyās, a bad emendation abandoned by Whitney, see his note Read either yā grisyas, or better yāh (or yāś ca) kriyās Cf §185
- añjanti suprayasam pañca janāh RV MS, 'the five tribes anoint him (Agni), possesséd of good regalement' yuñjanti suprajasam etc, AVPpp 2 74 1 (Barret, JAOS 30 244), 'the five tribes employ him of good offspring' (secondary but not bad Vedic sense)
 - §193. Somewhat remoter are the following
- hrdo astv antaram taj jujosat (TA. tad yuyota) RV. KS TA—TA secondary
- samvatsarasya dhāyasā (AV VS tejasā) AV VS TS KSA HG
- ramayata (KS °tā) marutah syenam āyınam (MS °tah pretam vājınam) TS KS ApS MS
- āšum tvājau (ApS ākhum tvā ye) dadhire devayantah KS ApS MS Corrupt in ApS, Caland translates the KS reading Explained in §296
- ya rte (TA ApŚ ApMB yad rte, PB †yakşate) cıd abhıśrışah RV AV SV PB † 9 10 1a, TA KŚ ApŚ MŚ Kauś GG jarı cetīd (mss cetīd, p p cya it, it) abhıśışah MS (corrupt)

5 Palatal stops and \$(s)

 $\S 194$. There are next a number of cases of palatal stops varying with the palatal sibilant, or once with the lingual sibilant (which varies frequently, as we shall see, with the palatal sibilant, so that this variant may represent the same tendency) But in all cases the lexical element is so marked as to make uncertain the degree to which real sound change enters. The single case of \S is

- abhy arşata (AV. Vait Kaus arcata) suştutim gavyam ājım RV. AV. VS KS Vait ApS Kaus For the favorite formula abhy-arş with sustutim see RVRep. 523ff The AV variant is a lect fac (root stu suggests the synonym arc)
 - §195. The rest concern s:
- pratyañ janân samcukośantakāle N. in Durga (Roth, Erläuterungen 12, n. 4); pratyañ janās tisṭhati sarvatomukhah (Svet U. and Siras U.* tiṣṭhati samcukocāntakāle) VS. Svet U. Siras U. Dhātup has a root kuś 'embrace, enfold', with which Durga's form seems connected
- ayasmayam vicrtā (KS viśrtā, v l °drtā) bandham etam VS TS. MS KS ŚB.: ayasmayān vi crtā bandhapāšān AV. The original vicrtā means loosen thou'. KS. seems felt as 2 plur. from vi-sr 'destroy', but there is no explanation of the plural.
- vistasya devī mṛcayasya (SS. mṛsa°) janmanah AB AS. SS mṛcayasya is rendered 'perishable'; perhaps better with causative force, 'injurious'. SS's mṛsô may well be a corruption, but the word is obscure in either form
- prthivyāh sampreah (MS MŚ. °cas, VS ŚB samspréas) pāhi VS TS MS. ŚB. TB ApŚ MŚ Also: divaḥ samspréas (MS sampreas) pāhi VS. MS. ŚB. The two words are synonyms
- świtro (MS citro) rakşitā AV. MS. TS ApMB. Also świtra (MS citra) addyanām VS MS Again the two words are synonyms Some AV. mss. have citro in the first variant; Ppp. ms śattro, Barret JAOS 32. 370 em świtro.
- yat kşurena marcayatā (MG vartayatā) sutejasā (AG PG HG ApMB supešasā) AV. AG. PG. HG. ApMB MG.
- agre (TB. agne, Poona ed agre) yajñasya cetalah (RV śocatah) RV KS. TB.
- ürdhı acitah (MS. KS. °śritah) śrayadhvam (VS. text †śna°, doubtless misprint tho repeated in comm, which glosses sevadhvam; SB correctly śra°) VS TS. MS. KS ŚB TA. Assimilation to śrayadhvam in MS. KS
- mṛśase (SV. mṛjyase) parase matī RV. SV. The change from (para-) mṛś 'thou dost embrace', to mṛjyase 'thou art purified', is suggested by the following pavase, or by recollection of mṛjyase soma sātaye RV. 9. 56 3.
- chlilipu chlilişate SS: aslılipu slilişate AV (mss; R-Wh. em asislikşum sıslıkşate). Unknown words.
- tanūpāš (TB Conc tanūpāc, Poona ed. text and comm țlanūnapāc) ca sarastatī VS KS TB. The TB (which obviously reads tanū-

napāc) has repeated this word from the preceding pāda, where it occurs as a name of Agni The other reading is clearly original

6 Miscellaneous

- §196. Finally, a couple of miscellaneous variants, in two of which j and h vary, in the other hs and h
- mahnā jinoşi (MS hinoşi) mahini RV TS MS KS ApMB N. Synon-ymous rime-words
- āyurdā (āyuşmān) deva (agne) jarasam (havışo, havışā) vṛnānah (etc), see §854
- duyah kosah samuksitah MS. dauyah kosah (AV devakosah) samubjulah AV. TS KS The MS. reading is a riming corruption

CHAPTER VI LABIAL MUTES AND V AND M

§197. The variants in this chapter are in large part genuinely phonetic. Especially the section on b and v is related to the almost complete confusion between these sounds in the later dialects, and the interchanges of v and m also are rooted deeply in phonetic relations between these sounds. But morphological relations, as for instance the parallel noun suffixes in v and m, are also concerned, and merely graphic corruptions likewise have no doubt played an important part, especially as between v, v, and v

p (once, ph) and v

- §198. Here we have undertaken to separate the cases in which p is the more original, they are listed in the following
- yas tānı (TA MahānU tad) veda sa pıtuh (AV sa pıtuş, most mss pıtuh, TA savıtuh) pıtāsat AV VS TA MahānU yas tā vıyānāt sa pıtuş (TA savıtuh) pıtāsat RV AV TA N 'He shall be Savıtar's father' is an absurd but persistent mouthing over of 'he shall be the father's father', cf Bergaigne 2 104, 108
- abhisaster avasparat (SV avasvarat) RV SV 'Fight away' 'sound away', in either case 'protect' (SV. comm pālayatu) But ava-spar, and not ava-svar, is elsewhere used in this sense; see e.g. RV 10 39 6, 8 66 14
- rtasya goptrī tapasah paraspī (SMB °vī, MG tarutrī) SMB ApMB MG paraspī 'protectress (of tapas)' parasvī (also in some mss of ApMB) may be a case of dissimilation from initial p (comm utkrstadhanarūpā)
- spārhā (TB svāruhā) yasya śrzyo drśe RV KS TB And
- spārho (TB svāruho) deva nayutvatā RV SV VS TB The TB reading is of course secondary, and unmetrical Comm, wobblingly, once susthu ratham ārūdhah, once svasmad eva prarūdhāh
- hıranyaparna sakune PG hıranyavarnah sakunah MU hıranyapalışah sakunıh HG Practically synonyms Contrast darbhath strnüa etc under \$200
- jāmım rivā māva paisı lokāt AV jāmım itvā mā vivitsi lokān TA The AV original 'may I, going to my kin, not fall from heaven' Poona ed of TA reads jāmi mitvā mā vivitsi lokāt (v i lokān)

Its comm regards the second person as addressed to the $yajam\bar{a}na$ (gloss, lapsyasi) But neither reading of TA. really makes sense, the they may contain a mechanical assimilation of p to preceding p

- nākro makarah kulīpayas (TS kulīkayas, MS pulīkayas, KSA pulīrayas) te 'kūpārasya (KSA † kūvarasya) VS TS MS KSA Von Schroeder suggests kūvārasya; certainly rightly. kūvāra and kūpāra are quoted lexically as equivalents for akūpāra 'ocean'.
- nāpa vrījāte na gamāto antam AV nāvaprjyāte na gamāte antam TB. ava-prj is the original, it seems to be a technical term for bringing to an end the warp in weaving Note apa ara also (§201)
- yatrāspṛkṣat (HG yatrā vṛkṣas) tanuvam (AV tanvo, HG tanuvar) yatra vāsah (AV yac ca vāsasah) AV. ApMB HG 'Wherever (defilement) has touched my body or my garment' HG's corruption seems primarily due to the preceding line, yadī vṛkṣāgrād abhyapatat phalam
- yamasya dūtaš ce vāg vidhāvati MS . yamasya dūtah švapād vidhāvasi TA. See §145
- yunajmı tısro vıpıcah süryasya te (MŠ tısro vıvıtah süryah savah, or save) TS ApŠ MS See §57
- ajāśvah paśupā vājapastyah (TB °vastyah) RV. MS TB Comm. on TB, vastyam grham (=pastyam, see RVRep. 58) This, and the lexical statements that vastya means 'house', may be based on corruptions of pastya, but thoughts of the root vas 'dwell' doubtless helped
- yat paśur (Kauś yad vaśā) māyum akrta (Kauś akrata) TS SS. KS. ApS MS SMB GG Kauś A synonym is substituted in Kauś sarpadevajanebhyah (AS sarva) svāhā AS AG. The the restriction
- sarpadevajanebhyah (AS sarva°) svāhā AS. AG Tho the context is different, AS looks suspiciously like a lect fac
- śatāpāṣṭḥādya (read, °ṣṭhā gha, with both Poona edd) viṣā pari no vinaktu TB TA śarā vāṣṭād dhaviṣā vārnah MS See §86
- ghṛlam duhānā viśvatah prapītāh (TB ApMB prapīnāh, AVPpp. pravīnāh) RV. AV VS TB ApMB Barret, JAOS 35 88, would keep pravīnāh, but since this is a late word, it is probably only a corruption
- §199. The one case of ph v concerns a senseless substitution of savam for sapham, some sort of implement:
- īṣām khṛgalyam śavam MS īṣām khagalyam śapham ApS. The corrupt in śavam, MS seems to be correct in khṛgalyam (cf khṛgala, RV), for which ApS has a Prakritic ἄπ. λεγ.

- §200. The v reading seems to be original in the following.
- vysium (SV * pr°) dwah parisrava RV SV (bis) prstim can mean nothing but 'rain', as Benfey translates, perhaps the root prus (which also appears as prs, §680) may have infected the word
- mahyam dattvā vrajata (TAA prajātum) brahmalokam AV. TAA. The TAA. reading, at best a poor infinitive from pra-jan, is an untranslatable corruption Comm takes it for prajātam by Vedic license' yathāpah pravatā yanti TA TU Kaus yathā yanti prapadah SMB See \$60.
- theha vah svatavasah (TA svatapasah) RV MS. KS TA AS. Significant of the growth in importance of tapas, which here crowds out svatavas, a standard epithet of the Maruts
- tve kratum apı vyñzantı viśve (AV apı pyñcantı bhūrı) RV AV. SV VS AA ApS. MS. See §57
- dwyam suparnam vāyasam (AV. payasam, KS. VS TS * SB vayasā, MS TS * vayasam) brhantam RV AV VS TS (bis) MS. SB AS Suparn There is no point in calling the eagle 'milky'; but Ppp. agrees on payasam (twice) Once the AV. comm. has the hardihood to say that payasam is for va° by Vedic license
- payasvan māmakam vacah (AV * payah) RV AV. (bis) KS. In AV. assimilation to preceding payasvan, obviously secondarily But TS TB MS have a further alteration: payasvad vīrudhām payah
- amba nispara (TS. ApS nisvara, KS KapS nisvara, MS nismara, p p nih, smara) VS TS MS KS SB ApS The majority (in which we count MS with m) points to v rather than p, but the word is obscure in all forms
- swarnapakṣāya (MahānU suparna°) dhīmahī TA'. MahānU 'Golden-winged' is doubtless original, see under next.
- darbhaih simila haritaih suparnaih (KS †suvarnaih) KS MS. hotrsadanam haritam hiranyayam AV hotrsadanā haritāh suvarnāh TB ApS suvarna- is certainly original, as AV. shows, cf preceding, and, for the reverse change, hiranyaparna sakune etc., §198
- parivadam parik savam (mss. mostly parichavam) AV Naks · parivadam parik sapam ApMB The variant word must mean 'sneezing', see Lanman ap Whitney The ApMB can hardly be anything but a corruption, one ms has 'vam
- tvam rājāsi pradīvah (VS VSK pratīpat) sutūnām RV VS VSK TS MS KS N See §64
- tam ajarebhir vṛsabhis tava (ApS tapa) svaih RV KS ApS. Followed by tapā tapissha tapasā tapasvān RV. KS, tapa tapasva tapasā tapissha

- ApS, which has clearly changed tava under the influence of this pada Caland understands tapa as a voc., 'O Brennender.'
- sa bhūmim višvato (ArS sarvato) vrtvā (VS. sarvata sprtvā) RV AV. ArS VS TA Comm. on VS vyāpya 'pervading', which is not far from vrtvā 'encompassing'.
- anupauhvad (ApMB. anu po 'hvad) anupahvayet (ApMB anuhvayah)
 HG ApMB In ApMB po intends vo (pronoun), HG is corrupt
 and obscure See §732 There is no real variant here, both forms
 having p
- āñjanena sarpışā sam visaniu (AV. spršantām, Ppp. [acc. to Roth] visanta, TA mršantām) RV. AV TA.
- jakswānsah papwānsas ca visve VS etc; the text of VS. is misprinted as papipānsas, corrected, p XXII]
- §201. In a class by themselves and of notable bulk are the variants between the prepositions apa and ava—So close are they in meaning that it is sometimes hard to decide the relative originality, except in so far as it is indicated by general usage, by the preponderance of one form among the variants, or by the historic relations of the texts in general: nāpa vrājāte (nāvaprjyāte)—. see §198
- ava (AV apa) tasya balam tıra RV. AV. Note that RV has only ava-tı, never apa-tı
- apa (TA. Ap\$† ava) bādhatām durītānī viśvā MS TA Ap\$. Both familiar
- dvışantam me 'vabādhasva (Poona ed 'dhāsai, but v. l. and comm. 'sva) TA: dvışantam apa bādhasva SMB If the Poona ed text is rıght, this should be added to VV I §152
- dhātā samudro apa (AG 'va) hantu pāpam AG PG.
- yat tatraıno apa tat suvāmı AV · yad atraıno ava tat suvāmı TA
- ıdam aham amuşyāmuşyāyanasya pāpmānam ava (ApMB. apa) gūhāmı HG ApMB
- yad avāmīkṣac (ApŚ apā°) chakunih KS ApŚ. MŚ
- yenāpāmṛŝatam (SMB v 1.°mṛṣatam) surām ŚŚ. SMB.: yenāvamṛšatām surām PG
- apa (AV ava) śveta padā jahr AV AG ŚG PG ApMB HG : apah śvetepad āgahr MG
- ābhur anyo 'pa (ApMB 'va) padyatām ApŠ HG ApMB · mātur anyo 'va padyata \$G.
- sarvān ava yazāmahe KS † TB TA ApŠ · sarvān apa yazāması Kaus. ava-yaz is more archaic
- ındur ındum avāgāt (KS avāgan, MŚ upāgāt, v 1 apāgāt) KS. PB TB. ŚŚ KŚ ApŚ MŚ

ava dīlsām asrksata (ApMB. adāstha) svāhā AV ApMB 1yam apa (v 1 ava) dīlsām ayasta SMB

apa kşudham nudatām arātım TB ava sedim trşnām kşudham jahı Kaus

§202. To these obviously belong two interchanges of $av\bar{a}n\bar{c}$ and $ap\bar{a}n\bar{c}$, both of which are contrasted with $pr\bar{a}n\bar{c}$, which makes it certain that $ap\bar{a}n\bar{c}$ is intended, and indeed this should probably be assumed as the true reading in TB in the first case

apāpāco (TB °vāco) abhibhūte nudasva RV AV AB GB TB But Poona ed of TB text and comm. apāpāco, clearly correctly āvus ca prāvus ca prāvīcāpāň (ApŚ cāvāň) ca MS ApŚ

p and m

§203. The few variants under this head are dubious or obscure, except for several cases of exchange between the roots tap and tam A certain phonetic fluidity (or perhaps graphic confusion?) seems suggested by all of them

§204. The roots tap and tam are quasi-synonyms since early times They interchange three times, in two passages, so that tap occurs exclusively in RV. texts, tam in Tait texts

tapasas (TB tamasas) tan mahinājāyataikam RV. TB

mā tamo (AS tapo) mā yajāas tamat (AS tapat), followed by mā yajamānas tamat (AS yajāapatis tapat) TB ApS AS

§205. The rest are sporadic

kşumāsi VS kşupāsi VSK An arrow is addressed obscurely Comm on VS 'shaker', thinking of the Dhātup root kşmā(i), perhaps confused with kşubh- Is VSK influenced partly by kşip?

amba nışpara (nısmara, etc), see §200

yuktās tisro vimījah yunajmi tisro vipīcah (vivītah) , see §57

namo 'gnaye prihwiksite (ChU MU prihwī') lokasprie (MU 'smrie, ChU 'kṣite) TS KSA ApS ChU MU And similarly namo vāyave 'ntarīksaksite , nama ādītyāya (namah sūryāya, nama ādītyebhyas) , each time with MU alone reading lokasmrie All in the same passage There is no doubt that lokasprie is original, Deussen renders MU 'Weltgewahrer', seemingly having 'sprie in mind

āñjanena sarpışā sam visantu (AV spṛśantām, Ppp [Roth] visanta, TA mṛśantām) RV AV TA

apāma edhi mā mṛthā na indra SMB amā ma edhi mā mṛdhā na (AS †ma) indra AS SG See §78

viśva sprdho (AV mrdho) abhimatir jayema RV AV TA

b and v

§206. This wide-spread interchange, tho partly graphic, is largely phonetic, and very common in later times. But it occurs also extensively in early times, applying both to original b and original v, see Wackernagel I §161. The mss are unstable and inconsistent in their writing of the two sounds. There are indeed words like the prepositions v1 and ava, or the roots v1 and v2 and v3, or the noun v1 are presumably never, or at most very rarely, written with b. On the other hand there is scarcely any original b which is not ocasionally written v (pv2 m3, for instance, for pv3 m3. This elusive theme (cf. Grassmann, KZ 12 123) is, perhaps, rather illustrated than cleared up by the Vedic variants. The divergent readings of the printed texts are not to be regarded as 'school' differences, but as illustrations of the total of an unstable and largely untrustworthy tradition.

§207. Nearly all cases are purely phonetic variations, in so far as they are not, possibly, graphic There are only a few which involve real lexical change These are

carmevāvādhus (TB °bādhus) tamo apsv antah RV MS KS TB ApŠ The original avādhus = ava + adhus 'they have put away'. TB understands it as an anomalous root-aorist from bādh 'they have overcome' Poona ed of TB has indeed avādhus in its text, but the comm even there has abādhus, glossing vināśitavantah

devim aham nurtum bādhamānah (TS vandamānah) TS KS ApŚ 'Subduing' or 'praising' the Goddess Destruction TS doubtless secondary, since its own sūtra agrees with KS, but it is natural enough, since the preceding passage ends with 'Homage to Destruction'

yatra-yatra withrto (KS bibhrato) jātavedāh AV KS: yatra-yatra jātavedah sambabhūtha (TB sambabhūva, but Poona ed text and comm tha) TB ApS The form is dubious. The text tradition of AV. (19 3 1) supports bi-, not vi-, mss almost all bibhrto or bibhrato, the the comm reads vi-, and so both editions. All three mss of KS bi- (vv 11 bibhrto and bibhyato). In spite of all this, it seems hardly possible to construe anything but vi-bhrto (note that the accent must be also changed in both texts). Cf next.

atandraso yuvatayo †vibhrtram (TB Conc vibhartram, Poona ed text and comm bibh) RV TB Cf preceding, here we have adjective epithets of Agni (TB comm poşakam, understanding a reduplicated form of bhr)

sakhāyau saptapadāv abhūva (ApMB °padā babhūva) ApMB HG. The

absurd form of most ApMB mss is retained for reasons explained by Winternitz, Introd , xvi.

usrā (MS usrāv) etam dhūrvāhau (KS dhūrbādhā). VSK KS MS Others, §122

yāv (MS KS yā) ātmanvad bibhrto (KS†°tho, AV msatho) yau ca rakṣatah (AV KS °thah) AV. TS MS KS

[tujo yujo vanam (SS. text, balam) sahah AA SS: tuje janā (ArS jane) vanam svah AV ArS This difficult passage only seemingly concerns our theme, since balam is Hillebrandt's emendation in SS]

§208. All the remaining cases concern the same word which appears now with b, now with v, the meaning being precisely the same. There are no school customs governing the sounds as a whole, tho there are some as regards individual words. The variation is about equally common with original b and original v, and in not a few cases it is impossible to be sure which was original. Among indications of greater originality three criteria may be considered, aside from the number and relative antiquity of the texts concerned. First, general prevalence of one spelling in the language as a whole. Second, such prevalence in the older texts. Third, the evidence of etymology. When all are combined, the case becomes quite clear. But especially b is for the most part doubtful historically and etymologically (cf. Wackernagel I §\$158b, 162), so that the variant words whose etymology is certain nearly all contain v

Original v

§209. We begin with forms in which v is certainly or probably original There are no less than nine variants (not all textually certain) containing forms of the root vddh or badh, of which the former seems older (badh not in RV) and remains commoner thru the language. The occasional b-forms met with from AV on are probably in part due to the suggestion of the root $b\bar{a}dh$ (and perhaps of bandh). In several variants, VS texts (particularly VSK) seem to favor badh, but contrary instances occur:

dvisato badho (MŚ vadho) 'si VS KŚ MŚ

mā tvā samudra ud vadhīn (VSK badhīn) mā suparnah VS. TS. MS KS

tvayāyam vṛtram vadhyāt (VSK ba°, VS SB badhet) VS VSK TS MS KS SB

mā me dīkṣām mā tapo nır vadhıṣṭa (KŚ ba°) TS KŚ MŚ abadhıṣma rakṣo 'badhıṣmāmum asau hatah (VSK rakṣo 'muṣya tvā badhāyāmum abadhıṣma) VS VSK ŚB. KŚ avadhıṣma rakṣah TS. MS KS TB ApŚ MŚ

- vīrān mā no rudra bhāmīto (SMB ŠvetU °mīno, Jörgensen °mīto for SMB) vadhīh (TAA SMB. badhīh; but Poona ed of TAA and Jörgensen's of SMB. both va°) RV. TS MS KS TAA. ŠvetU. SMB: mā no vīrān rudra bhāmīno vadhīh VS
- avartyaı badhāyopamanthılūram (TB avartyaı †vadhā°) VS TB (so Poona ed)
- nālārīd (TB °rīr) asya samṛtım vadhānām (TB ba°, but Poona ed. va°) RV TB
- ayanam mā vivadhīr (TAA viba°, but Poona ed text and comm viva°) vikramasra TA TAA.
- Cf. also the following, in which MS is surely corrupt (see §260) Apparently MS MS understand forms of vadh, badh, while TA has a form of v7dh:
- mā rudrīyāso abhi gur vīdhānah (MS abhi gulbadhānah) MS. TA: mā no rudrāso adhi gur vadhe nu (mss nuh) MS
- §210. Another group of seven variants contains the name of the demon Vala, also written Bala from AV. on (under the influence of bala 'strength'?). Aside from the fact that Vala is the exclusive form in RV., the word is probably connected with root vr:
- indro valam (MS balam) rakşıtāram dughānām RV, AV. MS.
- ivam valasya (AŚ balasya) gomatah RV †1 11 5, SV AŚ
- bibheda valam (AV AS balam but many AV. mss valam) bhrgur na sasāhe (AV sasahe) AV SV AS SS
- ud valasyābhınat (but all mss °nas, which read) ivacam ApS ud balasyābhınas (read balasyābhınas) ivacam MS The form abhınas is for abhınat, 2d person imperf, with s for t by analogy with 2d persons in s This curious and interesting form might be recorded in VV I §262; but there is no real variant, the true reading of both texts being abhınas
- yo gā udājad apa (MS api) hi valam (MS balam) vah RV MS indro yad abhinad valam (GB balam, but Gaastra valam with most of his mss) RV. AV SV AB GB
- sa bibheda balam (VS and Poona ed of TB valam) magham (MS madyam) VS MS KS TB.
- §211. There is no doubt that the words for fat, $p\overline{w}as$ etc, have original v, as shown by the cognate languages as well as by the preponderance of v in Sanskrit Nevertheless there are a few b forms, some of them of doubtful textual authenticity.
- pīvo vṛkla udārathih RV KS · pībasphākam udārathim AV. In AV Shankar Pandit prints pībaspākam (comm pīvaspākam, explained

as 'fat-cooking'), and declares this to be the unanimous reading of his authori'ies, which is at variance with Whitney's mss Ppp has $pivass\bar{a}kam$ (Barret, JAOS 30 191, em $p\bar{i}vasp\bar{a}kam$) $ud\bar{a}hrlam$ Cf Whitney on AV 4 7 3, 3 17 3, and Index Verborum of AV under $p\bar{i}b^{\circ}$ and $p\bar{i}v^{\circ}$.

prapharvyam ca pīvarīm VS TS MS KS SB VāDh pībarīm ca prapharvyam AV (comm pīv°, Ppp according to Roth reads like VS etc except prapharvyām)

neva mānse na pībasi AV nawa mānsena pīvari PG —SPP with some mss and comm reads pīvasi in AV, so also Ppp (Barret, JAOS 26 205) PG, tho with correct v, is corrupt otherwise (as if voc sing fem of pīvan)

§212. In the root vrh or brh 'tear', the original consonant is uncertain It has no known etymology, and both b and v are traditionally recorded in RV Wackernagel I §161 regards v as original, on not very substantial grounds. He also points out that confusion between this and the other root brh 'be great' etc., has helped the variation in spelling (cf. §215) Later, brh seems to be commoner in the sense of 'tear'. The two variants recorded amount practically to only one, as they are modulations of the same formula in the same passage. In them vrh is the real reading of all texts, Weber erroneously prints brh- in TS against nearly all his mas

ādītyās tvā pra brhantu (most mss v7h°) TS višvebhyas tvā devebhyah pra v7hāmī KS ādītyebhyas tvā pra v7hāmī MS Add to VV I §312

vasavas tvā pra vrhantu (TS ed bṛh°, most mss vṛh°) gāyatrena chandasā TS ApS

§213 There are five examples, mostly dubious, of vandhura (vandhur) bandhura, RV always spells the word with v Connexion with root bandh is therefore unlikely Bloomfield, RVRep 236, analyzes the word as van + dhura (dhur) 'board at the head of the wagon pole' trivandhuro (TB triban', Poona ed trivan', comm triban') manasā yātu yuktah RV TB (in Conc by error, TS) MS

ā yāhy arvān upa vandhuresthāh (GB AA ban°, but Gaastra and Keith in both van°) RV AB KB GB AA SS

pra nûnam pûrnavandhura (VS SB LS °ban°) RV VS TS MS KS. SB. LS

ratham hıranyavandhıram (TA sahasraban°, but Poona ed text and comm °van°, with v 1 °ban°) RV TA

trwandhurena (KS tribanº) trwytā rathena RV. KS

- §214. In the following isolated cases v is also probably original: rahisthebhir (MS ba°) viharan yāsi (TB pāhi, but comm and Poona ed text, yāsi) tantum RV MS KS TB AS ApS The word can only mean 'swiftest', root vah
- stad brahmann upavalhāması (AŚ apa°, LS upabalıhāmahc) tvā VS AŚ SŚ LŚ The root is ralh, apparently always except here in LŚ It is perhaps a form of 17h, §212
- capyam (TB Poona ed cappam) na pāyur bhisag asya vālah (KS vārah, TB bālah, Poona ed vālah) VS MS KS TB The word means 'sieve' and is regularly vāla, or in the older language vāra The converse of this in the variant kūrkuro bālabandhanah (vāla°), where properly bāla 'child', §215

Original b

- §215. In the following the b form is certainly or probably original The VS texts seem to show a tendency towards v, in spite of their seeming (?) preference for b in forms of vadh (§209) First, three cases in which etymology proves b the older
- savitrprasūtā brhaspataye (PB LS* $\dagger v_T h^o$) stuta GB PB Vait LS. Twice in LS, once printed v_T^o and once b_T^o , but comm both times v_T^o which must be correct (since quoted from PB which has v_T^o).—On the other root $v_T h$, 'tear', see §212
- kūrkuro bālabandhanah (ApMB vāla°) PG ApMB. Both must intend bāla, 'child', probably connected with Russian balovat' 'spoil' (treat as a child)
- ya ābabhūva (PB āva°) bhuvanāni viśvā (PB viśvāh¹, comm viśvāni) VS JB PB SS. Vait Tho PB comm repeats the incredible āvababhūva, it is doubtless corrupt
- §216. In the following b forms are older or more usual, tho the etymologies of the words are unknown
- yad dhastābhyām cakṛma (MS TB TA cakara) kilbiṣāni (TA. kilv°, but Poona ed kilb°) AV MS TB. TA
- višvasmād devakilbisāt AV MS sarvasmād devakilbisāt (VS °kilv°, LS eva kilb°) RV VS MS LS ApS
- kṛte yonau (KS kṛto yonir) vapateha bījam (VS SB vījam) RV. AV. VS TS MS KS SB
- basto (VS vasto) vayah VS TS MS KS SB ApS dhamantı bākuram (JB vā°) dritm RV JB.

Original b or v uncertain

§217. In the rest there seems to be no decisive evidence as to the originality of b or v The VS texts again seem to favor v First, three cases of $padb\bar{\imath}sa$ or ${}^ov\bar{\imath}sa$ 'fetter' It is always spelled with b in RV, which is not favorable to its connexion with Latin vincio (Wackernagel I §161); of Edgerton, Studies in Honor of Hermann Collitz 30, and on the false form ovinsa , JAOS 51 170

atho (LS ApS nır mā) yamasya padbīšāt (VS °vīšāt, LS 7 şadı ınšāt) RV AV VS LS ApS

samdānam arvantam padbīšam (VS MS °vīšam) RV VS TS MS KSA yac ca padbīšam (VS MS °vīšam) arvatah RV VS TS MS KSA Here the sole ms of KS has °vīšam

§218. Two variants contain the word bāna or vāna 'arrow', both Rigvedic In later Sanskrit the v form is commoner yatra bānāh (VS vānāh) sampatanti RV. SV. VS TS AG višalyo vānavān (TS bā°, MS bāņavan. KS bānaiān, NilarŪ vānavān)

uta VS TS MS KS NīlarU
§219. The rest are sporadic, and all concern words of obscure origin māgadhah punšcalī kitavah klībo ... (VSK punšcalī klīvah kitava ...)
te prājāpatvāh VS VSK klība appears to be commoner

dıgbhyo vadabe (KSA vadave) TS KSA badabā and vā° are also found drvāst VS. drbāst KS · drubāst VSK An arrow is addressed, said to mean 'piercing' (root dī)

kṣatrasyolbam (VS TB °vam, but TB Poons ed °bam) ası VS TS MS KS SB. TB ApS MS Both common, RV knows only b (once). vısvarūpā sabalīr (KS savaly) agnıketuh TS KS PG b is commoner

marudbhyo grhamedhibhyo (MS °dhebhyo) başkıhān (MS vaş°, ApŚ bāşkān) VS MS ApŚ Rare and obscure

subīraņa (HG suvīrmah) srja-srja (ApMB adds sunala), and,

śunām agram subīranah (HG suvīrmah) HG ApMB Anomalous name of a dog-demon The ApMB mss are discordant

aulaba (HG. °va) it tam upā hvayatha (HG °ta) HG ApMB In same context as the preceding

bh and v

§220. These variants, few in number, are never purely phonetic but always involve tolerable lexical shifts. From out of the facile interchanges of all prepositions come a small group involving abhi and vi, in most, probably all, of which the abhi forms are prior wisvāny anyo bhwanābhicaste (MS °nā vicaste) RV MS TB. visvānvo

bhuvanā vicaste AV. Cf abhi yo višvā bhuvanāni caste RV, and abhi višvāni bhuvanāni caste RV

devānām visihām (ApS † nisihām) anu yo vi tasthe VSK TB. KS ApS. divo vābhisthām anu yo vi caste MS

mandrābhibhūth (MŚ mandrā vibhūth) ketur TS. TB ApŚ. MŚ asrāmulho rudhirenābhyaktah (TA. °āvyaktah) MS TA. abhyaktah 'smeared', is clearly original TA. comm understands a-vyaktah (not ā-), explaining īdrgjātir iti niścetum aśakyah

§221. The participles abhrlam and avriam exchange in two padas of the same stanza, the original form of which contained both; secondary texts variously assimilate each to the other, see Whitney on AV. 6 125 2.

vanaspatibhyah pary ābhṛtam (MS āvṛtam) sahah RV. AV. VS TS. MS KSA

apām ojmānam parī gobhīr āvījam (AV. ābhījam), same texts SPP with some mss and comm āvījam for AV.

§222. The rest are sporadic.

yamīr yamasya bibhryād (AY vwṛhād) ajāmi RV AV. vwṛhād is unintelligible; it has intruded from the two preceding stanzas where it makes good sense See Whitney's note

ye no dvişanty anu tān rabhasva AV · yo no dvesti tanūm rabhasva MŚ.: yo no dvesty anu tam ravasva ApŚ See AJP 27 413; Caland on ApŚ 7. 17. 2

adrihathāh śarkarābhıs trwiştapı (MŚ tribhrstibhih) KS. ApŚ. MŚ The original means 'Thou hast made thyself firm over heaven with pebbles'. The MŚ assimilates the last word in meaning to śarkarābhis, 'thou hast made thyself firm with three-pointed pebbles'.

bhansaso (ApMB dhvansaso) vi vrhāmı te RV. AV. ApMB. Cf. §176; dhva° has a sort of assonance to bha°.

v and m, phonetic changes

§223. This theme is important both for text-variation, and for the history of Indian dialects. Much is here added to Bloomfield's paper JAOS 13 xcvii ff., and it may be remarked that grammatical treatises since that time (1886) hardly credit the phenomenon with the degree of importance that attaches to it. See Wackernagel I §177 note

§224. The cases which seem most clearly phonetic, in the sense that they defy independent lexical interpretation, are presented first. They are, to be sure, often mere corruptions, but even these contribute their

- mite of evidence to the proof of instability between these sounds First, with original v
- uc chvañcasva (TA chmañ°) prihwr mā nr bādhathāh (TA vr bādhathāh) RV. AV TA And
- ucchvañcamānā (TA ucchmañ°) pṛthwī su tışṭhatu (TA hı tışthası) RV AV TA (To be added to VV I §§116 and 332) See Wackernagel I §177
- susīmam somasatsaru AV. suševam somapitsaru (TS sumatitsaru) VS TS MS KS ŠB VāDh Attempts are made to explain sušīmam as su-sīman, or from root šī with suffix ma, but while some such influence may have contributed, probably the variant is essentially phonetic
- jyog jīvema sarvavīrā vayam tama MG (all mss.) agne sakhye mā riṣāmā vayam tava RV AV SV MS SMB HG ApMB mā riṣāmā vayam tava Vait GB AVPpp (Barret, JAOS 26 278) The formula vayam tava 'we belong to thee' seems to have been mispronounced in MG, was the latter vaguely felt as vocative of an impossible *vayamtama (as if superlative to vayas!)?
- ā tvam (GB ātmam, Gaastra ā tvam with v l ātmam; LS ā svam) indrāya pyāyasva VS TS MS KS AB GB SB AS SS Vait LS (Probably ā tvam is to be read in LS, its edition is very untrustworthy) The converse corruption in Kauś 65 15, where four of seven mss read devā tvā for devātmā
- anamīvāsa idayā (MS anamīmāsā īdayā, but p p °vāsah, idayā) madantah RV MS TB ApŚ anamīmāsa, if correct, might perhaps be a case of assimilation, but it may be only a misprint which escaped the editor's attention The pratīka occurs as anamīvāsah later in MS 4 12 6 (197-8)
- ni dūrašravase vaha (SS mahah, all mss ; ed em vahah) AV SS
- §225. On the other hand the *m* forms are original in the following, the *v* forms being often mere corruptions; of JB pratītam devebhyo justam ha vyavasthāt, where "havyam asthāt is pretty certainly intended ā galdā dhamanīnām MS N ā galgā dhavanīnām ApS dhamanī 'vein' is correct, indeed the whole pāda is corrupt in ApS, see §144
- Possibly thought of dhav(dhu) = dhav 'run' may have flitted thru the mind of the ApS redactor.

 agne yahi datyam mā risanyah (TB datyam vārisenyah) RV MS TB
- Ap\$ Comm on TB vārişenyo mā rīrişah (=mārişanyah¹)
 punar dātām (TA daltāv) asum adyeha bhadram RV AV TA
 them (the two dogs of Yama) today give back happy life' The

preceding pada is $t\bar{a}v$ asmabhyam dréaye sūryāya; perhaps TA's dattāv is contaminated by the preceding $t\bar{a}v$. The comm, at any rate, feels it as 3 dual impv. act. = $datt\bar{a}m$ (dattau prayachatām) There is no accent on $datt\bar{a}v$

- a mā mṛta (MG vṛtat, one ms mṛtam) AG ApMB MG cf. tam mā mṛthah SG mṛta is required 'may he not die'
- sarasvatyā adhi manāv (KS mānā, SMB Conc vanāva, Jörgensen manāv) acarkrsuḥ (acakrsuh, carkrdhi, see §170) KS TB ApŚ sarasvatyām adhi manāv acarkrsuh AV The mss of SMB which read vanāva have simply a phonetic corruption
- rhaspatış įvā (TS KS ApŠ °tıs tvā) sumne ramnātu (TS ApŠ ranvatu) VS TS MS KS SB ApŠ MŠ And
- deva tvaşlar vasu rama (TS. ranva, MS rane) VS TS MS KS SB Here the verb stem ranva of the Tait school is based on the adjective ranva, but surely promoted by the affinity between the sounds m and v. Comm. on TS 1. 3 7 1, ranva ramanīyam kuru See VV I p 121

v and m, lexical variants

§226. Next we come to cases in which the lexical element is more prominent than the phonetic That is to say, taken case by case, these interchanges might be regarded as involving synonymic padas or formulas, in the sense in which they are dealt with in RVRep 553ff Yet, because a large number of such cases persist in showing variation between m and v, there is surely a phonetic basis for even these as a whole

§227. Thus the roots man and van, and derivatives interchange a number of times, beginning with the RV. itself.

sīdantu manuşo yathā RV sīdanto vanuşo yathā RV SV LS In RVRep 60ff the first form is taken to be original. The mental operation at the bottom of the change reappears in the next variant (there discussed), in which, as in nearly all the cases in this paragraph, m is again prior:

manuşvad (TB vanuşvad) deva dhīmahı pracelasam RV. TB

etat tvātra (LS etat tān) pratimanvāno (AS °vanvāno) asmī (AS† LS asmīn) VS. AS SS Vait LS 'Thinking in reply' 'offering, presenting in return'

purutrā te manutām (AV vanvatām) vişthītam jagat RV AV VS TS MS KSA. N. 'Take note of' 'acquire', jagat is subject in RV. etc, object in AV See VV I p 266.

- yat kṣurena marcayatā (MG vartayatā) suteṇasā (AG PG ApMB HG supeśasā) AV AG PG ApMB HG MG 'Injuring' 'moving' In AVPpp we find varcayatā, a sort of vax media, perhaps with thought of varcas, but really of course corrupt
- yuktās tisri vimījah . yunajmi tisro vipīcah (vivītah) , see §57
- §235 In some of the preceding, other changes than this one are made in the words. In the remainder these changes are rather more drastic, so that the phonetic resemblance between the two words becomes much fainter, the variation in these is presumably almost purely lexical, with only the slightest phonetic tinge.
- ā raśmīn (RV raśmīm) deva yamase (TB yuvase) svaśvān (RV TB svaśvah) RV VS ŠB TB Tho TB is secondary, it makes about as good sense as the others, comm raśmīn pragrahān āyuvase ādāya miśrīkuru
- drapsaś caskanda prthwīm anu dyām (RV prathamān anu dyūn) RV AV VS TS MS KS ŠB TA Interesting case of the spiead of dyu in the sense of 'heaven', producing its opposite prthwī in all later texts against RV
- kauberakā viśvavāsah HG miśravāsasah kauberakāh ApMB (probably original)
- avımuktacakra (v 1 °rā) āsīran PG vvvṛttacakrā āsīnāh HG ApMB sa me mukham pra mārkṣyate (ApMB vekṣyatı) PG ApMB 'He will cleanse (enter) my mouth' Probably PG is original
- āñjanena sarpışā sam vısantu (AV sprsantām, TA mṛsantām) RV AV TA—Ppp (Roth) vısanta
- adharo mad asau vadāt svāhā ApMB adharo vad asau vadā svāhā HG † adho vadādharo vada HG ApMB certainly original, the first form of HG unquestionably intends the same, and vad is a corruption or phonetic variant for mad
- vṛ!rasyāsi (KS mitra") kanīnikā (VS SB "nakah) VS MS KS SB MS MG vṛ!rasya kanīnikāsi (VSK "nakāsi) VSK TS ApS Secondary change in KS

anu tvā harmo vrsā (Ap\$ mrgah) AV Ap\$

aşādhāyu sahamānāya vedhase (TB $\,$ mīdhuşe) RV $\,$ TB $\,$ N

mitro (VS vipro) babhūva saprathāh RV VS TS MS TA

pra hansāsas trpalam manyum (SV "lā vagnum) acha RV SV

kalpantām te (TA * me) dišah sarvāh (TA * śagmāh) VS SB TA (both) §236 Deserving separate rubilication are a few cases which involve differences in word-division, or in division of parts of compound words. Here the partially phonetic character of the change seems particularly clear, even if the secondary reading yields good sense

- ulem anamnamuh TS MS AB AS ApS MS: uleva namnamuh KB SB SS KS
- athem ava sya (AV athemam asyā) vara ā pṛthưyāh AV TS. AŚ ŚŚ MŚ The original is ara sya 'set free', AV secondarily brings in the familiar notion of 1yam pṛthưỡ (in genitive form)
- tuvi-svanasam (TS JB tuvis-manasam) suyajam ghrtasriyam RV TS JB. SB. MS The RV supports its reading by numerous instances of tuvi-svan (-1, -as), whereas tuvis- does not occur in compounds
- visvavidam (AV. °vido) vācam avisvam-invām (AV. avišva-vinnām) RV. AV. The AV change is due to preceding visva-vido, see Edgerton, Studies in Honor of Maurice Bloomfield 128
- manmā dīdhyānā ulā nah sakhāyā MS anvādīdhyāthām tha nah sakhāyā TB See the context, quoted VV I p 163; note that the preceding pāda ends in m
- dame-dame sustutir (AV KS °tyā, TS °tīr, MS °tī) vāvīdhānā (AV °nau, AS ŠS vām īyānā) AV TS. MS KS AS. ŠS The sūtra texts mouth over the passage into a sort of nonsensical sense 'good praise (is) going to you two in every house'
- bharatam uddharem anuşıñca (MS uddharema vanuşanti) TB. ApŚ MŚ. The TB comm says that $\bar{\imath}m$ (in uddhara- $\bar{\imath}m$) is for $\imath mam$ chāndaso 'yam mavarnalopah. The corrupt MŚ reading then seems to have a phonetic substitution of v for m
- vatso virājo visabho matīnām AV \cdot pilā virājām isabho rayīnām TB See §359.

v and m in inflectional endings

- \$237. Variations in nominal and verbal inflection elect interchange between acc sing and nom-acc dual, between nom-acc dual and gen plur; between 1st person dual and plural, and so on Similar cases occur among corruptions of the mss, thus in Kauś 60 19 two mss read manthantām for manthantāv, and in Kauś 71 1 all mss anśo rājā vibhajatīmām agnī, where the ed emends imām to imāv
- riena (MG rie 'va) sihūnām (ApMB HG. sihūnāv, MG sihūnā) adhi roha vansa (MG vansah) AV AG. ApMB HG. MG. Kauś Roth quotes Ppp as sihūnā dhi
- aya(h)sthūnam (TS °nāv) udītā (MS TS KS °tau) sūryasya RV TS MS KS For the VS SB form see §188
- putrah pıtarāv (AV °ram) avṛnīta pūṣā RV. AV The original dual refers to the Aśvins, AV has a stupid simplification
- yena strıyam (PG śriyam, SS striyāv) akrnutam (PG °tām, SS akurutam) SS PG SMB GG The SS is secondary and poor

apsarasāv anu dattām rnam yat (TB TA rnām) AV TB TA · apsarasām anudattām rnām MS (p p anu, dattām, rnām) MS is hopeless, see VV I p 282

idam vatsyāvah (AG vatsyāmo bhoh) AG HG See VV I p 249, others on the same page and on pp 263, 276

adhrsiam dhrsnvojasam (SV dhrsnum ojasā) RV AV SV 'Having terrible strength' 'terrible in strength'

v and m in noun-suffixes

§238. On this subject of Bender, Suffixes mant and vant, Baltimore. The variation between mant and vant is there shown to depend on the next preceding vowel, without regard to intervening consonants If that yowel was an a-vowel, the v form is regular, otherwise the m form In prehistoric times perhaps the m form occurred only after u-vowels, cf Sturtevant, AJP 50 360ff, TAPA 60 33ff The difference between this and Bender's formula would concern practically only preceding 2-vowels, and Bender's work shows that after them v is much commoner than after u-vowels, which looks towards Sturtevant's In any case the original conditions are, of course, much confused in the historic texts, and much more so in the later than in the earliest texts Our variants, however, show one or two cases in which an irregular form in an older text is replaced by a regular one later The same conditions appear to apply to other m and v suffixes that are found with mant and vant Variants occur in the readings of individual mss. thus at AV 19 42 3 sutrāmne for sutrāvne, and at Kauś 891 four out of seven mss manvabhih for manmabhih We shall return to this subject in our volume on Noun Formation

§239. We begin with variations of mant and vant (or, once, vin, once, varī)

udyan nahşatram arcıvat (TB °mat) RV SV TB Note that RV also knows arcımat

tapur yayastu carur agnivān (AV KS °mān) wa RV AV KS N agnivān is read by AVPpp; agnimant not in RV This may perhaps be used in support of Sturtevant's theory

pūṣā jāūtimān ŚG · pūṣā jātivin (read jāātī°) Kauś
tṛṭīyasyu savanasya ṛbhumato (ApŚ °syarbhu°) bṛhaspativato (KŚ
°mato) . KŚ ApŚ MŚ The majority show vat after i

ındram ādilyavanlam vājavanlam bṛhaspatimanlam (AŚ °vanlam) vistadciyāvanlam āvaha KB AŚ ŚŚ Here only AŚ has vant,

- and it is doubtless secondary, since the Brähmana text has mant; vant may be due to the influence of the surrounding forms in vant. But of next
- tāsv adhvaryo (SS °yav) . vājavate brhaspatīvate (SS °mate) višvadevyāvate AB AS. SS Here again we might suggest the surrounding vant forms as source of brhaspatī-vate, but this time the older Brāhmaṇa text reads -vate Note that AS belongs to the school of AB., and SS. to that of KB (cf. prec), the two schools seem to have affected different forms
- puṣpavatīh (TS V1Dh. puṣpā°) prasūvarīh (AV KS °sūmatīh, TS °sūvatīh) RV. AV. VS TS MS KS V1Dh The original form has suffixal varī, fem of van; according to any theory it must be judged as unhistoric It is replaced in later texts by the more regular matī, or in TS by the still irregular vatī, which looks like a blend of the other two
- apām napād.. kakudmān (MS kakubhvān) ..TS MS. KS · devīr āpo . kakunmān . VS VSK SB. See §178
- hıranyavad annavad dhehi (ApŚ [read] annamad dhehi) mahyam KS ApŚ See AJP 27 415
- tveṣam cakṣur dadhire codayanvati (RV °mati) RV TB ApŚ Psychologically, tho not formally, this variant belongs here, codayanmati in RV is a compound with the noun mati. 'they made (thee, Agni) a bright eye that inspires devotion'. Later texts conceive the word as containing a suffix, allowing it the v form required after an a-vowel TB comm., accordingly, vidhāyakavākyayuhte (karmanī).
 - §240. The rest concern man and van or related suffixal forms.
- nṛṣadvā (SV. °mā) sīdad apām upasthe (SV apām vwarte) RV SV. sadman (also RV.) is in the mind of SV
- kşıpreşave devāya svadhāvne (TB. °mne) RV TB N. The otherwise unquoted form of TB. plays upon dhāman (sva-dhāman svadhāvan).
- ādītyānām patvānv (PB °mānv) ihi (KSA.† ehi) VS TS MS KSA. PB ŠB TB. MŠ ApMB. Both forms are Rigvedic; cf next
- āyoh patmane svāhā KS. āyoş patvane svāhā ApŚ Cf. prec
- kavīn prehāmi indmane (AV vidvano) na vidvān RV AV Assimilation to vidvān in AV
- mitajñavo varimann (TB °vann, but Poona ed mitajmavo varimann) ā pṛthivyāh RV MS. TB varivan is not recorded, unless here

- varşmā (VS varşımā) ca me drāghımā (TS drāghuyā, KS drāghvā, MS drāghmā, KapS drāghīmā) ca me VS TS MS KS The curious TS form seems to contain in its u a relic of suffixal van
- [āpataye tvā paripataye grhnāmi] tanūnaptre (KS adds šakmane) sākvarāya šakvana (KS šakmann) opisthāya VS KS ŠB tanūnaptre šakmane šākvarāya šakmanā opisthāya MS tanū° šākvarāya šakmann opisthāya VSK In KS the stem šakman is first used as an adjective 'strong', then as a noun 'strength'
- abhikhyā bhāsā brhatā śuśukvanih RV drśe (MS drśā) ca bhāsā brhatā suśukvanih (KS °vabhih, MS suśikmanā) VS TS MS KS ŚB The MS form owes its i to dissimilation or thought of the word śikvan 'able' (RV), the change to m may be due to the feeling that m should occur after a non-a vowel
- avavyayann asılam deva vasma (TB ApŚ vasvah) RV MS KS TB ApŚ Comm on TB explains vasvah as acc sing of an agent noun, vāsayıtāram āchādakam The form is very difficult, but one may think of vasvah as voc of a stem vasvan 'wealthy', agreeing with deva, in which case the accent in TB must be deleted
- prathamāya januşe bhuvaneşthāh (ŚŚ bhūma neşthāh, AŚ ed bhūmaneşthāh) AV AŚ ŚŚ Ppp has $bh\bar{u}m^{\circ}$ The ŚŚ reading makes good sense 'thou shalt lead the world' AV \dot{b} has bhuvane-şthāh

m and b

- §241. The few variations of m and b are related to those of m and v thru the medium of the unstable conditions that govern the relation of b and v. A large number of interchanges between mahat and brhat are not included here, as being too simply and obviously lexical, see, provisionally, the Conc. under these words
- parā dehi šāmulyam (ApMB šābalyam) RV. AV ApMB The bridal garment, defiled after the wedding night, is named here alone šāmulyam, which at least suggests šamala 'stain' Apparently ApMB is influenced by šabala 'spotted' See §607.
- asambādham badhyato (many AV mss ma°) mānavānām (Ppp °veşu) AV. Kauś asambādhā yā madhyato mānavebhyah MS Sense and text tradition require madhyato The form ba° is probably due to assimilation to the preceding -bādham (so Whitney), it is in any case a corruption This is immediately followed by
- yasyā udvatah pravatah samam bahu (MS mahat) AV MS Synonyms, cf brhat mahat, referred to above But the occurrence of b for m twice in one stanza suggests phonetic moments.

andamṛdā yavyudhah KS anlabṛdā (MS °mṛdā, KapS īlamṛdā) āyuryudhah (TS yavyudhah, MS vo yudhah) VS TS MS The belongings of the word in question are entirely obscure; Mahīdhara on VS desperately, 'bringers of food' (bhṛtah')

anuşlub (°tum) mıtrasya, see §412

m and bh

- $\S 242$. The equally small group of m and bh variants is in general purely lexical.
- undra ukthebhir mandişihah (SS. bhand°) SV. SS Cf next; the roots are quasi-synonyms
- dwas (dwah) prsiham (PB prsihe) bhandamānah (PB mand°) sumanmabhih RV PB TA ApŚ Cf prec
- tāsām īšāno bhagavah (MS maghavan) VS TS MS KS. Practically synonyms
- sarvam tam (AV sarvān m, MS KS TA sarvāns tān) maşmasā (TS SB masmasā, MS †mṛsmṛsā, v. 1 mṛśmṛśā, VS bhasmasā) kuru (AV -karam) AV VS TS MS KS ŚB TA The onomatopoetic word found in various forms in the others is made into bhasmasā, as if 'to ashes', in VS
- savıtā bhriyām (KS ms † manyām) TS KS , von Schroeder emends to bhriyām
- acışyāma (p p. amı, for abhı, syāma) vrjane viśva ūtī MS · abhı şyāma vrjane sarvavīrāh RV KS Corruption if not misprint yuktās tisro vimrjah (nibhrjah) , and others, see §57

CHAPTER VII INTERCHANGES OF Y, R, L, V, AND H

§243. Most of the sections included in this chapter are small and of little phonetic importance. That on y and v, however, is extensive, and while largely dealing with matters of noun formation (suffixes) or with lexical interchanges, contains also some curious and interesting phonetic shifts. And the large group of variations between r and l is almost purely phonetic in character, as is also the smaller group concerning l and d which we add at the end of the chapter

y and r

- §244. Under this head occur chiefly variations between lexically different words, more or less close in meaning, and as usual often under suspicion of corruption
- dvişas taradhyā (ApŚ °yai) rnayā na $\bar{\imath}$ yase (SV $\bar{\imath}$ rase) RV SV. KS AB ApŚ . dvişas tad adhy arnaveneyase AV. Roots $\bar{\imath}$ r and $\bar{\imath}$ (intensive), both 'go'
- sändikera (PG śaundikeya) ulükhalah PG HG. sanderathas sandikera ulükhalah ApMB. Fanciful names of demons
- väyosävıtra (MS väyusavıtıbhyäm) ägomugbhyäm caruh (MS payah) TS MS KSA
- samvatsarāya paryūynīm (TB paryūrnīm) VS TB. Fanciful epithets of doubtful meaning
- ny asvınā hṛtsu kāmā (ApMB kāmān) ayansata (AV aransata) RV AV ApMB nı-yam 'settle', and nı-ram 'rest'.
- prānasya vidvān samare na dhīrah TS MS: yajñasya vidvān samaye na dhīrah AV Both samara and samaya mean something like 'juncture'.
- apo (RV AŚ āpo) adyānv acārişam RV VS MS KS ŚB. AŚ LŚ MŚ ApMB MG. apo anv acārişam (JB †acārşam) TS TB JB ApŚ · apo divyā acāyisam AV anu-car 'follow after' cāy 'fear, revere'
- vasūnī cārur (SMB cārye, ApMB cāryo, HG cāyyo) vi bhajāsi (SMB bhṛjāsi, HG bhajā sa) jīvan AV SMB ApMB HG Stonner on SMB. understands ca ārye, 'O lady' Is HG. Prakritic for ca āryo? (cf Pali ayyo) One ms. of ApMB also cāyyo All very doubtful
- yasyedam ā rajo yujah AV ArS · yasyedam ā rajah AA. · yasyedam oja

 \bar{a} rujah SS Obscure in all SS's \bar{a} rujah looks as if blended of \bar{a} rajo and yujah, whereas AA seems to have lost (haplographically) two syllables, \bar{a} ra(jo-yu) jah Or SS, may be regarded as showing a sort of metathesis of r; ojah vaguely = \bar{a} (y)ujah

gohya †upagohyo marŭko (PG mayūkho) manohāh PG. SMB See §81. sadā yācann aham girā (SV 1yā) RV SV. N. See §134

rudra yat te krayī (krīvī, kravi, girī-) .. see §47

tām pūṣānu yachatu (AV. pūṣābhī rakṣatu) RV. AV. See §184 antah śubhrāvatā (SV. śundhyāvatā) pathā RV. SV. See §173.

vijye †vivye vilşipet (p p vi-lşepe) MS · rijre vilşipe vidhame MS. (Read vilşipe in MS) According to Knauer (note on MS) these words are vocatives of cow-names No etymology for *rijyā or *vijrā suggests itself which would seem appropriate to a cow.

vanışihor hrdayad (AV * udarad) adhı RV. AV. (both) ApMB

agor arir (SV nāgo rayır) ā cıketa RV SV. Wholly different words and constructions

yena bhūyas carāty (MG caraty) ayam (AG ca rātryām, PG. bhūris carā dwam) AG PG. ApMB MG bhūyas and bhūris are different suffixal formations from the some root

sukram te (TA * vām) anyad yajatam (TA.* τaj°) te (TA.* τām) anyat RV SV TS MS KS AB. KB. TA. (both) AS. Svidh. N. The Poona ed of TA reads yajatam for raj°, but with v I raj°, which the comm also reads, he has a labored and worthless explanation.

y and l

§245. Under this head we find only partly synonymous variants concerning the roots yup on the one hand, and lubh or lup on the other. The two instances of yup lubh have been quoted in §113, which see The other is

mṛtyoh padam (MG. padāni) yopayanto (AV. °ta, MG lopayante) yad (AV. omits) eta (RV cita, TA. aima) RV. AV TA. MG

y and v

§246. Both y and v appear very frequently in suffixal and inflectional elements, among these must be included cases in which the y and v represent the vowels i and u under conditions required by morphology. There are, besides these, not a few variants of the kind which we call purely lexical, that is concerning radically different words. Not infrequently either the y or v form of a given variant is suffixal or inflectional while the other is radical. Indeed the rather numerous

variations in this section are unusually hard to classify. They present an aspect of great heterogeneity, suggesting in the large that the phonetic relations between the sounds y and v must have played some part in the matter, even tho in individual instances the precise extent of that influence is extremely hard to determine. It was probably most marked in the cases where a suffix containing y, such as yin, exchanges with one in v, such as vin (see the next paragraph). In the aggregate, these numerous variants form an important bulwark for the theory of interchange between the two sounds in Sanskrit and Prakrit, as recognized by Wackernagel I §188c, Pischel, Gram d Pht Sprachen §254

\$247. We begin with cases which seem most clearly to contain noun suffixes in both y and v forms Prominent among them is a group of forms in suffixal vin and vin. found, as far as the variants are concerned. collectively only in YV texts, and that too so that the v forms occur only in Taittiriva texts, the u forms in those of other YV schools must associate this fact first with an apparent tendency of Tait texts to prefer v in other suffixal forms (§248), and further with the preference of the same school for the vowel u in place of i (§622) The relation between uin and uin seems to be this The uin forms contain really suffixal in, added to stems in \bar{a} (all the variants noted concern such The y bridges euphonically the gap between \bar{a} and i (cf §§338ff), precisely as e.g. in agrist passives from roots ending in \bar{a} (adhāvi etc.) The vin of Tait texts is best explained as a blend of east or van with this in, e.g. svadhā-vin, product of svadhā-vant (RV) and svadhā-van with svadhā-v-in It is therefore likely that these vin forms are secondary to those in yin See Whitney, Grammar §§258a, 1230e, Brugmann, Zur Geschichte der hiatischen Vokalverbindungen, BKSGW 65 (1913), part 3, pp 211ff, Wackernagel I §188c (where, however, it is represented that the y and v forms exchange at random) Besides the forms noted in the following list, note vāvin. sthāyin, rsabha-dhāyın, in addition to Whitney's list §1230e

nama ışumadbhyo dhanvāyībhyas (TS °vībhyas) ca vo namah VS TS MS KS

namah srlāyibhyo (TS °vibhyo, MS srgāyi°) jighānsadbhyah VS TS MS KS

namo rudrāyātatāyine (TS °vine) VS TS MS KS

pıtāmahebhyah svadhāyibhyah (TB ApS °vibhyah) svadhā namah VS KS SB TB. ApS Also with pitrbhyah and prapitāmahebhyah

ūrjasiatīh siadhāyinīh (TS °vinīh) TS KS.

§248. Besides these we find a considerable number of miscellaneous

- cases in which y and v are in some sense suffixal, it is hard to classify them more precisely, and the degree of phonetic influence at work is likewise hard to determine. But it is to be noted that in not a few of them, also, Tait texts seem to prefer the v forms, altho instances of the contrary are not lacking
- aramgamāya jagmaye (TB ApŠ jagmave) RV SV TB Ap, Note stem jagmu, otherwise unknown, in Tait texts, for regular jagmu duvasyave (TA. duvasvate) tvā vātāya svāhā MS. TA Stems duvasyav

and dwasvant, but MS has v 1 dwasvate

- ojasvinī nāmāsı TS ApMB · ojasyā nāmāsi MS Agam Tait texts with v
- atharya putum me pāhi VS SS atharva putum me gopāya (AS $\uparrow pāhi$) TB AS ApS atharva looks like a phonetic variant, suggested by atharvan, for atharya (cf. RV athar, atharyu), epithet of Fire. Note v in Tait texts (to be sure also in AS)
- tapyatvaı svāhā TS tapatyaı svāhā KSA TA Stems tapyatu (RV) and tapatī Poona ed of TA tapyatvaı, v l tapatyaı
- ye te agne medayo (KS °vo) ya indavah TS KS. Here TS has the 1egular i-stem medi, while KS substitutes an otherwise unknown medu
- punse putrāya vettavai (ŚB [so, for Conc ŚG] BrhU vittaye, MG kartavai, KS† and v 1 of MG kartave) KS ŚB TB BrhU. ApŚ ApMB
- tvam no devatātaye (AV deva dātave) RV AV N See §61
- śrudhi śruta śraddhivam (AV śraddheyam) te vadāmi RV AV The anomalous RV form 15, as 1t were; explained in AV
- višvacarşanıh sahurıh sahāvān (AV. sahīyān) RV. AV. MS Again AV eliminates a rare hieratic form
- svā tanūr baladeyāya mehr (AV baladāvā na ehr) RV AV 'Come to me unto strength-giving' (RV pp $m\bar{a}$, \bar{a} , $\imath hr$) 'come to us, giving strength'.
- namo hradayyāya (KS hradavyāya) ca nweşyyāya (KS nweşyāya) ca TS KS: namo nīveşyāya (p p ni°) ca hrdyāya ca MS namo hrdayyāya ca nweşyāya ca VS Anomalous forms seemingly from hrd and hrdaya (but cf §658), or from hrada (Keith, 'of the lake') Stem hradavya quoted Pān 6 1 83. Vārtt 2, Pat
- idā manuşvad (AV mss manuşvad) iha cetayantī RV AV VS MS KS
 TB N The mss reading of AV is supported by APr 4 65 (comminanuşvavat) and adopted by Whitney The APr commiscoks in the right direction, it is a blend of manuşvat and manuşva-

- namah sūtāyāhantyai (TS °hantyāya, MS KS °hantvāya) VS TS MS.
 KS. a-hanti, 'not smiting' a-hantya = a-hantva 'not to be smitten' arāyo †asmān abhiduchunāyate TB. AS ApS arāvā yo no abhi duchunāyate RV TAA Vait MS The stem a-rāy-a (rai) is bahuvrīhi, a-rā-van karmadhāraya. Caland would read arāvā yo 'smān in
 - a-rā-van karmadhāraya. Caland would read arāvā yo 'smān in ApS', it seems indeed that the syllable yo is inherited from the RV. form of the pāda
- vasuranvo (MahānU onyo) vibhūr ası TA MahānU ranya ıs from root ran, as to ranva we must remember the quasi-root ranv (see last variant ın §225). Both comms have fatuous explanations, that on MahānU divides vasur anyo (=stutyah!)
- etera tvam atra sīrṣanvān (MS tvam sīrṣanyām, Conc, but Van Gelder's ed, 6 1 2, sīrṣanyān) edhi KS ApS MS The KS ApS reading alone makes sense 'by this be thou headed' = 'let this be thy head' The MS form, if Van Gelder is correct, can only be a phonetic variant for 'vān.
- unnetar un non (read no) nayonnetar vasvo abhy un nayā nah AŚ unnetar vasīyo na un nayābhi (KS vasyo 'bhy un nayā nah) MS KS ApŚ The AŚ form may be felt as acc pl of Vasu (n pr), but is really only a phonetic variant or corruption for vasyo (vasīyo) 'fead us unto welfare'
- §249. In a little group of three cases, AV. substitutes the more popular $var\bar{v}yah$ for varwah, of which the v is certainly connected with the u of uru
- asmabhyam ındra varıvah (AV. varīyah) sugam kṛdhi RV AV asmabhyam mahı varıvah sugam kah RV
- sakhā sakhibhyo varīvah (AV * varīyah) kṛnotu RV AV (both) TS KS GB Here Ppp has varīvah; one ms of GB varīyah, which, it seems, ought to be read in GB in accord with AV, unless GB quoted from Ppp
- tvaştā no atra varıvah (AV varīyah) krnotu AV TS
- §250. In another small group the y is definitely part of a case-ending, while the v remains suffixal or is a stem final
- yābhır ındro vāvrdhe vīryāya (AV vīryāvān) RV AV N 'Increased unto heroism' 'increased, (so as to be) full of heroism'
- gārhapatyah (ŚŚ. °tyāt) prajāyā (VSK prajāvān) vasuvitamah VS VSK ŚB AŚ ŚŚ Objective gen varying with possessive adjective prajananam vai pratisthā loke sādhu prajāyās (MahānU sādhuprajāvāns)
- prajananam vai pratisthā loke sādhu prajāyās (MahānU sādhuprajāvāns)
 tantum tanvānah TA MahānU But most mss of MahānU
 agree with TA, the ed follows one ms and the comm

namah samgare (TS † samgāya) ca pasupataye ca VS TS MS KS. Wackernagel, II. 1 p 315, plausibly takes samgāya for samgayāya.

sa ghā (TB sadyā, read sa ghā with Poona ed) no devah savilā sahāvā (TB savāya) RV MS ŠB TB AS ŠŠ

§251. In alternating verbal endings the same change between y and v occurs repeatedly. It is especially common in 3d person indicative-imperative variations, see VV I §§116, 104. We quote a single example here:

pra stomā yanty (SV yantv) agnaye RV SV.

Another stray variant concerning verbal inflection has been noted.

brahmattad upāsvattat (MahānU "syattat) tapah TA MahānU The reading of TA is uncertain, see VV I pp 45, 125

[madhye poşasya (AG °sva) trmpatām (MG puşyatām, AG tışthantīm) AG ŚG MG For po asva read °sya with Stenzler's Translation] And in different present stem-formations of verbs

manve (ArS manye) vām dyāvāpṛthwī (ArS adds subhojasau) AV. ArS Vait See VV I p 125

§252. We now come to the more strictly lexical variants, in which at least one of the two sounds y and v is not in any sense suffixal or inflectional (usually both are not) They are fairly numerous, but so miscellaneous that it is hardly profitable to try to group most of them. There are several interchanges of the pronoun forms tyam (tyat) and tvam

tam u tvam (SV tava tyan) māyayāvadhīh RV SV

tvam (KS tyam) hy agne agnınā RV TS MS KS AB KB JB SB AS SS Kaus

ımam \bar{u} (MS u, p p $\bar{u}[m]$) şu tvam asmāham (TA ApS tyam asmabhyam) RV SV MS TA ApS MS

§253. Another little group concerns real or specious derivatives of the root \imath 'go' in variation with av They tend to confirm the use of av as a verb of motion, see Neisser, ZWbch d RV 123ff

āpo agre visvam āvan AV āpo ha yad bihatīr ('I'S MS KS yan mahatīr) višvam (TA gaibham) āyan RV VS VSK TS MS KS TA 'Went (rushed') into the all', AV is of course secondary but perhaps intends substantially the same as the rest, rather than the banal 'helped all'

ati setum durāvyam (SV durāyyam) RV. SV The derivation of the RV form is uncertain, see Oldenberg, Noten on 9 41 2 The SV form, at least, is clearly meant to be taken from root i ('hard to cross')

- ayebhyah (TB ave^o) kıtavam VS TB aya 'dıce-throws' is of course original; note that av- occurs in a Tait text (see §247), is it a mere phonetic variant for ay-? (comm 'to helpers') Tho aya may not be derived from root i, the variant belongs to this group
- §254. Another group of cases is united by the circumstance that differences of word division produce different words in one form of the variant. In the instances first mentioned the v (or, once, the y) is suffixal, the other sound belonging to a separate word (particle or light monosyllable):
- rşînām putro abhısastıpā u (VS. ŚB °pāvā, TB °pā ayam) AV VS ŚB TB
- $tan\bar{u}p\bar{a}v\bar{a}nas$ (AV $tan\bar{u}p\bar{a}$ ye nas) tanvas $tapoj\bar{a}h$ (AV $tan\bar{u}j\bar{a}h$) AV AB AS $tan\bar{u}p\bar{a}van = tan\bar{u}p\bar{a}$
- svarvaj (AV svar yaj) jyotir abhayam svasti RV AV KB TB
- satyam (SV ApŠ sa tram) vrsan vrsed ası RV SV ApŠ The RV original is less commonplace than the later substitute, which opens countless Vedic pādas
- utānyo asmad yazate vi cāvah (TB vicāyah) RV MS TB N The original has vi-ca-āvah, vicāyah (comm višesena pūjāyuktah) is āπ.λεγ, corrupt, and untranslatable See Kaegi, Fesigruss Roth 159, 165
- yena bhūyas carāty (MG. caraty) ayam (AG ca rātryām, PG. bhūris carā dwam) AG. PG. ApMB MG The PG reading is clearly secondary
- nāras caranti svasīca iyānāh VS TS ŠB nāvo vi yanti susīco na vānīh PIS KS The passage is mystical and obscure, tho the individual words are simple enough, VS etc may have a lect fac
- pītā bhāsvaty anūpamā TA pītābhā syāt tanūpamā MahānU See §838
- praty eva (SS pra tveva) grbhāyata AV AB GB JB SS
- §255. The rest we shall not attempt to classify; note that in some of them one or the other form still contains suffixal y or v (the not both) ahrtam ahrtayone (MS ahrtavane) piba AV VS VSK TS MS KS
- SB AS SS 'Home of ghee' 'rich in ghee', ghrtavani is a secondary blend of the common epithets ghrta-vant and ghrta-yoni (both RV)
- anuvāsi (VS anuyā, MS anuvāya, GB † Vait † ahnānsi, em Vait ed to anuvāsi) rātriyai (VS rātryā, MS KS † Vait † rātryai) toā (VS MS omit) rātrim (VS MS KS † rātrīm) jinva VS TS MS KS Vait (pratīka in GB) The two folias are quite uncertain and may be phonetic variants The lexicons take them as containing the

- roots $v\bar{a}$ and $y\bar{a}$ But note that MS. presupposes a stem anuva, with short a
- trātāram indram akrnor avadhyam (VSK ayudhyam) VS VSK TS MS KS SB Synonyms; note the u, preserving a trace of original v Something like the reverse process in Pāli avudha = Skt. āyudha
- āvitsi (MS āyukşi) sarvā oşadhīh RV VS TS MS KS Roots ā-vid ā-yuj Other interchanges of vi yu in §805.
- nādya satrum nanu (SB† na nu) purā vīvītse (SB yuyutse) RV. SB. Metathesis of vowel and semi-vowel (vi yu)
- rāyah syāma rathyo vayasvatah (TB. mvasvatah) RV MS TB The startling change in TB is probably suggested by su-yamasya in the prec pāda Vivasvant goes well with Yama!
- śamgayī (MS ŚB. °gavī, TB °gaye) jīradānū (ŚB jīvadānā) MS ŚB.

 TB AS ŚŚ gava 'chattels' go 'cow'
- somī ghoşena yachatu (SV vakşatu) RV SV Substantially synonyms spardhante dhiyah (TS KSA divah) sūrye na (SV sūre na, TS KSA † sūryena) višah RV SV TS KSA See §109
- sarasvatyai yasobhagınyaı (KS vesabha°) svāhā VS KS
- brhann ası brhadravā (TS KS °dgrāvā, MS °drāyāh, MŚ °drāyah) VS TS MS KS ŚB MŚ The Maitr texts obviously secondary malmalābhavantīm tvā (N °tītyr̄, corrupt) sādayāmı TS MS KS TA N rudra yat te krayī (krīvī, kravī, girī-) see §47
- dhuñkşûgneyî (VSK vv ll dhuñkşyû° and dhuñkşvû°) VS VSK MS.

 agnaye dhūñkşnû (KSA ° sû) TS KSA Wholly obscure words
- nıkīrya (MS nıgīrya) tubhyam abhya āsam (ApS tubhyam madhye, MS tubhyam madhvah) Vait ApS MS nıgīrya sarvā ādhīh KS A desperate passage, see §47
- duşvapnahan duruşyaha TA Bıbl Ind, duşşvapnahan duruşşaha TA Poona ed, tevt and comm duhsvapnahan duruşvahā MahānU. Comm on TA duruşşaha duhhham utkarşenābhibhava, comm on MahānU duruşvahā tvam, duştam uşvam (¹) dāham hantı. The word seems to be durasyuha (°hā) 'kıllıng hım who plans evil (durasyu)'
- aśvān anaśśato (KS † ApŚ anaśyato, MŚ Van Gelder anaśvato, without v l) dānam KS TA ApŚ MŚ Poona ed of TA reads anahśato, v l anaśyato, the comm. ayahśaphān, with v l anaśato Obscure
- revolī ramadhvam (MS * °tīr amedhyam) VS TS MS (both) KS The variant of MS is corrupt, see AJP 27 403 But the reading of the ed is an emendation, mss °ramadhyam

ayuktāso abrahmatā vidasāma (RV yad asan) RV VS SB vidasāma, taken by Mahīdhara as from vi + das 'fail'

y and h

§256. A very few cases of miscellaneous character, consisting of easy lexical substitutions or corruptions Cf Weber, ISt 4 224 dyutāno vājibhir yatah (SV hitah) RV SV

sam sravantu diso mahīh (HG mayı) ApMB HG

endram vagnunā vahata PB vagnunendram hvayata TB ApŚ Note the metathesis of h from the beginning of the original hvayata to the middle in vahata PB comm glosses āhvayata

yamīr yamasya bibhryād (AV vivrhād) ajāmi RV AV See §222 tam aham punar ādade KS PG imam tam punar ādade 'yam (read 'ham) HG (plainly corrupt)

hinvano helpbhir yatah (SV hitah) RV SV

snuṣā sapatnā (TB comm and Poona ed text °nāh) śvaśuro 'yam astu (AŚ 'ham asmı) TB AŚ

r and l

§257. Nearly all the numerous variants under this heading are purely phonetic, the same word is spelled with r or l. The number in which lexical or other real difference is even conceivable is quite negligible. While the variants can hardly be said to establish any new principle, they furnish a large amount of new evidence for facts which have, on the whole, been fairly well recognized

§258 There is a tendency towards l noticeable in younger and less The RV, especially in its oldest stratum, has a marked hieratic texts In the RV itself are found doublets such as the roots fondness for rpru plu, mruc mluc, car cal, pruș pluș, the words puru pulu, aram alakam [despite Wust, in Ehrengabe W Geiger 185ff, which does not convince me-F E], sahamūra sahamūla, and the intensive stems jargur jalgul Such instability continues after the Mantra period thru the history of the two sounds in Sanskrit and the medieval dialects, until in Māgadhī Prakrit, and sporadically elsewhere, l stands for any and every r The reverse is also found, the only sporadically in the Prakrit dialects recorded Pischel §259, and cf Wackernagel I p 215f, Edgerton, Studies in Honor of Hermann Collitz 30f This confusion is reflected in the earliest language and thruout the Vedic period, not only in the variations of parallel texts, but in the ms readings of one and the same text

§259. The variants confirm and extend by further examples the scope A few other stray instances which have come to of these known facts our notice and are not included in Wackernagel. MS 3.7 9 has asvavāra and āśvavāra against aśvavāla and āśo in the corresponding passages of KS 24.8 and KapS 38 1 (see Von Schroeder, MS, p xv) PG 1 15 4 has grapsa 'tuft of grass' for AG 1. 14. 4 glapsa '(GG. 2 7 4 grathna). The variant plengha for prenkha 'swing' occurs in ApDh. 1 11. 31 16. Later on, similarly, derivatives of the roots ivar and ival figure on the same page of the Kathūsarītsūgara (5 118, 122) In Aufrecht's edition of AB., p. 428, it has been pointed out that this text has a number of cases of r for more usual l (urūka, bahura, etc). Such a thing is not surprising in a Rigvedic Brāhmana; and certainly AB's bahura goes RV one better, for that form is unknown in RV., where bahula is common. In fact, the AB passage in question, 2 20 14 (also in AS 5 1 15), containing bahuramadhyam, imitates RV. 10 42 8, which contains bahulāntāsa(h).—The statement was made by Von Schroeder, ZDMG 33 196, that MS has a general preference for l over r But this is not repeated, so far as we can see, in his edition of the text; we gather that it was tacitly withdrawn. In fact, the variants do not show any such preference for l in MS. While Maitr texts sometimes show l for r of other texts, one of these cases is a lexical variant (§260), and in most of the others the l form is more usual thruout the language generally Per contra, note MS aśvavāra above in this section, and kharvāś (to be sure with v 1 khalo), the only recorded occurrence of this word with r $(\S 265)$

§260. The very small group of lexical variants is now given first, one of them, even (the last), may possibly be purely phonetic—if not that, it is certainly corrupt

te no 'gnayah paprayah pārayantu (MS MG. pāla') TS TB PB ApMB MS PG MG The two words are practically synonyms, tho unrelated, both mean in effect 'preserve'. Note the adjacent paprayah, related to pārayantu

adhı skanda (Ppp kranda) vīrayasva AV · abhı kranda vīlayasva SG. 'Play the hero'. 'be strong' (vīl' for vīd') See §272.

dhik tvā jāram parasya janasya nirmārjimi. MŠ. dhik tvā jālmi. LŠ. The words are quite different in meaning and construction. mā rudriyāso abhi gur ijdhānah (MS. abhi gulbadhānah) MS. TA mā no rudrāso adhigur vadhe nu (mss. nuh) MŠ. See §209 gulbadhānah is not divided in pp, it can only be a corruption (or phonetic variant) for gur (etc.) = guh, 3 pl aorist

- §261. The rest are all purely phonetic in character We begin with a group in which r is regular in RV , but l is regular in later or less hieratic texts The r forms are either Rigvedic, and in later texts copied from RV , or conscious archaisms imitating Rigvedic diction, like bahura in AB (§259)
- aśrīrā (AV ApMB aślīlā) tanūr bhavatı RV AV ApMB The r form is not recorded outside of RV, which is the more remarkable because of its obvious connexion with the common word śrī For this the suffix ra is responsible, first by dissimilation of one of the liquids, then by reassimilation of the remaining r to l
- aśrīram (TB† aślīlam, both edd) cut kṛnuthā (TB† thāt, comm and Poona ed. text thā) supratīkam RV AV TB
- samūdham (VSK samūlham) asya pānsure (SV °le) RV AV SV VS VSK TS MS KS ŠB N The *l* form is regular after RV, the *r* form in RV only in this passage, directly repeated in all later texts
- mā tad bhūmyām ā śrişan (VSK v l ślişan) mā trneşu RV VS VSK TS MS KSA Cf aśleşā (āśreşā) below, §265
- andhāhīn (TS °he, KSA. °heh, em , ms °he) sthūragudayā (TS KSA °gudā, VS sthūlagudayā, and so MS pp) VS TS MS KSA. The RV knows only sthūra, but sthūla is regular later (cf however sthavira)
- anu no mārstu (VS TS ŚB TA anu mārstu) tanvo yad vīrīstam (VS TS KS † ŚB TA ŚŚ vīlīstam) AV VS TS MS KS ŚB TA ŚŚ rīs is Rigvedic, rare later
- capyam (TB Poona ed cappam) na pāyur bhisag asya vālah (KS vārah, TB bālah, Poona ed vālah) VS MS KS TB The r form is almost limited to RV, of however asvavāra in MS, §259
- devānšo yasmai tvede tat satyam upariprutā (ApŠ apariplutā) bhaāgena (ApŠ bhaāgyena) VS ŠB ApŠ The root is commonly pru lin RV, only very rarely so later
- aślonā' (comm aśronā) añgair ahrutāh svarge AV aślonāñgair ahrtā (read ahrutāh or "tā with Poona ed) svarge ȚA śrona chiefly RV
- §262. Next, a group concerning words in which both r and l are common in most periods of the language, but RV as a rule has r almost or quite exclusively. Here are included two variants in which AV goes RV one better in its hieratic r, but both RV passages are from the largely popular Book 10. Both cases, adjacent to each other, concern the root rabh labh, which in RV always has r except in a few passages of the tenth book, of which these are two. Both forms are common later

utālabdham (AV. utārabdhān, Ppp utāl°) spṛnuhi jātavedah; followed by: ālebhānād ṛṣṭibhir yātudhānāt (AV. utārebhānān ṛṣ° yūtudhānān) RV. AV.

The AV. is secondary and corrupt in its construction, see Whitney's note

The other variants in this section do not involve RV. Two concern sukla and sukra, both fairly common later, but the former not in RV Another concerns rohita lohita, of which again RV. has only the r form. The case of ksudra lsulla, where the l form is clearly Prakritic (with assimilated consonant group), also concerns words both of which are well known in the language as a whole

śukrāya svāhā VS MS SB · śuklāya svāhā VS MS.

peśo na śukram (KS TB śuklam) asutam (MS samh. mss aś°) vasāte VS MS KS TB

varunāya rājāe trayo rohutalalāmāh (TS† misprinted rohuto-la°, KSA. lohita°) TS KSA

atho ye kşullakā wa AV . hatah krımīnām kşudrakah SMB . atho sthūrā atho kşudrāh TA (perhaps consciously hieratic as regards both adjectives).

§263. Next, words in which r forms (all prehistoric) are more common in all periods, the l forms being largely problematic or textually uncertain (Wackernagel I §192b) — In this group might perhaps have been placed $gulbadh\bar{a}nah$ of MS, see §260

asya kurmo (RVKh kulmo, AVPpp ms krnvo) harwo medinam twā RVKh TS TB AVPpp (Barret, JAOS 37. 263f.): asmākam abhūr haryasva medī AV iha krnmo harvo medinam tvā KS. Scheftelowitz p 112 reads for RVKh iha kurmo hao vedinam tvā But his kurmo is an emendation of a ms reading kutso, which is probably a graphic corruption for kulmo

upapravada (RVKh upapla°) mandūki RVKh AV N Again Scheftelowitz reads upapra° in RVKh, this time with his ms. The form intended is upa-pra-vada, of ā-vada in next pāda. The reading with pla, if it is anything more than a ms. corruption, is mechanically assimilated to plavasva in the second half stanza.

antarılışam purītatā (TS purī°, MS pulī°, KSA pulī°) VS VSK TS MS KSA The r forms are commoner

satatam tu śirābhis tu MahānU samtatam śirābhis (Poona ed śilo, but v l and comm śiro, gloss nadībhih) tu TA No l form of this word is otherwise recorded

§264. Words in which *l* is regular, *r* rare Here, first, eight passages containing sarira or salila 'ocean' That MS invariably has salila

cannot be considered significant (cf. §259, end), since this is the regular form in all periods, even RV; neither RV nor AV knows sarira, which is practically restricted to YV texts and, along with many other r forms, may be regarded as a conscious hieraticism.

aśvam jajñānam sarırasya (MS salılasya) madhye VS TS MS KS ŚB prapīnam (MŚ v 1 °lam) agne sarırasya (MŚ salılasya) madhye VS KS MŚ · prapyātam etc TS ApŚ

vibhrājamānah sarırasya (MS salılasya) madhye (TA °yāt) VS TS MS KS SB TA

nyacyamānam salilasya (VS KS ŠB sarırasya, TS TA bhuvanasya) madhye AV. VS TS MS KS ŠB TA

3arıram chandah VS KS SB salılam cho TS MS

rarırāya svāhā VS · salılāya tvā TS MS KS Ap\$ M\$ salılāya svāhā \$B

arirāya (MS TA salilāya) tvā vātāya svāhā VS MS ŚB TA

varıre tvā sadane sādayāmı VS KS ŠB sahle etc MS sahle sadane sīda TA

§265. The rest are miscellaneous

kṛṣṇagrīva āgneyo rarāte (MS lalāṭe) purastāt VS MS The l form is commoner.

aśleşā (TS āśreşā) nal.
şatram TS MS KS In MS pp aśl $^\circ$; KS may intend either
 a- or \bar{a} - The word regularly has
 l Cf. $m\bar{a}$ tad $bh\bar{u}my\bar{a}m$ etc., §261

adhorāma (HG. text atho') ulumbalah (HG †ulumbarah) ApMB HG
The word (usually udum', probably related to udumbara, ud'
'fig-tree') appears in RV AV etc, always with l in the last syllable,
except here in HG, which may show dissimilation to preceding l
Cf §273.

mudgāś ca me khalvāś (MS kharvāś, v 1 khal^a) ca me TS MS KS A kind of grain, the r form not found elsewhere Note that it occurs in MS (cf. §259)

achalābhih (KSA °rābhih, MS [m]atsarābhih, VS rkṣalābhih) kapiñjalān VS TS MS. KSA See §184

r and v

§266. These interchanges, with the yet more scanty groups concerning τ and v and h, are sporadic and of slight phonetic importance. We record them on the chance that there may be a quasi-phonetic glide from one to the other in words that are lexically similar, which are regularly involved. In fact, so far as they do not concern corruptions

(as is often the case), they mean substitution of one word for another similar in sound. Thus the very hieratic word jīra-dānu is twice replaced by jīva-dānu at a time when the former is no longer understood udādāya pṛthivīm jīradānum (TS TB ApS "nuh; VS ŠB jīvadānum) VS. TS MS. KS ŠB TB ApS

śamgayī (TB °ye, MS ŚB °gavī) jīradānū (ŚB jīva°) MS ŚB TB. AŚ ŚŚ

§267. The rest are individual cases of more or less close synonymy, tapering off into doubtful or corrupt readings.

avakrakşınam vyşabham yathājuram (SV yathā juvam) RV. AV. SV. 'Ageless': 'swift'

ūrjasvatīr oṣadhīr ā rīśantām (KSA viś°) RV TS KSA† 'Graze on': 'enter', the latter an evident lect fac

puru reto dadhire suryasvitah (AV °sritah) RV. AV KS The AV is secondary and not very intelligent, 'sun-shining' and not 'sun-resorting' is original Yet KapS (see note on KS) has °sritah, evidently intending °sritah

rudra yat te krayī (krivi, kravi, giri-). see §47

pāti priyam ripo (and rupo) agram padam veh RV. (bis). pāty agnir vipo agram padam veh ArS

duredrsam grhapatini atharyum (SV athavyum) RV. SV KS. Ap\$
M\$. N The SV form is desperate Benfey suggests atharv-yum
with simplification of the group of three consonants (cf. §§419ff).
In some way the v of atharvan seems to be concerned.

aświnā gharmam pātam hārdvānam (TA hārddwānam, read hārdi^o with Poona ed; LŚ pātam aharvyānam, MS pibatam hārdrānum) VS. MS ŚB TA ŚŚ LŚ The MS corruptly mouths over an obscure form Note that the v of the original, by a kind of metathesis, reappears as the vowel u

hitvī (SV hitvā) širo jihvayā vāvaduc (SV rārapac) carat RV. SV.

tatra rayışlhām anu sambharaılam (MŠ °relām, AŠ corruptly °bhavatām) TB AŠ ApŠ MŠ

rathe akşeşv rşabhasya (KS TB °şu vr°) vāje AV KS TB ratheşv akşeşu vrşabharājāh V1Dh See §359

mıśravāsasah kauberakāh ApMB kauberakā vıśvavāsah HG.

āyurdā (āyuşmān) deva (agne) jarasanı (havışā, °50) vrnānah (etc.), see §854

asmān (MS KS asmān) u devā avatā haveşu (MS KS bhareşv ā) RV SV VS TS MS KS asmān devāso †'vatā haveşu AV

varunāya riśādase (KSA vidase) TS KSA So the ms of KSA: but von Schroeder emends to riśādase.

- §268. In several cases assimilation or dissimilation is concerned ugram ogistham tavasam (SV tarasam) tarasvinam RV AV SV Assimilation to tarasvinam in SV
- vātajavair (HG vātājirair) balavadbhir manojavaih MS HG Either assimilation in MS, or avoidance by dissimilation in HG or the banal sequence vātajavair manojavaih Since the latter process seems almost too clever for a sūtra text, probably MS is secondary
- dhanamjayam dharunam dhārayışnu RVKh bhūmıdrnham acyutam pārayışnu AV bhūmıdrnho 'cyuta's cyāvayışnuh AV The last, unquestionably secondary, changes to cyāv' after acyutah, 'unshaken (but) shaking (others)', an enticing mode of expression in the Veda (e g ajuryam jarayantam, RV 2 16 1).

r or v and h

- §269. These cases are yet fewer and slighter in phonetic significance; of §266
- aredatā (KS * ahed°, so ed , but ms īdatā, read probably ared° with v Schr on KS 32 3, n 3) manasā devān gacha (ApŚ gamyāt, TS manasā tac chakeyam) TS MS KS ApŚ ahedatā (ŚŚ ahel°) manasedam juṣasva AŚ ŚŚ The root red in Naigh 2 12 is followed immediately by hed in a list of ten words for 'be angry'
- sahamānā sahasvatī (PG sarasvatī) PG ApMB HG sarasvatī is a blunder
- tam tvā bhrātarah suvṛdhā (ApMB °dho, HG suhṛdo) vardhamānam AV ApMB HG See §109
- $t\bar{a}~(t\bar{a}v)~ehi~(eha, iha, MG~eva)$, see §§578, 888
- sa ghā (TB sadyā, Poons ed sa ghā) no devah savītā sahāvā (TB savāya) RV MS SB TB AS SS

l and d

§270. It is a familiar fact (Wackernagel I §222) that every d and dh between vowels is changed in the Sākala and Bāṣkala recensions of the RV to l and lh This variation is ignored in the Conc, because it is carried out with mechanical completeness. Clearly related to it is the change between vowels of the same sounds to dental l and lh in later Vedic texts, Wackernagel I §194. This alteration is carried thru, with as absolute completness as in RV, in two texts, VSK and SS, and also in the twentieth book of AV. These cases are recorded in the Conc, but we deem it a waste of space to list here the variants which concern VSK and SS alone. Elsewhere the same change occurs sporadically.

It is clear that ms. tradition in this regard is untrustworthy, and that editors have exercized their discretion to some extent. Thus N, seems to intend to write l thruout. In the following list all the variants with l in AV, occur in Book 20 and mainly in those parts of it which are copied from RV. So far as we have observed, these are the only variations from the text of RV, in those parts of AV, 20.

\$271. The list follows:

ıdāsmān anu ıastām ghṛtena ApS MS · idairāsmān (RVKh. ilaira vām) anu ıastām tratena RVKh. AV. Vait But Scheftelowitz reads idaira... ghṛtena for RVKh.

aıdamıda yavyudhah KS: ailabıda (MS °mıda, KapS īlarırda) ayuryudhah (TS yavyudhah MS. 10 yudhah) VS TS. MS. See §241 ādılyā rudrā 1asa1as tielate (AB tiel, for tied, GB. Gaestra ftenite, with all mss.) AV AB GB. JB SS.

astrām tādam pratīnāhā (ApŚ T tālam pratīnāham) MS ApŚ.

yad devā devahedanam (VSK TA * °helanam, but TA. Poona ed both times °hel°, with v. 1 °hed°) AV. VS. VSK MS. KS. SB. TB. TA. (bis) Vait ApS MS Kauś. BDh GDh.

nahy anyam badākaram (AA. bal \hat{n}°) RV AA. AŚ. But Keith reads AA. bal \hat{a}° (as is read in RV)

aśrathnun dṛdhāvradanta vīdītā RV.: avradanta vīlītā (fragment) N. indraś ca mrdayāti (AV. ŚG. mṛlº) nah RV. AV. ŚG.

īde (ŚŚ VHDh īle) dyāvāprthuī pūrtacittaye RV. AB. KB. AS. SŚ. KŚ. MŚ. VHDh.

īdenyo (AV. SS. Vait īlenyo) namasyah RV. AV. SV. SB. TB. AS. Vait krīdantau (N. krīl^o) putrair naptrbhih RV. AV. N.

yad vīdāv (AV vīlāv) indra yai sthire RV. AV. SV. Svidh.

vīdu (AV. Vait vīlu) cid ārujatnubhih RV. AV. SV. Vait.

vīhi sūra (TB sūra) purodāšam (AV. °lāšam) RV. AV. KS. TB. N.

vauşai (SBK SS. vauşai) AB. GB SB. SBK. SS. Vait MS. ApS.

vy ānad (AV. ānal) indrah pṛtanāh svojāh RV. AV.

d and r

§272. The same change occurs sporadically also between d and r. Twice this concerns the word $id\bar{a}$, $il\bar{a}$, or $ir\bar{a}$; the other cases are lexical or corrupt Cf also ahar $dw\bar{a}bhir$ $\bar{u}tibhih$, §360; here MS. has (for ahar) vahad (cf next §), but one ms vahad and p p. vahat.

ırāvatī (KS idā°) dhenumatī hi bhūtam RV. VS. TS. MS. KS SB. TA. AS ApS. MS

ida (ŚŚ ila, MS MŚ idā, ApŚ.* ira, in the same passage with *ida) ehi VS TS MS. KS. ŚB. TA. ŚŚ. LŚ. ApŚ. (both) MŚ

arnhasva vīdayasva (MS vīr°) su TS MS adhiskanda vīrayasva AV , abhi kranda vīlayasva SG See §260

 $v\bar{\imath}ruc$ chapathayopan $\bar{\imath}$ AV . $v\bar{\imath}du$ chapathayambhan $\bar{\imath}h$ ApS The latter is a clear corruption of the AV. reading, which Caland adopts

varenyakratūr (AV °tur, ApŚ īdenya°) aham RVKh AV. ApŚ · vīrenyah kratur ındrah suśastıh RV. See §§383, 554

d and r

§272a. On this subject see Hanns Oertel's helpful review of VV I, in GGA 1931 236ff, especially 239f, and his article in Ehrengabe für Wilhelm Geiger 136f. He refers to Patañjali (Introd to Mahābhāṣya, on Vārtt 9, p 11, 11, Kielhorn), who mentions the mispronunciations yartānas, tarvānas, for yadvānas, tadvānas; and to Wackernagel I p 212. Oertel would see in such variations as nātārīd (TB °rīr) asya samṛtim tadhānām (TB ba°) RV TB, where a difficult 2d person sing is substituted for a 3d person (cf VV I p 237), traces of this phonetic tendency. (Cf. ChU. 4. 1 2 pradhākṣīr for °ṣīd, Oertel, ll cc) It seems indeed possible that this has something to do with such variations, altho it should be remembered that there are many other equally curious variations in person of verbs which cannot be thus explained (VV I passim, especially p. 195f.). Other cases mentioned by Oertel (see also his note in ZII 8 289f.) are:

mayi rāyo mayi rakşah MS. 4 9 13 134 5, for which the Conc suggests dakşah for rakşah. mayi dakşakratū TS †2 5 2 4, ApŚ AG HG. mayi dakşo mayi kratuh VS MS SB TB. TA SS

na me tad upadambhişar dhṛṣir brahmā yad dadau MS (originally "dambhiṣad ṛṣir". Caland, ZDMG 72 10 infra) na ma idam upadambhiṣag (once erroneously udambhiṣag) ¬ṛṣir brahmā yad dade ApS (bis) Here the ApS form seems to stand for upadambhiṣad, with final g for d (=k for t), see our §142

yadā rāghatī raradah Vart.: yadā rākhātya» radatah ApS yad adyārādhyam vadantah MS See §70

To these materials collected by Oertel may be added the following ahar (MS 1ahad) duābhir (MS dwyābhir) ūtibhih VS MS. ŠB TA ŠŠ

LS One ms and p p of MS vahad (vahat), see §360, and the preceding §272 The MS is secondary, and may be considered hyper-Sanskritic

dadhır (SV. dadhad) yo dhayı sa te (SV. sute) vayansı RV SV.

balım ichanto vıtudasya (AG vı tu tasya, v 1 vıdurasya) preşyāh (MahānU AG presthāh) TAA MahānU AG See 865

dvişas taradhyā (ApŚ. °yai) rnayā na īyasc (SV īrase) RV. SV. KS AB ApŚ dvişas tad adhy arnaveneyasc AV

l and d and n

§273. By way of appendix may be mentioned a few stray cases in which l varies with lingual n and with dental d; these evidently show tendencies related to the preceding (A couple of variations between l and dental n might perhaps also be recorded here, but because of the ease of graphic confusion between these letters we have quoted them in §878, q.v.) In two contiguous passages $hariknik\bar{a}$, fem of the coloradjective harita, is changed in §§ to $hariklik\bar{a}$, perhaps by partial assimilation to the preceding r, but the characters are graphically much alike.

tāsām ekā harıknıkā (ŠŚ °klıkā) AV ŠŚ harıknıke (ŠŚ °klıke) kım ıchası AV ŠŚ

There remain a couple of partly phonetic variants between d and l: urūnasāv (TA. uru°) asutrpā (AV TA °pāv) udumbalau (TA ulum°) RV AV. TA AS See Lanman apud Whitney AV. The TA. comm, fatuously, prabhūtabalayuktau (as if uru-bala!). See adhorāma etc, §265.

ni nivariana variayendra nardabuda (KS nandabala) TS KS ApMB. Both ἄπ. λεγ; obscure epithets of Indra KS looks suspiciously like a case of popular etymology (as if 'rejoicing strength'), and is therefore probably secondary.

CHAPTER VIII THE SIBILANTS

§274. The general confusion of the sibilants, doubtless due to popular quasi-Prakritic influences (since they all become fused in the Prakrit dialects), goes back to a very early date. From the Veda down to modern times instability in this regard is habitual rather than exceptional in certain roots and words. The sibilants of such words as koşa koşa (cf §289, end), śrambh srambh, are really never determined, and even so clear a root as sru 'flow' threatens surprisingly to become śru, as we shall see (§275). See Bloomfield and Spieker, JAOS 13 exvii ff, Bloomfield, Kauśika Sūtra, p. lx, Winternitz, Introduction to ApMB, xvi, and Wackernagel I §197e. The following variants are in large measure purely phonetic, due to this traditional instability. But real lexical changes also occur often. Our treatment tries to consider both elements.

s and s

§275. We begin with purely phonetic interchanges, and first those in which § takes the place of regular or etymological s. In a number of cases the root sru, 'flow', of known etymology, appears as \$ru, the Pet Lex goes so far as to postulate a collateral root \$ru\$ in that sense \$sam yor abhi sravantu (MŠ \$ra°) nah RV AV SV VS KS TB TA ApŠ MŠ HG So Conc from Knauer's report of mss, but Vxn Gelder's ed reads \$ra° for MŠ without v 1

vn srutayo (AŚ vnsru°, ŚŚ vnśru°) yathā pathah SV. AŚ ŚŚ One ms of ŚŚ vnsru°

- dadhı mantham parısrutam (ŚŚ manthām parısrutam, one ms °śrutam)

 AV ŚŚ
- ā tvā parısrutah (MG °srtah, mss °srtam, AG °śrıtah) kumbhah (ApMB † °āh) AG PG ApMB MĞ emām (ŚG enam) parısrutah kumbhah (ŚG kumbhyā) AV ŚG—AVPpp ā tvā parısrtah, for which Barret JAOS 32 366 °śrıtah The readings of AG MG, tho certainly secondary, make sense

pratyañ (VS TS ŚB* TB °yañl, MS †* and KS v 1 °yak) somo atidruiah (AV text ati hrutah, VS †* MS atisrutah, KS v 1 °śrutah) AV VS (bis) VSK TS MS KS ŚB (bis) TB ApŚ The true reading of AV is °drutah; see Whitney's note

- §276. The small words sam 'weal', and sam 'together', interchange reciprocally, see §§278 and 280 for cases in which sam is original or both are justified.
- sam ūdho romasam hathah ApMB: sam ūdho romasam hatah RV. Comm on ApMB takes sam as 'Vedic' for sam; see Winternitz, p

§277. The rest are sporadic.

- endrāya tvā sṛmo 'dadāt (ŚG śramo dadat) MS ŚG MŚ SMB Sṛma is a name of an Asura; in the adjoining Brāhmana of MS it is explained by a myth which says that the earth, full of cattle, belonged to Sṛma, and that Indra got the cattle from him. There is no reason to question this myth; cf Sṛpa, Sṛmara, and Sṛmala, names of Asuras (Hariyanśa, see Pet. Lex) ŚG. has a secondary or corrupt reading ('dem Indra gebe dich die Eṛmūdung', Oldenberg). The theme of the passage is branding cattle
- āstām jālma (KS jalma) udaram šranšaynivā (KS srans°) AV KS. Both edd of AV. read thus, some mss śrans° and some srans, none the 'correct' srans°
- sam te hıranyam sam u santv (ApMB sam u santv) āpah AV. Kaus ApMB Metathesis of s and s in ApMB, see Winternitz, p xvi
- somas caturalşarasyāsrīvīr (MS °śrīvīr) nakşatrānı MS. KS A rare word, which however seems always to be written asrīvī except here in MS
- peŝo na ŝukram (KS TB ŝuklam) asitam (MS all samhitī mss aŝitam, ed. em asitam with p p) vasāte VS. MS. KS TB.
- ā šīrṣnah śamopyāt AV., comm. and Ppp samopyāt, which is probably right and is assumed by Whitney. Cf however Bloomfield, SBE 42 255 (keśam opyāt?)
- śwāvrt tat HG Kırste suggests sv-āvrt; the context gives no help in interpretation
- madhu vańsisiya AV Read vańs° cf JAOS 13 cvvm, and Whitney on AV. 9 1 14.
- §278. In the following s takes the place of regular or etymological ś
- sam te hıranyam sam u santv (ApMB. sam u santv) āpah AV. Kaus ApMB See §277, and for other sam: sam, §§276, 280
- [agnim ca viŝvaŝambhuvam RV † AV † KS TB †. Ap S. †. No variant; correct Conc]
- śimāh (VS simāh) krnvantu (VS * samyantu) śimyantah (VS samyantīh) VS TS KSA† The word can only be a form from sim = sam,

- occurring in the same pāda, is the s of VS due to dissimilation? Mahīdhara = $s\bar{l}m\bar{d}h$, glossed $rekh\bar{d}h$ or $mary\bar{u}d\bar{u}h$
- parnasado (SS °sado) jaritah (AV Vait. °dah, om jar°) AV AS SS Vait Original certainly sad-, 'the fall of a leaf' SS possibly understands 'settling down of a leaf' (root sad)
- viśve devā nātividhyanti sarve (KS śūrāh, ApŚ sūrāh) AV KS ApŚ The latter can only intend śūrāh Other cases of these two words, capable of lexical explanation, §284
- yam eva vidyāh śucim (VāDh sucim) apramattam ViDh VāDh N śukeşu me (AV sukeşu te) harimānam RV AV TB ApŠ 3 of SPP's mss, comm, and Ppp (Barret, JAOS 26 228) read śukeşu
- mrgasya srtam (HG. śrtam) akṣnayā ApMB HG (vv ll srutam and śrutam in ApMB) Kirste says 'probably srtam'. More likely śrutam is intended in both texts. It is a question of ill-omened sounds (śakunai ruditam ca yat is the preceding pāda of HG) 'Whatever (cry) of an animal is heard (that is) amiss' For śru sru ef §§275, 283
- pred u harwah śrutasya (SV sutasya) RV SV TS The word refers to Indra, SV is perhaps thinking of Soma Benfey abandons it and translates the RV
- namah śaspiñjarāya (TS sasp°) tviṣīmate VS TS MS †KS See next ye vaneṣu śaspiñjarāh KS ye vṛkṣeṣu śaspinjarāh (TS sasp°) VS TS MS MG See prec Except m TS the word is always written śaṣp°, and it is doubtless connected with śaṣpa (with haplology, Wackernagel I p 279). Perhaps TS gets its s by confusion with sasya 'grain', which is itself sometimes written śasya, cf Wackernagel I c, Keith on TS
- yā na ūrū ušatī višrayāte (AV °li, ApMB HG visrayātai) RV AV ApMB HG Comm on ApMB, šakārasya sakārah, cf Winternitz p xvi
- krīdī (VSK °lī) ca śākī cojjeṣī (ApŚ sākī ţcorjiṣī, v l °jīṣī, ca) VS VSK. ApŚ Name or epithet of one of the Maruts Doubtless 'mighty', root śak, so Mahīdhara, and sākī seems incapable of other interretation
- jīmūlān hṛdayaupaśābhyām (VS °śena, VSK v 1 °sena) VS VSK TS MS KSA
- na jyotīnsi cakāsati Suparn jyotisam na prakāšate RVKh
- trşiam pışıtam asyate AV 5 19 5b Whitney accepts Zimmer's emendation asyate
- yad asravan paśava udyamānam AV 7 66 1 Read or understand asravan with SPP, comm, and Whitney

sarau parnam wādadhat AV 5 25 1 Read or understand sarau with Whitney.

§279. In a couple of phonetic variants the words are so obscure that it is impossible to say which is original

rkso jatūh susilīkā (MS susulūkā) ta utarajanānām VS MS. The pp of MS reads susilīketi susi-līkā, suggesting that VS has the true reading But susulūkā occurs once in RV Both meaning and original form are obscure, folk-etymology may have been at work; Sāyana thinks of sisu and ulūka, in RV. it is associated with ulūka.

grāmyamankīradāsakau Ap\$ grāmyam mangīradāsakau M\$ vyāghram mangīradāsa gauh Vait Obscure proper names, see §49

§280. In some of the preceding there are perhaps possibilities of lexical variation, tho they seem to us too faint to be important. While the line is not hard and fast between the two groups, it seems to us that the following cases are lexically defensible in both forms. Thus the words sam and sam each make sense in these passages, of §\$276, 278-sam abdhyah TS MS ApS MS sam adbhyah (supplying sundhasva from the preceding) KS

 $mand\bar{u}ky\bar{a}$ su sam $\dagger gamah$ (TA gamaya) RV TA . $mand\bar{u}ky$ apsu sam bhuvah AV The latter reconstructs the passage secondarily.

yat ta āsthitum sam u tat te astu TB yat te virislam sam u tat ta etat Vait 'That shall be all right for thee'. 'that which was torn shall be (put) together for thee'

§281. When other changes accompany the alteration of the sibilant, the lexical element becomes clearer Thus in three cases of the roots sam-vas and sam-vas, which are practically synonyms, we are evidently dealing with a primarily lexical substitution, affected by phonetic moments.

teşv aham sumanāh sam višāmi (AŚ višāti, for °ni; MG vasāma) AŚ. ApŚ HG ApMB MG See Knauer's note on MG amāvāsye samvasanto (MŚ °višanto) mahitvā AV TS MŚ

tasyām devā adhısamvasantah TS TB tasyām devaih samvasanto mahitvā AV tayor devā adhısamvasantah ApS yasyām (v l asyām) devā abhı samvısantah MS

§282. The root ās 'sit' varies thrice with augmented forms of as 'attain'; they are practically synonyms in these passages. The ās forms all occur in RV., the as forms in SV, which is contaminated from such expressions as barhir āśāte RV 8 31 6 and 1 144 6: sahasrasthūna āsāte (SV ās°) RV SV.

- samīcīnāsa āsale (SV. āśata) RV. SV yatrāmylāsa āsale (SV. āśata) RV. SV.
- §283. The particle su varies with the reduplicating syllable su; in the first variant also the roots sru and sru, cf. §§275, 278.
- nṛcal.ṣāh soma uta suśrug (comm. and Poona ed text śuśrug) astu TB sucal.ṣāh soma uta sasrud astu MŚ See §145 sasrud is an em for mss sasrad, saśrud, suśud; Conc suggests suśrud, but sasrut occurs in RV., and 'flowing' fits Soma as well as 'hearing'. Perhaps susrui should be read in MŚ
- dṛśe ca (MS dṛśā ca, RV. abhikhyā) bhāsā bṛhatā suśukvanih (RV. śuś°, KS. suśukvabhih, MS suśikmanā) RV VS. TS MS KS SB See §240.
- §284. The words sūra and sūra interchange twice; cf. visve devā etc., §278:
- śūro (TB sūro) na mutrāvarunā gavişļuşu RV. TB The Maruts yoke their chariots in battle like a warrior' or 'as the sun (yokes his chariot)'.
- vīhi śūra (TB sūra) purodāśam (AV. °lāśam) RV AV KS TB. N. The original is addressed to Indra, the 'hero', TB transfers it to an address to the sun
- §285. The word sarva varies a number of times with various words in δ , some of them rather remote in form:
- sarvatah śarvaśarvebhyah (FA śarva sar°; some mss add sarvaśarvebhyah, MahānU sarva sarvebhyah) MS TA MahānU Se namah 'homage to every Śarva', or 'homage, O Śarva (or, O All [comm on MahānU sarvātmaka]), to all (the Rudras)'. MS has v 1 śarvatah for sa vatah Interesting for the thoro-going confusion of the two sounds; despite lexical possibilities, the case is fundamentally phonetic.
- sarvān agnīnr (AV. śivān agnīn) apsusado huve vah (MS huve, AV. havāmahe) AV. TS. MS AP.
- halpantām te (TA. *me) dišah sarvāh (TA *śagmāh) VS ŚB TA (both) viśte derā nātividhyantı sarve (KS. śūrāh, ApŚ sūrāh) AV KS ApŚ See §278
- §286. The root sūd varies with śudh and śubh, cf §174. and note AV radantam śuddham uddharet AV. 20 136 16d, where śuddham is based on mss readings sudam and sunam (Index Verborum)
- asūşudānta (MS KS aśūśubhanta) yazñiyā rtena TS MS KS TB āpo asmān (MS mā) mātarah śundhayantu (TS ApŚ śundhantu, AV MS KS sūdayantu) RV. AV. VS TS MS KS SB AŚ ApŚ

§287. The rest are sporadic, and rather remoter in the formal resemblance between the words in question:

yena striyam (PG śriyam) alimutam (PG ctām, SS striyāv alurutam)

SS SMB PG GG strī is certainly original

šumbhānas (KS stam^o) tanvam (TB tanuvam, SV †tanvām) svām RV. SV MS KS TB

svām tanvam (TS TB tanuvam) varuno 'suşot (TS TB asisret) TS MS KS TB 'Enlivened' 'entered into'

śunam ma ışlam ... svam ma (ma ıdam) ışlam , see §353

tās tvā višantu manasā sīvena (TB mahasā svena) AV TB

yad anena havışāśāste tad aśyāt (AS asyām) MS. SB TB AS SS 'May he obtain that': 'that (is) in this (offering, sc hotrāyām)', or, 'that here in this (offering) shall prosper' (the following words are tad rdhyāt). Earher in the same section occurs asyām rdhed dhotrāyām

śakma yat te goh KS MS · sagme te goh VS SB KS. samyat te goh TS See §47

tasthau nākasya sānavi (SV sarmani) RV. SV

apāvrnod duro asmavrajānām (MS asmadrathānām) RV MS TA

śwātrāh pītā (V1Dh snātāh prītā) bhavata yūyam āpah VS ŠB KŠ V1Dh

sadā (MS šacyā) pašyaniı sūrayah RV AV SV VS. TS MS KS ŠB NrpU GopālU VasuU SkandaU

tad asya priyam abhi pātho asyām (TB asthām) RV MS. AB. TB AŚ Poona ed text and comm asyām for TB, see VV I p 86.

aryo nasanta (SV nah santu) santsanta (SV †°tu) no dhiyah RV SV See Oldenberg, Proleg 72

āšum jayantam anu (KS yā samjayantam adhi) yāsu vardhase RV. VS TS. MS KS ŠB Even the original version is obscure

ā sutrāvne sumatım āvrnānah AV Perhaps orıgınally āśutrāvne, see §355

ś and ş

§288. Here the total number of variants is much smaller. Moreover many involve lexical changes, while most of the rest concern rare
and doubtful words, the true original form of which is uncertain. The
genuine phonetic variants are few, and none too certain in some instances. In the following & seems to replace proper & phonetically
nained devā āpnuvan pūrvam arṣat (VS arṣat) VS VSK IṣāU. The
word clearly means 'going' (root rṣ), VS comm rṣa gatau. Cf
however anarṣatīm (alarṣirātīm)... §292

abhyaşıkşı rājābhūm (MS v l °bhūt, ApŚ °bhūvam) MS ApŚ abhrśıkşa rājābhuvam (v l °bhūvam) MŚ (quoted from unedited mss, probably only a textual error)

§289. We find s for proper s, aside from a few corruptions, only in the name of an Asura, Sanda or Sanda The weight of evidence seems to favor the spelling with s.

śandāya (VSK şa°) tvā VS VSK TS MS ŚB ApŚ

nırastah śandah (VSK MS † *4 6 3 şa°) VS VSK MS (bıs) ŚB TB KŚ ApŚ MŚ

apanutiau (KS °tā) sandāmarkau (MS * şa°) TS MS (bis) KS TB ApŠ MŚ See von Schroeder's note on MS 4 6 3 82 16, which indicates that he then believed MS to intend şanda thruout But need it have been consistent? The mss are unanimous for ş in some places, nearly unanimous for s in others Those of MŚ vary Corruptions

yenāpāmṛsatam (SMB v 1 °ṣatam) surām \$\$ SMB yenāvamṛsatām surām PG

varuneti sapāmahe (MS†°hai, LS †sayāmahe) VS TS MS KS SB TB AS SS LS The LS has probably a mere misprint

[kavaşyo koşadhāvanīh (MS text kośa°, all mss koşa°, TB† 'koşa°)
MS KS TB Read 'koşa° in all There would be no variant but
for the em in MS, which is unjustified, althouthe word meant is
that more commonly written kośa]

§290. The following variants seem also to be purely phonetic, in so far as not mere corruptions, the obscurity of the words makes it impossible to decide which is original

ındrānyaı kīrsā (KSA °ṣā) TS KSA

rk so jatūh susilīkā (MS šušulūkā) VS MS See §279

 $k\bar{u} \hat{s} m\bar{a} \tilde{n}$ (VSK † v 1 , MS $k\bar{u} \hat{s}^{o}$) chakapında
ıh (MS $\hat{s} a^{o}$) VS VSK MS $k\bar{u} \hat{s} m\bar{a} \tilde{n}$ chakablı
h TS KSA

kūṣmāndāh, ku°, and kūṭ°, kuṣ°, also °māndyah and °māndānı, various Dharma texts, see Conc Names of certain expiatory verses

ākaršye karšyo yathā ApS gīh kosvoşyaur yadā gırah Vait madhv ity ākarşaih kusair yathā KS The meaning of the whole passage is obscure

§291. Coming to lexical variations, we find three cases of visva varying with vişu (vişvak), the meanings are fairly close

višvam salyam krnuhi vislam astu RV visvak salyam krnuhi cillam esām AV See Bloomfield, The Atharvaveda 50, Whitney on AV 3 1 4, Oldenberg, Nolen on 3 30 6 [But no emendation of AV

- is necessary. Render: 'Make accomplished on all sides the purpose of these (our party)' Ppp (Barret, JAOS 32. 351f) has viśvam vistam krnuhi salyam eşām, closer to RV. Same general sense in all F. El
- adhı kşamı vışurüpam (ArS kşamā vıśva°) yad asti (ArS asya, MS† āsta) RV AV ArS MS TB (Add to VV I §229 for the verbs) purudasmo vişurūpa (KS °dasmavad visvarūpam, TS. ApS. urudrapso
- viśvarūpa) induh VS TS KS SB ApS
 - §292. The rest are isolated and unclassifiable:
- ınarsarātım (SV alarsırātım) vasudām upa stuhi RV. AV. SV. N The RV. form is derivable from root rs 'injure'; cf Neisser, ZWbch. d RV, s v. The SV form seems on the face of it to contain the root r, it may be corrupt Benfey, 'rasche Spende habend'.
- nābhimīse (MS KS nābhidhīse) tanvā (TS tanuvā) jarbhurānah (TS MS KS. jarhīsānah) RV. VS TS MS KS SB 'Not to be touched (attacked)'
- asya hotuh pradišy (AV. prašisy) rtasya vāci RV. AV. VS MS KS TB N Synonyms: 'at the command'.
- prānān samkrośaih MS . samkrośān prānaih (VS. °krośaih prānān) VS TS samphosān (ms °gosān) prānaih KSA Synonymous roots krus and ahus
- vavor vām devau devesv anisitam (TS aniso) ojah TS MS KS. 'Undestroyed', from a- and pple of ni-syati, 'incessant', a-nisita
- sam ivā sisanii (Vait siso) Vait LS KS Garbe takes sisanii from sis 'leave'; it is more likely from sas (sis) 'ordain'. Caland apparently rejects it as corrupt, for he translates sisanti ('sharpen')
- vanaspatīnr osadhī rāya ese (*rāye asyāh) RV (both) Roots is and as, practically synonyms The two versions in adjacent hymns, see RVRep 258 Add to VV I §121, 324
- aspārsam enam šatašāradāva RV AV In AV most mss, SPP, and even Ppp (Barret, JAOS 26, 257), read aspārsam, in spite of Whitney, who keeps the RV form in his Translation (root spr, aor.), we think that the AV tradition intended asparsam, as a form of sprs. 'I have touched him with (life of) a hundred years' Of course the form is highly anomalous
- dīrghām anu prasitim (KS samṛtim) āyuşe dhām (KS tvā) VS TS MS SB TB dīrghām anu prasrim samsprsethām MS Cf §78
- ire ışah (KS viśve, MS iva eşah) samdadhur bhūrıvarpasah (TS † bhūrıretasah) RV. SV VS TS MS KS SB
- praināso agna riam āšusānāh (AV āsašānāh) RV AV. VS TS 'Blowing upon': 'sharpening' (both practically 'furthering, tending')

- abhıştır (HG °tīr, ApMB abhıştır) yā ca no grhe (RVKh ca me dhruvā) RVKh ApMB HG
- \bar{a} darşate savasā sapta dānūn RV AV N \bar{a} daršatı savasā bhūryojāh AV The whole thought is made over in AV
- atrā te bhadrā raśanā apaśyam (KS bhadrā vṛṣanā agṛbhnām) RV VS TS KS
- aśūśubhanta (TS TB asūṣudanta) yajñıyā rtena TS MS KS TB See §286

s and s

§293. Here there are only a very few variants, and their phonetic interest is slight. Usually the change is due to a change in the preceding vowel from an a to an 'alterant' i, u, or to different word-division which brought s into another word where it follows an alterant vowel. The list is not complete

dawyā mmānā manasā (VS manuṣah) purutrā VS MS KS TB made susipram (SV madeṣu sipram) andhasah RV SV Cf PAOS 13, p exviii

āprno 'sı samprnah (ApS āprnoşı samprna) SS ApS The latter is corrupt

vasışthahanuh VS oşışthahanam TS TA

sugantuh karma karanah karaşyan JB sugam tvah karmah karanah karah karasyuh LS

tenemām upa siñcatam RV AV TA N tena mām abhişiñcatam ŚŚ asūrte (MS KS °tā) sūrte rajasi mṣatte (MS °tā, KS na sattā) RV VS MS KS N See §828

kratvā varistham vara āmurim uta RV AV kratve vare sthemany āmurīm uta SV

rşīnām ca stutīr (SV sustutīr) upa RV SV VS TS MS KS §294. The rest are scattering

ye vylşeşu (KS vaneşu) saşpıñyarāh (TS saspı°) VS TS MS KS MG See §§32, 278, and next

namah saspıñjarāya (TS saspı°) tvişīmate VS TS MS † KS

sarvam tam (AV sarvān ni, MS KS TA sarvāns tān) maṣmaṣā (TS SB, masmasā, MS † mṛsmṛsā, one ms mṛśmṛsā, VS bhasmasā) kuru (AV -karam) AV VS TS MS KS SB TA The word is sound-imitative (cf Eng mash, similar but independent) VS rationalizes with thought of 'ashes' (§242)

ā sutrāvne sumatım āvrnānah AV oşışihadāvne sumatım grnānāh TS Whitney suggests, attractively, āśutrāvne (to match oşışiha- in

TS); but su-trāman, su-trāta, and su-trātra seem to support the tradition of AV (āšu seems not used with the root (rā).

kh, ks and sibilants

§295. In view of the common later confusion of \$ and kh, it is surprising to find practically no variants between these sounds, of the mes. reading sudas at AV. 20 135 4, for khudas of SS:

kaşolkāya svāhā TA TAA.. khalholkāya svāhā MahānU Neither word is interpretable

§296. There are, however, a couple of cases of variation between lh and \acute{s} , which point in a like direction, of the reading $khun\~a$ for $\acute{s}un\~a$ (thru $\~sun\~a$) 'by a dog', Pārsvanātha Caritra 2 268.

āšum tvājau (ApŚ ākhum tvā ye) dadhīre devayantah KS ApŚ MŚ The original is āšum, which refers to Agni To make a 'mole' out of Agni seems sufficiently absurd, but the reason is plain. The viniyoga of the sūtra, in both ApŚ and MŚ, reads ity ākhukarīṣam (MŚ *kirim) nivapati, 'he throws down a mole-hill'. Hence the word ākhu has crept into the sūtra in ApŚ (where Caland translates āšum)

ud vanšam wa yemire RV SV TS. KB. N· ūrdhvam kham wa menire Mabābh 12 284 78

§297. And one case of ks and & (levical).

mayum te sug rehatu (KS te kşut) VS MS KS SB The same with other animal names in the same passage

s(\$) and h

§298. There is but faint evidence for this interchange. The few instances are all lexical or morphological, or else very much under suspicion of corruption. In so far as phonetics may be concerned as a contributory factor, we may call the change quasi-Prakritic, see Wackernagel I §221, Pischel §264. In the following it is to be presumed that an original s is replaced by h.

dhiyū na (SV no) vārān upa māsi (SV māhi) šašvatah RV SV Verb endings, see VV I p 101 The reverse is found in the first variant in §299

dhruvāsah (TB ApS dhruvā ha) parvalā ime RV AV. KS TB ApS SMB MG The obsolescent ending āsah is replaced by the regular ā(s) plus the particle ha

jātavedo nayā hy enam sukrtām yatra lokah JB· jātavedo vahemam (SS vahasvarnam) sukrtām yatra lokah (TA lokāh) TA SS. The Conc. suggests possibly nayāsy for nayā hy in JB

- āsannışūn hrtsvaso mayobhūn RV AV TS MS KSA N $\,$ āsann eşām apsuvāho mayobhūn SV $\,$ See §820 $\,$
- [pratyan (etc) some attitutah (°srutah etc, AV text °hrutah), see §275 The true text of AV. is °drutah]
 - §299. In the rest it appears that an older h is replaced by s
- stuto yāsı (RV yāhi) vašān anu RV VS TS KS ŠB LŠ See VV I p 105 The converse of the first variant in §298
- turīyādītya (VSK. turyā°) savanam (RV hav°) ta indrīyam RV VS VSK TS MS KS SB Synonymous roots su and hu
- ghṛtapruṣo haritas tvāvahantu KS . ghṛtapruṣas tvā sarito vahanti (AŚ harito vahantu) TB AŚ ApŚ
- guhā hitām nihitām (KS † omits nihitām, by haplology) gahvareşu KS MS · guhā satīm gahane gahvaresu TB ApS
- pratno hi (TA pratnoși) kam īdyo adhvareşu RV AV TA MahānU The TA reading is corrupt, comm pratanoși!
- [suhaveha (AV. misprinted susaveha) havāmahe RV AV VS MS KS See Whitney on AV. 3 20 6]

CHAPTER IX PRESENCE OR ABSENCE OF NASALS, SEMI-VOWELS, LIQUIDS, SIBILANTS, H, AND VISARGA

1 Presence or absence of nasals and anusvara

§300. This phenomenon occurs mainly but not exclusively before consonants. When it occurs before vowels, it is really a matter of sandhi, namely, of the use of a nasal as a sort of 'Hiatus-tilger', to bridge the gap between two vowels; the semi-vowels are used in the same way. Before consonants, it is to some extent rhythmic, and therefore of genuinely phonetic bearing, even the rarely if ever purely phonetic, since morphological or lexical considerations play a part. This rhythmic shift is Prakritic in character, see Geiger, Pali §§5, 6; Edgerton, Studies in Honor of Hermann Collitz 32. It appears most clearly when a short vowel followed by a nasal or anusvara varies with a long vowel without nasal. Thus in variant forms of the same word, or at least from the same root.

ya eşa svapnanansanah (AV °nāsanah) RV. AV N.

pūṣne 'āghṛnaye svāhā TA ' pūṣna āghṛnaye (em , mss āpṛṇaye) svāhā MŚ āghṛni is a regular epithet of Pūṣan For aūghṛni, comm. añjanena dīpyamānah, but it can only be a phonetic variant or semi-corruption for āgh'

§301 From different and equally regular forms of the verb:

agnım naras trişadhaslhe sam īdhıre (SV TS 2ndhate) RV. SV. TS KS. agnım īdhe (SV 2ndhe) vıvasrablıh RV SV

atra pitaro yathābhāgam mandadhvam TS TB Ap\$ · atra pitaro mādayadhvam VS VSK MS KS ŚB A\$ \$\$ L\$ M\$ Kau\$. SMB. GG KhG. V1Dh Add to VV I \$240

krūram ānanša (KS † ApS ānāša) martyah (KS † martah) AV. KS. ApS See VV I p 187

na papatrāya rāsīya (SV ransışam) RV AV SV See VV I p. 109.

§302. In words not etymologically related, but more or less similar in sound.

atho (LS ApS nur mā) yamasya padbīšāt (VS °vīšāt, LS† şadunšāt) RV AV VS LS ApS See §217

agnım īdīla (SV ındhīla) martyah RV SV. Cf next; both verbs are common in Agni-worship

yam sīm ıd anya īdate RV yam sam ıd anya ındhate SV. Cf prec

yācad (SV. TS. KS. yanead) vikram ny atrinam RV. SV. VS TS. MS. KS. Roots yā and yam quasi-synonyms

ato no 'nyat pitaro mā yorla (HG. yūdhram) Apš NS. HG.: mā vo (AS no) 'to 'nyat pitaro yoyurata (AS. yuūgdhram) AŠ. Kauś. If we may 'trust yuūgdhram, the other verbs are from yu 'unite', therefore synonymic. Ci. VV I pp. 42, 150

āpo aemān (MS. mā) mātarah śundhayantu (TS. ApS. śundhantu, AV. MS. KS. sūdayantu) RV. AV. VS TS MS. KS. SB. AS. ApS.

§303. Rather more numerous are cases in which the absence of the nasal does not involve a long preceding vowel, but is due to sundry morphological circumstances which admit of closely related forms with or without nasal. Accidents of nominal and verbal inflexion occasionally involve presence or absence of a nasal. These variations are of course primarily morphological; at most they may be said to have a certain phonetic aspect, so that they are not wholly unrelated to the phonetic shift here considered. It would hardly be profitable to list them all here. So far as they concern verb forms they will be found in VV I: see §192 there (interchange of nasal and non-nasal presents), §210 and 217 (nasal presents or imperiects varying with non-nasal aorists, as vida: vinda, vrjyāḥ: vrājyāt, etc.); §279 (masāya· maisāya); §280 (adadrhanta: adadrhanta); and many variations between 3d persons singular and plural in ti, nti, te, nte, etc., on pp. 255 ff.

§303a. Twice subjunctives in $-(\bar{a})si$ are reported with an anomalous \hat{n} before the s. We might be tempted to emend the sole ms. of KS. in the second; in the first no v. l. is reported for SG. and Oldenberg keeps $vy\bar{a}nsi$, the he translates $vy\bar{a}si$ (see his note, p. 36):

jālānām janayās ca yān (ŚG. janayānsi ca; AVPpp. janayāsi [not °mi, as Whitney says] ca) AV. ŚG Barret, JAOS 32. 360, needlessly emends Ppp. to the Ś reading Add to VV I §253.

§305. Again, in other cases we find stem-forms with and without nasals, involving no real grammatical change. These concern stem or word formation:

urcī gabhīrā (TS gambhīrā) sumatis te astu RV. TS. MS. KS. In this

and the next TS replaces an antiquated form with one which is regular in the later language.

gabhīram (TS. gambh°) ımam adhvaram kṛdhi VS TS MS SB Cf.

samudra wāsı gahmanā (TB ganh°, but Poona ed gah°) TB ApŚ satyaujasā drnhanā (KS † drhanā, MS durhrnā) yam nudethe TS MS KS. sacctasau druhvano yau nudethe AV Both TS. and KS.

KS. sacctasau druhvano yau nudethe AV Both 18. and KS. understand a form of drh drnh (cf adadrhanta adadrnh, VV I p 187); AV and MS struggle in common with another idea

antah subhrāvatā (SV. sundhyātatā) pathā RV. SV Cf §173

samudrāya śiśumārah VS MS: sindhoh śinsumārah (KSA † śiśū°) TS KSA The form śinśu° occurs in RV; cf. Pali sunsumāra Later śiśu° is regular, but it may well be only a secondary adaptation by popular etymology to śiśu 'boy' The long ū of KSA. may be a mere corruption in the single ms

§306. The prefix sam varies with its own reduced grade, sa-, and with a syllable sa- of other sorts (some of the cases textually dubious):

samvid ası TS savid ası VS KS. PB: savitā savite savij jinva MS. samstup chandah VS MS KS. SB: sastup chandah TS.

namo vrddhāya ca savrdhe (TS samvrdhiane, KS savrdhvane, MS savrdhvane) ca VS TS. MS KS

satatam tu śirābhis tu MahānU · samtatam śirābhis (Poona ed śilā° v l. śirā°) tu TA

nakşatrānām sakāšān mā yauşam MS : nakşatrānām mā samkāšaš ca pratīkāšaš cāvatām Vast Kauš

agne sasrjmahe (MS samsr°) girah RV SV. MS KS Here sa- is the reduplicating syllable

sa (MS sam) dundubhe sajūr indrena devaih RV AV VS TS MS. KSA N The MS hardly makes sense; it is probably due to assimilation in meaning to sajūr

sam (MS sa) dāśuşe kıratu bhūrı vāmam TS MS AS. ŚŚ Again MS is hardly interpretable, its change is the reverse of the prec.

sam yajñapatır (VSK yajamāna) āśiṣā VS VSK. TS. MS KS. ŚB ŚŚ KŚ ApŚ MŚ: sa yajñapatır āśiṣā Vait (probably to be corrected to sam, see Caland on Vait 4 21)

§307. Other cases of final anusvāra before consonants (cf. also §401): rayobhūmis tvam mām (Mahān U. tvam ām, so TA. Poona ed with v. l tvam mām) rodayasva pravadanti dhīrāh TA Mahān U.

tato (PB te) ha jajñe (MŚ 'ham yajñe) bhuvanasya gopāh (MŚ goptā) TB PB ApŚ MŚ See §192, MŚ clearly secondary va īm vahanta āšubhīh RV yadī vahanty āšavah SV

svahpatır yadī vrdhe SV svarpatım yad īm vrdhe RV AV

yo rayivo (SV rayim vo) rayintamah RV SV KB SS SG The SV doubtless corrupt

tasvām no devah (MS tasvām devah) savitā dharmam (VS † VSK † TS † SB † dharma) sāvisat (VSK ° sak) VS VSK TS MS KS SB. Stems dharma dharman

mā mā yūnarvā hāsīt (JB yono vām hārasīh) PB JB LS Incomprehensible in either form

sa īm (TS ī) mandrā ... (see §374) VS TS MS The particle īm becomes $\bar{\imath}$ in TS, before m, this might be put with §401 sam īm (SV u) rebhāso asvaran RV AV SV

Nasal as 'Hiatustilger'

§308. The Rigyeda itself has a number of instances of nasalization of a final vowel before an initial vowel, in heu of regular sandhi the nasal (in the recognized RV cases always anusyāra) acts as 'Hiatustilger' See most recently Oldenberg, Noten on 1 33 4 variants present one of these instances in which secondary texts leave the hiatus unrelieved, and in another case ApMB MG read tanun for RV tanu, all intending a loc sing

svāyām †tanūn (RV tanū) rtviye (RV † °vye) RV ApMB MG See Winternitz, Introd to ApMB, XIX Knauer mistakenly considers the form an abbreviation of tanvam

ā te suparnā aminantan (MS TS °ta) evaih RV, TS MS KS AB

§309. Somewhat similar are cases in which other nasals, n or mseem to act in the same way as 'Hiatustilger' between vowels, or, conversely, we find in some texts omission of final m before an initial vowel. either with secondary sandhi of the two vowels thus brought into proximity, or leaving hiatus

yadīn (AV yady) rnam samgaro devatāsu AV TA Comm on TA yadīn mam, yad eva prasiddham mam. We must apparently understand in for im (aliter $\bar{\imath}$), the particle of emphasis, the TA form is unprecedented and suggests an attempt to avoid hiatus A heavy syllable is favored as the second syllable of the pada, cf **§438**

abhīm riasya (SV abhy riasya) sudughā ghriascutah RV SV The SV, the secondary, suggests light pronunciation of the final nasal, felt as if mere Hiatustilger

abhī (SV abhīm) rtasva dohanā anūsata RV SV

- yenāksā (SMB °kṣān, PG °kṣyāv, ŚŚ yenā kṣām) abhyaṣicyanta (ŚŚ SMB abhyaṣiñcatam, PG. °tām) AV. ŚŚ SMB PG Nom.: acc. forms
- \bar{a} $p\bar{u}s\bar{a}$ etv \bar{a} vasu TS: \bar{a} puslam etv \bar{a} vasu AV. If TS has the original form, AV. may be regarded as a lect fac, with avoidance of hiatus.
- agner jihrām abhi (MS jihrābhi, p p jihrām, abhi; AV. KS. jihi ayābhi) †gṛṇālam (AV gṛṇata) AV. VS TS. MS. KS. 'Sing to (with) the tongue of Agni.' MS might intend an instrumental, but note the p p
 - §310. Miscellaneous non-final nasals, before consonants:
- agnır ukthena vähasä VS TS MS KS AŚ. ŚŚ: agnir uktheşi anhasu AV. apām rasam udvayasam (KS udayansam, TA. udayansan) VS. TS. MS. KS ŚB TB TA
- agnim adya hotāram avīnītāyam yajamānah pacan paktīh (VSK. paūktīh) pacan.. VS VSK. MS. KS. TB. (See also Conc. under sīsena agnim adya etc, TB, but Poona ed. of TB. lacks the word sīsena, which is also shown to be an intrusion by the lack of sandhi.) paūktīh 'heaps' is secondary or corrupt The same blunder in Kauś 22 10; see Bloomfield, GGA 1902 492.
- §311. Miscellaneous non-final nasals before vowels (once before y); to these should be added a few cases of presence or absence of initial nasal consonants which we have placed below in §421, where they seem more properly to belong:
- tam āhutam našīmahi (AV "tam aś") RV. AV. AB. Parallel roots aś and naś
- tasya rathag
rtsaś (MS °krtsaś, KS °krtsaś) ca \dots VS. TS MS. KS. ŚB See §46
- namah kṛtsnāyatāya (VS. °yatayā, KS kṛtsamvītāya, TS. MS kṛtsnavītāya) dhāvate VS. VSK. TS. MS KS. A sort of metathesis of nasal in KS.
- na kir devā minīmasi RV.: na ki devā inīmasi SV. Svidh. The strange inīmasi is questioningly classed by Whitney (Roots) as an isolated 9th class present from i(-noti) Benfey equates it with min° with unexplained loss of m Reverse of Hiatustilger?
- sam tvā tatakşuh (LŚ °kṣnuh) Vait. KŚ. LŚ. See VV I p. 146. The monstrous form of LŚ may be influenced by its viniyoga: its takṣnuyuh (itself somewhat anomalous).
- agnaye dhūnkṣnā (KSA. °kṣā) TS KSA.: dhunkṣāgneyī (VSK. vv. II. °kṣyā and °kṣvā) VS VSK. MS. Possibly the second naṣal of TS. is due to the influence of the first.

- annam me (ApŚ *no) budhya (ApŚ °dhnya) pāh, and °yājugupah MS ApŚ One ms of MS writes buddhya each time, perhaps budhnya is intended
- Cf jīvām rlebhyah (read mr° with SPP, comm, and many mss) parınīyamānām AV
 - §312. Note finally the following curious variant
- kāyamāno (MŚ kāmayamāno) vanā tvam RV SV MŚ N Sāyana glosses by kāmayamāno, the later regular form, which is secondarily introduced in MŚ

2 Presence or absence of y

§313. A large proportion of the variants under this head concern the presence or absence of suffixal ya A form containing this suffix varies with a corresponding form without it, usually either a primary noun or adjective in a, or a secondary derivative in suffixal a. These cases belong to Noun Formation and are to be dealt with there more fully. To some indeterminate degree they also concern phonetics, notably where y appears after a double consonant in such pairs as bhakşa bhakşya, etc. Metrical considerations enter to some extent, the form with y may be read as a syllable longer than the other form, and this occasionally has import for our judgment of the variation, as will be pointed out in individual cases

(a) Words equivalent in meaning, y follows two consonants

§314. We begin with cases where the y follows two consonants (and is often written, and regularly pronounced, iya, see §784), and in which the form in y is equivalent in meaning to that without y. The latter in a few instances is formally proved to contain the secondary suffix a by showing vriddhi of the first syllable, while the y form lacks vriddhi aghorena caksusā mitrivena (ApMB maitrena, KS ApS caksusāham

śwena) AV KS ApŚ ApMB But maitrena may be a noun, 'friendship', mitriyena must be an adjective

māham pautram (KBU putryam) agham rudam (AG niyām, see §724, SMB nigām, and riṣam) AG SMB ApMB HG KBU

ya āntarıkşāh (sc. sarpās etc.) HG $\,$ ye sarpāh pārthıvā ye antarıkşyā AG

vāyur na īdīta īdītavyair devair antarīksyaih (ApŚ āntarīksaih) pātu KS ApŚ: vāyus tvāntarīksāt pātu sūryo dīvah MŚ The latter contains the primary noun and belongs with §321

prabhāyā agnyedham (TB āgnendham) VS TB On the troublesome TB form see §491

- §315. In the rest, the great majority, secondary vriddhi appears in neither form or in both:
- sumnāya sumninī sumne mā dhattam TS TB ApS: sumnāyuvah (KS "yavas) sumnyāya sumnam (KS sumnyam) dhatta MS KS. sumne sthah sumne mā dhattam VS SB Both sumna and sumnya are used as both adjectives, 'gracious', and nouns, 'grace'
- agnır devebhyah suvidatriyebhyah (TA. °trebhyah) RV AV TA N.

svargasi KS · svargyasi ApS

- ūrdhvam manah svargyam (TA suvargam) MS TA
- na yajñasya manvate martyāsah (TB Ap\$ martāsah) RV. KB TB Ap\$ The reading martāsah is poor metrically
- krūram ānanša (KS † ApŠ ānāša) martyah (KS † martah) AV KS. ApŠ Agam martah is unmetrical
- marteşv (VS MS KS martyeşv) agnır amrto nı dhāyı RV VS TS MS KS ApMB
- sumıtrā (VS SB MahānU SS KS sumıtrıyā, AS LS sumıtryā) na (KS na) āpa osadhayah santu (KS † °yo bhavantu) VS TS MS KS SB TB TA MahānU AS SS LS BDh Followed by:
- durmıtrās (VS SB MahānU KŚ °triyās, AS SS LS °tryās) tasmai santu (KS * TS † TB TA MahānU BDh bhūyāsui) yo ..., same texts
- śārgah srjayah (TS KSA ākhuh srjayā) śayāndakas (KSA °kās, em v Schr °kas, TS śayandakas) te maurāh (KSA °tryāh, em unnecessarily to °trāh in ed) VS TS. MS KSA
- abhi dyumnam (RV VS sumnam) devabhaktam yavışiha (MS KS devahıtam yavışihya, MS p p °şiha) RV VS TS MS KS ApMB yavışiha and 'ihya are perfect equivalents, the former seems to be preferred at the end of a tristubh pāda, the latter of eight and twelve syllable pādas
- tvām agne samıdhānam yavışiha (RV °ihya) RV. TB. ApŚ The ştanza is pure jagati in RV , half of it is made triştubh in the others
- śałam pūrbhir yavışthya RV · yavıştha pāhy anhasah RV TA See RVRep 539
- gambhīrebhih (AV TS HG °raih) pathibhih pūrvinebhih (MS pūrvebhih, AV pūryānaih, TS HG pūrvyaih) AV TS MS KS SMB AS HG
- brhat sāma kṣatrabhṛd vṛddhavṛṣnyam (MS °nam, so ed with p p, other mss °nim, read probably °nyam, TS °vṛṣniyam) TS MS KS AS
- tāsām visisnānām (KS °nyānām) MS KS

amo nīveṣyāya (p. p nī°) ca hṛdyāya ca MS: namo hṛdayyāya ca nīveṣyāya ca VS.: namo hradayyāya (KS hradavyāya) ca nīveṣyyāya (KS. °ṣyāya) ca TS KS From the noun rīveṣya 'whirlpool', is derived nīveṣyyà 'of the whirlpool'. The stem nīveṣya (or nī°, note accent) is equivalent to this latter and is probably merely a phonetic simplification of it; practically a question of mere orthography. One KS. ms nīveṣyyāya

namah sīghryāya (TS sīghriyāya) ca sībhyāya ca VS TS: namah sībhāya ca sīghrāya ca MS KS

tau te bhakşam (LS °şyam) cakratur agra etam VS JB TB ApS LS SS tayor anu bhakşam bhakşayāmi TB. ApS : tayor aham anu bhakşam (LS °şyam) bhakşayāmı VS. LS : tayor aham bhakşam anubhakşayāmı JB SS

jaitrāyā (ApMB °tryāyā) visatād u (HG. °tām, ApMB °tān) mām RVKh VS. ApMB. HG.

devānšo yasmai tvede...bhañqena (ApŚ bhañgyena) VS ŚB ApŚ yamam bhañgyaśravo (KS MŚ bhañga°) gāya KS TA. ApŚ MŚ yamam gāya bhañgyaśravah (KS MŚ bhañga°) KS TA ApŚ MŚ maṇdūkāñ jambhyebhih (KSA. jambhaih) TS KSA TB. ApŚ jambhābhyām taskaran (p p °rān) uta MS: jambhyais (KS. °yebhis) taskarān (KS T °rān) uta VS TS KS.

aśtasya vāje (KS krande, TB. krandye) puruşasya māyau AV KS TB yo'sya (MŚ asya, but Van Gelder 'sya) kauşihya (KS kausiha) jagatah KS TS ApŚ. MŚ.

štelāya raidarvāya (PG °vyāya, AG. ŚG. °dārvāya, MG vaitahavyāya) .. AG PG. ŚG ApMB. HG MG

pāpāt svapnyād abhūtyāh AV. · pāpah svapnād abhūtyai KŠ It would be pedantry to see in svapnya any really different meaning from svapna [inatamam āptyam (AV. āptam) āptyānām RV AV. N The AV. must doubtless be emended to āptyam with Whitney]

(b) Words equivalent in meaning; y follows one consonant

§316. Next, forms in which the y follows a single consonant, both forms still equivalent in meaning. A small group shows the vriddh of secondary derivation in the form without y, not in that with y meghyā (VS maighār) vidyuto vācah VS TS MS KSA

brhanto dairāh (VS divyāh) VS MS ApS divya from div, daira from dera, but meaning the same.

achınno dıvyas (KS ApS daıvyas) tantur mā mānuşas (KS ApS manuşyas) chedi MS KS ApS See next

brhaspatir devānām (SS. dawo, this belongs to §324) brahmāham manuşyānām (SS mānuşah) VSK. TB SS KS ApS MS: brhaspatir brahmāham mānuşah LS mānuşa and manuşya are precisely equivalent in all uses, tho here the former happens to be an adjective, the latter a noun Cf. prec

kalpayatam mānvşīh TB ApS drihantām davvīr višah kalpantām †manuşyāh KS

dhişanāsi pārvatī (VS ŚB par°, TS TB ApŚ parvatyā) VS TS MS. KS ŚB TB ApŚ MŚ Adjectives pārvata and pariatya (and, if VS ŚB are right, parvata. Mahīdhara, parvatātmikā); all 'of the rock' The VS ŚB. reading is supported by the ms readings (two occurrences) of KS, parvatī both times, von Schroeder has emended, with doubtful justice

aranyāya (MS āranāya, but p p aranyāya) sīmarah VS. TS MS KSA. §317. The rest show vriddhi either in both forms or in neither. Among them stands out a considerable group of cases of the perfectly equivalent stems dawa and dawya:

davo (HG °vyo) yo manuso gandhah ApMB. HG

dawā hotārah sanışan na etat AV.: dawyā hotāro (TS. °rā) vanuşanta (TS vanı°, KS †vanışan na) pūrve (KS etat) RV. TS KS.

dawyā (AV °vā) hotārā (TS °rāv, AV. °ra) ūrdhvam (MS adds mam, KS hotārordhvam mam) adhvaram nah AV. VS Ts. MS. KS 18 17a (†)

dawyam (MS °vam) mānuṣā yugā (MS yujā) RV SV VS TS. MS. ŚB

pauruşeyâd dawyāt KS : pauruşeyān na dawāt AV. 4 26 7c mānuşād dawyam (MŚ $^\circ$ vam) upaımı TB ApŚ. MŚ

sam davena (VS SB both also °vyena, TA devena) savitrā VS SB TA Mahīdhara glosses both forms by devena

§318. Another compact group is formed by variants of sūra and sūrya, again perfect equivalents.

brhat sūro (KS. sūryo) arocata RV KS

sūryāso (SV sūrāso) na daršatāsah RV. SV

sajūh sūra (MS sūrā, TS sūrya) etašena VS TS MS KS ŠB sa sūra ā (ŠŠ sūrye) janayañ jyotir indram (ŠŠ indrah) TB ŠŠ

spardhante dhiyah (TS KSA divah) sūrye na (SV sūre na, TS. KSA T sūryena) visah RV SV. TS KSA

§319. The rest are sporadic:

āpura stā mā prajayā paśubhih pūrayata ŠŠ · āpūryā sthū mā pūrayata prajayā ca dhanena ca TS AŠ

- agneh purīsavāhanah (MS purīsya°, VS † SB † °vāhaņah) VS TS MS KS SB purīsa and °sya are equivalent, Pān 3 2 65
- kāmāyai svāhā MG· kāmyāyai svāhā MS MS. Probably MG. corrupt
- śakalyam (AG śākalam, sc tarpayāmi) SG. AG Both patronymics from śakala Since Oldenberg's translation of SG reads śāko, we assume that śākalyam is the true reading, śao probably misprint
- yakşmam śronibhyām (ApMB. śroni^o) bhāsadāt RV AV. ApMB. yakşmam bhasadyam śronibhyām bhāsadam AV In RV bhāsada is a noun, in the second AV version it and bhasadya are both adjectives, and one (probably bhasadyam, but Whitney suggests bhāsadam) must be omitted as an ancient gloss
- rāyas rosam audbhidam (ApMB. °dyam) RVKh VS HG ApMB pā amānāh, °nyāh, and °nyah, various Dharma texts All adjectives from pavamāna.
- māyobhavyāya (ŚG āyo°) catuspadī AG ŚG . catvārī māyobhavāya TB ApŚ ApMB SMB PG HG MG Equivalent nouns
- adveşe (MS °şye) dyāvāpṛthivī huvema (MS huve) RV. VS MS 'Having no hostility' = 'not hostile'.
- [mıtrāvarunābhyām ānuşļubhābhyām . VS TS MS KSA† Conc wrongly quotes KSA as ānuşļubhyā°]
- anyam te asman (NrpU. 'sman, AV. asmat te) nı vapantu senāh (AV senyam) RV. AV TS NrpU Senyam must = senā
 - (c) Words not equivalent in meaning, y follows two consumants
- $\S320$. In the rest, the two variant stems are not precisely equivalent to each other. In many cases the derivative adjective in ya is paralleled by a case-form of the primary noun or its equivalent, or by the primary noun used appositionally, or by a compound of it. In other cases the difference is yet greater, and sometimes the phonetic resemblance becomes rather remote, so that the extent of real phonetic influence is especially tenuous
- §321. As before, we list first cases in which the y follows two consonants, being then sometimes written $\imath y$
- mandrābhibhūtih (MS mandrā vibhūtih) ketur yajñānām (MS yajñiyā) vāg . TS MS
- viśve devā mama śęnvantu yajñiyāh (ArS yajñam) RV ArS ŚŚ
 yajñam-yajñam (KS yajñiyā yajñam) prati devayadbhyah (KS † ŚŚ †
 °vadbhyah) VSK KS. TS ŚŚ KŚ MŚ
- mā no rudrāso adhigur vadhe nu (mss nuh) MS, mā rudrīyāso abhi gulbadhānah (TA gur vydhānah) MS TA

- ıyam pıtryā (AB vai pıtre, AS. SS pıtre) rāsiry ety (AV GB civ) agre AV AB GB AS SS
- putrah pitre (KŚ pitrye) lokakrj jātavedah TB KŚ. ApŚ 'As a son to his father': 'as a son at the (rite) of the tathers'
- yā (AV omits) antarikṣa (KS AG °kṣyā) uta pārthwīr yāh (KS. pār-thwāsah, AV vā pṛthwyām) AV KS TB ApŚ. AG. (AVPpp. . pārthwā yāh)
- namah kātyāya ca gahvareşṭhāya (MS °şthyāya, p p °şṭhāya) ca VS TS. MS KS
- indro jyeşihānām (MS KS jyaişihyānām, VS ŚB jyaişihyāya) VS TS MS KS ŚB 'Of the noblest': 'of the highest nobilities': 'for highest nobility'.
- adhvar.ām adhvapate śreṣṭhah svastyasyādhvanah (ApMB śreṣṭhasyādhtanah, MG śraɪṣṭhyasya svastasyādhvanah) pāram aśīya AŚ ApMB MG Read svastyasyā° in MG with most mss
- arghah HG arghyam SS HG. arghyam bhoh Kaus: arhanīyā āpah ApG. arghyam '(water) of the argha'
- adhyakşayanukşattaram TB · †ādhyakşyayanukşattaram VS.
- §322. A considerable group concerns uktha and ukthya, the latter meaning 'a ceremony accompanied by ukthas', or 'one to be revered with ukthas'.
- uktham vācīndrāya TS AB GB AŚ Vait Ap
Ś MŚ : uktham avācīndrāya ŚŚ . ukthyam vācīndrāya ś
rnvate tvā AŚ
- mantram vadaty ukthyam (NrpU uktham) RV VS MS KS AA Ap\$ NrpU
- añgānı ta ukthyah pātu MS ApŚ ukthas († read ukthyas?) te †'ñgānı pātv asau AŚ
- ukthebhyas tvokthävyam grhnämi KS·ukthyebhya ukthyäyuvam ApS. uktham (AS ukthyam) indräya sansyam RV SV AS
 - (d) Words not equivalent in meaning, y follows one corsonant
- \$323. Coming to the cases in which a single consonant precedes the y, we find first a number of interchanges between $v\bar{v}$ 'hero' and $v\bar{v}$ 'heroism'
- yau vīryair vīratamā šavisthā AV: vīrebhir vīratamā šavisthā MS: vīryebhir vīratamā šavisthā (TB šac°) VS ŠB TB. ŞB AŠ ŠŠ eşa te yajño yajñapate sahasūktavākah suvīrah (AV suvīryāḥ, VS sarvavīras) AV VS TS MS KS ŠB
- anāmi kṣatram ajaram suvīryam (MS KS suvīram) RV TS MS KS sa (also sā) no dohatām suvīryam (MŚ suvīram) TB ApŚ MŚ (In all texts with both sa and sā)

- purukşu ivaşlā (MS °ļah) suvīryam (VSK TS suvīram) VS VSK. TS MS
- nırdevam nırıīram (KSA °ryam) krivā.. TS. KSA.
- prajām suvīrām (PG. suvīryām) krtvā TS PG
- §324. Next a group containing forms of stems div and divya, or once deva and daivya; of several similar cases at the beginning of §316 divas chadmāsi AG.: divyam chadmāsi. LS
- divo dhārām bhindhi KS.: bhindhīdam (MS bhindhy ado) divyam nabhah AV TS MS KS
- madhye divo (MS * divyo) nıhitah pr
śnır aśmā VS TS MS (both) KS SB
- ahar divābhir (MS. vahad divyābhir) ūtibhih VS MS ŚB. TA ŚŚ LS divābhir is for divā + ābhir, but is understood by comm. on TA as one word, = dyotamānābhir. This misunderstanding is responsible, also, for the variant of MS, which furnishes the only possible form if the word is to be taken as a single adjective.
- vācā trā hotrā prānenodgātrā . . pañcabhir dawyair (MS devair) ṛtngbhir uddharāmi ApS MS
 - §325. The rest require no subdivision.
- ālīr (IS KSA ālī) vāhaso darvīdā te vāyave (TS KSA. vāyavyāh) VS TS MS KSA.
- pāra (p p of TS pāre) ilṣaio 'vāryebhyah (KSA T 'vārîyebhyah) pakṣmabhyah svāhā TS KSA.: aiāra (p p of TS °re) iksavah pāryebhyah (KSA pārīye°) pakṣmabhyah svāhā TS KSA · pāryūni palṣmāny avāryā ilṣaiah, and: avāryāni pakṣmāni pāryā ilṣavah VS MS
- pāryūya kaitarlam TB · pērāya mārgāram VS avāryūya mārgāram TB : atārāya kevartam VS
- eşa u sya vrzā rathah RV SV.: eşa sya rāthyo vrşā VS SB
- sugam ca me supatham (VE KapS. °thyam) ca me VS TS MS KS KapS
- mā tvat ksetrāny aranāni (MS °nyāni, p p °nāni) ganma RV TS MS KS TB
- brhatā tvā rathamlarena traisļubhyā (KS tristubhā) vartanyā MS KS brhadrathamtarayos tvā stomena tristubho vartanyā. TS
- sūpasthā ası vānaspatyah MS: sūpasthā dero vanaspatrh TS ApS
- agne tram purīsyah VS KS. SB: agneh purīsam asī VS VSK TS MS. KS SB TB ApS MS And others, see Conc
- namah sobhyūya ca pratisaryūya (MS °sarāya) ca VS TS MS KS namo lopuūya colapvūya (MS °nūya) ca VS TS MS KS

- namah parnāya (TS. KS † parnyāya) ca parnašādāya (VS. °śadāya, TS. °śadyāya) ca VS TS MS KS.
- sukras te grahah (VS SB. grahyah) VS TS MS KS SB, MS 'Draught': '(juice) for the draught'.
- atho varunyād uta RV. AV VS: nir mā varunād uta (ApS adhi) LS ApS Inferior meter in the latter
- sa budhnyād (TS, KS AŚ. °nūd) āṣṭa januṣo 'bhy (TS KS AŚ januṣābhy) agram AV TS, KS AŚ (AVPpp agrees with the others, Barret, JAOS 37.260)
- tayā grnantah sadhamādeşu AV.: tayā madantah sadhamādyeşu (RVKh. VS °mādeşu) RVKh VS MS KS TB: tasthur grnantah sadhamādyāsah RV. AV. (Scheftelowitz prints °mādhyeşu for RVKh, but his ras °mādyeşu) In MS KS TB sadhamādya means the same as °māda 'feast', but in RV. AV 'participant in a sadhamāda' nur mā muācāmi sanathāt IS ApS: nuācantu mā (anathuit RV. AV.
- nır mä muñcâmı sapathāt LS ApS.: .nuñcantu mã sapathyāt RV. AV $$\operatorname{VS}$$
- agne devānām ava heda ıyakşva (KS ıkşva) KS ApŠ · ava devānām yaja hedo agne (KS yaje hīdyānī, MŠ yaje hedyānī) AV. KS. MŠ : ava devān yaje hedyān TB ApŠ.
- namo dundubhyāya cāhananyāya (MS dundubhaye cāhananīyāya) za VS. TS MS KS
- anhasaspataye tvā VS SB KS: anhaspatyāya tvā TS MS. TB. ApS §326. We conclude the cases concerning the noun-suffix ya with a few variants which are in one way or another anomalous or at least peculiar:
- ūrjasvatī rājasvas (TS rājasūyāya, MS KS °sūyās) citānāh VS TS MS KS ŠB rājasūya, adjective in MS KS, is equivalent to rājasū, the suffix ya is here added after a vowel In TS it appears as a noun Phonetically, the interchange in this and the next is between -ūy- and -v-
- svāhā rāzasūyāh (VS SB °svah, TS °sūyāya citānāh) VS TS MS. SB MS Cf prec.
- mahādevam antahpāršvena (VS † °paršavyena) VS TS TA Formally, the VS form is based on paršu 'rib'. Mahādhara: antar pāršvāsthisambandhinā mānsena The form antahpāršvya occurs in the next formula
- āganma mitrāvarunā tarenyā (KS °yam, MS. varena) TS. MS KS Here the adjective varenya- is corrupted in MS to varena, instr sing of vara-.

Other cases of y in formative and inflexional elements

§327. There remain a few other cases which concern the presence or absence of a y which, when present, is still a formative or inflexional element, tho not the familiar secondary noun suffix which has been dealt with above. Thus, first, a couple of cases concerning the gerund or gerundive endings ya

upastutyam mahi jūtam (MS "tyam janima tat; TS." upastutam janima tat) te jarvan RV. VS TS (both) MS KS Vait Gerundive varies with past pple

uta prahām alīdīvyā jayātī (AV. °dīvā jayatī) RV AV The RV has a gerund form; the AV. a nom sg of stem -dīvan

In another case an infinitive martaie varies with mytyave, dative of mytyu (equivalent in meaning):

jīvātaie na mṛtyave (PB martave) RV PB

§328. A few variants concern noun inflexion Thus change of gender accounts for the following (fem forms in y-ah varying with mase or neut forms without y):

āpo me hotrāśansınah (AG °sınyah) ŞB ApŚ AG 'The waters are my Hotrāśansins'; the priest-name is once made fem to agree with āpah

varşāś cālşuşyah VS. SB: varşānı cālşuşānı TS MS KS Here the noun itself changes gender.

Or different case-forms vary:

vn śloka etu (AV. etr; TS ŚvetU. ślokā yanti) pathyeva (KS pathela) sūreh (AV MS† sūreh, KS† sūreh, TS ŚvetU sūrāh) RV AV VS. TS MS KS ŚB ŚvetU Alternative forms pathā and pathyā The latter may be nom in RV. (so Oldenberg, Noten on 10 13 1); m most texts it is certainly instrumental

mām narāh (MŚ ApŚ. narah) kṛnuta vedim etya (MŚ etat, but read eta with all mss but one; ApŚ † 2 2 6a eta) TB ApŚ MŚ Caland recognizes eta as secondary to etya The reading etat (actually etad, before d-) has no standing; were it anything but a blunder it would belong to §401.

rān ma āsan (MŚ PG āsye) AV TS GB TAA Yait ApŚ MŚ Kauś PG BDh Both these forms are regular, from the related and equivalent stems āsan and āsya Interest attaches to the form āsyan, which is read by Gaastra in GB with all his mss, and which is also the reading of most mss of AV and Kauś, so that it seems to be the true Atharvan reading and should be adopted in all three texts (Curiously, however, Garbe reports no such reading from

the mss of Vait, possibly this is an editorial oversight) The form asyan is evidently a blend of the other two forms

§329. In the inflexion of the verb, likewise, variant forms with and without y occur. Thus, first, an inserted y is all that distinguishes a verb-form of the fourth present class from one of the sixth (and sometimes of the first), the same root now and then forms both, cf. VV I p 125, where other instances are quoted, less close to each other in sound than the following:

tapate stāhā TS KSA TA . tapyate stāhā VS

tapatyai (TA Poona ed tapyatrai, v. l. tapatyai) svāhā KSA TA:
tapyatvai (v. l. °tyai) svāhā TS The form tapyatrai, if correct,
would be from the Rigvedic adjective tapyatu, which is based on
the present stem tapya- as much as tapatyai (pres. pplc.) is based
on stem tapa-

 $\S 330$. So the y of the passive, in forms which vary with active or middle forms; see VV I pp 49 ff, where other cases, most of them more remote from each other in sound.

yenākşā (ŠŠ yenā kṣām, SMB yenākṣān, PG yenākṣyāv) abhyaṣıcyanta (ŠŠ. SMB °ṣiñcatam, PG °ṣiñcatām) AV ŠŠ SMB PG

§331. Other verbal variants will be mentioned in the sections immediately following, where phonetic tendencies are more clearly at work. We will add here a single stray instance of verb forms

ubhau lokau sanem (MS sanomy) aham TB TAA ApS. MS Sec VVIp 78

Presence or absence of y after palatal sounds and k, s, etc

§332. Deserving of special treatment and emphasis are a considerable number of variants in which this evanescent y follows palatal consonants, or sibilants, especially $k_{\bar{y}}$. Here it is not to be doubted that the appearance and disappearance of the sound y is phonetic in character, connected, that is, with the difficulty of distinguishing pronunciation or non-pronunciation of y after such consonants. The y may sometimes be interpreted as an inflectional element, as in the following verb forms (most of them collected in VV I pp. 28-9):

vācaspate vāco vīryena sambhrtatamenāyakṣase (TA 'yakṣyase, SS. 'yachase) MS TA SS Aorist in MS, future in TA; in SS a further phonetic variation (see §184), bringing the form into the sphere of ā-yam

(net tvā.) dadhrg (TA dadhad) vidhal.syan paryañkhayāte (TA °tar, AV. vidhal.san parīnkhayātar) RV AV. TA Many mss of AV vidhal.syan, which is certainly intended

Sardhāńsy agne ajarām (SV. ajarasya) dhal; atah (ApS dhalsyase) RV SV. MS ApS See VV I p 29.

bhalşa bhalşyamānah (ICS. bhalşa) VS KS—So the single ms of KS, ed emends to bhalşya. If the ms reading were kept we should have to assume a pple middle in form but passive in meaning melşyāmy ūrdhias tişlham AV., so emended by RWh, all mss mel şāmy, yenālşā (°lşyār, etc.)—(see §330)—In PG. al şyār is taken to be from alsī 'eve', but is really a phonetic corruption

§333. In one verb form the y appears after t^2 , it may be regarded as belonging with the t_2 cases in view of §§182 if:

tenārātsyam (GG SS MS "sam, so also p p. of MS; most mes of MS "syam with MS text) MS SS MS. GG The proper form is arātsam, norist; the conditional does not fit See VV I p 29.

§334. Other verb forms which belong in this category:

ratho na vājam samsyann (SV. °sann) anāsīt RV SV. Clearly a phonetic slip in SV., making a sort of norist pple.; Benfey, tho he interprets the form as aor, translates a future

ā 175cyantām (AV 175cantām) adītayc durciāh RV AV The AV. form is evidently a phonetic blunder, cf VV I pp 29, 51 f

§335. Besides the verb forms quoted in §332, and a few containing the noun suffix ya, §§314 ff., we find the following cases of y present or absent after ks

dhuñkṣāgncyī (VSK °ṣyāgncyī or °ṣrāg°) VS VSK MS · agnaye dhūñkṣā (TS °ṣnā) TS KSA See §255

tarakşuh (KSA † °kşah) krşnah krā caturakşo (KSA °kşyā) gardabhas ta itarajanānām TS KSA. The ed emends to caturakşo, which seems necessary

alsyos (mes alsos) tanto rapah AV.

Cf further such mss readings as ribhuñkşamāna for ribhuñkşya° at Kauś 23 9.38 26

§336. The other cases concern y present or absent after palatal consonants Prominent among them are several cases concerning the root scut (Wackernagel I p 268). The forms written with scyut may be partly contaminated with cyu, indeed the mss also show forms which might be derived from that root, and sometimes their confusion is such that their intentions are doubtful:

prasthitā vo madhusculah (VSK MS °scyulah) VS VSK MS TB So the editions But Poona ed of TB records a v. 1 °scyuloh; and per contra, all samhitā mss of MS read °cyulah or °sculah.

srucā devam ghrtascutā (KS and v l of MS °scyutā) RV. TS. MS KS

ghrtascuto madhuscutah TS MS KS SB ghrtascyuto madhuscyutah VS MS Sov l. and p. p of MS in the other passage. Moreover KS has v l ghrtacyuto, and for madhus its two mes. read scyutah and cyutah

dyaur yatas cyutad agnāv eva tat ApS: prihvvyām avacuscotaitad TB ApS: yata scutad dhutam agnāu tad astu KS.: yatra cuscutad agnāv evaitat MS. (but the latter is a dubious emendation, better, yatra scutad): yata scutad (so read) agnāv eva tat AS See on this variant VV I p 139

§337. Other, miscellaneous cases after palatals.

nisnoh śnaptre (TS śnyaptre, MS śipre) sthah VS TS MS KS. ŚB KŚ ApŚ. The pronunciation of n after ś must have been approximately n, this is indicated by the TS variant (v l. and p p, however, śnaptre), so the Vyūsasiksū 248 prescribes (cf. Keith, HOS 18 xxxvii).

apāśnuṣnīm apā rakṣah (and, apā ragham) TA apāśnyuṣnīm etc. TA.

So, correctly, Poona ed Aśn(y)uṣnī is an otherwise unknown
epithet of Agnī The comm explains only the form with u,
monstrously: aśnīnām bhoktīnām uṣnīr dāhako yo 'gnīh Cf prec
mano yuotīr (VS SB LS rūtīr) yuṣatām āyuaṣya (TS TB Vait āyuam,

mano jyotir (VS SB LS jutir) juşatam ajyasya (IS IB Vait ajyam, AS ājyam me) VS VSK. TS. MS KS TB SB. AS Vait LS. KS.

divo jyote (KS * °tir) vivāsva (MS devajūte vivasvann)...MS KS : vivasvān aditir devajūtis TS

mṛśase (SV mṛŋyase) pavase maiī RV SV.

syāmā sarūpamkaranī AV 1 24. 4a Here the Berlin ed reads sāmā with nearly all mss, but against comm, Ppp, and the evident sense, which demands syāmā, see Whitney's note

Presence or absence of y before initial vowel

§338. To a considerable extent y is evanescent when unconnected with any consonant. That is, first, at the beginning of a word, and most commonly (the not always) when the preceding word ends in a vowel Secondly, or better as a special case under the preceding, there are cases in which the y, when it occurs, is not initial, but joins into one word two words which are unconnected in the form without y. In either case the forms without y often show a hiatus between two vowels, so that y presents the aspect of a kind of 'Hiatustilger', reminding us of the similar use of this sound in Prakrit (Pischel §353) and Pāli (Geiger §73); cf. Edgerton, Studies in Honor of Hermann Collitz 31 The phenomena are, to be sure, accompanied by all sorts of etymological and grammatical changes; rarely do they show such purely phonetic character as in this:

- agne akṣīnı (IIG agneyakṣīnı) nır daha svāhā ApMB IIG As Kırste observes, IIG must intend agne ak², so that y is a simon-pure 'Hiatustilger' and nothing else Sec also anāmayaidhi etc, §344 §339. The cases of initial y are
- punar brahmāno (AV brahmā) vasunītha (AV onītir, KS odhītam and † onītha, MS odhīta) yajāaih (AV MS KS agne) AV. VS TS MS KS SB agne is probably original; it is preceded by r or m in AV KS, by e in MS, the latter would be specially apt to lead to the development of initial y-
- añjantı suprayasam (AVPpp yuñjantı suprajasam) pañca janāh RV AVPpp MS Sec §192
- prievaidhi sūnava ā (MS sūnave yah) suševah VS TS MS KS TB ApŠ devebhir aktam (VS TS yuktam) aditih sojosāh VS TS MS KSA

kāşthā azmeşv (SV yazñeşv) atnata RV SV A lect fac in SV

- viśvalarmā vimanā ād vihāyāh (KS °nā yo vyomā, MS vimame yo vihāyāh, TS manasā yad vihāyāh) RV. VS TS MS KS AS N amestam ası svāhā VS SB vamestam ası (with or without svāhā) TS
- MS KS TB 'Sacrificed at home (to Yama)' Preceded by ass in all The preceding vowel 2 makes insertion or omission of y particularly easy
- āśum jayantam anu yāsu vardhase RV VS TS MS SB: yā samjayantam adhı yāsu vardhase KS The latter is doubtless secondary Preceded by girā KapS āśram, doubtless intending āśum
- §340. In some instances case-forms of the relative stem ya exchange with similar forms of the demonstrative stem a. This may be assumed to be partly due to the instability of initial y
- trınsad yasyā (TB asyā) zaghanam yozanānı MS KS TB

asya (SV yasya) te sakhye vayam RV SV

- ghorā rṣayo namo astv ebhyah (MS astv adya yebhyah) AV TS MS cakṣur yad eṣām manasas ca satyam AV cakṣur yeṣām (v l hy eṣām) tapa uccabhīmam MS cakṣuṣa eṣām manasas ca samdhau TS
- tapa uccabhīmam MS cakṣuṣa eṣām manasas ca samanau 18 yasyām (v 1 asyām) devā abhi samvisantah MS Others with tasyām, see §281
- §341. And the same with adverbial forms derived from the same stems
- mitro no atra varuno yujyamānah AV mitro yatra varuno ajyamānah RV Double case, the y of yatra seems as it were to jump the next word and attach itself to the participle in AV
- yaded (KS ād id) antā udadrhanta (TS adadrhho) pūrve RV VS TS MS KS This pāda precedes or (m KS) follows the next, the

- words yad (yadā) and ād are transposed in KS, owing to the transposition of the two pādas
- ād (KS yad) id dyāvāpythivī aprathetām, same texts See prec
- athā (TB.* yathā; AV MS TB * yatra) devath sadhamādam madema (AV madanti, comm madema) AV MS KS, TB. (all three) ApS Preceded by a vowel all three times in TB
- yathā (RV. atho, VS ŚB athā) na (RV. ta) indrah kevalīh (VS TS ŚB. ındra ıd wsah) RV. AV. VS TS. KS ŚB.
- yathaınam jarase nayāl AV.: athaınam jarımā nayet HG.
- Cf. also: yasya (vy asya) yonını pratı reto etc , §363, and yasyām ıdanı vısvam (vısvam hy asyām) etc , §386
- §342. Less common is the second class of cases, in which y in one reading connects two words which are unconnected in the form without y. In some cases it is scarcely to be doubted that the appearance of the form with y is related to avoidance of hiatus, as in the variant quoted at the end of §338. While no other case is as clear as that, lexical reinterpretation and other sound-changes being always involved, it is significant that the form containing the y is more often secondary, namely in the following group:
- vaisvānaram ria ā (TS riāya) jātam agnīm RV. SV. VS. TS MS. KS PB. SB 'Born for the ria' is obviously secondary.
- sudevam indre asınına (MS indrayasıv) VS MS TB As in the last, a dative is substituted for a locative, both depend on dadhuh in the context.
- sahasrākşo (VSK TS. KS 'kşa) medhāya (TS. KS medha ā) cīyamānah VS VSK TS MS KS. SB 'For (at) the sacrifice'; the latter probably original. Keith on TS. 4. 2 10 1 translates 'for'; his text seems to require 'at'.
- graha viŝvajanīna niyantar viprāyāma te (MS p p viprāya, mate; KS. nyantar vipra \bar{a} †satī) MS KS As in prec , a loc with \bar{a} varies with a dat
- yo gopā apı (TB gopāyatı) tam huve RV. AV TB ApS.
- ta ā vahanti (MS. tayāvahante, KS tad āharanti) kavayah purastāt TS
 MS KS TB See Keith on TS. 1 1. 2 1 The original reading
 probably in TS; Keith thinks that MS may intend the same, with
 tay for te, altho its Brāhmana explains tayā as referring to the
- datto asmabhyam (KS. dattvāyāsma°, AŠ. dattāyāsma°, corrupt for dattvā°, SMB. dattāsma°) dravneha bhadram AV. KS AŠ SMB.: dadhatha no dravnam yac ca bhadram MS. See §367.

- mahyam vātah pavatām (KS $^{\circ}$ te) kāme asmın (AV kāmāyāsmai) RV AV TS KS
- $\S343$. In some cases, however, an original single word is broken up by omitting y, and leaving hiatus secondarily.
- vāvakayā yaš (TS pāvaka ā) cıtayantyā krpā RV VS MS KS \$B Cf Oldenberg, Proleg. 453
- vāhi gāyāndhaso (SV. gā andh') made RV SV The RV has a regular 2d sing impv pres from gai, the SV an aor inj, gās Add to VV I §158
- pnteva putram jarase nayemam (MS ma emam) MS KS ApMB HG
 The MS p p reads jarasena, ā, imam, corruptly pointing to the
 reading of the other texts
 - §344. Consider also the following peculiar case.
- amā ma edhi mā mṛdhā na (AS† ma) indra AS ŚG. apāma edhi mā mṛthā na indra SMB: anāmayaidhi mā riṣāma indo Kauś. The mss of Kauś read anāmayedhi, the emended "yaidhi is supposed to contain double sandhi, for "ya(h) edhi "be free from disease". But the Kauś reading may really intend amā ma(y) edhi, like AS ŚG. with 'Hiatustilger' y as in §338. See Bloomfield's Introduction, p. lviii, and of §78
- §345. We have now considered the cases of plus or minus y which seem most clearly phonetic in character, in addition to those in which suffixal y is concerned. There is little else to record, except a group of variations between the pronominal stems ta and tya. The more archaec tya is generally the original, but twice it replaces ta in secondary texts $yad\ dha\ sya\ (AV\ sa)\ te\ paniyasi\ RV. AV\ SV\ TS\ MS\ KS$
- mayı tyad (MS tad) ındrıyam brhat (KS TB TA mahat, MS. vīryam) VS MS. KS TB SB. TA AS SS Pratika ın MS mayı tyad (so Knauer, but mss mostly tād)
- yathā ha tyad (TS ApŠ HG tad) vasavo gauryam c.t TS MS KS ŠŠ ApŠ HG TA AŠ ŠŠ
- ā nu tac (SV tyac) chardho divyam vrnīmahe RV SV.
- pratı te (AV tye) te azarāsas tapışthāh RV AV
- ud it te vasunitamāh ApS ud u tye (MS MS ud-ut te) madhumattamāh RV AV SV MS GB PB AS SS Vait MS
- §346. Other lexical variants, except those considered above where phonetic conditions are favorable, are very few
- peśasvatī tantunā samvayantī (KS TB °vyayantī) MS KS TB Roots vā and vyā
- endram vagnunā vahata PB . vagnunendram hvayata TB ApS (with metathesis of h)

§347. We conclude with a few textual errors and false readings which should probably all be eliminated:

susaty m id gavām asyasi pia khudasi SS: susadam id gavām asti pra khuda AV. Berlin ed., violently emending the mss which agree precisely with SS but for the slight corruptions gavom and sudasi

vidad gavyam saramā drdham ūrvam (TB. ūrvyam) RV TB But Poons ed. of TB has the correct ūrvam, text and comm, without v i

salāsatī (comm. satyasatī) prajāpatih TB But Poona ed comm. salāsatī.

hiranyavad annavad dhehi (ApS annam adhychi, read annamad dhehi) mahyam KS ApS The corruption may be graphic in nature prayapsyann iva sakthyau (TB. text sakthau) TB ApS But Poona ed text and comm. sakthyau, the only possible reading.

oşışıhahanam sıngınıkosyabhyam (TA °kosabhyam) TS TA: vasışıhahanuh singını kosyabhyam VS Poona ed of TA °kosya°

ayoddheva (TB °dhyeva) durmada ā hi juhve RV. TB. Tho Poona ed. has the same reading, it is surely corrupt; perhaps graphic. The comm has the same, but explains it as tho ayoddhā-iva

3 Presence or absence of r

 $\S 348$. Owing to the rarity of r in formative syllables, this interchange appears mainly in radical syllables, producing lexical variations which are naturally along the line of least resistance; that is, the variant words are more or less synonyms. It may be assumed that the relatively faint pronunciation of the liquid was a contributory cause. The materials are very heterogeneous, however, and of less phonetic significance than was the case with y.

§349. We begin with groups of variants concerning nearly synonymous words and roots; and first, śravas and śavas and related words śūro nṛṣātā śavasaś (SV MS śra°) cakānah (SV. ca †kāme) RV. SV. TS MS.

grnānāh śravase (SV. śa°) mahe RV. SV.

satrā dadhānam apratiskutam šavānsi (SV. šravānsi bhūri) RV. AV. SV. TB

ā yo visvāni savasā (SV sra°) tatāna RV. AV. SV

śramsthāh stha MS $\,$ KS $\,$ śamsthā stha rāstradāh $\,$ VS $\,$ SB

§350. The roots dhā and dhr and the like, in virtual synonyms.

sado vaneșu dadhișe (SV. dadhrișe) RV SV

vīṣā dharmānı dadhışe (SV dadhrışe) RV SV TS. MS KS ApŚ yo nah pıtā janıtā yo vıdhātā (MS. vıdhartā) RV VS TS MS KS AŚ.

- dhātā vidhātā (MS dhartā vidhartā) paramota samdrk (KS paramo na samvrk) RV VS TS MS KS
- dawyāya dhartre joṣṭre (MS dhātre deṣtre) VS TS MS KS ŚB devayor dharme (MS °mā, AV dhāmann) asthıran AV TS MS KS kṣayasyāsı vidhatah (SV vidhartā) RV SV Here vidhatah from root vidh
 - §351. Roots pū and pr
- atırātram vavarşvān pūrta rāvat (KS vavṛṣvān pūta rāvat, TS varṣan pūrtır āvṛt) svāhā TS MS KS
- apālām indra (MG indras) triş (ApMB MG trih) pūtvī (AV pūtvā, MG pūrty a°, ApMB pūrtvy a°) RV AV JB ApMB MG \$352. Roots prī and pā
- śvātrāh pītā (V1Dh snātāh prītā) bhavata yūyam āpah VS ŠB KŠ V1Dh. pra vām adhvaryus caratı prayasvān (AV °tu payasvān) AV AŠ ŠŠ Comm on AV prayasvān
- $\S 353$. Miscellaneous synonyms or near-synonyms, with some corruptions involving no further changes, or very slight ones, in the words; in the first case r possibly plays the rôle of 'Hiatustilger'
- ahım budhnyam (TS 'nıyam) anu rīyamānāh (TS samcarantīh, MS KS anv $\bar{\imath}$ yamānāh) VS TS MS KS ŠB Practically synonyms, note that r is initial, after a vowel, and probably secondary, a sort of 'Hiatustilger'? r is used in this way in Pāli
- antarikse pathibhir īyamānah (GB hrīyamānah, so Gaastra without the v l hīyamānah recorded in Bibl Ind ed) RV GB The AVPpp 1. 107. 4 (Barret, JAOS 26 290) has the RV reading, GB perhaps corrupt, certainly secondary Note the final r of the preceding word
- vanasade (MS vanarşade, KS vanrşade) vet (TS MS vat) VS TS MS KS SB See §650
- mā tvam hārşīh śrutam mayı PG. śrutam me mā pra hāsīh RVKh 'Take away'. 'abandon'
- purā jatrubhya (TA ApMB jartrbhya, MS cakrbhyā, p p vaktrbhyah)

 ātrdah (MS °da) RV AV SV MS PB TA KŚ ApMB Comm
 on TA tries to derive its corrupt form from root jar (jr)
- vikirida (KS °da, VS. °dra, MS vyakrda) vilohila VS TS MS KS See §168
- ya rte (TA ApŚ ApMB yad rte, PB† yakşate) cıd abhısrışah RV AV SV PB TA KŚ ApŚ MŚ Kauś GG ApMB jarı cetid abhısışah MS (corrupt, see §193)
- jāg
rtsyas (mss , v l yā gr°) trīpañcāsīh AV yā(h) krechrās trī° AVP
pp See §§185, 192

- sunam ma ıştam sunam sänlam (p. s. srānlam). . MS: svam ma (AB ma ıdam) ıştam. . svam srānlam (TB text srālam, Poona ed. srānlam)... AB. TB. Ap\$.: svam ma ıştam astu sunam sānlam . . KS
- hotā yakşat sarasvalīm (KS brhaspatım) . . śronitah (KS śonitaś; Conc. suggests reading śro°) . VS KS
- prthur bhūvarı (KS vibhū°) sinīvāly urandhra (KS urandha) ācitte ... KS ApS An obscure epithet of earth; perhaps belongs in §350.
- agne 'dabdhāyo 'sīrtatano pāhı vidyot KS: agne 'dabdhāyo 'sītatano pāhı mādya dīvah. TS TB ApS: agne 'dabdhāyo 'sītama pāhī mā dīdyoh VS SB. In KS, apparently the original, 'having uninjured body'; TS, 'having not cold body', an over-sophisticated lect fac VS has a further change, by haplology, and is really uninterpretable; comm either 'most eating' or 'most obtaining', of which the former is adopted by BR and fits Agni well enough, but is formally unsatisfactory
- vi jihīşva lokam kṛnu AV.: vi jihīrşva lokan kṛdhi TA The AV. is original: 'go apart (root hā), make room ' TA. comm. takes it as desiderative from hṛ (vihartum icha), which would require jihīrşasva
- anādhṛṣṭam sahasyam (TS KS. sahasrıyam) sahasvat TS MS KS AS "Thousandfold mighty', probably original: 'powerful and mighty', lect fac
- yo agnih kravyavāhanah (VS KS kavya°) RV. VS. KS AS · yad agne kavyavāhana TS. Euphemistic change of kravya° to kavya°.
- yata ātlas (AS ārtlas) tad agan punah TS. AS 'Whence it was taken, to it it has returned' AS mere blunder or misprint
- prati vastor aha (AV.* ahar) dyubhih RV. AV. (both) SV. ArS VS KS. SB. praty asya vaha dyubhih TS The comm on AV. has aha; ahar is a blunder suggested by dyubhih
- apām tvā sadhişi (MS † sadhrişu) sādayāmi VS MS KS. SB sadhiş-i, 'in the seat'; sadhrişu ('mere blunder', Keith on TS 4 3. 1. 1) perhaps with thought of RV. sadhrī
- anābho mṛda dhūrta (MS °te, v. 1 °ta) MS MS : anārbhava mṛda KS ApŚ See §749
- sam no bhava hrda ā pīta ındo RV GB AS Vait MS According to Gaastra, all his miss read ındro for ındo, a stupid blunder which he disregards, printing ındo in his text
- ā na indra (and, ındo) mahīm ışam RV (both)
- vyrddhyā apagalbham (TB apra°, but Poona ed text and comm apa°) VS TB Probably mere misprint.

- potrāgnīdhro (read with Gaastra potā°) nihitam pādam ekam GB §354. The following involve different word-divisions
- yasya (ApMB vy asya) yonım patıreto grbhāya (ApMB HG pratı rete grhāna) ŚG HG ApMB
- āyuhpati rathamtaram (MS āyuh pratırath°) tad asīya etc ApS MS The latter corrupt.
- yena bhūyas (PG bhūris) carāty (MS caraty) ayam (AG ca rātryām, corrupt; PG carā divam) AG PG ApMB MG See §61
- tan mā jīnva (KS mārjītvā) TS MS KS 'Quicken me' 'cleansing it' sa vaḥ sarvāh sam caratī prajānan AV.: sarvah sarvā (p p. sah, sarvāh) vī caratī prajānan MS The latter carelessly assimilates to the following sarvāh
- mā mā yūnarvā hāsīt (JB yono vām hārasīh) PB JB LS Both forms obscure
- agnir hotrenedam (SS hotrena) havir ajuşata MS SS agnihotrenedam havir .TB AS But agnir hoo must certainly be read in all texts, with Poona ed of TB
- ud vansam ıva yemire RV. SV $\,$ TS $\,$ KB $\,$ N : $\,$ \$\tilde{u}rdhvam kham ıva menire $\,$ Mbh
- §355. In the next group accompanying changes in adjoining vowels or consonants make the two variant words less close phonetically:
- ürdhvacıtah (MS KS 'srıtah) srayadhvam VS. TS MS KS SB TA See §195
- svām tanvam (tanuvam) varuno 'suşot (TS TB akikret) TS MS KS TB. See §287.
- pred u harıvah śrulasya (SV sulasya) RV. SV TS See §278
- trıbug (AS trıbrud) gharmo vibhātu me (KS gharmas sadam ın me vibhātı) KS TB TA AS See §145
- śwā rulasya (TS. and v I of MS rudrasya, VSK śwa rlasya) bhesajī (MS. 3ā) VS. VSK TS MS KS See §684
- aprītapā ādhūyamānah TS viņnur āprītapā āpyāyyamānah VS 'Drinker of unpurified (soma)'. 'protecting when propitiated (?)'
- rudrānām urvyāyām (ApS ürmyāyām, SS omyāyām) SB ApS SS See §228
- amocı (AV amulthā) yakşmād durītād avartyai (AV avadyāt) AV PB ApMB See §60
- anu daha sahamūrān kravyādah (SV kayādah) RV SV: sahamūrān anu daha kravyādah AV Benfey explains the SV form as from kaya = kāya + ad, 'body-eating' This would imply metric shortening of ā to a There may be involved euphemistic avoidance of the word kravyād, as in kravyavāhana kavya°, §353

- ā sutrāvne (MS KS bhūyış(hadāvne) sumatım āvrnānah AV MS. KS oşış[hadāvne sumatım grnānāh TS It is likely that the original form was āśutrāvne, cf. Whitney on AV. 19. 42. 3 The TS. form, tho impeccable, is secondary
- §356. Among the rarer cases of presence or absence of r in formative elements, we begin with a miscellaneous group concerning verb inflexion: ghrtam duhata (RV * duhrata) āśiram RV. (both) SV See RVRep 137, 562, and VV I p 169.
- te dalşınam duhate (AV te duhrate dakşınam) saptamataram RV. AV. See VV I, 1 c
- utamam (NilarU uta tvā) gopā adršran (TS NilarU adršan) VS TS MS KS NilarU See VV I p 170 Followed by
- adrirann (TS † adriann) udahāryah VS. TS See ibid
- apa snehtīr (SV snīhtim) nrmanā adhatta (SV. adhad rāh, KS † nrmanām adadhrām) RV AV SV KS: upa stuhi (Poona ed snuhi) tam nrmnām athadrām TA See §110, and VV I p 170
- sarasvatyā (AV °yām) adhi manāv (KS mānā, v l manā, SMB vanāva, but Jorgensen manāv, AV. manāv) acarkrsuh (KS and SMB Jorg acal°, SMB Cone carkrdhi) AV KS TB ApŚ MŚ SMB. PG The KS also has v l acark°, which perhaps should be read thruout Jorgensen assumes dissimilation, see VV I p 149.
- Compare further variants between the verbal endings -re and -rire, VV I p 170, and ghrtam mimilse (TA *kṣire) ghṛtam asya yonih RV VS TA, ibid p 214
- §357. Finally, another not much larger group concerns suffixal or inflexional syllables of nouns. These cases belong to noun formation or inflexion. It may be noted, however, that in a number of cases—those listed first—the r, when present, follows a consonant group. In these, especially, some phonetic element in the shift may be suspected, cf. the similar cases with y, §§314–5, 321–2, and our chapter on Consonant Groups below
- bhūrī śastam (SV śastram) prthuh svaruh RV. SV VS Synonyms, but here the form without r is older
- atıvıddhā vithurenā cid astrā (MS astāh) RV MS KS The MS is secondary and may be a phonetic simplification or corruption
- na kir devā minīmasi RV na ki devā inīmasi SV Anomalous reduction of na-kis to na-ki
- sūro rathasya naptyah (ArS naptryah, TB naptriyah) RV AV ArS KS TB Feminine stems naptī and naptrī, the latter influenced by naptar

- trașțimati (TA Conc trașțiri, which is a v. l. in Poona ed, its text trașți, le sapeya TS ApS TA: traștimantas (MS MS trașți, ApS trașți, traștu, traș
- praty etā vāmā...pratisthotopavaktar (SS °vakta, v. 1 °vaktar) uta

 KB SS praty etā sunvan..pratisthotopavaktar uta .AS The
 form can only be construed as nom, °vakta, if it is intended, must
 stand for °vaktā with partial sandhi (ā shortened, §991) But it
 looks as if all texts intended °vaktar Hillebrandt, on SS, p 252
 note, suggests that ru is a bad writing for u, but it is pretty widespread to be a mere graphic error Is r a kind of sandhi consonant
 or Hiatustilger, as in Pāli? Cf. the first variant in §353. Or is
 °vaktar used as nom? Cf the nom neut (?) forms in -tari,
 Wackernagel III p 205 supra
- viśvā amīvāh pramuñcan mānusībhih (KS °sebhyah) AV. KS: viśvā āšāh pramuñcan mānusīr bhiyah VS TS See §783
- rapiā (ApMB vapirā, HG MG vapiar) vapası (PG °ti) kešašmašru (AG PG. MG kešān) AV. AG PG ApMB HG MG vapirā is an assimilation to preceding instrumentals
- ā mā stutasya stutam gamyāt (Vait gamet) TS Vait · ā mā stotrasya stotram gamyāt PB Synonyms

matyaı śrutāya (mahe śrotrāya) cakşase AV. (both)

gharmanı pâla tasavo yajala (TA °lū, MS. °lrā) vāļ (MS veļ, TA. vaļ) VS MS TA. SB yajala (°lā) is a verb, 'sacrifice ye'.

gaur dhenubhavyā (HG dhenur bhavyā) ApMB HG See §818

- agner agneyāny (KS. agniyāny) asi (one ms and p p of MS agner agner yāny asi) MS KS.: devānām agneyāny asi TS: agner yāny asi TS. MS KS ApS MS agneyānī, certainly the true reading of TS and probably of MS, is a curious tatpurusa compound in which the stem vowel of the first member is assimilated to the vowel of the genitive ending 'Path of Agni' is meant in every case KS has the regular form, and for that reason may be suspected of being secondary.
- hrhaspatisulasya (TS MS add ta, VS VSK. SB add deva soma ta)
 inda (TS indo, VS SB indor) indriyāiatah... VS VSK. TS.
 MS KS SB Gen i voc
- sa tritiācīr (KS. °cī) abhi caṣṭe ghṛtācīh (KS °cī) RV VS TS MS KS SB The KS changes an accus plur, with which a noun has to be

supplied (the commentators and translators are at sea as to what noun), into a dual form agreeing with rodasi in the preceding pada. devi dvārau (Vait. devīr dvāro) mā mā samtāptam TS. AS. Vait. Cf prec., and §732.

asmadrātā madhumatīr (KS °tī) ... MS KS SS. and others, §800. gaurīr (°rī) mimāya ..., see §545.

4 Presence or absence of v

§358. Doublets with or without v seem to have existed to some slight extent in IE times, and still exist historically in the Veda and even in Sanskrit (cf Wackernagel I §232c). Among the variants they are fairly numerous. Undoubtedly most interesting is the large class in which v is initial before a vowel. Frequently, tho not always, the preceding word ends in a vowel, so that we seem to be dealing with a tendency to bridge over hiatus by the sound v, as in the case of y (§§338–44), and to a much slighter extent r (§353). As with those sounds, however, the form with v is not by any means always secondary in text history

v initial before a vowel

- §359. Here the place of honor belongs to the rime-words τ ; abha and $v\tau$; abha, perfect synonyms, which exchange on a large scale. In some cases we seem to detect quite clearly the abo e-mentioned tendency to avoid hiatus by using the form with v when the last word ends in a vowel. But this is by no means universal
- vrṣabhena (TS rṣ°) tvaṣṭā TS KS. This is an instructive case; it is preceded by a word ending in a vowel in KS, in a consonant in TS We can hardly believe that it is entirely accidental that KS begins with v-.
- valso virājo visabho malīnām AV · pilā virājām isabho rayīnām TB Observe that is is preceded by a final -m, vis- by a final vowel. It is as if v shifted to m (§236).
- vrşabhena (TS rş°) gāh (KS gāvah) TS KS. KSA. The single ms of KSA has corruptly aśvā-vrşa°, which Von Schroeder emends to aśvān vr°, but he adds a note that perhaps the TS reading (aśvān rş°) should be adopted
- vrşabham (VS* rş°) naryāpasam RV. AV. SV. VS (both) MS TB Here preceded by a consonant.
- rşabhāya (MS vrş°) gavayī (TS. KSA rājñe gavayah) VS TS. MS KSA A consonant precedés
- rşabho (KS vr°) gaur vayo dadhuh VS MS. KS TB A consonant precedes.

- vṛṣabho 'sı svargah AV rṣabho 'sı svargo lokah TB Inital in verse kakubham (VSK TS ApŚ "ham) rūpam vṛṣabhasya (KS rūpam rṣ") rocate bṛhat (VSK bṛhan) VS VSK TS MS KS ŚB ApŚ MŚ
- astabhnād dyām, vrṣabho (TS MS dyām rṣ°) antarıkşam RV VS TS MS SB TB KS
- brhad rsabham (TB vr° , but Poona ed text and comm r°) gām vayo dadhat VS TB
- śākvarā (LŚ ye śāk°) rṣabhā (AV vṛṣ°) ye svarājah AV LŚ Note the vowel preceding
- rathe akşeşv rşabhasya (KS TB °şu vr°, so AV comm, and so Ppp intends, Barret, JAOS 30 204) vāje AV KS TB ratheşv akşeşu vrşabharājāh ViDh
- §360. There are no other forms with and without v that are precisely identical in meaning. But we find a considerable number of other cases of presence or absence of initial v before a vowel, in many of which the preceding word ends in a vowel, so that we may suspect influence of the tendency to avoid hiatus, even the lexical considerations always play their part, and even the the form with hiatus is sometimes secondary, reversing the direction of the process.
- te arşantu te varşantu . LS te varşantı te varşayantı AV Roots arş 'rush' and varş 'raın' One is inclined to suspect assimilation to the following varş- in AV
- njūle (KS vrj°) parī vrūdhī nah RV VS TS MS KSA ApŠ Imtial in the verse. Von Schroeder says on KSA, 'wohl fehlerhalt fur rjūle' Perhaps assimilated to the following vrūdhī
- salmalır vrddhyā (KSA rddhyā) VS TS KSA SB Synonyms agne vājajīd vājam tvā VS SB TB Vait ApŚ ājīm tvāgne MŚ Synonyms since earliest times Note preceding vowel before vāja° varenyakratūr (AV °tur, ApŚ īdenya°) aham RVKh AV ApŚ vīrenyah kratur indrah sušastih RV
- hrtsu kratum varuno (MS °nam) vıkşv (RV apsv, MS dıkşv) agnım RV VS † TS † MS KS SB † For the RV orıgınal is substituted vıkşv after preceding vowel, with quasi-'Hiatustilger' v and other phonetic changes (cf especially §153a) On MS see §869 (a further, graphic change)
- tad āyuh (ApŚ vāyuh) MS KS ApŚ 'That is life (wind, breath)' asum (AV TS vasum) gharmam divam (VS svar) ā tişṭhatānu (AV rohatānu) AV VS TS MS KS ŚB asu 'life' vasu 'weal' (with ungrammatical m), preceded by vowel, asu is original, as shown by RV 10 14 12, 15 1 (cf 10 15 9, 10)

- devā gātuvido gātum vitivā (VSK. gātum itvā) gātum ita AV VS VSK. TS.

 MS. KS ŠB TB Cf. gātum vitivā gātum ita MS ApŚ; devā
 gātuvido (MŚ adds gātum vitivā) gātum yajnāya vindata . TB

 ApŚ MŚ 'Finding' and 'going upon' the way are much the same
 thing, but the former is obviously original; VSK. assimilates to the
 following ita
- tve 1şah (KS viśve, MS tva eşah) samdadhur bhūrīvarpasah (TS † bhūrīretasah) RV VS TS MS KS ŚB On MS see §694. KS clearly secondary, with quasi-epenthetic v between vowels
- dhışane vīdū (VS VSK vīdvī, KS. vīle, MS MŚ īdıle) satī (MS. KS. MŚ omit) vīdayethām (MS MŚ īdethām) VS VSK TS MS KS SB. Ap\$ MŚ See §169
- tigmam anīkam viditam sahasvat AV tigmam āyudham vīditam (KS "dham īditam) sahasvat TS MS KS. 'Implored' of KS. is secondary to 'strong'; AV is still farther afield, see §169
- yo antaro mitramaho vanuşyāt (KS anu°) RV KS. ApS. 'Who.. fights against us' KS seems to feel a form from anu + as, as in English slang, 'who is after us' Reverse of 'Hiatustilger'. KapS vanuşyā.
- namo vīdhryāya (MS vīdhryāya, p p vīdhryāya, TS nama īdhryāya) cātapyāya ca VS TS MS KS Both forms are obscure; TS probably secondary See Keith's note
- īšāna ımā bhuvanānı vīyase (SV īyase) RV SV. Note absence of sandhı (complete hiatus) ın SV, reverse of 'Hıatustılger' with a vengeance!
- mahīva dyaur adha (AV vadha) tmanā RV AV vadhatmānā (sic) not divided in pp, and regarded by Whitney as a mere corruption, he translates the RV. Still, the AV may be rendered: 'slay (our assailant, O Soma) by thyself'
- ahar (MS vahad) divābhir (MS divyābhir) ūtibhih VS MS. ŚB. TA ŚŚ LŚ ahar, adverb. 'by day' One ms of MS. with p p vahad (d or d for r, §§272, 272a); preceded by a vowel, so that it is a case of 'Histustilger'.
- visām vavarjusīnām (AV. visām avar^o) RV AV. The original means, 'of the folk who have prepared (the barhis)', Bloomfield, JAOS 35 275 The AV. uses it in a patchwork hymn dealing with a wholly different situation; the initial a-must be taken as privative, 'who have not defended themselves' (vij = pari-vij as in Classical Skt). Cf Whitney ad loc. The retention of the perfect pple. form shows the badness of the AV.

- mahī no vālā iha vāntu bhūmau AV · miham na vālo vi ha vāli bhūma RV Reverse of 'Hiatustilger'
- abhūr āpīnām (HG °nām; AV mss v āpī°) abhīšastīpāvā (AV °pā u) AV HG. ApMB Others, §46
- ramayata (KS °lā) marutah syenam āyınam (MS marutah pretam vāyınam) TS KS ApS MS
- mā tvā ke cin ni (AV cid tvi) yemur vim (SV cin ni yemur in, TA cin nyemur in) na pāsinah RV SV AV VS TA vim, acc of vi, secondarily reduced to the particle in (id)
- vīdvīr yāmann avardhayan VS vidvīr yāman vavardhayan TB (Conc)
 But Poona ed of TB has correctly yāmann avar°
- §361. In two cases of this kind the secondary form with initial v (after a vowel, 'Hiatustilger') is felt as containing the preposition ava pro \bar{a} rata (TB. ' $v\bar{a}$ rata) maruto durmad \bar{a} iva RV. TB 'Rush along, Maruts, like madmen' Comm on TB av \bar{a} rata d $h\bar{a}$ vata
- uruşya rāya eşo (VSK rāyo 'veşo, 1 e ava, 1şo, TS MS KS rāyah sam 1şo) yajasva VS VSK TS MS KS SB ava-yaj 'remove by sacrifice' with object 1şo, 1s peculiarly mept
- §362. A couple of other peculiar cases seem also to belong in this category, althouthe v, when found, is not initial in its word
- agninendrena somena upa te huve savāham (KSA huve 'sā aham)
 TS KSA 'I summon for thee, O offering' 'I, so and so (asau
 'N N'), summon for thee' If, as we are inclined to assume, KSA
 is original, the TS reading uses v as a sort of 'Hiatustilger', yielding
 a different lexical result The same with brāhmanān rtvijo devān
 . istena pakvam . devān sendrān
- aākākam (MS aākāv-aākam, so divided in pp, KS aākaākam) chandah VS TS MS KS SB Nothing is known of the original form or meaning of this word (said by comms to mean 'water'), note the curious KS variant, with short a It may be that MS has a kind of 'Hiatustilger' with its v

n initial before a consonant

- §363. So far initial v before a vowel In a few cases the same v appears or disappears before an initial consonant
- resīnām (VS SB vre°) tvā patmann ādhūnomi VS MS KS SB MS. resīṣu (sc te svkra sukram ādhunomi) TS An epithet of water, of unknown etymology and meaning, v- presumably unoriginal
- agne yajasva (AV vyacasva) rodasī urūcī RV AV MS See §57. apāvrnod duro asmavrajānām (MS asmad-rathānām, pp asmin, ra°)
 - RV MS TA . The MS is hardly interpretable.

yasya (ApMB vy asya) yonım pratı reto grhāna (SG patıreto grbhāya) SG. ApMB. HG. Cf §354. vy asya 'open' must be intended; yasya makes no sense.

v not initial

§364. Coming to non-initial v, present or absent, we shall find that strictly phonetic influences are more indeterminate, the even here we believe that they are not absent. We shall, however, begin with several groups of cases which concern lexical interchanges between familiar forms both well established in the language. In them probably the phonetic moment is evanescent. Thus, first, the prefixes sva- and sa- vary. Comment is hardly necessary, except that both vary equally easily with su-, see §§612 and 741:

satavasemam (KS sva°) yajñam divi deveşu dhattām MS. KS TB. sūro na svayugvabhih (SV sayu°) RV, SV.

višvā dvesānsi tarati svayugvabhih (SV. sayu°) RV. SV. Better meter in RV. (anapest after cesura)

ındra svayugbhir matsveha (ApŚ sayugbhir didyun na matsvā madāya) mahe ranāya AV ApŚ

yayño bhūtvā yayñam āsīda . salṣaya (MS. svalṣaya) chi TB ApS MS. §365. There is, of course, a much clearer change of meaning in the rather numerous cases of shift between various forms of the pronouns in tv- and forms of the demonstrative stem ta- At the end of the list we add, because of the phonetic similarity, a single case each of shift between a tv- form and the enclitic te (2d person), and between kva and lā (both from the interrogative stem):

tam id arbhe havişy ā samānam it RV.: tvām arbhasya havişah samānam it SV. KS TB ApS Followed by:

tam ın mahe vrnate nānyam tvat RV: tvām maho vrnate (TB. ApS. vrnate naro) nānyam tvat, same texts

tam (TA. tvam) u nır vāpayā punah RV. TA

tvām (MS tām) šašvanta (MS °tā) upa yantı rājāh RV. SV. VS. TS MS

paramām tam (TB ApS tvā) parāvatam AV TB ApS

etat ivātra pratīmanvāno (AŠ °vanvāno) asmī (AŠ †asmīn) VS. AŠ ŠŠ Vait : etat tān pratīmanvāno asmīn LŠ.

yā tām rātrīm upāsmahe PG : yām tvā rātry upāsmahe (TS upāsate, SMB rātrz yazāmahe) AV. TS SMB.: ye tvā rātry (MG rātrīm) upāsate KS MG

tvam gopāya MG· tam gopāya etc., see Conc

- prajāyai mṛtyave tvat (TA tat) RV TA Here the stem tva- is not the 2d personal pronoun
- tayānantam (MŚ tvayūgne) kāmam (ŚŚ lokam) aham jayānı (MŚ °mi) AŚ † ŚŚ. ApŚ MŚ ApMB
- iayā (ApMB ivayā) prattam svadhayā madantu (ApMB $^{\circ}ti$, v l $^{\circ}tu$) ApMB HG
- tayāham (MS tvayā°) śāntyā śāntım karomı MS TA. tābhıh śāntıbhıh śamayāmy aham AV
- tvayā (TAA 10 1 9 tayā) hatena pāpena TA TAA † MahānU
- yayıryuktanı sāmabhır āktakhanı tvā (MS rhtakhanı tā) MS TA The words are bad enough in either case MS pp rhta-khám, tā, making tā an independent enclitic, rhtakhanı is not in any lexicon But āktakhanı is little better TA comm āktāny āpyāyıtānı khānīndriyāny avayavā yasya pravargyasya so 'yam āktakhas tādršam, sāmagānena hi pravargya āpyāyıto bhavatı (!)—Boehtlingk, pw 2 293, 'dessen Buchse geschmiert ist'
- puras tvā (ŚŚ purastāt) sarve kurmahe AB ŚŚ Here -tāt is an adverbial ending, not a pronoun The sense requires object tvā Simplification of three consonants to two (§§419 ff) in the secondary ŚŚ
- yat tvemahe (SMB te mahe) prati tan no (Kaus prati nas taj) jusasva RV TS MS. Kaus SMB PG ApMB All mss and comm. of SMB agree, but it can only be a (phonetic?) blunder for the other reading Comm, unbelievably te tvām (!) yat phalam mahe (!) tan no 'smabhyam jusasva prayachety arthah.
- kva (SV kā) pratnā va āhutih RV SV
- §366 Further, v is occasionally found in formative elements, varying with other forms without v Thus in nasal present stems of verbs, of VV I p 121
- deva tvaşlar vasu rama (TS ranva, KS rana, MS rane) VS TS MS KS SB (In MS rane is a noun)
- āpas tvā sam arınan (MS arınvan) VS MS SB āpah sam arınan TS KS
- manaı (MS manve) nu babhrūnām aham RV VS MS KS ŠB N See VV I pp 76, 121
- With these may be grouped the following, the here the two verbs are lexically unrelated.
- jananta (SV jinvanta) uşaso bhagam RV SV
- §367. Larger is the list of variations between gerund forms in suffixal $tv\bar{a}$ ($tv\bar{i}$) and other forms lacking v, but they are mostly under suspicion of corruption

- asya pītā (SV pītvā) svarvidah RV SV. Lect. fac in SV for pītā, loc sing of pīti, 'in the drinking of it'
- yenendro havisā $k_T t v \bar{\imath}$ (ApMB $k_T t \bar{\imath}$) RV. ApMB The ApMB form (v 1 $k_T t v \bar{\imath}$) may be interpreted as nom sg of $k_T t i n$, but is doubtless corrupt. It is a case of simplification of three consonants to two (§§419 ff), the next word begins with a-, and the actual reading is $k_T t (v) y$ -a-.
- datio asmabhyam (KS dativāyāsma°, AŚ datiāyāsma°, corrupt for dativā°, SMB. datiāsma°) dravneha bhadram AV KS AŚ SMB: dadhatha no dravnam yac ca bhadram MS 'Give ye (giving) to us riches, prosperity'
- hotā viştīmena (ŠŚ viştīne) jaritar AV 20. 135 5, AІ 8 3 24, ŠŚ Vait This pāda is omitted in the Berlin ed of AV and therefore in Conc Most ŠŚ mss viştī, per contra, v l of AV viştvī. It is very obscure in any case
- daśasyantāmrtāya (ApMB °tvāmrtāya) kam RV. ApMB The ApMB. form is doubtless felt as a gerund, in sense equal to RV's pple, but may fairly be called corrupt, cf Winternitz, p xx
- yuktvā (TB. Conc yuktā, Poona ed text and comm correctly yuktvā) harī vṛṣanā yāhy arvān (MS KS arvāk) RV MS KS TB
- apālām indra (MG. °ras) trīs (trīh) pūtvī (AV. °vā, ApMB pūrtvī, MG. pūrty a-) RV AV. JB ApMB MG The last seems clearly corrupt
- [indrah pāśena †sıktvā vah ApMB. ındrah pāśena vah †sıktvā (so intended, see Index of Words) HG. ındrapāśena sıtvā PG The true reading is sıtvā]
- §368. A few stray cases concerning noun inflexion or different noun suffixes.
- madhvo (SV madho) rasam sadhamāde RV SV These alternative forms of gen sing of madhu occur frequently in the pairs madhvah madhoh, see Conc p. 681a
- ed u madhvo (SV PB madhor) madintaram RV AV SV PB AS SS vaso vasvoh purusprhah RV . vasor vaso purusprhah SV
- asammṛṣto jāyase mātroh (TB mātṛvoh) such RV TB With mātṛvoh, guaranteed by all mss and Vaidikas, cf perhaps pitṛvya, and note that mātroh in RV. is trisyllabic
- mahāntam gahvaresihām SV . tanūr varsīsihā gahanesihā MS Root gah, with different suffixes
- gambhīrash pathsbhsh pūrvyash (AV. pūryānash) AV. TS HG The AV is clearly secondary, and contains a phonetic simplification Cf next

- prehi-prehi pathibhih pūrvyebhih (AV pūryūnaih) RV AV MS. AŠ. AG Cf prec
- aprajastām pautram
rtyum ApMB $\,$ HG . aprajāstvam mārtavatsam AV. Others, §650 $\,$ Suffixes tā and tva
- §369. Of the lexical variations which remain, special phonetic interest attaches to this, on which of Wackernagel I §232c:
- saumyās trayah śvitimgāh (KSA śi°) TS KSA
- With &nt- and &nt-, synonyms, is to be compared also the synonymous &nt-, see §195
- cıtra (VS śvitra) ādityānām VS MS.
- citro (AV śvitro) raksitā AV MS.
- §370. After two consonants—as in a few stray cases already mentioned under other heads, especially in §367—we find cases which belong with §§419 ff. below.
- sistle springe ralsase (AV ralsobhyo) vi nikse (KS nalse, AV mss nilsve), RV. AV. TS MS KS The Berlin ed and Whitney's translation adopt the RV. reading for AV, despite the absurd statement of the comm that the superfluous v is chandasa See Whitney's note, which points out that viniksva occurs in the next verse
- dhuńkṣāgneyī (VSK. °ṣvā° or °ṣyā°) VS VSK MS And others, see \$255.
- svarṣām (TB suvar°) apsām (TB Poona ed , twice, †apsvām, in text and comm) vrjanasya gopām RV VS MS TB. apsvām is uninterpretable
- mā tvāgnir dhvanayīd (MS dhana°, TS °yid, KSA °yed) dhūmagandhih RV VS TS MS KSA The text of MS is based on pp, the samh mss are all corrupt but have v in place of dh (tvāgnir vunairddhamagandhir). It seems that vu in these mss is a graphic corruption for dhva, which should probably be read in MS as in the other texts
 - §371. After or before single consonants; a miscellaneous group
- āpo devīh svadantu (VSK sad°) svāttam cit sad devahavih VS VSK ŚB: svāttam sad dhavir āpo devīh svadantu MS: svāttam cit sadevam havyam āpo devīh svadatainam TS ApŚ The reading of VSK is poor (cf. svāttam). Cf. next
- em enad adya vasavo rudrā ādityāh sadantu (MS svad°) MS KS TB Here svad° does not belong, the reverse of the prec
- aparıhvıtāh (MS °hrtāh) sanuyāma vājam RV. MS KS Intended for synonyms; MS. slovenly, and suggesting phonetic corruption
- tunduumnam vibhvāsaham (SV. vibhā') RV SV vibhā 'glory' and vibhvā

(for 'van) 'excellent'. Grassmann calls SV's reading false, which is rather harsh since it makes good sense, 'winning glory'.

apām rasam udvayasam (KS udayansam, TA udayansam) VS TS MS KS SB TB TA. The original has an adjective 'strength-arousing', KS. and TA a verb form, which in TA. is 3 plur aor. of ud-yam KS may intend the same with udayansam followed by s; but in VV I p 214 we have allowed it to pass as 1st person sing.

viśvam tu tvāhutayah sarvā yatra brahmā viśvāmṛto 'sī PrānāgU: viśvantu tvām āhutayaś ca sarvāh prajās tatra yatra viśvāmṛto 'sī MU The Conc says, 'read viśantu' for both In the Poona ed (Upaniṣadām Samuccayah, An Skt Ser, 1895), the MU. passage (p 406) reads višantu in text and comm, but the PrānāgU (p 307), viśvam tu in both Certainly višantu must be read

annutur ası dive TS KS JB PB. Vait annutur ası GB The Conc calls the latter a 'blunder', yet, curiously, Gaastra also has annur.

mitrāvarunā šaradāhnām (MS °hnā) cikitnū (MS cikitiam, KS jigatnū, AŠ cikitvam) TS MS. KS AŠ See §45 The AS form is difficult and suspicious

salyaujasā drnhanā (MS. durhrnā, KS † drhanā) yam nudethe TS. MS. KS.: sacetasau druhvano yau nudethe AV See §305

vande dārum vandamāno vivakmi RV: vandadvārā vandamānā vivasļu SV. See VV I p. 218.

anu daha sahamūrān kravyādah (SV kayādah) RV SV : sahamūrān anu daha kravyādah AV. See §355

anukāšena bāhyam MS: anūkāšena bāhvyam VS: antarenānūkāšam TS KSA The VS reading is apparently a blunder, comm. reads bāhyam, which must be right, as the contrasting antaram in the preceding formula shows.

§371a. One anomalous case involving false word-division:

uror ā no deva rīṣas pāhī TS. MS KS 'TB · pururāvno deva etc VS SB. I.S. The former (original) means 'Protect us, O god, from wide hostility'. The Vāj reading is only an ancient phonetic corruption: Eggeling, 'fiercely howling (demon)', which probably comes close to what was felt as the meaning, but Mahīdhara derives rāvan from rā 'give'.

5. Presence or absence of a

§372. Beginning with IE times, and continuing into the life of the individual languages of the family, combinations of s + stop (also s + nasal) vary with the consonant alone minus the s Hindu speech

not only reproduces some of these doublets, but out of its own impulses (analogy and phonetic combinations) extends the process (roots spaś paś, kr skr, etc.) See Wackernagel I §230 in lieu of the almost endless bibliography of the subject. The variant combinations are always imital, and the evanescence of the s is perhaps connected with old conditions of sentence euphony (external sandhi)

- §373. Thus easy opportunity is offered for various readings in this respect. Moreover genuinely different roots exist which are sufficiently synonymous for purposes of exchange. However, the entire phenomenon operates among the variants to a very limited extent. There are also a few cases, all lexical so far as not suspicious, in which initial s before a vowel varies with a form without s, a sort of psilosis comparable to presence or absence of h, below. In addition a very few iniscellaneous cases medially
- §374. Beginning with the cases of initial s before consonants (those which occur are k, t, and p), we present first the few strictly phonetic cases, in which we are certainly or probably dealing with alternative forms of the same word
- sa prathamah samkṛtir viśvakarmā TS TB ApŚ. sā (MS MŚ yā) prathamā samskṛtir viśvavārā (MS yajñe asmin) VS MS ŚB (Pratīka, MŚ) The root kṛ regularly appears as skṛ with sam, so that the Tait form is irregular
- ut te stabhnāmı (TA tabhnomı) pṛthwīm tvat parı RV AV TA Cf Whitney §233c In TA this law operates in spite of timesis, this is not without parallel
- tegān (TS TB ApŚ stegān) danstrābhyām VS TS MS KSA TB ApŚ No doubt the same word is meant in all, but its etymology and meaning are uncertain RV has stega Perhaps the root tig (originally stig) is concerned. It may be significant that in VS MS KSA the word is preceded by one ending in s, while in TS it is initial in its section. As suggested in §372, this is probably the way in which this whole class of variants originated
- tarī mandrāsu prayakṣu AV · stanī mandras suprayakṣuh KS : sa īm (TS ī) mandrā suprayasah (TS mandrāsu prayasah, MS mandrā suprayasā starīman) VS TS MS Probably all the forms may be corrupt, at least they are all difficult But note starīman in MS (tarī AV)
- §375. The rest are lexical, that is different words are concerned, and they are also accompanied by other changes in sounds divah samspréas (MS sampreas) pāhi VS MS SB And

- prthwyāh sampreas (TS TB ApŚ, °cah, VS ŚB samsprśas) pāhi VS. TS MS ŚB TB ApŚ MŚ sam-pre and sam-sprś, praetically synonyms. See §195
- dwam agrenāspīksah †VSK., wrongly quoted in Conc as °ūpīksah dwam agrenāspīksal (TB °āpīāt) VS TB And others
- viśvā sprdho (AV mrdho) abhimātīr jayema RV. AV. TA
- ānjanena sarpışā sam visantu (AV. spršantām, Ppp [Roth] i išanta, TA mršantām) RV AV TA
- yatrāspṛkṣat tanvo yac ca tāsasah (ApMB tanuvam yatra tāsah) AV. ApMB · yatrā vṛkṣas tanuvat yatra vāsah HG
- sa bhūmum viśvato (ArS sarvato, VS sarvata) vytiā (VS spṛtiā) RV. ArS AV. VS. TA. See §200.
- tutho'sı janadhäyāh (PB °yah) MS KS PB MS LS : stuto'sı janadhāh TB ApS See §93
- samsrāvabhāgā (VS ŠB samsrava°; MS °gāh, KS. Kauś. °gās) sthcşā (Kauś tavışā) brhantah VS TS MS KS. ŚB Kauś Sce §§96, 747.
- §376. Initially before vowels, we find a pair of cases of interchange between sa conjunctive and a privative (antonyms), the rest is sporadic: ajoṣā (SV saj°) vṛṣabham paim RV. AV. SV ajoṣā 'unersāttlich, gierig'. sacelasāv (VSK °sā) arepasau VS VSK SB.: sacelasau sarelasau TB And others, see §180
- ā (VaradapU. sā) nah śṛnvann ūtibhih sīda sādanam (VaradapU śaśvat) RV TS. KS VatadapU The comm. is hard put to it to explain sā, he takes it for sa with Vedic lengthening. It is in fact inexplicable
- yavā ayavā ūmā abdah (KS yavā āyavā ūmā † evā abdas) sagarah sumckah MS KS MS: yāvā ayāvā evā ūmāh sabdah sagarah sumekah TS. The form sabda of TS, for regular abda, is wholly obscure, doubtless due to some analogy
- anāgaso yathā sadam it sam kṣiyema Vait anāgaso adham it samkṣayema TB See §110
- §377 The very few cases of evanescent medial s are entirely sporadic, except a few cases of precative and other optative forms (as bhūyāma bhūyāsma), which are found in VV I §175 and are not repeated here: agnir no vanate (VSK vanute, SV TS KS vansate) rayim RV SV VSK TS MS KS Present and s-agrist.
- tasya te bhaktıvānsah syāma (MS KS °vāno bhūyāsma) AV MS. KS · tasyās te bhakşıvānah syāma (MS KS ApŠ 4. 13 7† bhaktıvāno bhūyāsma) MS. KS TB ApŠ. (both) Suffixes vans and van

6 Presence or absence of visarga

§378. This change, of course, can occur only at the ends of words or parts of a compound word (or before pāda endings), and in fact it is most commonly found at the ends of pādas. Included are some cases where the actual reading of the text does not show visarga, owing to conditions of sandhi. Altho the modern Indian pronunciation makes this sound regularly an aspiration followed by a vowel, which takes the coloring of the preceding vowel (Wackernagel I §225b), there seems reason to believe that its pronunciation in ancient times was much fainter, and certainly it was never followed by a vowel. The variants support this theory by showing not a few cases in which visarga is evanescent. In the majority of cases both forms are morphologically explicable, involving different forms of noun or verb inflexion or the like, some must be considered mere corruptions.

§379. In VV I §25 we have already presented a group of cases in which verb forms with final h vary with corresponding forms without h, a fairly frequent phenomenon.

pra-pra yajñapatım tıra (TA tırah, Poona ed tıra) AV VS TS MS

KS TA AS SS ApS

süryasya tapas tapa (MS MŚ tapah) MS TA ApŚ MŚ nı düraśravase vaha (ŚŚ vahah, em , mss mahah) AV ŚŚ

nıyudbhır (AV. vıyugbhır) väyav (AV VSK MS väya) ıha lä vı muñca (ŚŚ †muñcah) AV VS VŚK MS ŚB TA AŚ ŚŚ ApŚ Add to VV I §25

vrśvasmāt (TA dvo vr°) sīm aghāyata uruşya (TA °yah) RV TA lāv imā upa sarpatah SV. JB · emām anu sarpata MS agne vittād dhanşo yad yajāma (TB °mah) RV TB aśvinā bhişajāvatah (MS °tam, TB †°ta, both edd) VS MS TB anyavratasya (TA anyad vra°) saścima (TA °mah, RV saścire) RV VS

MS SB TA (corrupt)

pratı bhāgam na dīdhıma (SV °maḥ) RV AV SV VS N vıratāh smah (ŚG sma bhoh) ŚG PG.

abhrratāh smah (YDh sma ha) ViDh YDh BrhPDh Here, in late texts, we find what may be a trace of the modern pronunciation (smah sma-ha)

iasmın vayam upahūtās tava smah (MŚ sma) TB MŚ

tau saha (VS SB tā ubhau) caturah prasārayāvahai (SB °yāva, MS `°yāvah) VS TS MS KSA SB ApS

viśvāh pinvathah (TB °tha) svasarasya dhenāh RV MS TB (comm °thah in Bibl Ind ed, but Poona ed °tha) This is probably only a case of sandhi before s + consonant, ef §978 ff

- ata ũ şu madhu madhunābhi yodhi TS: adah su madhu madhunābhi yodhīh RV. SV AV AA. MS See VV I p 101.
- agne (MS agnir) deveşu pra vocah (MS voca) RV. SV MS. TA. Add to VV I §§25, 156
- sam agnis tapasāgata VS. MS SB. (preceded by svāhā, probably felt as part of the formula tho in MS edition separated by a mark of punctuation) svāhā sam agnis tapasā gata (*gatah, Poona ed gata) TA * As pple gatah is defensible See VV I p 161
- varebhir varān abhi şu prasīdatah (ApMB pra sīdata) RV. ApMB A participle (gen sing, Grassmann, acc pl, Oldenberg) is made into a 2d plur in ApMB
- tha tama (HG †ramah) MS AB AS. ApS HG Here ramah is a noun form
- §380. In noun inflection the variation occurs between nominative and vocative case-forms.
- punar āgāh punarnava (AV "nava and "navah) RV AV (bis)
- mcerur asi nicumpunah (TS TB mcañkuna, MS KS mcuñkunah) VS. TS MS KS SB TB LS. Vocative in TS TB by assimilation to an adjoining formula, see §150
- riena (MG. rte 'va) sthūnām (MG °nā, ApMB HG °nāv) adhi roha vanśa (MG vanśah) AV. AG ApMB HG MG Kauś Here the nom is secondary
- agne ghrtenāhuta (KS °tah) AV VS TS MS KS ApŚ
- yajñah praty u sihāt (KS pratyasihāt, v l praty u°, MS adds sumatau matīnām) KS MS yajña pratutisiha sumatau suševāh TB ApŚ indrah (indra) somasya pītaye (also °ye vrsāyate) RV (all three)
- ındra (MS ındrah) stomena pañcadasena madhyam (KS °dasenougah) TS MS KS AS
- paramajyā rcīşamah (SV.†°ma) RV. SV AV
- devebhyo (ApŚ deveşu) havyavāhanah (RV * °na) RV. (both) ApŚ.
- sahasrākşo amartyah AV.. sahasrākşāyāmartya AV.
- pavamānah (SV °na) samtanım eşi kṛnvan RV SV
- tvaştā devaih sahamāna ındrah MG tvaştar devebhis sahasāma ındra ApMB
- yo agnıh kravyavāhanah (VS KS kavya°) RV. VS. KS AS yad agne kavyavāhana TS See §353.
- hıranyapakşah sakunıh HG · hıranyaparna sakune PG hıranyavarnah sakunah MU
- subtrana srja-srja śunaka ApMB. suvū unah snja-srja HG The latter is doubtless corrupt, a voc is required.

- ındra kraivā (MS ındran krivā) maruto yad vasāma RV MS KS See §664
- ayā somah (SV soma) sukrtyayā RV SV See VV I §328
- ā tistha mitravardhana (KS TB † Ap\$ † °nah) AV KS TB Ap\$
- āpṛno 'sı sampṛnah (ApŚ āpṛnoṣi sampṛna) . ŚŚ ApŚ The latter is secondary and poor
- undra karmasu no'vata VS KS indrah karmasu no'vatu TB (but read undra ...'vata, see VV I p 260)
- ındra (MS ındrah) śrutosya mahato mahānı RV. MS The nom is hardly construable
- _ indrah (SV. PB indra) suteşu someşu RV SV. PB AS SS
 - ındra (MS ındrah) svadhām anu hi no babhūtha RV MS KS
 - $k\bar{a}$ mena kṛtah (RV. and p p of MS kṛta) śrava ıchamānah RV MS TB
 - uşihā ratham (TB. rathe) adhı tam (VS SB yam, TB yad) vajrahasta (TB. °tah) RV. VS SB TB
 - dhānāsomān manthina indra (MŚ indrah) šukrāt TS KS MŚ The nom is not construable, see Knauer's note.
 - mıtra satyānām pate (SS satyānām adhipate) TB SS: mıtrah satyānām (VS SB satyah) VS TS MS KS SB PG.
 - vrśvā (KS PG vrśvāś ca) †deva (PG devah) prtanā abhrşya (KS °şyāh, PG †°şyak) KS TB. ApŚ. PG HG.
 - vrīhīnām medha (MŚ medhah) sumanasyamānah TB ApŚ MŚ śuddho mamaddhi somyah (SV somya) RV SV.
 - sajoṣā ındra (TB ındrah) sagano marudbhıh RV. VS TS MS TA. MahānU. AS
 - §381. In miscellaneous other forms of nouns and adjectives, commonly with change of construction which can be more or less justified, sometimes involving different but related stems:
 - pibāt somam amadann (AV somam mamadad) enam ıştayah (AV ışte)
 - AV AS SS See VV I p 88, loc sing of isla nom pl of isli ghriavatī savitar (MS KS "tur) ādhipatye (TS "yaih) TS MS KS AS Loc sing instr pl Cf \$706
 - avyo (SV avyā) vāre (SV * vāraih) pari priyah (and priyam) RV SV As prec
 - candrena jyotir amrtam dadhānāh (KS \(\text{TB} \) comm and Poona ed \(\text{onā} \) VS. KS \(\text{TB} \) sukram na jyotir amrtam dadhānā \(\text{MS} \) (but \(\text{p p.} \) \(\text{onāh} \) The plural agrees with asvinā and sarasvatī together as subject, the fem sing with the nearest subject, sarasvatī alone
 - dhanamjayam dharunam dhārayışnu RVKh bhūmidinham acyutam pārayışnu AV bhūmidinho cyulas cyāvayışnuh AV Change of

- gender, neuter to masculine; the latter certainly secondary, see \$268
- sa viśvācīr (KS °cī) abhi caṣṭe ghṛtācīh (KS °cī) RV. VS TS MS KS. ŚB Change of acc pl to dual, explained in §357 'But the actual reading is ghṛtācīr (before initial vowel following)
- tarī mandrāsu prayakşu AV (taken by Whitney as loc plur): stanī mandras suprayakşuh KS (apparently felt as nom sing) And others, all forms dubious and likely to be corrupt; see §374
- samhīlāsī višvarūpā (VS SB SS °pī, TS. ApŠ * °pīh) VS TS. MS KS. SB SS ApS (bis) In TS the old nom fem of the vrkīz type
- khajāpo 'jopakāśinīh ApMB . bajābojopakāśinī HG. Both words unintelligible, §69 Perhaps h in ApMB ending of wikis type.
- anāhanasyam vasanam carīṣnu (ApMB HG ja°, PG jarīṣnuh) ŚG PG ApMB HG See §57. The nom masc transfers the epithet, whose meaning is not very clear, from the garment to the person who is the subject.
- yenā samatsu sāsahah (SV. °hīh, MŠ °hī) RV. SV. VS. ApŠ MŠ See §584
- aghadviştā devajātā AV. Kauś: atharvyuştā devajūtāh ApŚ In AV. nom sing fem In ApŚ, which is ot erwise corrupt, the actual text has jūtā followed by a sonant, and Caland understands a sing, but the verb is plural, and the Conc gives what seems intended as the reading of the text (nom plur.).
- sīrāh (TS MS KS sarāh, AV. sarā) patatrinī (TS MS KS °nīh) sthana (KS stha, AV bhūtvā) RV. AV VS TS MS KS. Sing in AV, plur in the others
- ya ābabhūva (PB āva°) bhuvanām viśvā (PB viśvāh¹, comm. viśvām) VS JB PB ŠŠ Vait viśvāh is certainly wrong
- vīruc chapathayopanī AV · vīdu chapathajambhanīh ApŚ (corrupt, Caland adopts the AV. reading) See §272
- uta tām uşaso budhi RV GB Cone budhih for GB, and so all mss. apparently read, but Gaastra emends to budhi (loc sing 'at the awakening of dawn').
- arāddhyā edidhişuhpatim VS.. ārādhyai (read with Poona ed. ar°) † didhişūpatim TB The VS form is anomalous, as a fem word the stem can only end in u, and the nom form in composition is absurd
- avasyuvātā brhatī (TS ° tīr) na (TS nu, AS tu) šakvarī (TS °rīh) TS. MS KS AS Sing : plural.
- ımam yajñam avantu no ghrtācīh (MS KS AŚ avatu yā [AŚ no] ghrtācī) TS MS KS AŚ Sing : plural.

- parasur (TS. parsur) vedih parasur nah svasti (TS. °tih) AV. TS svasti is familiar as both fem. and neut.
- vişihıtāh (AV. °tā) pṛthivīm anu RV. AV. VS. AB TB. SMB. Fem. pl : neut pl (in different contexts).
- śam rālrī (VS rālrīḥ, VSK. TA rālrıh) prati dhīyatām AV. VS VSK. TA MS All noms sg
- śałamūlā śałāñkurā TA. MahānU.: śałamūlāḥ śałāñkurāḥ MahānU. Fem sing: plur.
- śrnvantv āpo dhuşanāś ca devīļ (MS.* dhişanā ca devī) VS. TS MS* KS. ŚB Sing.: plur.
- viśo (SV. diśo) wśwā anu prabhuḥ (TB. prabhu) RV. SV. MS. TB. Agni is meant, and a nom. or voc masc is required; prabhu, repeated in the comm, is apparently understood as an adverb, but is probably only a phonetic error.
- samsıtam kşatram (MS. KS. TA add me) jişnu (AV. kşatram ajaram astu jışnuh) AV. VS. TS MS. KS SB TA. The AV. form would be mase, which cannot be construed; Whitney accordingly adopts jişnu
- valso jarāyu (KS. garbho jarāyuh) pratidhuk pīyūşah AV. TS. MS. KS. The regularly neuter word is here masc in KS., perhaps attracted to the gender of the preceding masc
- sa nah pṛthu (TB pṛthuḥ) śravāyyam RV. SV. ŚB. TB Transference of the epithet with change of gender from neut to masc.
- sīsam ca me trapu (TS °puś) ca me . . . VS. VSK TS MS. KS. The rare stem trapus, for the regular trapu
- sapatnīr Jabhibhūvarī (ApMB. °rīh) RV. ApMB. Only a nom sing fem can be construed See Winternitz, Introd, xxii
- sarasvatī (AV. TB.7°tīh) svapasah sadantu (AV. sadantām) RV. AV. VS. MS. KS TB N. Whitney calls the °tīh form a blunder and emends This is perhaps going too far; but of course it is a nom sing. like the other.
- sarasvatyā (TV °tyāh) suprppalaḥ VS. MS. TB Instr.: gen.
- sahasrasīrṣā (ArS °ṣāh) puruṣah RV. ArS VS SB. TA. ApS Both nom. sing; °sīrṣāh as if from an s-stem (contamination from siras?)
- atividāhā vithurenā cid astrā (MS astāh) RV. MS KS The MS is doubtless corrupt
- varşman kakubhi (TB. Conc °bhih, MS kakubbhih) sisriyānah (TB srayasra) TS MS TB See §400
- upahūtāh sapta hotrāh TS TB SS.: upahūtā saptahotrā SB Sing plur.

- agne tvam purīşyah VS. KS SB: agneh purışyam asi VS. VSK. TS. MS. KS SB TB. ApS. MS. Voc gen.
- hıranyayāh (MS °yā) śucayo dhūrapūtāḥ RV. MS. The only grammatically construable form is °yāh; MS. seems corrupt
- so 'ham vājam saneyam agne (KS. sanāmy †agneh) VS TS. MS. KS. Voc. 'gen.
- sapratha (MŚ °thah) sabhām me gopāya (MŚ. pāhr. and 'jugupah) TB. ApŚ MŚ. Both voc ; stems in a and as
- ımā brahma brahmavāhah (TS † °ha) RV. AV. KS TB. As prec
- svāhā tvā subhava (VSK. TS. ApŚ. °vah, KS. subho) sūryāya VS. VSK. TS MS. KS KB ŚB. ApŚ Vocatives; s and a-stems On KS. see §749
- dātum cec chikṣān sa svarga eva AV.: dātum cec chaknuvānsaḥ (Poona ed chaknavān sa) svarga eṣām TA. See §826.
- dyumad vibhāti bharatebhyah sucih (VS suci, comm sucih) RV. SV. VS. TS MS KS suci might pass as an adverb.
- dūrvā rohatu puspinī (RV rohantu puspinīh) RV. AV. Sing: plur. tripadā yā ca saļpadā (VS yāś ca saļpadāḥ) VS TS MS KSA. Sing: plur.
- trṇam vasānā (HG. °nāh) sumanā asas (HG. asi) tvam AV. HG. The form can only be nom sing fem, HG is impossible
- prthwyā (MS * °vyāh) sambhava VS TS MS (both) KS SB. KS ApS Probably the only correct reading is °vyā (see von Schroeder's note). §382. In adverbial forms:
- athā (AV adhah, comm adha, but Ppp adhah) sapatnī yā mama RV. AV ApMB.. adhā sapatnān māmakān AV. See §74.
- śrnvanty (PB °tv) āpo adha (PB 'dhah) ksarantīh RV PB
- parā svapnamukhāh śucah AV parah svapna mukhā krdhi KŚ See §820 The variation -mukhāh (bahuvrīhi): mukhā belongs to the preceding section
 - §383. Involving different divisions of words.
- samudrād udajani vah (ApŚ udacann wa) srucā MS ApŚ See §53.
- ıdam aham rakşo 'bhı (MS *rakşobhıh) sam ūhāmı (TS sam dahāmı) TS MS (both) KS MS As the Conc suggests, rakşobhıh must be a corruption
- girā ca (AV. vīrājah) śrustih sabharā asan nah RV. AV. VS TS. MS KS SB See §57
- śarīram yajñaśamalam (MahānU yajñah śa°). TS KSA. TA. MahānU See §818
- tıgmāyudhāya bharatā srnotu nah (TB srnotana) RV TB N.

- āsann ā (SV PB āsan nah) pāiram janayanta (KS °tu) devāh RV SV VS. TS MS KS PB ŚB
- pra su (HG sa) mṛtyum (SMB pra sumariyam, MG prathamam artım) yuyotana (MG yuyotu nah) SMB ApMB HG MG
- ürjam bibhrad vasuvanih (vah sumanäh, vah suvanih, vasumanäh).., see §227
- upānasaķ saparyan RV † upo nu sa sap° SV
- kavır yah putrah sa īm ā (TA Conc. sā ımāh, Poona ed sa ımā) cıketa RV AV TA. N ımāh has no standing
- ava (RV. abhı, MS ā vah, VS SB vācā) somam nayāması (RV mṛšāması, VS SB avanayāmı) RV. AV VS TS MS. KS. SB The reading of MS is secondary but simple
- ındrah päsena †sıktvā vah (HG pāsena vah †sıktvā) ApMB HG · ındrapāsena sıtvā PG See §819.
- riasyariena mām uta (TA 11a) TB. TA. riasya iv enam āmutah MS (corrupt, see §838)
- adyā mamāra sa hyah sam āna (MS Samhītā, sahyah samānah) RV AV. SV MS N. sam āna, verb, samānah, ad]
- vīrenyah kratur ındrah susastıh RV cf varenyakratūr (°tur, īdenyakratūr) aham, §554 Conc suggests vīrenyakratur, Oldenberg, Noten, goes further and suggests varenya- (or °yah) kratur.
- vāāmanascaksuhsrotranhvāghrānaretobuddhyākūtisamkalpā (TA TAA °ākūtih samkalpā) me sudhyantām TA TAA MahānU Despite the persistence of the reading °ākūtih (to be sure, one ms of TA reads like MahānU), it seems to leave us with an impossible ending for the long compound
 - §384. Miscellaneous:
- purā jatrubhya (TA. ApMB jartrbhya, MS cakrbhyā, p p vaktrbhyah) ātrdah (MS °da) RV AV. SV. MS. PB TA. KŠ ApMB See §57, ātrdah apparently-abl sing of a noun, MS corrupt, perhaps feels ātrda as imperative.
- apa (AV ava) śveta padā jahi AV. AG ŚG PG ApMB. HG: apah śvetapad ā gahi MG (but most mss apa, so read, cf §817)
- apa (MG apah) prāgāt tama ā yyotir eti RV MG Here all mss of MG. have the visarga, which is certainly near to nonsense
- parītosāt iad arpitha ALS: parī dosād ud arpithah KS The true reading in both seems to be udarpitah, see §63
- sugantuh karma karanah karisyan JB: sugam tvah karmah karanah karah karasyuh LS On the obviously corrupt LS see §739
- gharmam kocantah (AS °ta, SS °tam) pravaneşu (AS SS pranaveşu) bibhratah AB AS SS Cf VV I p 165

aghāya bhūma harvah parādai (MS °daih) RV. AV. TS MS parādai is an infinitive; parādaih is a very poor reading, perhaps felt stupidly as a second person aorist injunctive (addressed to Indra, despite the 1st person verb bhūma¹), or else as an instreplur. 'by betrayal'. tām ha varitar na pratvaarbhnan AV. AB GB JB ŚŚ Gaastra reads

nah in GB (v l na), but the sense clearly requires na

na sīsarīdata (HG †sīsarīdatah) ApMB HG Both hopelessly corrupt, Winternitz p xxvi suggests sīsarī datah)

adrnhathāh sarkarābhis trivisjapi (MŚ tribhrsjibhih) KS ApŚ MŚ.

samudram nah subhvam (AVPpp ms subhavas) tasthivānsam AVPpp MS samudram na subhvah svā abhis[ayah RV . samudram na subhuvas tasthivānsam AV And others, §§119, 789. nah, pronoun na, comparative particle

bhişajam na (MS nah) sarasvatīm VS MS TB na, comparative particle.

7. Presence or absence of h

§385. The small number of cases of this sort at the beginning of words shows something that resembles occasional psilosis, or its reverse In the interior of words it is even rarer, and entirely sporadic, partly a matter of corruptions, but of the startling samjigaire in the first variant under §387

§386. Initially h appears and disappears before vowels and y, once r. The variation is almost wholly lexical, it occurs especially with particles and light words, and sometimes involves different divisions of words: sa ugrah sa hi (PG i) havyo babhūva TS PG This has most the appearance of a purely phonetic variant; an otherwise unknown i (said to mean 'and', the mss are unanimous) seems to be substituted for his and may be suspected of being only a phonetic variant for his

hımkārāya (and, hımkrtāya) svāhā VS. MS. SB: īmkārāya (and, īmkrtāya, KSA †ım°) TS KSA TB ApS. Interjections

tasmınn (AV yasminn) ā (VS tasmın ha) tasthur bhuvanānı viśvā RV. AV VS. cf tasmınn ārpıtā bhu° vi° RV.

cakşur yeşām (v 1 hy eşām) tapa uccabhīmam MS And others; see §340 yasyām ıdam visvam (MS visvam hy asyām) bhuvanam āvviesa VS TS. MS KS SB

mahaś (MS mahī) cid yasya mīdhuşo yavyā RV VS. VSK. MS ŠB: mahī hy asya mīdhuşo yavyā TS

dhiyo hinvāno (MS dhiya invāno) dhiya in no avyāt (RY. avyāh) RV. MS TS Rime words

antarıkşe pathibhir iyamanah (GB hriyamanah, v. 1 hiyamanah, but no v 1 in Gaastra) RV GB See §353.

- uta no brahmann anşah (MS. °man hanşah) RV. MS KS AB SB SS KS The secondary hanşah is unaccented in MS, perhaps felt as a verb form from root hu: 'and do thou sacrifice for us in the brahman'.
- tena samhanu kṛnması AV.: tena sann anugṛhnāsı HG See §47.
- atho mālātho pīlā TA. hatā mālā halah pīlā SMB; halo halamātā krimih AV. The TA. probably secondary.
- raksohāmīvacātanah (AV* atho amīva°) RV AV. (both) VS. TS MS KS. ApŚ If the AV variant is based on the other, which is not certain, it is clearly secondary.
- ānirīmukhah... HG ālıkhann anımışah... hanirīmukhah... PG Barbarıc names of demons, with vague suggestions of popular etymology (as if related to ānira and a fem form of hanir).
- atho ye ksullakā wa AV hatah krimīnām kşudrakah SMB.: atho sthūrā atho kşudrāh TA.
- āsannışūn hrisvaso mayobhūn RV. AV TS MS KSA N : āsann eşām apsuvāho mayobhūn SV See §820
- vanishor hrdayād (AV * udarād) adhi RV. AV (both) ApMB
- §387. Medially this phenomenon is even rarer, and in general it has no particular phonetic interest. Only the first variant deserves special attention, in it all mss of Vait are reported as agreeing on the remarkable form samjigāīre, which is certainly for ohire and shows an unquestionable 'psilosis' between vowels which, just because it runs counter to all expectations in Sanskrit, must apparently be assumed to be a genuine (dialectic) phonetic variant.
- tāh prācya (Vait °yah, MS. prācīr) uzjīgāhire (Kچ°hīre, Vait samjīgāre) Vait KŚ MŚ prācīś cojjāgāhire ApŚ
- sa (read sa) nah prajām pašūn pūhy aranīyamānah (p p aháh, ánī (sic!), yámānah) MS sa no rucam dhehy ahrnīyamānah TA Read doubtless ahrnīyamānah in MS; the absurd p p points in this direction
- marudbhyo grhamedhibhyo (MS °dhebhyo) başkıhān (MS taş°, ApŚ bāşkān). The word is wholly obscure
- tujo janā (ArS jane) vanam svah AV. ArS.: tujo yujo vanam (SS balam, emend) sahah AA SS The passage is obscure, we see little to choose between svah and sahah
- pary agmm ahrsata (VSK 7 arşata or aharşata) RV VS VSK · parīme 'gmm arşata AV (v l m AV arışata) Ppp (Barret, JAOS 43 99) reads as in RV. except aharsata, with one ms of VSK; Barret em ahrsata

CHAPTER X. CONSONANT GROUPS

§388. In this chapter we include, first, variations between identical double consonants (or aspirates with preceding non-aspirates) and the same consonant alone; second, cases of assimilation of one consonant to an adjoining consonant, or the reverse, and finally, some cases of partial simplification of groups of more than two consonants, by the omission of one consonant (or the reverse)—in so far as the consonant omitted or inserted is not one of those whose character particularly lends itself to such treatment, that is, a nasal, semi-vowel, liquid, sibilant, h, or visarga, all of which have been treated in Chapter IX

1 Double and single consonants

§389. The principal subject of this section is double and single consonants between vowels, that is, not immediately preceded or followed by another consonant When associated with other consonants, the tradition is so confused that a detailed record would hardly Thus, after other consonants, especially after nasals be profitable and r, consonants are very commonly written either single or double in Editors have followed very different courses, sometimes they attempt, with more or less consistency, to regularize the discordant spellings of their mss, sometimes they add to the confusion whole subject Whitney, Giammar §§228-232, Wackernagel I §98 plain fact is that after or before other consonants it was in practice virtually impossible to distinguish between pronunciation of single and double consonants, as Wackernagel says 1 c It seems therefore fruitless to collect such variants as the following.

śunddhi (PG MG śundhi) śiro māsyāyuh pra moṣīh AG PG. ApMB MG Many mss of ApMB read śundhi

o şu (MS şū) vartta (MS KS varta) maruto vipram acha RV MS KS The spelling vartta (2d plural) is etymological; Muller prints varta in his one-volume edition (1873) of RV.

§390. Similarly before another consonant, a double consonant which would be required by etymology is very often written single (Whitney and Wackernagel II cc) Very little value is or can be attached to the readings of mss and editions in such cases Thus the word pattra

'wing', from root pat with suffix tra, may be spelled patra at any time, as in'

syenasya patram (MS pattram) na plihä sacibluh VS MS. KS TB, where only MS. has the etymological spelling. So in:

ukthapatra (MS °rā, TS °patra) īdyo grbhītah VS † TS MS KS † SB †, the editor of TS alone prints °patra, all others (contrary to the Conc) °patra, but most mss. of TS. actually read °patra The same arbitrary procedure is applied to TS in

yena (yenā) rṣayas (yenarṣ°) tapasā satram (TS \dagger sattram) āsate (VS. ŚB āyan) VS. TS MS. KS ŚB ,

where again most mss of TS. read satram, with the others, but against the etymology (root sad) We have not burdened this book with a list of such cases

- §391. Equally a matter of orthographic convention, and unworthy of prolonged consideration, are such variant spellings as occur in the following verb forms:
- tā yā devā. ā ca šāsvā (VS. and Poona ed of TB šāssvā) ca gurasva VS TB. The root is šās, the ending sva.
- ıyam vah sā satyā . yām ındrena samadhaddhvam (MS °dadhvam) TS. MS: eşā vas sā satyā...yām ındrena samadadhvam KS Reduplicated stem dhad or dad plus ending dhvam
- §392. Before dismissing this subject, however, we shall record a number of variations where real lexical or morphological shifts occur, or at least may possibly be felt as occurring, to be sure we shall find that some of them are mere corruptions or orthographic variants of the same sort as those just illustrated
- arhann idam dayase visum abhvam (TA abbhwam, MS ā dhanvā) , RV MS TA. The TA may quite possibly have intended abhvam (on the epenthetic u cf §790). But if the comm is right it would be a lexically different word, he analyzes it as ab-bhwam 'produced from water (and the other four elements)' This is implausible as to sense, but formally possible
- ut tvā (SV. PB Svidh u †tvā, two words) mandantu somāh RV. AV. SV PB. SS. Vait Rvidh Svidh The Conc prints utvā as one word, implying belief that ut tvā is intended. This is probably right, since the interjection u (of most doubtful authenticity even later) can hardly be assumed for SV, and the other u is enclitic, and could not stand first
- ya älrnatty (SamhitopanisadB älrnoty) avitathena (VäDh avida^o) karnau SamhitopanisadB. VäDh. N ülrnoty is an impossible form and must be an error.

- ayam yah puro vibhinatty (SV. °naty) ojasā RV SV. The form vibhinaty is not noted by Benfey in his Glossary or the notes to his translation, and is doubtless a mere orthographic variant if not a misprint
- agnir hotā vetv (SB vettv) agnir (SB AS agner) hotram vetu prāvitram . SB. TB AS SS So the Cone; TB. Poona ed reads vettv and vettu In any case there is here probably a real lexical variation between roots vī 'enjoy' and vid 'know' (SB comm. jānātu). Cf. next, and the variations between the participles vīta and vitta, \$398 below
- prati tvādītyās tvag veitu (TB Poona ed † veiu) VS TS MS KS SB TB:
 prati tvā dīva (TB dīvah) skambhanīr veitu (TB. Poona ed † veiu)
 TS TB And others in the context The text of TB actually
 reads veiv-ity āha; doubtless veitu is intended
- āprā (AV * āprād) dyāvāprihwī antarıkşam RV. AV. ArS VS TS MS. KS ŚB. TB AA TA N See VV I pp. 27, 129.
- yad ūrdhvas tisihā (KS tisihād) dranneha dhattāt RV MS KS AB TB.

 N Here the KS form assimilates, perhaps, to the following dhattāt, which however is originally and properly 2d person Cf.

 VV I p 27.
- agnır dād (TS dā) dravnam vīrapešāh RV. TS See VV I p. 26
- satvānām (KS †sattv°) pataye namah MS KS This is certainly not a real lexical variant, for the gen. plur of satvan would be satvanām (cf §494), MS must intend gen plur of sattva, like KS.
- brhaspataye mahisa (TS mahi sad) dyuman namah AV TS. The AV. has a corruption (called by Whitney 'senseless') based on the pronunciation of ddy as dy, and bringing in its train a false division of words; see §826.
- sadanān (Vait sa dahan) pradahan v (Vait nv) agāh GB Vait Particles u and nu; the passage is metrical and v(nv) is read consonantically
- lokam (RV. ulokam) u (ApŚ 1d) dve upa jāmī (RV. jāmīm) īyatuḥ RV. MS ApŚ.

Double and single consonants between vowels

§393. The shift between double and single consonants when both preceded and followed by a vowel is more worthy of attention. Here we seem to find traces of the Prakritic tendency to treat a short vowel plus a double consonant as the phonetic equivalent of a long (or nasalized) vowel plus a single consonant, so that (in Pāli and Prakrit) the two may interchange at random, without regard to etymology. See Geiger,

Pāli §§5, 6, Edgerton, Studies in Honor of Hermann Collitz 32 f. While other considerations regularly enter in with the variants, it seems to us hardly to be doubted that this phonetic tendency existed in the Vedic language. It appears most clearly, of course, when the preceding vowel is long before the single consonant, but short before the double consonant.

§394. In some variants the preceding vowel is the diphthong e This sound, of course pronounced as a monophthong from early times, may be either long or short in Pāli and Prakrit; there it is always short when followed by two consonants, long when followed by one. In Sanskrit it is invariably considered long. But we find variations in the mss between single and double consonants after it, as in AV. 15. 10. 2 (see Whitney's note), where nearly all mss read mānaye tathā for mānayet tathā. And so in the variant

sa no jīveṣv ā yame AV: sa no deveṣv ā yamat RV. TA, where most mss of AV read yame, but the comm yamed, which is certainly intended, the next word begins with d- and the actual reading of RV TA is vamad. See Whitney's note on AV 18. 2 3, and VV I

p. 74 This is clearly a phonetic simplification

§395. The other variations, first where the quantity of the preceding vowel shifts with the doubling of the consonant, involve lexical or morphological shifts. Thus in equivalent noun stems of different declensions, the stem apsaras appears also as apsarā independently apsarassu (HG. °rāsu ca) yo gandhah ApMB HG

yā medhā apsarāsu (MG medhāpsarahsu, Scheftelowitz reads medhāpsarassu for RVKh) RVKh MG: apsarāsu ca yā medhā TA MahānU HG ApMB ApG

Here the fem gender of the word, and its nom sg apsarāh, may have helped in the change But the like is found with neuters, where no such influence can be suspected.

yā te agne 'yāśayā (VS ŚB 'yahsayā, TS 'yāśayā rajāsayā) VS TS MS KS ŚB MŚ · yā te agne 1ajāsayā (VS ŚB rajahsayā) VS MS. KS ŚB MŚ

§395a. The adjective mahad varies with its composition-form mahā-agre vājasya bhajate mahādhanam (SV bhajase mahad dhanam) RV SV.

§396. The forms rāye and rāyas vary with rayyai and rayyās (see Edgerton, l c, §393). Undoubtedly the former are from rai, while the latter are from the parallel stem rayi (which by the way is usually masculine, but occasionally feminine) But the phonetic shift here considered seems also likely to be involved, the rai forms seem original: agne samrād ise rāye (ApŠ rayyai). AŠ. ApŠ ise rāye. VS MS

SB. TB. (The Conv quotes AS ApS. under this form too, but it refers to the same passage, agne samrād etc)

rāyas poṣena (MS rayyā) mā pasyata (and: vah pasyāmı) TS. MS KS. §397. The base su, used as a root noun, must appear as sut; a superlative from it, -suttama, varies with the parallel base -sū-tama:

ındrāya (MS MŚ ^oya tvā) susuttamam (VS ŚB susūtamam) VS MS. KS ŚB. MŚ

§398. The roots $v\bar{v}$ 'enjoy' or the like, and vid 'find' with dental suffixes, produce forms which are lexically independent but show the same phonetic shift, it appears that in both the variants recorded, the forms of $v\bar{v}$ are older Cf §329, again hota vetv (vettv) . :

ışlam ca vīlam (SB AS vitlam) ca (SS cābhūt) MS SB TB AS SS socasva devavīlamah (KS °vitlamah) RV. RVKh VS TS MS KS.

SB TA: rocasva devavītamah VS

§399. More numerous are the cases in which the preceding vowel is either short or long in both forms of the variant. They are chiefly lexical. We begin with those in which the vowel is short. Forms of the root cit, with dental suffixes, vary several times with derivatives of ci or cyu.

acıttapājā (TA acyuta°) agnīt, and.

acuttamanā (TA. acyuta^e) upavaktā MS TA. SS Proper names of rishis; 'unthinkable' and 'unshakable' both make good sense, the latter is secondary.

citim (MS KS MS. citin) juhomi manasā (VS TS SB add ghrtena)
VS TS. MS KS SB MS ApS. See Keith on TS (HOS 19
p 444, n. 1). Citim is perhaps, as Keith says, a mistake for
citim; but it seems widely attested, and we doubt whether it 'should
have been corrected' by the editors of the texts where it occurs
To be sure, one ms of MS has citim; but MS citim The passage
belongs to the ritual of 'piling' (citi) the fire-altar. In the same
context occurs:

citim acitim (KS ms teitm acitim, emended by von Schroeder) cinavad KS†°vo) vi vidvān RV TS KS Add to VV I §337 Cf. prec mā tvā ni kran pūrvacito (AV. °citā, MS °citau) nikārinah AV. VS TS. MS. KS. Lexical, but the reading with it seems to correspond better to what is expected (contrary to the view of Whitney and Keith). It refers to people who may 'get ahead of' us in the favor of the gods 'Having thoughts (devotion, or magic?) first', or, in MS, 'in first thought': 'piling (the altar) first'.

- §400. One case concerns different case-forms of the same stem.
- varşman kşatrasya kakubhı (TB Conc °bhıh, Poona ed °bhı, MS kakubbhıh) şışrıyānah (TB şrayasva) TS MS TB Loc sing instr plur. of kakubh The form kakubhıh is an impossible blend of the two, and should doubtless be removed from the text with Poona ed.; yet the comm seems to have read so (but he glosses uttamānge, as if loc)
- §401. The rest are miscellaneous, and in part concern mere corruptions and false readings
- nama ākhidate ce prakhidate ca VS MS KS. nama ākkhidate ca prakhhidate ca TS The curious doubling in TS, is authorized by TPr 14.8, but the mss. show all sorts of variations, see Whitney's note on TPr, and Weber's on TS 4.5.9.2
- ayā san (ayāh san, ayās san) manasā hitah (MS kritah, p p kritah, KS kritah) MS. KS TB. ApŚ. ApMB HG. ayāsā manasā (vayasā) kritah AŚ ŚŚ Kauś. ayasā manasā dhritah ApŚ ApMB kritah is obviously a blunder Cf §402
- verttāya (VS vertāya) svāhā VS TS MS KSA vertāya probably an
- nurtah (SS nurtiah) puruṣād dṛth AV SS The passage where this occurs is rank nonsense, and any reading will do as well as any other
- vasśvānarah pratnathā nākam āruhat (PB †āruha) AV PB TA ApŚ In all followed by diva-, āruhad is the actual reading PB has a phonetic simplification or corruption; a 2d sing impv is inappropriate (subject nominative, and parallel 3d person verb in last pāda) Add to VV I §332
- phalāya, and phallāya, KhG bhalāya, and bhallāya, SMB GG See \$79
- samudrād udajanī vah (ApŚ udacann īva) srucā MS ApŚ See §53 imām narāh (narah) kṛnuta vedim etya (eta, etat), see §328
- yamasya loke adhırajjur äyat (TA äya, MS. loke nıdhır ajaräya) AV MS TA Corruption in MS.
- viviți (viciti, vivityai, viviștyai) svāhā, see §866
- māyādevā avataran HG adevā devavattaram ApMB Several HG mss. read avattaram, pointing to probable corruption in its text
- ava tara (TS avattaram) nadīşv ā VS TS MS KS ŠB : avattaro nadīnām AV. See §832
- ışto yajño bhrgubhır drannodā yatıbhır (MS once yattibhır) āšīrdā... MS.† KS† ApІ The isolated yattıbhır can only be a mistake

- privo (VS MS prdvo) nyañkuh kakkatas (MS kakuthas, TS kasas) ... VS TS MS
- dandra (TS °dran) nīlalohita VS TS. MS KS. ŚB Epithet of Rudra; the TS form apparently felt as a participle Keith, 'waster'.
- apā vṛdhi parivṛtam (TB Conc °vṛtim, comm °vṛtim; Poona ed text and comm °vṛtim) na rādhah RV. TB
- ātmāsy ātmann ātmānam (GB Cone ātmanātmānam) me mā hinsīh GB Vait. Kaus Gaastra reads correctly like the others for GB.
- rajam (AV Berlin ed rajjum, by emend) granther dānam (AŚ dhānām) AV AŚ. Vait The emendation is probably right, at least in giving the true original reading of the passage; but there is no variant Caland in his translation of Vait quotes it as reading rājam, perhaps by a slip
- jīvebhyas tvā samude vāyur ındrah AV 8 1 15a Conc. says read sammude, but Whitney would keep the text, analyzing with p p sam-ude 'conversation' The comm however connects the word with root mud If this were right the variant could be classed with §306 Uncertain
- svarvido abhi gā adrim uşnan (SV ışnan) RV. SV. Conc. suggests muşnan in RV, see however Oldenberg, Noten, ad loc
- §402. Next we come to cases in which the vowel preceding the single or double consonant is long in both cases. Particularly interesting, as suggesting the Prakritic influence to which we alluded above, are cases where a secondary or corrupt reading appears with a single consonant after a long vowel, the proper form having double consonant. This seems to point towards a tendency to simplify double consonants in that position. Thus:
- sarvasmād devakilbisāt (VS °visāt, LS eva kilb°) RV VS MS. LS ApS The LS obviously has a secondary lect fac, altho it makes good sense
- ayā (MS ayāh, KS ayās) san (KS ms ayāsā) manasā hitah (MS. kṛttah, p p kṛtah, KS kṛtah) MS KS TB ApŚ ApMB HG: ayāsā manasā (AŚ vayasā) kṛtah AŚ ŚŚ Kauś: ayasā manasā dhṛtah ApŚ ApMB Cf §401
- jīvām tiebhyah parinīyamānām AV mṛtāya jīvām parinīyamānām TA Read mṛtebhyah in AV with some mss and SPP.
- sarvam nı şvāpayā janam RVKh AV Edgerton, AJP 35 439, has suggested şvāpayāj janam as the true reading
- §403. There are several variations concerning the synonymous adverbs $pa\$c\bar{a}$ and $pa\$c\bar{a}t$, before following d. In the first, at least, the

form with double d is the older, so that the same tendency is involved: apaścāddaghvane (SV. apaścāda^o) nare (SV. naraḥ) RV. SV. TB. ApŚ. apaścāddaghvānnam (AV. apaścādaghvānnasya) bhūyāsam AV. MS ApŚ. MŚ.

paścādoṣāya glārinam VS.: paścāddosāya glāram TB.

§404. There is some confusion between pratita (and part^o), pple, of root $d\bar{u}$ in composition, and pratita (part^o), similar form from root i in composition (and, once, an anomalous apratitam). In the first two cases the form with double t is the proper or original one, and the other may be a phonetic (Prakritic) simplification. In the other two the true reading has single t, and the double t is textually very dubious:

yai kusidam apratītam (TS. "titlam, and so TA. Poona ed., with v. l "tītam. SMB. apradattam) maycha (TS. mayı) TS MS. TA. MŚ. SMB.: aparnityam apratītlam yad asmi AV: yāny apāmityāny apratītlāny (TB. Poona ed "tītāny) asmı TB ApŚ. It seems that the original form must be apratītlam, from pratī-dā (cf. SMB); but possibly the pple. of pratī-1 may be defended. So the comm. on TA. reads (apratītam), glossing na pratyarpītam.

sycne paritto (VSK. parito) acarac ca prâte VS. VSK SB: sycne câta ula yo'carat parittah AV. Here the true form is certainly from pari-dâ.

apah siṣāsan srar (TB. ApŚ. surar) apratītaḥ (TB Conc °tītlaḥ, Poona ed text and comm °tītaḥ) RV. AV. KS TB. ApŚ Here the double t has no standing.

stuhi śūrari rajrinam apratīkam (TB. Conc. apratītam, Poona ed ^otītam) MS TB. The only correct reading is apratītam 'invincible'. On MS, see §138

§405. In the few remaining cases the doubling is secondary or corrupt: cirā (AV. taira) yamaḥ sādanā (TA. °nāt) te minotu (AV. kṛṇotu) RV. AV., TA. A clear error in TA.: see note of Whitney-Lanman on AV.

ugrani prišyā (MS. ugrani pašyāc) ca rāṣṭrabhṛc ca tām MS TA. Names of Apsarases The MS. has a corruption, probably due to mechanical form-assimulation to the final of rāṣṭrabhṛt, see §\$20.

nama āl hidate ca prakhidate ca VS. MS. KS: nama ākl hi^o ca prakkhi^o ca TS. See \$401.

spāna bhrājā°...VS. TS. ŠB KŠ. ApŠ: srāna bhrāj...TA.: srān nabhrād...KS.: surān nabhrād MS. MŠ Keith on TS. suggests srāna nabhrāj- as the original form.

2. Assimilation of two consonants to one double consonant

- §406. The variants seem to show clear traces of the common Middle Indic tendency to assimilate two adjoining consonants. Especially a semi-vowel or liquid is assimilated to a different consonant, and an adjoining different consonant is assimilated to a nasal. With these cases we shall group a few instances of the converse, in which the double consonant appears to be older than the two different consonants. Here we have then a sort of dissimilation, which indirectly points perhaps to a feeling of phonetic correspondence between two like consonants and a group consisting of one of them and (especially) a semi-vowel or liquid.
- §407. We begin with cases concerning r, the weakest of all the consonants (Geiger, $P\bar{a}li$ §51; Jacobi, Ausgewählte Erzählungen in Mähäräsfr \bar{a} xxxi).
- usrāv (VSK KS usrā) etam . . . anaśrū (KS anaśśū, v l. °śrū) . . . brahmacodanau VS VSK TS KS. ŚB. MŚ See Keith on TS 1. 2. 8. 2; he points out that anaśśū, as well as anaśrū and anaśśrū, is capable of a kind of interpretation. Yet it is probably secondary, if not corrupt
- manyor mṛdhrasya (HG. mṛddhasya) nāśinī ApMB. HG.: manyoh krodhasya nāśanī PG Kirste suggests reading ṛddhasya, saying that manyoh seems superfluous. But the parallels show that manyoh is original and that HG has a phonetic assimilation in mṛdo.
- krīdī ca šākī cojjeşī (ApŚ sākī †corjişī ca) VS VSK ApŚ. Here the dissimilated form is secondary, it is no doubt vaguely felt as meaning 'food-seeking' ($\bar{u}rj + \text{root }\imath s$).
- āvat tam (TA read āvar tam, §873) ındrah sacyā dhamantam RV. AV. SV. KS TA
- §408. The next-weakest consonant, that is most apt to be assimilated to another consonant, in Pāli-Prakrit is y We have a number of cases concerning it, to them should be added a few cases of final ny varying with nn before an initial vowel, which really concern morphology but which we have placed with similar phenomena under Sandhi, §928
- abhinne khilye (TB khille) nidadhāti devayum RV. AV. TB. Comm. on TB. khilābhūte, the clearest possible case of purely phonetic assimilation
- duşvapnahan duruşyaha TA. Bibl. Ind : duşsvapnahan duruşşaha TA. Poona ed, text and comm : duhsvapnahan duruşvahā MahānU. See §255.
- aśvān anaśśato (KS †Ap\$ anaśyato, MS. van Gelder, anaśvato) dānam KS TA. Ap\$. M\$. See §255

- ud u tye (MS MS ud-ut te) madhumattamāh RV AV SV MS PB GB AS SS Vait MS The secondary MS MS reading involves substitution of te for the older tye
- yad annenātirohati RV ArS VS TA·yad anyenābhavat saha AV Here the form with ny is secondary, but interesting as pointing to the light pronunciation of y On the nonsensical reading of AV (the comm has annena) see Edgerton, Studies in Honor of Maurice Bloomfield 127
- pītā bhāsvaty anūpamā TA pītābhā syāt tanūpamā MahānU See §838 The assimilation is secondary
- capyam (TB. Poona ed cappam) na pāyur VS MS KS TB capya seems well established, tho etymologically obscure, cappam may be a graphic blunder.
- sūryācandramasau vṛkyābhyām (KSA vṛkkā°) TS KSA The TS form is a secondary and (as shown by Av vərəōka) unhistorical form, dissimilatory in character, quite analogous to the preceding. It has caused quite unnecessary trouble for etymologists (cf. Uhlenbeck's plaintive query s v vṛkka)
 - §409. A single case concerns l
- gavo gulgulugandhayah (Vart guggulu°) Vart KS ApS MS The usual Sanskrit form is guggulu, but gulgulu occurs so persistently in Vedic texts that one is constrained to accept it as the original form
- §410. As to v, it was already found involved in two cases mentioned in §408 Besides, we find.
- tan nas trāyatām tanvah sarvato (Ap\$ tan no msvato) mahat KS Ap\$ tan me tanvam trāyatām sarvato brhat AV An obvious secondary assimilation in Ap\$, assisted of course by the preceding tan nas
- yathāyatham nau tanvau (AS tanvā, MS tan nau) jātavedah KS AS MS The MS is obviously corrupt, no v l quoted
- mıtrāvarunā saradāhnām (MS °hnā) cıkıtnū (MS cıkıttam, KS yıgatnū, AS cıkıtvam) TS MS KS AS See §45
- vrśvavrdam (AV °do) vācam arrŝvamrnvām (AV arrŝvavrnnām) RV AV See §236
- apa durhārddiśo jahi Kauś Read °dviśo, the corruption may be graphic (§869)
- §411. Of cases concerning the assimilation of non-nasal consonants to adjoining nasals, there occur the following, besides one or two mentioned in the preceding sections as concerning semi-vowels
- aganma yaira pratırania (MG prataram na, mss °ran na) äyuh RV AV MG

- dawyā (AV dawā) hotāro (TS. °rā, AV. °rah) vanuşanta (TS vani°, KS † vanişan na, AV. sanışan na) pūrve (AV. KS. etat) RV. AV TS. KS
- akşatam arışlam ılāndam SMB: akşatam asy arışlam ılānnam gopāyanam SG Epithets of the cow; cf the cow-name ılāndā, MS. 4 2 1: 22 7, 10, and 4 2. 7: 28 12 Altho SMB comm. says ılāndam ılānnam kṣīrādılakṣanam, it is probable that both this explanation and SG's form are due to secondary etymologizing
- yad ejati jagati yac ca ceşlati nāmno (Mahān U. nānyo) bhāgo yan (TAĀ. Poona ed 'yam) nāmne (Mahān U. yatnān me, v l yan nāmne) svāhā TAĀ Mahān U. Here probably Mahān U. is secondary if not corrupt, and the (partially) assimilated form with two nasals is original.
- ukṣantūdnā maruto ghrtena AV 3. 12 4 So Conc, with Whitney's Transl, the comm, and SPP. But according to Whitney no ms reads so, except one of SPP's śrotriyas; most of them have °ūnnā, a few °ūtnā Ppp (Barret, JAOS 32 366) has °ūnā See §183.
- [svāhākriasya sam u tṛpnuta ṛbhavah (TB. Conc tṛnnutarbh°; ApŚ and TB Poona ed tṛpnutarbh°) RV. TB. ApŚ tṛnnu° probably mis-print]
- §412. When a final mute is followed by an initial nasal, the rules of external sandhi require nasalization of the mute. Lack of assimilation is here the exception, not the rule. But it occurs in a couple of cases: sahasrāpsāh prtanāṣān (SV °ṣād) na yajñah RV. SV.
- anustum (MS "tub) mitrasya (GB. Vait add patnī) MS. KS. GB Vait It is perhaps not accidental that both the sounds here concerned are of very rare occurrence as finals.
- §413. In a case or two m at the end of a reduplicating syllable, or absolutely final, is alternatively assimilated to a following n, or remains anusvara. This may be merely a matter of writing:
- devya (ApŚ dwyā) āpo nannamyadhvam (KŚ namnam°).. PB KŚ
- vājasya hi prasave (TS. °vo) nannamīti (TS. namna°) TS. MS KS ā yam (MS MŚ āyan) narah sudānavo dadāšuşe RV. TS MS KS AŚ MŚ Lect fac in MS MŚ (verb form, 'they have come').
- §414. Conversely, before initial m, final n varies with anusvāra. But two cases are purely morphological, concerning the masc. and neuter (adverbial) forms tam and tad (tan); and the third is regarded by Whitney and the Conc as a mere corruption:
- tam (MS tan) mā devā avantu śobhāyar (MS °y1) TS MS. TA

tan (JB tam) mā punsı kartary erayadhvam JB KBU trīta etan manuşyeşu māmīje TB: trīta enam manuşyeşu mamīje AV.

Conc and Whitney's note say, read enan with SPP. At any rate a neuter and not a masculine form is intended

§415. Finally we come to assimilation of other consonants to adjoining mutes. In every case a preceding mute may be regarded as assimilated to a following mute (precisely as in Prakrit), with one excepteption which is extraordinary and may be corrupt, in it a following nasal (I) seems to be assimilated to a preceding mute:

sisum nadīnām harim adribudhnam (TS "buddham) VS TS MS. KS

SB Keith assumes adribudhnam in his translation

§416. The other cases present the order of sounds which would be expected as a basis for assimilation. Nevertheless in several of them the dissimilated form is historically secondary. All happen to belong also in §139, where they are discussed individually, there is, then, no need to repeat them here

§416a. To complete the subject of assimilation and dissimilation, as it appears among the variants, a general remark may be added on the not very numerous traces of assimilation and dissimilation of vowels, details of which will be found in later parts of this book. We shall find some signs of a tendency towards u coloring in vowels associated with labial consonants. This appears in the variation of av with uv, §§601-4, and in that of r with vu, §§678-80. We have also noted, among the variants of u with a and i, what appear to be sporadic cases of assimilation to, or dissimilation from, similar vowels in adjoining syllables. These will be found in §§605, 607, 609, 622-4

3. Simplification of Consonaut Groups

§417. Under this heading there are first one or two special cases to be distinguished. On the insertion of t and k after final n and \bar{n} before a sibilant, see §§938 f. On the optional dropping of a mute etymologically required between a nasal and another consonant, see Whitney, Grammar §231; Wackernagel I §233a. The dropping of the mute is required by APr 2 20. The VPr 6 30 requires it before a voiced mute, the variants show also a case where the dropping occurs before a voiceless mute in writing, but as this case involves dropping of t before another t, it may be considered merely a matter of writing a double consonant as single after a nasal (§389). The other Prātisākhyas ignore it. All texts seem to show it sporadically. But editorial as well as scribal vagaries have helped to make the record of little value. Note Weber's disregard of the

TS mss in the first two variants, which is typical; other less conscientious editors have doubtless been equally arbitrary, without troubling to record the actual readings of their mss

\$418. We quote the following variants for what they are worth, which in our opinion is not much, for the reasons just stated:

brhaspate tyamyam (KS ms. 'ya emend. 'yam) yungdhi (AS. yundhi) vācam TS MS. KS AS. But practically all mss. of TS yundhi.

varwrādhi (TS MS SB °vrāgdhi) harasā... VS. TS. MS. KS. SB. But here too all mss of TS. vrādh; and so pp of MS.

āditvam garbham vayasā sam angdhi (VS andhi, TS, KS, anjan) VS TS MS KS SB.

athāmṛtena jaritāram andhi (ApŚ. angdhi) TB ApŚ. But TB, Poona ed angdhi, text and comm

sucir ankte (SV. ante) sucibhir gobhir agnih RV. SV.

vah pauruseyena kravışā samankte (AV. samante) RV. AV. Kaus

udno (VS MS apo) dattodadhim bhintta (VS. MS bhinta) VS TS. MS.: udno dehu udadhim tbhindhi KS

śunddhı (PG MG and v 1 of ADMB. śundhī) śiro māsyāyuh pra mosīh AG. PG ApMB MG

ayam sa śińkte (AV. śińte) yena gaur abhīvṛtā i.V. AV. JB N.

sampasyan pañktīr (AV. pañtım) upatışthamānah RV. AV.

achā vīram naryam panktırādhasam (SV. panti) RV. SV. VS. MS. SB TA.

[pāāktrah (KSA em †pāāktah) kašo mānthīlavas (KSA. †man°) te pntynām (KSA †pitrnām) TS KSA. The mss of both texts all read pāmtra, intending pāātra; TS comm pāmtra-kašān, as a dvandva l

§419. There remains a miscellaneous group of cases in which a consonant is alternatively present or absent in a group of consonants. numbering three (or two at the beginning of the word) when the evanescent consonant is present. We do not include here cases in which the variant consonant is a nasal, a semi-vowel, a liquid, or a sibilant, since these have been treated in Chapter IX (Such cases are common when the evanescent consonant is y or v, see §§314-5, 321-2, 332-7, 357, 367, 370.) The only prominent group which stands out among them concerns derivatives of the roots su and stu The ritualistic use of these words is such that the interchange is easy; there are many situations in which suta and stuta, soma and stoma will do about equally well: gırah somah (SV. gira stomān) pavamāno manīsāh RV. SV. Here there

is a change in syntax, but cf the next, where there is none.

- ghṛtāhutah somapṛṣṭhah (MS stoma°) suvīrah AV MS stomapṛṣṭho ghṛtavān supratīkah KS TB † 3 7 2 7b, AS ApS The originality of AV is supported by the RV. epithet somapṛṣṭha (fashioned on the model of ghṛtapṛṣṭha)
- apsu dhautasya te deva soma njihih (TS tr. soma deva ts) sutasya (KS stu°, MS ştu°) TS MS KS PB : apsu dhūtasya deva soma te maturdo njihi ştutastotrasya (AS njihih sutasya) AS SS
- nārāšansena stomena (RV somena) RV VS TS MS KS AB SB LŚ. Kauś See Oldenberg, ZDMG 54 54 and 56, Hillebrandt, Lieder des RV 124 Grassmann would emend RV to stomena, but this is undoubtedly a later lectio facilior
- [sutā (mss stutā) mayā varadā vandamānā (mss vedamātā) AV: stuto mayā varadā vedamātā TAA Whitney's Translation abandons the unfortunate emendations of the AV edition. Weber, ISt 2. 144, discusses the TAA passage, he would understand stuto as stutā-u]
 - §420. The rest need no subdivision.
- parijmā cit kramate (AS SS cid ramate) asya dharmani AV AS SS 'Even a wanderer walks (rejoices) in his (Savitar's) ordinance' Whitney's note implies that he regards ramate as a preferable reading, to us it seems merely a lect fac
- tam tvam višvebhyo devebhyah kratūn (KS °bhya rtūn) kalpaya KS ApŠ Apparently KS has the true reading, cf Caland on ApŠ 10 25 1, kratūn is suggested by the following phrase, daksināh kalpaya
- ahorātrābhyām puruşah samena (GB.* kṣanena) GB. (both) SB.
- yena śrzyam akrnutām PG yena strzyam akrnutam (ŚŚ strzyāv akurutam) ŚŚ SMB GG śrzyam is clearly a secondary simplification with phonetic aspects
- brhann ası brhadravā (TS KS brhadgrāvā, MS brhadrāyāh, MS brhadrāyah) VS. TS MS KS SB MS The form containing g seems to be the older
- śumbhānas (KS stam^o) tanvam (TB tanuvam, SV †tanvām) svām RV SV MS KS TB 'Adorning (establishing) his own person'
- anyavratasya (TA anyadvra) sascima (TA omah, Poona ed oma, RV sascire) RV VS MS SB TA Tho the comm on TA takes anyadvratasya as two words, accent and sense agree in showing that it was felt as one, anyad is the 'stem' form
- māteva putram bibhrtā sv (VS SB bibhrtāpsv) enat (TS KS enam) VS TS MS KS SB The verse is addressed to the waters, which accounts for the secondary change of VS SB

- namah śuskyāya (MS śusyāya) ca harityāya ca VS TS MS KS. Von Schroeder thinks MS is probably to be emended to śuskyāya, but it may be the true reading (a phonetic simplification)
- bhayam sīlimabhyām (KSA ° madbhyām) TS KSA Stems in -man -mant; obscure names for some part of the horse's body
- §421. In some cases an initial consonant, or even two initial consonants are dropped altogether (or added).
- kṛtān nah pāhy anhasah (TA enasah) MS TA: ṛtān mā muñcatānhasah TB The latter is poor, comm rlāt prāptāt tasmād anhasah
- riasya dhāmno amriasya yoneh TS. riasya yonem mahişasya dhārām VS KS SB. ghriasya dhārām mahişasya yonem MS: ef ghriasya dhārām amriasya panthām TS KS ApS. Ritualistic rigmarole The MS pāda may be a blend of the other two, both of which are found in KS
- śraro (RV. VS avo) devasya sānası (TS TA °sim) RV. VS. TS. MS. KS TA
- stavāno (VS TS KS ŠB avā no) devyā kṛpā (VS ŚB dhiyā) RV VS TS MS KS ŚB avā no is a facile and slipshod substitution.
- āyobhavyāya (AG māyo°) catuşpadī AG ŠG: catvārī māyobhavāya TB ApŠ ApMB SMB PG HG. The SG is obviously secondary and poor, it must be understood as a quasi-derivative from āyu(s).
- yāsām agnīr iştyā (KSA nīstyā) nāmānī veda RV TS KSA The KSA reading is an attempt to 'correct' an obscure passage 'Whose names Agni knows by the sacrifice'. 'whose foreign (external) names Agni knows'
- erum tundānā patyeva jāyā AV.: perum tuñjānā patyeva jāyā TS. The original form of eru peru is unknown, it probably means the male organ.
- purudasmo vişurüpa (KS. purudasmavad viśvarüpam) ınduh VS KS SB.· urudrapso viśvarūpa ınduh TS. ApS Synonyms
- madhvā (VS adhvā) rajānsīndrīyam VS MS KS TB. Comm. on VS madhvā, the only possible reading Is adhvā a misprint?
- [lvayā jvasena sam ašīmahı tvā SG.: tvayāvasena etc TS KS TB AS MS Kaus SMB PG jvasena is a misprint, corrected SBE 29 98, note]

CHAPTER XI. VARIATIONS BETWEEN SHORT AND LONG A

§422. The outstanding feature of these variants is the light they throw on the matter of rhythmic lengthening, and, to a less extent, rhythmic shortening. They are supported in these respects to a much smaller degree by the variations between short and long i and u, recorded in the next chapter.—In §§300-2 we have referred to variations between \bar{a} and short a plus nasal, they will not be repeated here. See likewise §§395-8 for the same variation before single and double consonants

§423. Particularly important are the cases in which the variant vowel is final, either absolutely, or in the seam of a compound, or before a suffix that is treated as if it were a part of a compound. It is in these that we detect most clearly the lengthening of a short vowel due to sentence rhythm. We shall present them first, following them with variations between initial and medial long and short a, in stem formations of nouns and verbs (where we still seem to find traces of rhythmic lengthening), and in inflexional elements (where it seems to be virtually non-existent). Finally there will be presented a group of purely lexical and miscellaneous variants of non-final a and \bar{a}

§424. In all these classes there are instances of shortening as well as lengthening; that is, cases in which \bar{a} , not short a, is historically the more original, not to speak of different formative elements where both forms may be justified. Shortenings of \bar{a} before more than one consonant seem occasionally to suggest the Prakritic tendency to shorten long vowels in closed syllables (cf. §§393 ff.). But other considerations usually enter in, so that the extent of this purely phonetic shortening is problematic.

§425. The relation of rhythmic lengthening to meter is well stated by Wackernagel I §26ba. The poets make free use of the license to lengthen a final short a in syllables where the meter requires a long But fundamentally it is a matter not of metrical requirements but of sentence rhythm. Among lengthenings of final short a which can with certainty be regarded as rhythmic, the majority do not occur in syllables required to be long by meter. As stated by Wackernagel, the rhythmic lengthening is prehistoric and occurred originally when the syllable would otherwise be short (that is, when a single consonant followed the vowel), and when the neighboring syllables were short,

especially the following one. Analogical extension has obscured without obliterating the original conditions.

1. Final a and \bar{a}

§426. Under this head are included a and \bar{a} not only as absolute finals in a word, but also as stem-finals in parts of compounds, or before such suffixes as vant (treated as compounds in respect of sandhi), or even in the reduplicating syllable, which as regards sandhi behaves in the same way, the it may be regarded as closing the gap between final and medial conditions. But to avoid possible vitation of results thru this grouping, we shall separate the absolutely from the relatively final cases

§427. To show the precise extent of genuine rhythmic lengthening, some further distinctions will be necessary. In some of the words concerned, the regular final is \bar{a} , not short a, either in all periods of the language, or at least in the earliest. In others, both a and \bar{a} can be more or less justified morphologically or lexically, or the lengthening may have been assisted by some formal analogy. Take as an instance the gerund ending ya or yā Altho ya prevails entirely in the later language, yā is much the commoner in RV., and is probably the older form (a stereotyped instrumental case-form; whether ya is to be regarded as an originally distinct ending, not identical with $y\bar{a}$, need not here be discussed; cf. Wackernagel III p 34 f. and references in small Or again, the instrumental singular ending of a-stems print there) (ena) often ends in \bar{a} ; it is at least possible that other instrumental forms in \tilde{a} may be concerned in this (as suggested by Wackernagel I p. 312 infra; rather different is the implication of III p 92). Obviously such forms must be separated from cases of purely rhythmic lengthening We shall therefore begin with-

(a) Absolutely final a, originally short, varying with rhythmically lengthened \bar{a}

§428. Here we include thirty-eight variants in which the lengthening is certainly secondary and seems due to the sole and exclusive operation of the law of sentence rhythm, at least there is no apparent morphological or analogical justification for it. The principle is ably discussed by Wackernagel I §§264–6. The pada-pāṭhas regard the lengthening as one of sentence rhythm, for they regularly substitute short α . Their opinion is confirmed by the fact that the lengthening practically never occurs at the end of a pāda or sentence, nor, in TS, at the end of a

handthā (Wackernagel 1 §265a, note); of VV I p 174. Originally it depended on the quantity of the surrounding syllables—The typical case was that in which final a followed by a single consonant (so that the syllable was light) was both preceded and followed by light syllables. This succession of three light syllables was avoided by lengthening the a.

\$429. Most of the cases are verb forms ending in a: thirteen of the 2d sing impv. -a, eight of 2d plur. -ta and -tha, two of 2d sing. middle -sva, four of 1st plur. -ma, and one each of 1st sing perfect -a, 2d sing perfect -tha, and 2d plur. perfect -a. There are seven other cases two of sma and pra, and one each of ca, uta, adva, and sapta. On $pr\bar{s}$, probably not to be connected with IE * $pr\bar{s}$, see \$\$439, 449, 465.

§430. No school tendencies are revealed by the variants. Late and popular texts replace an older or hieratic a by \bar{a} , and vice versa, with perfect indifference. But some general considerations suggest themselves:

§431. First: the variant word never occurs at the end of a pida or sentence, except in one or two peculiar cases (Note that in AV. 19-39, 10d surā is a misprint for sura, see Whitney's note, the pāda is repeated without variant from AV. 5-22, 3d) One exception has been explained in VV I p 174: vanaspate 'ra srjā (KS. srja) AV. VS TS. MS KS. For another see nuhāram etc. §446

§432. Secondly: only once does the lengthened syllable occur before an initial vowel, leaving hiatus:

indra somain pibā imam RV. AV. SV. MS: indra somani imam piba RV. ŠŠ Here indeed one might be tempted to understand pibās in the first form; but p p. of RV. MS both piba. Cf. Oldenberg, Noten on S 17. 1.

§483. Thirdly: Otherwise the word following the $a\bar{a}$ always begins with a single consonant, except in two cases, in both of which the \bar{a} is secondary (AV.; short a RV.) and seems due to special reasons. In both cases, as its happens, the following word is pra. We are not inclined to see any significance in the conjunction mute plus liquid (as if this group failed to make the preceding syllable heavy); possibly more important is the fact that p is a labial consonant (cf. §464):

ut tişihata (AV. Kauś. $^{\circ}$ tā) pra turatā sakhāyaḥ RV. AV. VS. ŚB. TA. Kauś The \bar{a} may be attracted to match the ending of taratā, where \bar{a} is in every way regular and demanded by the meter.

thota (AV. °tā) pra ca tisthata RV. AV. VS TA This pāda of AV. (18 2 2b) is RV. 10 14. 14b; the preceding one is RV. 10. 14. 15a (these two RV. verses are jumbled in AV., see Whitney-Lanman).

yamāya madhumattamam But further, RV. 7. 102 3b has juhotā madhumattamam, the first word is the first word of AV. 18 2. 2b, and the second is the last word of the preceding pāda. Apparently the secondary \bar{a} of AV juhotā is a reminiscence of juhotā RV. 7 102 3b, where the \bar{a} is regular, in that RV. passage it was immediately followed by madhumattamam, in AV. it is immediately preceded by that word.

§434. With these, the only two real exceptions, are to be compared two others in which two following consonants are or seem to be concerned:

ekayā ca dašabhiš ca svabhūte (AV cā suhūte) AV. VS MS SB TA. AS. SS Both are regular, in AV cā plus one consonant, in the others ca plus two.

agne purisyādhipā bhava (TS bhavā) tvam nah VS TS MS. KS. SB. Intended for a tristubh pāda Perhaps tvam is surplusage, whether it is or not, a long syllable is required by the meter before it, and tvam (if kept at all) must be read tuam But since vocalic y and v do not count as consonants for the purposes of the law of rhythmic lengthening (Wackernagel I §265a, note), the \bar{a} is not followed by two consonants and the lengthening is demanded. It is the other texts, with bhava, that are irregular.

§435. Fourthly, as to the quantity of the surrounding syllables, the variants do not support quite so strikingly the principle stated above, that they should both be short. We may remember that, in fact, one form of the variant always keeps short a. In about half the variants the preceding syllable is long. The following syllable conforms better; it is short in about three fourths of the cases. In eight cases both the adjoining syllables are long. In five of these, the older form of the variant has short a, but in the other three \bar{a} is older. It is, however, probably not accidental that in six of the eight cases the following syllable is an enclitic pronoun, that is a 'light word', lacking in accentual prominence, even the metrically long. It is also worth noting that in half the cases the variant vowel is in the second syllable of the pāda; this is a favorite position for rhythmic lengthening, as we shall presently see

§436. The eight cases where long syllables both precede and follow are:

hınva (Vait °vā) me gātrā (KŚ. gātrāni) harivah TS Vait KŚ. ApŚ. MŚ Lengthening only in the late and pseudo-hieratic Vait pary ū şu pra dhanva (AV. °vā) vājasātaye RV. AV. SV. KS AB ŚB. Lengthening secondary

abhı vānīr rşīnām sapta (SV °tā) nūşata RV. SV.

vidma (Kauś text °mä; read °ma with AV.?) te svapna janitram AV. Kauś (pratika only).

adha sma (MS smā) te vrajanam kṛṣnam astı (MS. astu, KS. °nam astu kṛṣnam) RV. SV. VS TS MS. KS. ŚB Lengthening secondary. vidmā te nāma (AV vidma te dhāma) paramam guhā yat RV. AV. VS TS

MS KS SB ADMB.

astı hı şmā (TS MS. KS astu sma) te kuşmının avayāh RV. VS. TS. MS. KS. ŚB.

adyā (SV GG Svidh. adya) no deva santah RV. SV AB KB AA TA. MahānU AS, SS ApS AG SG. GG. Svidh.

§437. The only other cases of a following long syllable, not final in its pada, are:

vahā (TB. N vaha) devatrā didhişo (MS. dadh°) havīnsi MS KS TB N. upa (MS utā) no mitrāvarunāv ihāvatam (MS °ņā ihāgatam) MS. TB. TA

undrasya nu vīryāni pra vocam (AV nu pra [read prā, §449] vocam vīr°) RV. AV. MS ArS AB KB TB. AA N. Note that ā is clearly secondary and is followed by a labial consonant (§464).

§438. In quoting the full list of these variants we shall classify them according to the position which the variant syllable occupies in the verse All but one of the thirty-eight variants are metrical; and that one is cadenced prose and imitates a tristubh pada. In two cases the order of words is so changed that the variant syllable occurs in different positions Of the rest, the variation occurs most often in the 2d, 3d, and 4th syllables of the pada, viz, six, four, and six times respectively It occurs three times in the fifth syllable of tristubh-jagatī pādas before the cesura, and once as the initial syllable, so that it occurs twenty times in the first part of the verse, and fifteen in the last But of these sixteen, eleven concern the eighth syllable and two the tenth, one case each concerns the seventh and muth syllables of jagati padas, and the sixth of an anustubh This summary indicates that, except where metrical requirements have caused the lengthening, the occurrences tend to be pretty closely restricted to the first part of the verse, and specifically to the second, third, and fourth syllables (and the fifth when that precedes the cesura) In the last part they occur as a rule only when the meter requires a long syllable

§439. In the first syllable of a padar

pra (KS prā) na āyur jīvase soma tārīh RV KS AB GB Vait MS It is unlikely that a rather late text like KS has preserved a historic representative of IE *prō. Cf. pra (prā) smā mināty (minoty) ajarah, §512, which probably belongs here, and §449.

§440. In the second syllable:

hınva (Vait. °vā) me gātrā (KŚ. gātrānı) harvah TS. Vait KŚ. ApŚ. MŚ. vahā (TB N. vaha) devatrā didhişo (MS dadh') havīnşi MS. KS. TB N. vidmā te nāma (AV. vidma te dhāma) paramam guhā yat RV. AV VS TS. MS KS. ŚB. ApMB

vidma (Kauś °mā) te svapna janitram AV Kauś.

adyā (SV. GG Svidh adya) no deva santah RV. SV. AB KB. TB AA. TA MahānU AS SS. ApS AG. SG GG. Svidh

upa (MS. utā) no mitrāvarunāv ihāvalam (MS °nā ihāgalam) MS. TB. TA. §441. In the third syllable:

juhota (AV °tā) pra ca tīsthata RV. AV VS TA

pretā (TS upa preta) jayatā narah RV. SV. AV. VS TS Read pra-itā in RV. etc TS seems to have tried to improve the meter, but only makes it worse

janışvā (MS °şva, RV. KS. °şla) hı jenyo agre ahnām RV. TS MS. KS. ApS.

adha sma (MS smā) te vrajanam krsnam astı (MS. astu, KS. °nam astu krsnam) RV. SV VS TS MS KS SB.

§442. In the fourth syllable:

varıvasya mahāmaha (SV. °syā mahonām) RV. SV.

iam ā prna (TB. prnā) vasupate vasūnām RV TB

ut tışthata (AV Kauś °tā) pra taratā sakhāyah RV. AV VS SB. TA. Kauś See §433

ā juhotā (TB. ApŠ °ta) duvasyata RV SB TB ApS (pratīka)

ramayata (KS °tā) marutah syenam āyınam (MS. marutah pretam vājınam) TS KS ApS MS Three mss of KS. ramayata

aslı hı şmā (TS MS KS aslu sma) te suşmının avayāh RV. VS. TS. MS. KS SB

§443. In the fifth syllable, before the cesura:

udīrayathā (MS MŚ. °tā, AV. KS °ta) marutah samudratah RV. AV TS. MS KS. AŚ.

yatrā naś cakrā (Cone cakra for KS with one ms, but ed cakrā with others) jarasam tanūnām RV VS MS. KS. GB ŠB ApŠ ApMB. HG.

prānco agāma (TA prānjo 'gāmā) nrlaye hasāya RV. AV. TA.

§444. In the sixth syllable of anustubh:

ındra somam pibā ımam RV. AV. SV. MS.. ındra somam ımam piba RV. SS See §432.

- §445. In the seventh syllable of lagati
- pary ū şu pra dhanva (AV dhanvā) vājasātaye RV AV SV KS AB ŠB The third syllable after the cesura in tristubh-jagatī meter tends to be long
 - §446. In the eighth syllable of tristubh-jagatī
- apo devīr upa sīja (MS sījā) madhumatīh VS TS MS KS SB
- brhaspate parı d $\bar{i}y\bar{a}$ (TS d $\bar{i}ya$) rathena RV AV SV VS TS MS KS No real varıant, sınce d $\bar{i}ya$ ends a kandık \bar{a} in TS , see §428 and VV I p 174
- agne purīşyādhipā bhava (TS bhavā) tvam nah VS TS MS KS ŠB An irregular verse, which psychologically belongs here unless tvam be deleted, see §434
- vanaspate 'va srjā (KS srja) AV VS TS MS KS Also belongs here properly, see §431 and VV I p $\,174$
- dyumantam śuşmam ā bharā (SV bhara) svarvdam RV SV
- adılsan vā (MS dhıpsyam vā, TB yad vādāsyan) samjagara (TB °jagārā, MS °cakara) zanebhyah MS TB TA
- vayam rāṣṭre jāgryāma (MS†KS†°mā, MS pp and TS jāgryāma) purohitāh VS VSK TS MS KS
- yasmād yoner udārīthā (KS °tha) yaje (MS KS yajā) tam RV. VS TS MS KS ŚB
- sapta yonīr (KS yonīnr) ā pṛnasva (TS KS TB °svā) ghṛtena VS TS MS KS SB TB
- ekayā ca dašabhīs ca svabhūte (AV cā suhūte) AV VS MS ŠB TA AŠ SS
- bhagemām dhıyam ud avā (TB \dagger ApMB \dagger ava) dadan nah RV AV. VS TB ApMB
- nhāram in ni me hara (TS †harā) TS KS The TS form is quoted as a case of lengthened final a in TPr 3 12, the actual quotation there includes the following word nihāram, which is the initial of the next pāda. There is no doubt of the pāda-division; the pāda is anuṣṭubh, not triṣṭubh. But the lengthening of a final in its pāda is so utterly anomalous that one of two things must be assumed. Either the lengthening was due to a careless assumption that the pāda was triṣṭubh (including the following nihāram), or (and this we believe is the correct explanation), the real reading intended in the samhitā-pātha is not hara but harās, subj. and not imperative. This was wrongly analyzed by the pp as hara, and hence arose the TPr rule on the subject. This variant should then be added to VV I §152. We do not count it in our figures for this section.

- §447. In the ninth syllable of jagati-
- abhı vānīr rsīnām sapta (SV °tā) nūşata RV. SV.
 - §448. In the tenth syllable of tristubh:
- vīrebhir asvair maghavā bhavā (TS °va) nah RV. VS. TS. MS. KS No true variant, since bhava ends a kandikā in TS; cf §428 and VV I p. 174.
- gharmam pāta vasavo yajata (TA °tā, MS °trā) vāṭ (MS veṭ, TA vaṭ)
 VS MS ŚB TA Cadenced prose, imitating trisṭubh meter;
 hence lengthening secondarily in TA Note that TA is the only
 text that has a short vowel in the following syllable
 - §449. Different syllables, with change of meter:
- ıdam me prāvatā vacah RV VS TS KS TB: oṣadhayah prāvata vācam me MS: asyā avata vīryam Kauś Where the lengthening occurs it is favored by its metrical position.
- indrasya nu vīryāni pra vocam (AV nu pra vocam vīr°, but most mss, SPP, and Whitney Transl prā for pra) RV AV. ArS MS. AB KB TB AA N—Ppp (Barret, JAOS 48 47f) like RV On prā cf. §439 and 437
- (b) Words in which absolutely final a varies with \bar{a} , the \bar{a} being capable of more or less justification on formal grounds
- §450. Here other considerations enter in and make it impossible to regard the law of rhythmic lengthening as the sole determinant, althout remains an important and perhaps in many cases the decisive factor. We include here adverbs in tra or $tr\bar{a}$; adverbs in tha or $th\bar{a}$, dha or $dh\bar{a}$; gerunds in ya or $y\bar{a}$, instrumentals from a stems in na or $n\bar{a}$; and neuter nom-accs in ma or $m\bar{a}$; also one variant of acha $ach\bar{a}$. It is noteworthy that in nearly all the cases, except the gerunds (in which the ending $y\bar{a}$ is probably older than ya), the variant vowel occurs in the second syllable of the pāda (cf. §438). Furthermore, it nearly always (with only one exception) is followed by a word beginning in a single consonant. Except in the case of gerunds, it never comes at the end of a pāda.
- §451. Adverbs in tra trā, viz yatra, tatra, atra There is a suffix $tr\bar{a}$, whose independence of tra seems indicated by a difference of accent (Whitney, Grammar, §1099a), the former is accented on the suffix, the latter on the stem So far as we have noted, our variant forms in $tr\bar{a}$ always accent the stem Still, the existence of the $tr\bar{a}$ -suffix cannot be ignored in considering these variations. While they are probably to be regarded as primarily rhythmic lengthenings, some influence from the suffix $tr\bar{a}$ may be at least suspected

§452. In all eight cases the adverb comes at the beginning of the pāda, so that the variant syllable is second — It is always followed by a single consonant; the following syllable is short three times, long five times. In nearly all cases the older version has \bar{a}

yatrā (MS. *yatra, AV. *yenā) nah (AV *te) pūrve pitarah paretāh (RV. MS.* pareyuh) RV AV. (bis) MS (tris).

yatrā sapta rṣīn (TS KS yatra saptarṣīn) para ekam āhuḥ RV. VS TS MS KS. N.

yatrā (TS yatra) suhārdah sukrto madantı (TS. °te) AV. TS

airā (AV. tatra) yamah sādanā (TA °nāt) te minotu (AV kṛnotu) RV. AV.† TA

tatrā sadah (SV. tatra yonım) krņavase RV. SV. KS

 $tatr\bar{a}$ (SV tatra) no brahmaṇaspatih RV. SV.: tatra undro brhaspatih VS

yatra (SV. yatrā) devā iti bravan (SV bruvan) RV. SV

atrā (VS atra) jahīmo (RV TA jahāma, AV jahīta) ye asann asevāh (AV. asīvāh, and asan durevāh; VS SB 'sīvā ye asan) RV AV. VS. SB. TA

§453. Adverbs in tha, thā, and dha, dhā Among the variants are found only atha, athā, adhā, adhā, and one case of itha, ithā Here there is less reason for assuming rhythmic lengthening, or more reason for suspecting formal analogy, because most adverbs of this type regularly have \bar{a} The only form that usually ends in tha is atha, and adha is the only one usually ending in dha. The numerous forms in thā and dhā may therefore be supposed to have had some influence in producing the (not uncommon) forms athā and adhā. There is this time no difference in accent. The ithā itha variant really belongs below, with §477, since the word regularly has \bar{a}

§454. In the seven atha and adha variants, the adverb is always initial in the pāda. The following word begins with a single consonant in every case but one, but the following syllable is long also in every case but one

atha (AV adhā) māsı punar āyāla no grhān AV HG

adha (TB adhā) vāyum nıyutah sascata svāh RV VS MS TB

atha viśve arapā edhate grhah TS: adhā viśvāhārapa edhate grhe VS atha jivrir (read jirvir, see Whitney) vidatham ā vadāsi AV.. athā jīvrī...ApMB; adhā jīvrī vidatham ā vadāthah RV

adha syāma (MS. athā syāta) surabhayo (ApŚ corruptly, syām asur ubhayor) gṛheṣu AV MS KS ApŚ.

athā (AV atha) devānām vasanīr bhavātı RV AV. TA.

athā (TS.* atha) bhava yajamānāya sam yoh RV. TS MS KS. AS. No true variant, the short a once in TS (3 2 11. 2) is due to the fact that the word happens to end a kandikā; see §428. This shows that after all the lengthening to athā was at least partly rhythmic, and felt as a matter akin to sandhi

§455. For completeness we add here the single case of *itthā* varying with *ittha* The latter is not recorded in the lexicons, tho it occurs in this variant in four texts. It is, however, clearly analogical, due to thought of *atha*. Of course the original and regular form is *itthā*, and the variant properly belongs with shortening of original final ā, §477: *ihettha* (AV "thā) prāg apāg udag adharāk AV. GB AS SS Vait

§456. Gerunds in ya $y\bar{a}$ 'According to Whitney, Grammar §993a, 'fully two thirds' of the RV forms in ya have \bar{a} , as if instr sing forms of i or ti stems. This, together with the fact that these $y\bar{a}$ gerunds are not governed by the laws which govern rhythmic lengthening, indicates that the variation is of a different sort. It is likely that the gerund ending was originally $y\bar{a}$, and that the later regular ending ya is secondary.

§457. In a majority of the variants the gerund occurs at the end of a pāda, a striking proof that we are not dealing with rhythmic lengthening: hiranyayāt pari yoner nişadyā (MS °ya) RV MS Ap\$

vanaspate raśanayā niyūyā (MS °ya, KS TB raśanayābhidhāya) RV.

MS KS TB AS N

vıśvā agne abhıyuzo vıhatyā (AV TB °ya) RV AV MS KS TB rudrāh samsrzya (MS °yā, TS ApŚ sambhrtya) prthivīm VS TS MS. KS ŠB ApŚ

mıtrah samsıyya (MS °yā) prihivīm VS TS MS KS ŚB ApŚ

§458. Instrumentals of a-stems in na $n\bar{a}$ In the few variants occurring under this head we may suspect that the analogical influence of other instrumental forms in \bar{a} assisted the tendency to rhythmic lengthening of the a There are only four cases, three of which concern the pronouns tena and yena, these three forms are initial in their pādas. In the remaining case the variant vowel is in the eighth syllable of a tristubh pāda, so that the meter requires a long, which RV. has, while SV. substitutes short a against the meter. In all four cases the next word begins with a single consonant, and the following syllable is short:

kavır girbhih kāvyenā (SV ona) kavıh san RV. SV

tenā (AV TB Poona ed and MS ed tena, but all mss of MS tenā) sahasrakāndena AV TB ApS. MS : tena vayam sahasravalšena TB ApS

tena (AV tenā) vayam bhagavantah syāma RV AV. VS. TB ApMB.

yena vahası sahasram VS MS. ŠB \cdot yenā (KS yena) sahasram vahası AV TS KS. Vait

§459. Nominatives and accusatives neuter (or nom masc) in ma $m\bar{a}$ (once, $a\bar{a}$) Here the phenomena of noun declension play a rôle Sometimes a change of gender is certain or possible (masc \bar{a} . neut a) Sometimes there is a change of number altho the ending short a in the neuter plural is twice as common as \bar{a} (Whitney, Grammar §425d), nevertheless \bar{a} is in a sense characteristic of the plural, and when found there cannot be regarded as merely a rhythmically lengthened a, despite the fact that the p p regularly writes a Note the fact that twice among the variants it occurs at the end of a pāda, where rhythmic lengthening is impossible, and cf Wackernagel III §145h There is, indeed, among the variants only a single case (the first quoted) where both ma and $m\bar{a}$ appear to be certainly neut sing, so that the lengthening must surely be rhythmic (cf Wackernagel III §145b)

§460. The variant vowel occurs in the second syllable of the pāda five times, in the fourth twice, and in the fifth of a tristubh once, thus in the first part of the verse eight times out of eleven. In the other three cases it is final in the pāda, and certainly not rhythmically lengthened. The following word begins with a single consonant in every case but two, where it begins with pr-(of §§433, 464). The preceding syllable is always long, the following one is long just half the time sarmā (TA °ma) saprathā āvrne KS TA · sarma yachātha saprathah (read °thāh with all mss, of Lanman, NInfl 560) AV. The form must be singular, as the adjective shows, and KS has a clear rhythmic lengthening. This is the only indubitable case.

vyomā (TS °ma) sapiadašah VS TS MS KS ŠB KS MŠ—BR assume a change of gender here in vyoman The formula is so devoid of meaning that anything is possible, but it may be merely a phonetic variant

ayam sahasram ānavo undharma (ApŚ °mā) SV ApŚ MŚ Cer tainly not rhythmic lengthening, as it is final in the formula, rather change of gender, neut to masc, in ApŚ Even the original neuter is used as an epithet ('Weltordner', Benfey).

brahma (ApŚ °mā) devānām prathamajā riasya PB ApŚ Here there is certainly a change of gender (in ApŚ masc, 'priest of the gods').

rtasya bráhma (AV bhūtānām brahmā') prathamota (emended by RWh in AV to prathamo ha) jajñe AV TB The difference of accent proves that different genders are intended But the pāda is hard to interpret without some emendation; see Whitney's note

- tan no brahmā (TA °ma) pracodayāt MS. TA. MahānU. Here also there is change of gender (MS brahmā').
- trınsad dhāma (MS. MŚ trinsáddhāmā as one word) vi rājati RV. AV. SV ArS VS TS MS KS SB The MS understands its compound as of masc gender.
- brahma devakṛtam upahūtam TS MS TB. AS SS: brahmā devakṛtopahūtā SB Here the number is changed from singular to plural in SB
- varma (AV. °mā) sīvyadhvam bahulā pṛthūni RV. AV. KS ApS. Both forms here are plural; and so in the next.
- yaira gavām nihitā sapia nāma (AV. nāmā) RV AV. Cf. prec; note the variation at the end of a pāda.
- tava śravānsy upamāny ukthyā (SV. $^{\circ}ya$) RV. SV. The only case of a n pl in a \bar{a} not from an n-stem
- §461. One case of the preposition acha achā. The original quantity of the final a is uncertain; but in RV. it is always long except before a pause and in two other cases (Grassmann, s. v.). One of the two exceptional cases is concerned here Wackernagel II. 1 p. 131, believes that achā is original.
 - acha yāhy ā trahā dawyam janam RV.: achā no yāhy ā raha RV.SV. We consider that rahā raha in this variant does not deserve quotation above under final a ā in verb forms, because the second form of the text actually reads rahābhi, fusing raha with following abhi. The p p, of course, always reads short a.
 - (c) Short a as final of stems in composition, and in analogous cases, optionally lengthened
 - §462. Just as the general laws of external sandhi are applied to the combination of parts of noun compounds, and even of stem-finals with certain suffixes (as vant and vin), so short a as stem-final may be rhythmically lengthened in these conditions. And the final vowel of the reduplicating syllable seems to be treated in the same way.
 - §463. The conditions of the lengthening are in large part similar to those where a is absolutely final. So the \bar{a} is invariably followed by a single consonant, without one exception among the variants. But the surrounding syllables are rather more apt to be long, instead of short as we should expect. The preceding syllable in fact is almost always long in the variants, and the following syllable is long in nearly half the cases. Most of the variants are prose, so that they furnish little evidence as to meter or position in the verse. There are five metrical

variants of a \bar{a} before the suffix vant, in every one the variant syllable is second in the pada

- §464. Wackernagel, who discusses this question in II 1 §56, recognizes an influence of a following consonant on the lengthening to this extent, that he finds it especially common before v If the evidence of the variants is to be trusted, it would seem that other labial consonants, especially p and m, exert the same influence, of above, §§433, 460 Nearly all the cases occur before one of these three consonants—For compounds of a privative, sometimes lengthened to \bar{a} , see §§469 f.
- §465. Prepositions in final a, optionally lengthened in composition All the cases are prose In two out of three the following consonant is m or v.
- apamıtyam apratīttam yad asmı AV (pratīkas in GB Vait Kauś) yāny apāmıtyāny apratīttāny (TB Poona ed °tītāny) asmı TB ApŚ (Metrical in AV, but prose in TB ApŚ)
- upāvīr (TS ApŠ upa°) asī VS TS MS KS ŠB. KŠ ApŠ MŠ See pw VII p 325
- prayāsāya (VS $pr\bar{a}^\circ$) svāhā VS TS KSA TB TA On $pr\bar{a}$, not to be identified with IE *pr\bar{o}, cf §§429, 439
- [prāvanebhih (MS KS pravanena) sajoṣasah RV VS TS MS KS ŚB Probably to be derived from root pru, rather than pra + vana See §491]
- §466. Other compounds The variation occurs thrice before p and twice before v The first three cases are metrical, the others prose For variations of the adverb $uttar\bar{a}$ with the stem uttara in composition see §476
- āvitte dyāvāpṛthivī ṛtāvṛdhau MS KS āvinne dyāvāpṛthivī dhṛtavrate TS TB And (in same passage) āvittau (TS āvinnau) mitrāvarunau dhṛtavratau (TS °nāv ṛtāvṛdhau) VS TS MS KS ŚB Note ā before v alone, but short a before vr- (the syllable being long already) Cf §665
- sahasrapoşam subhage (TS * °gā) rarānā RV TS MS KS SMB ApMB sahasrāpoşam subhage rarānā AV Kauś
- ide agnim svavasam (AV svävasum) namobhih RV AV MS TB AS
 Only the AV truly belongs here, as a compound of sva with vasu
 The others have a compound of su with avas
- deva samsphāna sahasrapoşasyesişe (AV sahasrā°) AV TS · sahasrapoşasyesişe SMB (Conc quotes the latter again for AV TS, but it occurs in them only as part of the longer phrase)
- dvārapāya svāhā, dvārapyai svāhā, dvārapopa spṛśa, dvārapy upa spṛśa, all HG dvārā° etc. ApMB

[brhaspatīnā rāyā svagākītah TS: †svagākārakīto mahyam MŚ. Cone svagak° for MŚ]

§467. Formations in vant and vin The variants seem to suggest a tendency for Tait texts to prefer \bar{a} before these suffixes, and Maitr texts short a, but they are not unanimous, and are probably too few in number to justify such an inference. It may be noted that similar variants before the parallel suffixes mant and min have not been observed, we have seen (§§238 ff) that they did not occur originally after a vowels. The first five variants are metrical

aśvavat (RV aśvā°) soma vīravat RV SV VS.

ındravanto (TS ındrā°) maruto vışnur agnıh RV AV. TS. KS †40 10b. puspavatīh (TS puṣpā°) supıppalāh VS TS MS KS §B

puspavatīh (TS V1Dh puspā°) prasūvarīh (TS °vatīh, AV. KS °matīh) RV. AV VS TS MS KS

sīkāhastā (TS KS sīkāvanto, MS. sīgavanto) nīsangīnah VS TS MS KS

ındravān brhad bhās svāhā KS . ındrāvān svāhā ·TS $\,$ TB : ındravān svavān brhad bhāh MS

dürehetir indriy
āvān (PB † °yavān) patatrī (PB °trih) TS PB TB PG ApMB

vālavān varşan bhīma rāvat svāhā MS . vātāvad varşam ugrar āvrt svāhā TS \cdot vātāvān varşann ugra rāvat svāhā KS

agnīndrayor aham devayayyayā vīryavān ındrıyavān bhūyāsam MŚ·
ındrāgnıyor (MŚ °nyor) aham devayayyayendrıyāvy annādo (MŚ
°drıyavān vīryavān) bhūyāsam TS "MŚ· ındrasyāham devayayyayendriyāvī (KS °yāvān, MŚ °yavān) bhūyāsam TS KS MŚ

jusiam devebhyo havyam ghriāvat (TS ghriavat svāhā) TS MS

dhişanās tvā devīr viśvadevyāvatīh (MS MS dhişanā tvā devī viśvadevyavatī) prthivyāh sadhasthe VS TS MS KS SB And so with aditis (vā (°tis tvā) devī , devānām tvā patnīi devīr . , janayas tvāchinnapatrā devīi , varūtrayo janayas (varūtiī, etc) ; gnās tvā devīr All in same texts, Maitr always reading viśvadevya°, the others °vyā°

[somam te krīnāmy ūrjasvantam payasvantam vīryāvantam TS KS Conc vīryavantam for TS]

§468. The reduplicating syllable Two cases, in both the following consonant is m or v

trita etan (AV. iria enam, comm etat, read etan or enan) manusyesu māmrje (AV mamrje) AV TB The AV form is more usual but bad metrically; TB (probably secondarily) improves the meter by using the stem māmrj- (found RV)

- sucanto agnim vavidhanta (AV $v\bar{a}^{\circ}$) indram RV. AV KS The regular form is $v\bar{a}^{\circ}$ but forms with $v\bar{a}^{\circ}$ are found in RV.
- (d) Final \bar{a} optionally shortened to a, and other a \bar{a} either absolutely final, or in the seam of compounds
- §469. We group here a varied assortment of cases which complete the list of what may be called in a large sense 'final' a \bar{a} Real phonetic shortening of \bar{a} is not common. In most of the following variants both short and long a can be justified morphologically. We begin with an interesting group concerning a privative and the preposition \bar{a} . Some of these concern lengthenings of a privative and properly belong in the preceding sections, but are mentioned here because of their similarity to those which involve the preposition \bar{a}
- §470. Thus, it has long been recognized that the RV form ā'deva, 'godless', is the same as ādeva, which varies with it in two of our variants, one of which occurs in both forms in RV itself. A somewhat dubious theory on ādeva, rejected by Oldenberg, Noten on RV 6 49 15, is put forward by Wackernagel II 1 p 131
- visa ādevīr abhy asnavāma RV viso adevīr abhy ācarantīh RV AV. AB bhuvad (SV bhuvo) visvam abhy ādevam (SV ad°) ojasā RV SV Here the ā may be due to the tendency towards an anapest after the cesura, with short a we have a tribrach
 - §471. Less certain cases of lengthening of a privative are.
- adayo (TS adāyo, MS ādāyo) vīrah (AV adaya ugrah) satamanyur ındrah RV AV. SV. VS TS MS KS In pw I p 297 it is said that ādāya is an error for adaya But the p p repeats the form, it might be interpreted as 'taking, seizing', from ā-dā
- yavā ayavā ūmā abdah (KS yavā āyavā ūmā tevā abdas) sagarah sumekah MS KS MŚ: yāvā ayāvā evā ūmāh sabdah sagarah sumekah TS ApŚ The forms yava(n), yā°, and ayava(n), ayā°, are used with great confusion, but the a- seems to be felt as privative, the y-forms designate the first half of the lunar month, the ay° forms the latter half The form with āy° is not noted except here and in the next, it seems to be equivalent to ay°
- sajūr abdo (MS* abdā) ayavobhih (TS ApŚ 'yāvabhih, MS MŚ āyavabhih, KS āyavobhih) VS TS MS KS ŚB ApŚ MŚ Cf preceding
- §472. In the next we have a clear case of the preposition \bar{a} varying with a privative.
- yām āpīnām upasīdanty āpah AV · yām apītā upatisthanta āpah LS

'Whom, fattened, the waters wait upon': 'whom the waters, undrunk, wait upon'

§473. In the rest, real phonetic shortening of \bar{a} seems at least possible, especially in the couple of cases where it occurs before conjunct consonants, of the similar law in Pāh and Prakrit (§§393 ff.) The words are however largely problematic, and in some of them a privative may be involved; so in the first

svastidā āghrnih (TB TA. aqh°) sarvavīrah RV. AV. MS TB. TA This familiar epithet of Pūsan certainly contains the preposition ā The form aghrni is recorded in no lexicon. Comm. on TB desperately takes the a as privative asodhavyadīptih ('). The comm on TA varies in different mss, one reading is ūgatadīptih (taking a as =ā) The reading adopted in Poona ed is adīptiah, asmāsv anugrāhī, which is not utterly unreasonable, of the classical aghrnin (pw II p 286, 'nichts verachtend') But of also pūṣne 'ūghrnaye svāhā, §300, where the yet different form aūghrni occurs, and is certainly a phonetic variant for āghrni

asleşā (TS āśreşā) nalṣatram TS MS KS. Name of a nakṣatra, more commonly āśleṣa, both these forms are otherwise unknown BR. derive aśleṣa from a privative, but āśleṣa (āśr°) from the preposition ā, this is hardly credible. The two forms must be of the same origin, one a phonetic variant of the other. The prevalence of ā-forms suggests that a- is a case of shortening before two consonants.

ā no višva (MS °vā) āskrā (TB višve askrā) gamantu (MS °ta) devāh RV MS TB AS The word is obscure, askra seems to be otherwise unknown Comm on TB ābhimukhyena kaitārah santah, which implies ā and supports BR's derivation from ā plus root (s)kr (Sāyana derives from kram) This would then be another case of shortening before a two-consonant group.

§474. There are three other cases which would be counted as rhythmic lengthenings of a privative, but for the fact that they seem to be misprints or textual blunders. The ā forms occur each time only in TB. Bibl Ind ed, and each time the Poona ed reads short a in text and comm without report of variant, agreeing thus with the other texts arāddhyā edidhişūhpatim VS. ārādhyar †didhişūpatim TB Conc. For misfortune?

aşādham (TB Conc aş° or āş°) yulsu prlanāsu paprım RV VS VSK MS. TB AS SS 'Unconquerable'

aṣādham (TB āṣ°, Cone) ugram sahamānam ābhih RV. AB TB

§475. Next, a few cases of final \bar{a} of feminine stems, optionally shortened to a in composition and before vant They hardly confirm, but are not numerous enough to dispute, the statement of Wackernagel II 1 §56e that the shortening is specially common before consonant combinations and in the neighborhood of long syllables. Perhaps by chance, a labial consonant follows the vowel in nearly every case $n\bar{a}sik\bar{a}vate$ (TS *kavate) $sv\bar{a}h\bar{a}$ TS. KSA.

amāyān māyavatlarah SB.: māyām māyāvatlarah AB

idaprajaso (KS idā°) mānavīh TS. MS KS

śirahpāṇipādapārśvapṛṣṭhorūdarajañghaśiśnopasthapāyavo (MahānU. °pṛṣṭhodarajañghā°) me śudhyantām TA. TAA MahānU.

ūrņamradasam (TS. TB. ApŚ. ūrņā°) tvā stṛnāmi (KS ūrnamradah prathasva; Kauś ūrṇamradam prathasva) svāsastham (VS Ţ ŚB Ţ °sthām) devebhyah VS. TS KS. ŚB. TB. KŚ. Kauś: uru prathasvarnamradam svāsastham devebhyah MS.

§476. The adverb utlarā varies with the adjective stem utlara in composition:

mıtrāvarunanetrebhyo vā marunnetrebhyo vā devebhyo uttarāsadbhyah (VSK. uttara°) svāhā VS. VSK. ŚB.

ye derā metrāvarunanetrā vā marunnetrā vottarāsadas (VSK. vottara°) tebhyah svāhā VS. VSK. ŚB.

§477. The rest are sporadic. The stem asla asla belongs with noun formation rather than here; ā occurs in the regular inflexion of the stem (cf. Wackernagel II. 1 p. 131, III p 358). On athā atha see §455; on achā: acha, §461. Otherwise we record here only the form viŝvāhā or ha, and a couple of lexical variants:

śivā riśvāha (VS. and p p of MS. °hā) bheşajī (MS °jā; TS viśvāhabheşajī) VS. TS. MS. KS. (Cf. watam rakṣanti viśvahā etc., §511). The reading of MS p p. suggests interestingly that we may have a case of shortening for the sake of rhythm or meter (note surrounding long syllables). If the word is a compound of viśva and ahan, as Grassmann believed, the variation would rather be one of noun declension (neut plur. in a·ā, cf. §§459 f.).

cli rā (AV. atīra) yo maruto manyate nah RV. AV. vā wa yad indra citra mehanā (SV. PB ma iha na) RV. SV. PB. AŚ. ŚŚ N See §832

athem ara sya (AV. athemam asyā) vara ā pṛthwyāḥ AV TS AS SS MS 'Then set him free upon the choice spot of earth': 'then him upon the choice spot of this earth...'.

2 Non-final a ā in verb inflexion

- §478. In various verbal stem-formations and a few verbal inflexional forms, a medial varies with \bar{a} Rhythmic considerations play a part in some of these, notably in the well known variation between $\bar{a}ya$ and aya in denominative stems (VV I p 155), with which must properly be classed verbal adjectives in u from denominative stems, showing the same shift.
- devān devayate (TB ApŚ MŚ devā°) yaja (MŚ yajamānāya svāhā) RV SV. KS TB. ApŚ MŚ
- agne prehi prathamo devayatām (AV. devatānām, MS KS devāyatām) AV VS TS MS KS SB The verse is meant for jagatī in all except AV.; meter favors devā°.
- apānudo janam amitrayantam (AV amitrā°) RV. AV. TS. KS devayuvam (TS TB devā°) visvavārām (AS °re) TS. SB TB AS. SS devīr āpo agreguvo...devayuvam (VSK deva°) VS VSK SB.
- §479. Similar conditions exist in the radical syllable of the causative (VVI p 155).
- vasospate ni ramaya (N $\ r\bar{a}m^{\circ},$ so v $\ l$ of AV) AV. N $\ :$ vasupate vi ramaya MS
- yāvayāsmad dveşam KS: yavayāsmad dveşah VS TS SB. Kauś. yavaya (v. 1 yā°) dveşo asmat MS: yavayāsmad aghā dveşānsi TA.
- yāvayārālim KS. yavayārālīh (MS. Kauś °tim) VS TS. MS SB Kauś The p p of MS has yāvaya
- tatra havyānī gāmaya (KS ga°) RV. KS TB ApS MS But von Schroeder reads gāmaya in KS with one of his three mss
- §480. There are shifts between strong and weak perfect stems which involve this variation; see VV I p. 187, to which our first variant should be added
- adıtsan vā (MS dhipsyam vā, TB yad vādāsyan) samjagara (TB. °jagārā, MS °cakara) janebhyah MS TB TA These are first person forms, so that either a or ā is permissible by regular grammar
- yat sāsahat (SV sāsāhā, KS †sāsāhat) sadane kam cid atrinam RV SV. KS
- bibheda valam (AV. AS balam) bhṛgur na sasāhe (AV. sasahe) AV. SV. AS SS The ā is probably due to the meter here, in the middle it is highly irregular, tho not unknown (Whitney, Grammar §793h). But the AV. form is itself not regular, it should be sehe
- svām cāgne tanvam (TA tanuvam) piprayasva (AV. piprā°) RV AV. TA. MahānU See VV I p 187 The ā here disturbs the meter, but is otherwise hardly much worse than the rival form.

§481. There are a number of cases of sigmatic aorists containing a or \bar{a} , or sigmatic aorists with \bar{a} varying with other aorists or presents in medial a They are mostly collected in VV I pp 128 f, 186 On the latter page, under §277, is to be added the following.

ānyāvākṣīd (VS ānyā vakṣad) vasu vāryānī VS TB Cf also·

grāvāvādīd (ApŠ grāvā vaded, so KS ed, with v l as Conc) abhi somasyānšum (ApŠ °śunā) KS ApŠ

§482. Subjunctive forms with an ending containing \bar{a} often vary with indicative or imperative (injunctive) forms with endings containing short a. They hardly concern phonetics, and can be found in VV I, in the appropriate places (§§117, 124, 137, 152–4, 167f). Nor shall we list here the different modal forms of the roots $d\bar{a}$ and $dh\bar{a}$ which show alternatively a and \bar{a} (VV I §193), or augmented and augmentless verb forms in initial $\bar{a}.a$, VV I pp 180f, and elsewhere, of which the following may be mentioned here as examples

ayann (TB ApŚ āyann) arthām kṛnavann apānsi RV KS TB ApŚ ahā yad dyāvo (AV devā) asunītim ayan (AV āyan) RV AV āyan is imperfect indicative, ayan subjunctive

There are yet other variations in verbal endings showing this shift We shall quote only one of the dual endings -tam and $-t\bar{a}m$, 2d and 3d persons, which should be added to VV I §337

ā mā gantām (VSK † °tam) pītarā mātarā ca (VSK †yuvam) VS VSK 10 3 12c, TS KS ŠB Subject voc in VSK, nom elsewhere Surrounding pādas have 3d person verbs

3 Non-final $a \bar{a}$ in noun formation

§483. In this class nearly all traces of rhythmic or metrical influence disappear, the variants are almost exclusively morphological (occasionally lexical), and concern phonetics only to a slight extent. Yet even here it is hard to rule out altogether phonetic considerations. Our volume on Noun Formation will deal more extensively with this group

§484. Most of them fall into two classes First, there are variants in which two primary noun formations interchange, one having a and the other \bar{a} in the radical syllable, the suffix being usually the not always the same Included here are some obscure words of doubtful origin, where the original form is uncertain and the variation may be phonetic in some sense Second, there are cases of variation between secondary formations with the viriddhi of secondary derivation and other, primary or secondary, formations without this viriddhi. The distinction between the two classes is not always clear or definite

§485. Under primary formations with radical a or \bar{a} , we may call attention first to a number of variations between the stems yava(n), yavas, $y\bar{a}v^o$, and ay^o , $\bar{a}y^o$, to which attention has already been drawn in §471 The original form of the word in question is unknown:

sayūr abdo (MS *abdā) ayavobhih (KS āy°, TS ApŚ 'yāvabhih, MS. MŚ āyavabhih) VS TS MS KS ŚB ApŚ MŚ

yavā ayavā ūmā abdah (KS āyavā ūmā tevā abdas; TS. ApŚ yāvā ayāvā evā ūmāh sabdah) sagarah sumekah TS MS. KS. ApŚ MŚ

yavānām (TS yāv°) bhāgo 'sı VS TS MS KS SB

ayavānām (TS ayāv°) ādhipatyam VS TS MS KS

yavāš cāyavāš cādhīpataya āsan VS MS KS ŚB: yāvānām cāyāvānām cādhīpatyam āsīt TS

§486. Rather numerous are cases in which the primary suffix a is used with well-known roots in forming primary derivatives with either a or ā in the root syllable, type bhaga bhāga They call for no comment: subhagamkaranī mama AV. subhāgamkaranam mama SMB Most samhitā mss of AV subhāga.

mām agne bhāgınam kuru ApMB: mām indra bhagınam kṛnu AV

samsrāvabhāgā (°gāh, °gās, VS ŚB KŚ samsrava°) stheṣā (Kauś taviṣā) brhantah VS TS MS KS ŚB. Kauś

namah parnāya (TS KS † parnyāya) ca parnaśādāya (TS °śadyāya, VS. °śadāya) ca VS TS. MS KS.

prātah prātahsavasya (ApŚ. MŚ °sāvasya) šukravato...ŚB. KŚ ApŚ MŚ prātahsāva is the only form known to RV, but the other is commoner later

prātah prātahsavasyendrāya (ApŚ MŚ °sāvasyen°) ..KŚ ApŚ. MŚ śrāvaś (VS. śravaś) ca me śrutiś ca me VS. VSK TS MS KS. śravaś might be taken as an s-stem, but not śrāvaś

ksuro bhrajas (TS bhrjvān, MS bhrjas, VS bhrājas) chandah VS TS. MS KS ŚB.: bhrajas (KS ed †bhrā°, v l bhra°) chandah VS (in next verse) TS KS (in same verse) ŚB Comm. on VS bhrajas for bhrā°.

vahnih samtarano (TA sampārano) bhava VS TA Different but synonymous roots

§487. Forms in primary ya, practically gerundives in meaning:

yad bhūtam yac ca bhavyam (AV *ArS VS bhā°, AV.* yad vā bhāvyam) RV AV (bis) ArS VS TA Gomm on AV and Ppp bhav° Metrical lengthening, possibly

uttarasyām devayajyāyām upahūtah (TB also °tā) TS SB TB: upahūto 'yam yajamāna (MS °nā) uttarasyām devayajyāyām (MS. °yājyā-yām) MS AS SS

- §488. Forms in other suffixes.
- havanasrun (TB hāvanasrūr) no rudreha bodhi RV TB hāvana- is not otherwise recorded from root $h\bar{u}$
- dūṣīkābhir hrādunim (KSA † hra°) TS KSA: hrādunīr dūṣīkābhih VS MS. The word is not otherwise recorded with short a, if KSA is correct, it has probably suffered analogical influence from the sphere of hrada
- duācarebhyo (MG °cārıbhyo) bhūtebhyah MG VıDh · ahaścarebhyah ŚG (Sc. namah in both) Also, naktamcarebhyah ŚG. VıDh · naktamcārībhyo bhūtebhyah MG Stems cura and cārın
- tatam me apas (TB ApS. ma āpas) tad u tāyate punah RV KB TB AS ApS Both apas and āpas are Rigyedic
- vratāni (MS TB ApŠ vratā nu) bibhrad vratapā adabdhah (TB SS ApS SG adābhyah) MS AB TB AS SS ApS SG Here the gerundive varies with a participle.
- §489. The remaining variants under this head are in some way or other doubtful or obscure, but seem generally to be primary formations, occasionally they may be lexically different in origin
- adayo (TS adāyo, MS ādāyo) vīrah (AV ed with p p adaya ugrah, but mss adā°, and so comm) satamanyur indrah RV AV. SV VS TS MS. KS On the initial ā of MS see §471 The second ā is anomalous if the word means 'pitiless' (so AV comm). Possibly 'without a share' (dāya), tho this fits none too well For other suggestions see Keith's translation of TS and note
- marudbhyo grhamedhibhyo (MS °dhebhyo) başkihân (MS. vaş, ApŚ bāşkān) VS MS. ApŚ. Cf §219 The word is obscure, is the ā somehow connected with the suppression of the second syllable in ApŚ?
- tāṣat ApŚ raṣaṭkārah AG ŚG If Garbe's conjecture is right (all mss of ApŚ raṣat) it is a deliberate and artificial variation of the familiar exclamation vaṣat
- ākhuḥ kaso mānthālas (MS mānthālavas, VSK māndhālas) te pītrīnām VS VSK MS: pānktrah (KSA † pānktah, but mss of both texts pāmtra-) kaso mānthīlavas (KSA † man°) te pitrīnām (KSA † pitr°) TS KSA See §77
- hemantāya kakarān (KSA 7 kakārān) VS MS KSA ApS Name of an unknown animal or bud
- [śiśirāya ukalarān (KSA † ukarān, Conc ukārān; ApS ukirān) VS KSA ApS]
- āstām jālma (KS jalma) udaram šranšayıtvā (KS srans°) AV KS.

- nākro makarah kulīpayas (TS kulīkayas, MS pulīkayas, KSA pulīrayas) te 'kūpārasya (KSA † kūvarasya) VS. TS. MS KSA Read kūvārasya in KSA; see §198
- sanderathas sandihera ulūkhalah ApMB.: sāndīhera (PG saundikeya) ulūkhalah HG PG Fanciful names of demons
- ālhuh srjayā sayandakas te maitrāh (KSA sayāndakās te maitryāh, em in ed to °kas te maitrāh) TS KSA · sārgah srjayah sayāndakas te maitrāh VS. MS The word say° is obscure, and may have been originally a compound
- vāśā stha VS TS ŚB TB ApŚ. vaśāh stha MS KS MŚ. Addressed to waters vāśā probably 'bellowing' (BR and Keith 'obedient', implausibly following one of Sāyana's guesses); vaśāh 'cows' It is held by some that vaśā is connected with the root vāś, 'bellow'.
- §490. Coming to secondary noun formations, we find first a number of cases in which two secondary stems exchange, one having vriddhi in the first syllable and the other lacking it
- tısras ca rājabandhavīh (HG. °vaıh) HG ApMB. prajāh sarvās ca rājabāndhavaih (MG °vyah) PG MG: sarvās ca rājabāndhavīḥ (SG†°bāndhavaih) AG SG (Oldenberg suggests reading °vīh in SG) Alternative stems bandhava and bān°, both from bandhu
- mitrāvarunau prašāstārau prašāstrāt (KŚ prā°) KŚ ApŚ MŚ. The office of the prašāstr is prašāstra or prā°
- dwyam suparnam vāyasam (AV payasam, KS VS SB TS* vayasā, MS TS* vayasam) brhantam RV. AV VS TS KS MS SB. AS. Suparn vāyasa and va° both 'bird', vayasā is instr of the unrelated vayas 'strength'.
- dhişanāsi parvatī (TS TB ApŚ 'tyā, MS KS MŚ pārvatī, but KS mss par') VS TS. MS KS ŚB TB ApŚ MŚ. In the Tait texts a secondary adjective parvatya, in the Maitr. school an equivalent pārvata, the form parvatī must also have the same meaning (Mahīdhara seems to explain it as having 'Vedic' shortening); it is too well attested to make emendation advisable. See next
- prati tvā parvatī (TS TB °tır, MS KS MŚ pārvatī) veitu VS. TS. MS KS ŚB TB MŚ See prec Twice in KS, once the sole ms has parv°, the other time pārv°, but KapS parv°
- gārgī (AG gargī) vācaknavī (sc trpyatu) AG. ŠG. Patronymics, gārgī is to be expected See next
- śakalyam SG śākalam AG (with both sc tarpayāmi) Read no doubt śākalyam in SG (misprint, Oldenberg's translation has Śākalya) Cf prec

- ya āntarıkşāh (sc sarpās tebhya ımam balım harāmı) HG: ye sarpāh pārthıvā ye antarıkşyā ye dıvyā AG.
- vāyur na īdīta īdītavyair devair antarīksyaih (ApŚ āntarīksaih) pātu KS ApŚ
- āngūṣānām (SV angoṣinam) avāvašanta vānīh RV SV The SV form in this and the next is dubious
- āngūşyam (SV angoşinam) pavamānam sakhāyah RV SV Cf prec svetāya vaidarvāya (°vyāya, °dārvāya, vaitahavyāya), see §315
- suvarnasianyam avrātyam (BDh avratyam) V1Dh BDh Perfect equivalents
- narāšanse (VS nār°) somapītham ya āšuh (KS ānašuh) VS MS KS TB It is at least conceivable that narāšansa, as name of a certain libation, is a secondary derivative without vriddhi
- [narāšansa stavīsyate AV AŠ ŠŠ In the Berlin ed of AV. 18 printed the false emendation $n\bar{a}r\bar{a}^{\circ}$]
- sūyavasınī manave (RV TA manuşe, KS mānuşe) dasasyā (TA °sye, TS MS KS yasasye) RV VS TS MS KS SB mānuşa of KS = manuşa of TA (manuşe in RV. is dative of manus, a more primitive form, all ultimately connected with manu, whence the dative manave)
- agnīd rajanarauhmau (so ed, v l rāja°, p p rājan, rau°) purodāšāv adhišraya MS A name of a sāman, see note in MS, and BR s v rājana, which seems to be the true form; rajana would perhaps be an equivalent formation if it were acceptable
- yakşmam śronibhyām (ApMB śronī^o) bhāsadāt RV ApMB : yakşmam bhasadyam śronibhyām bhāsadam AV
- aranyāya (MS āranāya) symarah VS. TS MS KSA Both mean 'of distance'
- kalpayatam mānuşīh TB $\,$ ApS . drnhantām davīr visah kalpantām † manuşyāh KS
- achınno dıvyas (KS ApS davyas) tantur mā mānuşas (KS ApS manuşyas) chedi MS KS ApS
- brhaspatır devānām (ŠŠ davo) brahmāham manuşyānām (ŠŠ mānuşah) VSK TB SŠ KŠ ApŠ MŠ
- §491. In other cases a secondary formation with vriddhi of the initial syllable varies with some form of the primary word from which it is derived, or with a related word.
- sunam vāhāh sunam narah (TA nārāh) RV AV TA narah, plur of nr, nārāh, plur. of nāra, from nr or nara
- namas ie rathamtarāya (AA rātho) .. AA LS SS Both words refer to

- the Rathamtara saman, AA. forms an adjective from the noun rath, with samne understood.
- bhuvanam ası sāhasram (MS. *sah°, ŚG. sahasrapoşam, MS. *sahasrapoşapuşı, ApŚ sahasrapoşam puşa) MS SMB ApŚ MŚ. ŚG Probably read sāhasram in MS *, note that MŚ. has this
- vāyosānira (TS pp °trah, MS vāyusavıtībhyām) āgomugbhyām caruh (MS. payah) TS. MS KSA Both = 'of Vāyu and Savitar.'
- tasmaı brahma ca brāhmās (TA brahmā) ca AV TA.
- nāsām āmitro (TB nainā amitro) vyathir ā dadharşati RV. AV. TB āmitra = 'belonging to the enemy (amitra)'.
- agnes tvā (MS agnes tvā) mātrayā jagatyai (KS. °tyā, MS. jāgatyā) vartanyā. .TS MS. KS 'with the path of the jagati' or 'with the jagati as path'. KS v 1. jāgatyā
- jagad asi MS MS : jāgalam ası MS. TA ApS : jāgalāsı MS : jāgalo 'si MS MS All 'composed in jagatī meter'
- prabhāyā agnyedham (TB āgnendham) VS TB. The TB. form is problematic, comm agneh prayvalandkartāram, which would make it equal to agnyedham Should we read āgnyendham, 'having to do with fire-kindling'? Or āgnīndham?
- sadyahkrīš (ApMB sādyaskrīš) chandasā saha SG ApMB. sadyaskrī (masc '), name of an ekāha The ApMB. form would seem to be a secondary derivative, but in that case would have to be fem., and there seems to be no fem noun with which it could agree
- prāvanebhh sajoṣasah RV. VS TS SB.: pravanena sajoṣasah MS KS The āπ λεγ prāv° is doubtful; Grassmann as secondary adj, '(fires) of the abyes' But RV. pp prav°, possibly rhythmic lengthening (note that the following consonant is v, cf. §464). The primary word is probably to be derived from root pru, tho it has been interpreted as a compound of pra and vana; in that case it would belong to §465
- śāśvatībhyah (AV ApŚ and TB Poona ed śaś°) samābhyah AV. VS TB IśāU. ApŚ The adjective śāśvata = śaśvat, fem forms of both yadı varunasyāsı . Kauś: yadı vāruny ası Rvidh ApG.: yady asi vārunī.. GG
- yathā yamāya harmyam (TA hā°) AV. TA.; and
- evā (TA. evam) vapāmī harmyam (TA hā°) AV TA hārmya is recorded only here, and may mean the same as harmya, or be a corruption of that; but TA takes it as a secondary adj, 'suitable for the house', supplying a noun, and this is also possible
- sūpasthā ası vānaspatyah MS. sūpasthā devo vanaspatth TS. ApS.

ms šb mš

eşa u sya v
rşā rathah RV. SV \cdot eşa sya rāthyo v
rşā VS ŚB adhyakṣāyānukṣattāram TB tādhyakṣyāyānukṣattāram VS

somo vaisnavo rājā (AS SS somo vaisnavas) . añgiraso (AS †āñg°, SS āñgiraso vedo) vedah . SB AS SS. 'The Añgirasas (1e, the AV) are the Veda', so SB The others mean the same thing. 'the (Veda) of the Añgirasas'

§492. There remain a number of other cases which seem to concern noun formation in a broad sense. First a group of variants between $\bar{a}grayana$ and $\bar{a}gr\bar{a}^c$, name of the first soma offering at the Agnistoma, which is apparently derived from agra, the \bar{a} may be rhythmic in character. The variants seem to suggest a preference for the \bar{a} form in MS MŠ and KS, with short a elsewhere.

nıdhanavata āgrayanah (MS KS āgrā°) VS TS MS KS \$B āgrayanas (MS KS āgrā°) ca me VS TS MS KS

āgrayanāt (KS MS āgrā°) trīnavatrayastrīnsau VS TS MS KS SB āgrayano (MS MS āgrā°) 'sī svāgrayanah (MS MS svāgrā°) VS TS

āgrayanas te dakṣakratū pātv asau AŚ · ātmānam ta āgrāyanah (ApŚ †āgra°) pātu MS ApŚ

§493. When roots ending in \bar{a} are used as final parts of compounds, the \bar{a} is frequently shortened, bringing the word into the common a declension

ūrnamradasam (etc., see §475) svāsastham (VS † ŠB † °sthām) devebhyah VS TS KS ŠB TB KŠ Kauś uru prathasvornamradam svāsastham devebhyah MS

krşno 'sy ākhareşihah (MS KS and most mss of MŚ °şihāh) VS TS MS KS ŚB TB MŚ ApŚ

yuvā kavih purumstha (KS °sthā) rtāvā RV TS MS KS

mitro na (MS MŠ nā) ehi sumitradhah (TS KS °dhāh, MS*°dhah saha rāyas poṣena) VS TS MS KS ŚB

yo devānām nāmadhā (AV °dha) eka eva (KS eko astr) RV AV VS TS MS KS.

adabdho gopāh (KS †gopah) parı pāhı nas tvam (KS parı pātu visvatah) RV TS KS

pravāyāhne 'har jinva MS: pravayāhnāhar jinva VS The MS form is suspicious in the light of the surrounding parallel formulas, which are instrumental in form If correct it is a dative from pra-va, VS has instr. of pra-vā The root is vā, 'blow'

§494. Other variants involving different related or quasi-related noun stems

- aprajastām pautramṛtyum ApMB HG: aprajasyam pautramartyam SMB. aprajāstvam mārtavatsam AV On stems prajas and prajās (;prajā) see Wackernagel II 1 p 95 f
- sa tvā manmanasām karotu (ApMB °sam krnotu) PG ApMB. 'He shall make thee (fem) me-minded' Stems man-manas and man-manasa
- agnir adhyalşah (TA °şāh) MS TA. 'Agni is overlord' There is no apparent explanation of the anomalous ā of TA., as if from stem adhyakşas' It is repeated in the comm, with gloss svāmī
- satvanām (MS satvānām, KS †sattvānām) pataye namah VS TS MS. KS Stems satvan and sattva; MS. has a bad writing for sattv°, cf §392
- ımām narāh (narah) , see §328 Nom pl of stems nara and nr. tısrah kşapas (TA °pās) trır ahātıvrajadbhıh RV TA. Stems kşap and kşapā
- tābhr (TB yābhr) yāsı dūtyām (MS °yam) sūryasya RV MS TB Stems dūtyā and °ya (Pıschel, VSt 1 22, Oldenberg, Noten on 6 58 3)
- agne pṛthuṣpate...varuna dharmanām pate TB · agne pṛthivyā varuna dharmānām. ŠŚ Stems dharma and °man (Also listed in Conc under varuna)
- §495. The numeral for 'eight' has stem final, in declensional forms as well as in composition, ending in both \bar{a} and a, the former predominates earlier, the latter in the latter language, cf. Wackernagel III p 358 f
- aşiasthûno daşapakşah Kauś: aştāpakşām daşapakşām AV aşiābhyah (KSA aşia°, but ed em aşiā°) satebhyah svāhā TS KSA [aştābhyah (Conc wrongly KSA asta°) svāhā TS KSA]
- [agnaye gâyatrāya truvte rathamtarāyāşṭākapālah (wīth varr) VS TS
 MS KSA All texts aṣṭā°, Conc aṣṭa° for VS]

§496. A couple of doubtful cases

- samudrasya tvāvakayā (TS ApŚ tvāvā°) VS TS MS KS ŚB ApŚ MŚ. avakā, name of a water-plant, from ava, avākā presumably the same, perhaps with rhythmically lengthened ā before suffix ka, cf similar cases before vant and vn, §467, and Edgerton, JAOS 31 118, where this should in that case be added Boehtlingk, 'die untere Ethaut' for avākā, evidently thinking of avā(ā)c, Keith, 'wind', we see little reason for either interpretation.
- nırıfım nırıarıalpena (MS nırıalpena, TS nırıalmakena, KS nırıalmaka-) sīrşnā VS TS. MS KS Obscure word, see §810 TS comm, followed by Ketth, 'bald'.

4. Non-final a ā in Noun Declension

§497. In inflexional forms of nouns the shift between a and \bar{a} is regularly accompanied, and no doubt wholly determined, by morphological or syntactic changes. Rhythmic or other phonetic considerations enter in hardly at all. We begin with purely formal shifts, not accompanied by change of syntax, that is, the variant forms are felt as of the same case, number, and gender

§498. First, the forms apas and apas are frequently interchanged as nom and acc of stem ap (Wackernagel III p 240):

Sam no bhavantv āpa oṣadhayah (6 23 3 apa oṣadhāh) śwāh AV 2 3 6, 6 23 3 But mss at 2 3 6 also apa (comm. āpah), which Whitney's Translation restores, and this despite the fact that both forms are nominatives! The shortening may be influenced by the meter, it furnishes the desired anapest after the cesura

apo (RV. AŚ āpo) adyānv (TS TB JB. Apś anv, AV. dwyā) acārişam (JB †acārṣam, AV acāyiṣam) RV AV VS TS MS KS ŚB TB JB AŚ LŚ Apś MŚ ApMB. ApG MG Here the form is accusative

§499. Stems in d do not usually show ablaut in the stem syllable except in the case of pad, which shows some fluctuation in composition and in case-forms (Whitney §387 4, Wackernagel III p 235 f) The variants present a couple of cases of this stem, and also one of sad, not recognized as lengthening the stem a by Whitney §387 or Wackernagel III p 237, foot

d npac catuspad (SV dvnpāc catuspād) arjum RV SV.

dvipac catuspād (AV VS Kaus, dvipāc catuspād) asmākam RV AV VS VSK TS Kaus

catuşpadām uta yo (TS ca) dwpadām AV TS catuşpāda uta ye dwpādah KS MS Here the ablaut is regular, different case forms

vıśvā āśā dakşınasat (AB AS °sāt, SŠ °tah, LS °dhak) VS. MS AB SB TA AS SS LS ApS

§500. Twice Tait texts present vriddhi-grade forms of ptr in the bahuvrihi compound dáksa-ptr, which Wackernagel II 1 p. 101 (cf also III p 200) properly compares with tvát-pitārah.

sudakşā dakşapıtarā (TB °tārā) RV. TB
ye devā manojātā (MS KS MS manu°) sudakşā dakşapıtaras (TS †
°tāras) . TS MS KS BDh VıDh

§501. Of n-stems, there is one case of nom. pl vrşanah (Wackernagel III p 267) replaced in a later text by the more regular-seeming vrşanah trsanah (TB vrşanah) samıdhīmahı RV. AV SV SB TB

- §501a. And once a form with irregularly lengthened a, pasumānti, from a mant stem (noted RPr 589 = 9 30), is replaced in SV by the regular form.
- miteva sadma pašumānti (SV °manti) hotā RV SV —Similarly. ava dronāni ghrtavānti sīda (SV °vanti roha) RV SV.
- §502. As to s-stems, the ending as in the neuter nom.-acc of adjectives may be lengthened to ās (Wackernagel III p 288).
- śarmā (TA °ma) saprathā āvrne KS TA. śarma yachātha saprathah AV But all mss of AV °thāh, which should doubtless be read; comm °thah
- yachā nah (AV yachāsmaı) šarma saprathah (AV VS KS TA ApŚ ApMB HG °thāh) RV AV VS MS KS TA ApŚ SMB HG ApMB N
- visām agnim atithim suprayasam (KS °yāsam) RV KS The meter favors a long, and this may be the reason for KS's secondary reading, v Schr emends to °yasam, rather rashly, we think Cf. Whitney §415b, 2, 3 (But Wackernagel III p 282 denies ās to other words than usas) Oldenberg, Noten, denies ground for emending the RV, which is unquestionably conservative and wise, but the meter is nevertheless poor, and he offers no explanation of it
- ayā san (so read, MS ayāh san, KS ms ayīsā, ed emend ayās san) manasā hitah (MS kritah, pp kritah, KS kritah) MS KS TB. ApS ApMB HG: ayāsā manasā (AS vayasā) kritah AS SS: ayasā manasā dhritah ApS ApMB HG See next.
- ayā san (MS ŠŠ ayāh san, KS ayā° san, Kauś ayāsyam) havyam ūhışe MS KS TB AŠ ŠŠ ApŠ Kauś ApMB HG ayasā ha° ū° ApŠ ApMB. HG The old adjective ayās becomes ayas in oblique cases in some secondary texts, a natural change owing to the ranty of stems in ās, and to the agreement of the nom form with noms of stems in as See Geldner VSt 3 122 n 5, Neisser, ZWbch d RV, s v, Wackernagel III p 282
 - §503. A couple of miscellaneous equivalent noun forms
- agne yan me tanvā (TS tanuvā) ūnam (SS yan ma ūnam tanvas) tan ma ā pīna VS TS SB SS PG Abl-gen sing of u-stem
- anadvāns tapyate vahan (MS talpate vahān) ApS MS The passage of MS is unpublished, if correctly reported, the ending of the nom sing pres pple would be lengthened by analogy with mant and vant stems
- §504. Concerning pronoun declension, we have one case in which the dual stem yuva- is replaced by the later yuvā-:

athā somasya prayatī yuvabhyām RV.: adhā somasya prayatī yuvābhyām KS But v. l. of KS yuva°.

§505. Coming now to forms involving some syntactic shift, we find first exchanges between forms of masculine and feminine gender in adjectives modifying nouns of common gender

svām (MS KS. svam, MG sva-) yonım gacha svāhā AV. VS TS MS KS SB MG yonı may be masc or fem, the Tait school makes it fem in all the variants

agne svam (TS TB svām, ŠB tvam) yonım ā sīda sādhyā (VS ŚB sādhuyā) VS TS MS KS ŚB TB See prec

svam (TS svām) yonım ıhāsadah VS TS † MS KS (No svam in TS) yajño bhūtvā yajñam ā sīda svām (MŚ svam) yonım TB ApŚ MŚ [svāmkrto (KS svam°) 'sı VS TS MS KS ŚB KŚ ApŚ MŚ Here both forms are quasi-adverbial, in a compound verb form]

dhruvam (TS °vām) yonım ā sīda sādhyā (VS SB sādhuyā) VS TS MS KS SB.

mā mā (KS mām) hinsişlam svam (KS yat svam) yonim... MS KS: mā mā hinsīh svām (KS svam) yonim... VS KS SB TB, ApS: mainam hinsişlam svām yonim AB

sa no dadātu tam (AV. tām) rayım AV AA ŠŠ rayı, masc or fem athāsmabhyam sahavīrām (AV VSK MS KS °ram) rayım dāh AV. VS VSK TS MS KS HG Cf prec

abhīmam (TS °mām, MS MŚ v. l °mān) mahınā (VS. MŚ v l. °mā) dıvam (MS dıvah) VS TS MS TA. ApŚ MŚ.

yā (MS ya) ışavo yātudhānānām VS TS MS. SB NīlarU ApMB ışu, m or f.

§506. These are the only cases noted of this change due to change in gender of the noun modified (the words concerned being yon, ray, and dw). There are not a few others in which the epithet is transferred to a different noun, involving change of gender. These will be treated in our volume on Noun Declension, and we deem it unnecessary to list them here We may, however, quote a few examples of forms in -am -ām, which are both adverbs equivalent in meaning, or of which the form in -ām is an adverb, that in -am a mase or neut adjective:

ındremam prataram (VS TS SB °rām) kadhı (VS MS SB. naya) AV.

VS TS MS KS SB

ud enam uttaram (VS TS KS SB *rām) naya AV. VS TS MS KS SB

Vait ApS MS Kaus

jīvālave pralarām (RV °ram) sādhayā dhıyah RV SV.SMB drāghīya āyuh pralaram (TA†°rām, MG pralıram) .RV AV. TA AG MG And others, see §575 asmın kşaye prataram didyanah SV.: adhi kşami prataram didhyanah RV. AV.

§507. In the declension of nouns, pronouns, and adjectives there are quite a few case forms which differ from one another only or chiefly in the quantity of an a vowel. This is, for instance, true as between the instr. sing. and other singular oblique cases of \bar{a} -stems, and between the nom mass. sing and plur of a-stems; as well as between mass. or neut. and fem. forms, treated in §\$505–6. We give merely a couple of examples of these, followed by an exchange between the nom. and accuspronouns tram and trām. Since this matter does not properly concern phonetics, we shall reserve a full list and discussion for our volume on declension:

surayā (MS. KS surāyā) mūtrāj janayanti (VS. 7MS. °ta) retaḥ VS MS KS † TB. 'By (from) surā they generate(d) seed from urine.'

surayā (MS. surāyāh) somah suta āsuto madāya VS. MS. KS. SB. TA.

dīkṣayedam (KS. dīkṣāy°) havir āgachatam naḥ KS. TB. ApŚ. All mss. and ed. of KS. read so; but it seems that it must be an error for dīkṣay°.

ã yat tṛpan maruto vāraśānāh (MS. onah) RV. TS. MS. KS. The originally plural epithet is transferred to a singular noun in MS.

pra candramās tırate (TS†°tı, AV.†°mas tirase) dīrgham āyuḥ RV. AV. TS MS. KS N Nom. voc.

bhaga eva bhagarān astu devāh (AV † devah) RV. AV. VS. TB. ApMB. devāh voc. pl.; devah (lect. fac.) nom sing. Ppp ms. devāh, wrongly emended to devah by Barret JAOS 35. 88.

namah kṛṭṣṇāyatayā (VSK 'yatāya)... VS. VSK. Others, §311. Metathesis of quantity in VS, which simulates an instr. fem. but is really uninterpretable

tvām (TB. tvam) rāya ubhayāso janānām RV. MS. KS. TB. The construction is changed; both realings are construable.

5 Non-final a:ā lexical and miscellaneous.

§508. In a considerable group of cases forms with the prepositional prefix \bar{a} vary with forms beginning in short a, of different origins; cf. the cases of \bar{a} and a privative, §§469 ff. First, cases in which the short a is the augment:

vedhām aśāsata (SV. medhām āśā°) śriye RV. SV.†

- āganma (AŚ ag°) vrśvavedasam VS ŚB AŚ
- āganma (SV ago) vrtrahantamam RV SV AA SS
- ürdhvo adhvaro asthāt (VS SB 'dhvara āsthāt, KS 'dhvare sthāh, ApS adhvare sthāt) VS MS KS SB ApS
- agnaye samıdham āhārşam (ŚG GG ahārşam) AG ŚG SMB GG PG HG ApMB
- yad gharmah paryavartayat (MŚ paryā°) TB ApŚ MŚ
- ājagan rātrī sumanā iha syām AV SPP , Berlin ed ajagan, with slight ms authority, some mss ājāgan, see Whitney's note on AV 19 49 3
- §509. Other cases involving presence or absence of the preposition \bar{a} , before forms in short a
- āgne (RV. agne) yāhı sušastibhıh RV VS TS MS KS SB
- aryamāyāli vrṣabhas tuviṣmān TS · āryamā yāti vrṣabhas turāṣāt MS KS patho anaktu (AV KS °ti, TS patha ānakti) madhvā ghṛtena AV VS TS MS KS.
- äsmāsu (KB as°) nŗmnam dhāt (KB dhāh) MS KB TA ŚŚ kāny antah puruse arputānı (AŚ °sa ār°) VS AŚ ŚŚ LŚ
- tāny antah puruṣe arpıtām (AŚ Vait °ṣa ār°) VS AŚ ŚŚ LŚ Vait yasmın sūryā ārpıtāh (KŚ †TB TA ar°) sapta sākam AV KŚ TB TA ındram yajāe prayaty ahvetām (TB Conc āhv°, Poona ed ahv°, comm. ahv° with v l āhv°) VŚ TB
- agnaya upāhvayadhvam Vait : agnır me hotā sa mopahvayatām SMB agne gṛhapata upa mā hvayasva KS ApŚ MŚ In Vait $upa + \bar{a}$ [antarıkşam (VS ān²) pṛthwīm adṛnhīt VS TB But Poona ed of TB $\bar{a}n^{\circ}$, which is clearly right]
- §510. The pronouns asmat 'from us' and asmāt 'from him, it' exchange:
- kṛtam cid enah pra mumugdhy (AV. TS* mumul.tam) asmat (KS asmāt) RV. AV. TS MS KS
- praty auhatām (MS ūh°) asmnā mṛtyum asmāt (AV asmat) AV VS TS KS MS TA
 - §511. The rest are miscellaneous.
- vratam ralsanti viśvahā AV · vratā raksante viśvāhā RV Probably both forms are adverbial (not compounded with -ahan), and the penultimate vowel lengthened in the RV form for some obscure reason, cf śivā viśvāhā (°ha) etc., §477.
- ye te panthāno bahavo janāyanāh AV. ye te 'ryaman (KS arya°) bahavo detayānāh TS MS KS † 10 13a jana-ayana deva-yāna But rhythmic or metrical considerations may be involved here

- gharmam pāta vasavo yajata (TA. °tā, see §448, MS °trā) vāļ (MS vct, TA vat) VS MS SB TA vat, vāļ, or veļ, a meaningless sacrificial exclamation
- āhalag (MS ah°, TS TB āhalam, KSA ahalam) iti vañcati (TS. TB sarpati) VS TS MS KSA SB TB An onomatopoetic interjection All texts may intend āh°, since the vowel is fused with a preceding final-ā, comm on VS TS āh°, pp of MS, to be sure, ah°, in default of comm or pp there is no evidence as to which KS intended
- ainārasya parah putrah SB āhnārasya parasyādah SS Proper names of barbaric appearance and unknown relationships
- śatakṣaraś chandasānuṣtubhṣna ApŚ śatākṣarachandasā jāgatena Kauś The Conc suggests śatākṣ° in ApŚ, but probably wrongly, Caland, 'der hundertstromige' (sruva).
- agdhād elo . samasanād ekah TS . adhvād elo . . sanād ekah sanā-sanād ekah MŚ See §181
- agnaye tvā mahyam āyur (MS mayo) dātra edhī VS VSK MS SB SS — Near-synonyms
- ankankam (MS ankav-ankam, so p p, KS ankankam) chandah VS TS MS KS SB The curious shortening in KS seems secondary, and may be related to the fact that two consonants follow (Prakritic shortening) Cf §362
- āpiye (AV apriye) sam nayāmasi RV. AV See §878
- vātajavair (HG vātājirair) balavadbhir manojavaih MS HG. See §268 gāva upāvatāvatam (SV upa vadāvate) RV SV See §60
- āntrīmukhah HG ālikhann . . hantrīmukhah PG. See §386 visvakarman bhauvana mām didāsitha (ŚB manda āsitha) AB ŚB. ŚŚ. See §840
- §512. Finally, a few cases with readings which are dubious or clearly erroneous.
- pra smā mināty ajarah RV KS · prāsmā minoty ajarah ApŚ We cannot interpret prāsmā, unless as prā (for pra) smā (for sma). In that case the writing of the two words together is merely an editorial error, and the variant should be added to §439
- nīlāgalasālā AV. 6 16 4c nīlagalamālah swah pasya NīlarU. 22b The true reading of NīlarU. 1s certamly that of AV, see Jacob's Concordance s v, two mss and the comm read so, and the comm quotes AV 6 16 4
- aśīrṣānā ahaya (SV. °ṣāno 'haya) wa RVKh SV: aśīrṣāna wāhayah AV But we must read in RVKh as in SV, with Scheftelowitz (p. 106).

- agnis ca dahatam prati AV. SV. Misprinted āgnis in AV, see Whitney's note
- airā (AV taira) yamah sādanā (TA. onāt) te minotu (AV krnotu) RV AV TA. Cone sadanā for AV
- asmān devāso 'ratā (Cone. 'rata) haveşu AV † And others, all with avatā
- ā na 111do satagrinam (SV. misprinted sāta") RV SV. See Benfey's Corrigenda
- arrān (GB āriān) chi somakāmam tiāhuh GB etc Gaastra correctly arrān
- tière detā udīcyām tu abhişiñcantu (error for °cyām tvābhi°) ércyase Rvidh . udīcyām tiā diét viére devāh . . abhişiñcantv AB.
- jāmim (KS teami) mā hinsīr amuyā (MS anu yā) sayānā KS TB MS mā jāmim mosīr amuyā sayānām AV The KS (one ms only) must certainly be emended to jāmim
- paramāna ridharmani RV SV Once misprinted paramānā in SV corr Benfey's Corrigenda
- frarşāharam sama gāya (correct Cone) MS SB MS prastolar vārşāharam sama gāya ApS


VARIATIONS BETWEEN SHORT AND LONG CHAPTER XII I AND U

\$513. In contrast to the $a\bar{a}$ variants, those between i and \bar{i} and between u and \bar{u} are both fewer in number and more miscellaneous in In particular they show relatively little clear evidence of the rhythmic lengthening which was so prominent a feature of the last This is perhaps partly due to the fact that variations between $i \bar{i}$ and $u \bar{u}$ as finals of noun stems are more often matters of morphology To put it otherwise, there is great confusion in the Vedic language between the short and long z and u declensions, and only occasionally can such variation be plausibly attributed to rhythmic or other phonetic On the other hand, these variants show a rather noteworthy number, proportionately speaking, of cases of 'phonetic' shortening of an $\bar{\imath}$ or \bar{u} historically long. By this we mean a shortening which seems to have no justification in any known morphological category or any analogical influence - See §§300-2 for variations between ī, ū, and short z, u, plus nasal, and §§395-8 for the like before single and double consonants

1 Final short i lengthened phonetically

§514. We begin with cases in which final ι , originally short, is lengthened, apparently as a matter of straight phonetics. As in the case of a \bar{a} , we include not only absolutely final \imath , but \imath in the seam of compounds, before the suffix vant, and in the reduplicating syllable the last, nearly all the cases concern prepositional adverbs in final ? §515. The variants do not conform very well to the general principles established at the beginning of Chapter XI, except that the following syllable regularly begins with a single consonant, and that as a rule they do not occur at the end of a pada (On the one exception to this last, see §518) The syllables surrounding the variant syllable are as apt to be long as short A majority of the variants are prose, of the metrical ones, about half have the variant syllable as the second of the Only in one case can the lengthening be said to be required by the meter (obhe aprā rodasī vi [vī] sa āvah, §516). There seems to be a special tendency for \imath to be lengthened before v, but also before r and

sibilants (cf §464, and Wackernagel I §§38, 41).



§518. The only other absolutely final $i\bar{\imath}$ concerns the imperative ending dhi, which appears sometimes as $dh\bar{\imath}$, probably under the same general conditions as final \bar{a} for a in verb endings. It happens that almost no variants of this sort occur; we may note that in the pāda: $sa\ no\ bodhi\ srudh\bar{\imath}\ havam\ RV\ VS\ MS\ KS\ SB\ ApS\ several mss of MS. read <math>srudh\bar{\imath}$, but the printed texts are all alike. The single variant noted is, in fact, not recorded in the Conc. Strangely enough, the variant syllable is at the end of its pāda, where rhythmic lengthening is generally not allowed. The following pāda begins with havam, and it has been plausibly suggested by Benfey ($Quant\ II\ 51$), and approved by Oldenberg ($Proleg.\ 421$), that the lengthening in RV. is due to the common cadence $srudh\bar{\imath}\ havam\ (cf.\ RVRep\ 673, top)$. In all texts but one this pāda has $srudh\bar{\imath}\ n$ and that one (AS) is the only one in which the word $havam\ does\ not\ immediately\ follow\ (the pāda\ being\ quoted\ in\ isolation\ there).$

ımam me varuna śrudhī (AŚ śrudhı) RV SV. VS TS MS KS AŚ. ApMB.

§519. Next we find three cases concerning the reduplicating syllable. The lengthening here is doubtless rhythmic, except in the first variant where it is obviously secondary and late (occurring before two consonants, the only case of this kind among the phonetic lengthenings of i).

ımam agne camasam nıā vı jıhvarah (TA jī°) RV. AV. TA AG.

yıyapsyata (AS yz°) wa te manah (AS mukham) AS SS Desiderative from yabh, the form with yz° is not recorded lexically nor in Whitney's Roots

udgrābhenod ajigrabhat (KS ajīgrabham and ajīgrbham) MS. KS.

§520. There are two cases of apparently rhythmic lengthening of \imath before the suffix vant

mādhyamdīnasya savanasya nīskevalyasya bhāgasya šukravato (ApŚ adds manthīvato) madhuścuta (KŚ* manthīvata, v. l manthī) indrāya (MṢ savanasya śukra° manthīvato nīsk° bhāgasyendrāya). . KŚ (bis) ApŚ MŚ Stem is manthīn (weak manthī) + vant.

paramesihī ivā sādayatu . rašmivatīm (MŚ rašmī°) MS KS.

§520a. In one case $\bar{\imath}$ is required in composition with a derivative of the root k_T , while the \imath -form (otherwise textually dubious) may possibly represent an $\imath n$ -stem before $c\bar{a}rin$:

ıma udvāsīkārına ıme. .TB ApŚ ımā uddhāsıcārıņa ıme...MŚ. Cf §59

§521. And finally, a single case of a noun compound, with what looks

like genuine rhythmic lengthening of \imath as stem final of its first member: $y\bar{a}$ te agne harisayā (VSK harī°, MS MŚ. harā°) tanūr varşişļhā gahvareşļhā VS. VSK ŚB. (Pratīkas MS MŚ.)

- 2 Final i in the seam of compounds shortened phonetically
- §522. No wholly satisfactory formulation of the circumstances of this not uncommon phenomenon has yet been attained. We cannot improve on Wackernagel II 1 §56 e-g (cf also Leumann, Gurupūjākaumudī 13 ff). It seems most likely to have been dependent originally on the opposite conditions to those which caused rhythmic lengthening, that is, to avoid a succession of long syllables, ī was shortened before two consonants and between long syllables. The variants are on the whole favorable, or at least not unfavorable, to this hypothesis
- §523. Radical $\bar{\imath}$ is shortened in the word $sen\bar{a}n\bar{\imath}$, not only in composition but in case-forms (below, §527), the following group of variants occurs all in one passage, where TS alone has the shortening:
- tasya rathagrisaś (KS 'krisaś, MS °krisnaś) ca rathaujāś ca senānīgrāmanyau (TS senām°) VS TS MS KS ŠB And so with tārkṣyaś cārɪṣtanemiś ca, senapic ca susenaś ca, rathaprotaś (TS rathe°) cāsamarathaś ca, rathasvanaś ca rathecitraś ca
- §524. The other cases concern the feminine nouns $prthiv\bar{i}$ and (once) $prapharv\bar{i}$.
- yā devy asīstake prānadā prapharvīdāh (ApŚ °vndāh) KS ApŚ namo 'gnaye prthivikṣite lokasprte (ChU prthivīkṣite lokakṣite, MU prthivīkṣite lokasmrte) TS KSA ChU. MU.
- pṛthiviṣadam (MS pṛthivī°, VS † °sadam) tvāntarikṣasadam (VS †adds divisadam devasadam) ... VS. TS MS KS ŚB TB

pṛthivispṛñ (MS pṛthivī°) mā mā hinsih MS TA

ye devā divibhāgā ... ye pṛthivībhāgās (TS KS pṛthivī°, but 2 mss of KS °vī°) TS MS KS

svadhā pitrbhyah pṛthimṣadbhyah (MŚ GG pṛthinī°) AV ApŚ MŚ Kauś GG HG

3 Miscellaneous final 17

§525. There is very little else On na ced avedī (avedī) etc, see §530 below, it does not belong here except by grace of Boehtlingk's emendation, which is not justified Otherwise we have noted only a few stray cases concerning noun declension, which really belong later and are placed here only because both forms happen to have final z or ī.

agne tvam sūklavāg asy upašrutī (MS. °ir, TB °śrito) divas (TB divah) prthivyoh MS SB. TB AS. SS The form is locative of an i-stem:

MS is anomalous (or possibly felt as a sort of neuter accusative adverb?)

ado (MŚ ato, AV ado yad) devī (AV. KS devī) prathamānā prthag yat (AV. °mānā purastāt) AV KS. ApŚ. MŚ Nominative and vocative

stomatrayastrınse bhuvanasya patni TS KS AS: stomas trayastrınse bhu° patnī MS As prec see §818

sam devi (KS devī) devyorvasyā...TS KS ApS

rātrı (TB rātrī, v. l of KS rātrıh) stomam na jıgyuşe (KS † TB °şī) RV KS TB

satyād ā (ApŚ satyā tā) dharmanas patī (Vant MŚ pari) AŚ Vant ApŚ. MŚ

aświnendram na jāgrin (TB° vī) VS MS TB. The -vī form is a dual adj, and so Mahīdhara takes the -vi form also; but possibly it may be a neut sing adverb

gāyatrī (MG °trī) chandasām mātā (MG mōtah) TA. TAA MahānU. MG Nom: voc

na sīsarīdata (HG † sīsarīdatah) ApMB HG See §384.

4 Noun stems in 1 7

§526. It is well known that the division between short and long *i*-stems is lax, many words slip over from one category to the other sporadically or even frequently, and in some cases it is hard to be sure to which they originally belonged Practically all the variants in this division concern such fluctuations Little evidence for rhythmic influence can be discerned

§527. We begin with cases where the original is certainly or probably $\tilde{\imath}$ First, a case of the stem $sen\bar{a}n\bar{\imath}$, where the root $n\bar{\imath}$ 'lead' guarantees the original length of the vowel In §523 we have seen that the shortening occurs also in composition:

namah senābhyah senānībhyas (VS TS °nıbhyas) ca vo namah VS TS MS KS

§528. In the same context occurs the following variant Boehtlingk takes the form in short \imath from a stem $\$van-\imath n$ 'having dogs', while he derives the other from $\$va-n\bar{\imath}$ 'leading dogs', this seems improbable in the light of the variants, both are probably from $\$va-n\bar{\imath}$, with (possibly rhythmic) shortening in the one case (so Mahīdhara, followed by Griffith and Keith).

namah śvanibhyo (MS śvanī⁵) mṛgayubhyaś ca vo namah VS MS KS: namo mṛgayubhyah śvanibhyaś ca vo namah TS

Other cases of probably original ī are

sucakşā aham akşībhyām (MG akşı°) bhūyāsam AG PG MG N The ī-form is regular in the older language Wackernagel III p 303

varūtrīm (KS † varu°, TS, varūtrīm) tvastur varunasya nābhīm VS TS KS ŠB tvastur varutrīm va° nā° MS MŠ

rātrīm-rātrīm (AV TS rātrīm-rātrīm) aprayāvam bharantah AV TS MS KS SB

rālrım (KS rātrīm) jinva TS KS PB Vait

rātrīm (TS rātrim) pīvasā TS KSA

šam rātrī (VS rātrīh, VSK TA rātrıh) pratı dhīyatām AV VS VSK MS TA

rātrım (SMB PG MG °rīm) dhenum wāyatīm (AV upāyatīm) AV HG APMB SMB PG MG

ye rātrım (KS °rīm) anutışthantı (KS † °şthatha) AV. KS

pratı tvā parvatī (TS TB °tır, MS KS MS pārvatī) vettu VS TS MS KS. SB TB MS See §490

veşaśrīr (TS° śrir) asi TS KS GB PB Vait LS

mahīnām (VSK mahınām) payo 'sı VS VSK TS KS ŚB KŚ ApŚ MŚ ŚG Even from the stem mahı, the VSK form would be anomalous

hrādunībhyah (KSA °nıbhyah) svāhā VS TS KSA This is uncertain, both short and long i are otherwise known RV has hrādunim, but hrādunī-vrt See also dūşīkābhir hrādunim etc., \$543

śimībhih (KSA † śimi°, VS śamī°) śimyantu (VS śam°) tvā VS TS KSA §529. But in the rest stems in short i seem to be primary.

svāhākrtībhyah (TS ApŠ and most mss of MŠ °krtī°) preṣya TS ŠB KŠ ApŠ MŠ "To hail-makings", suffix ti

ayāś cāgne 'sy.anabhiśastiś (AŚ ApMB HG °tīś) ca MS KS AŚ ŚŚ KŚ ApŚ Kauś ApMB HG Suffix ii, as in the last

ākūtım (SMB °tīm) devīm manasah (SMB °sā, AV subhagām) puro dadhe (SMB prapadye) AV TB SMB As prec

ātır (TS KSA ātī) vāhaso darvıdā te vāyave (TS KSA vāyavyāh) VS TS MS KSA ātı is Rigvedic

abhıştır (HG °tīr, ApMB abhısrīr) yā ca no grhe (RVKh ca me dhruvā) RVKh ApMB HG

diva (divas, divah) skambhanir (VS SB $^{\circ}$ nīr, VSK † skambhany) asi VS VSK TS KS SB TB ApS Here fem gender is responsible for the long $\bar{\imath}$

śirah-śirah prati sūrī n caşte TS ApŚ śiro devī prati sūrir n caşte KS Here too sūri is made fem, agreeing with a fem entity śronibhyām (TS. śroni°) srāhā TS KSA yakşmam śronibhyām (ApMB °nī°, v 1 °ni°) bhāsadāt RV. ApMB : yakşmam bhasadyam śronibhyām bhāsadam AV

mitrārarunau śronibhyām (TS śroni^o) TS. KSA

sam methur (ApMB sam te methī) bharalu sam yugasya tardma (ApMB, trdma) AV. ApMB

rtun prssibhth (KSA em prssibhth, ms bhr°) TS KSA Ci. Macdonell and Keith, Vedic Index 2 358 f.

prstībhyah (KSA † prsti°) srāhā TS. KSA

imām khanāmy osadhim (ApMB "dhīm) RV. AV. ApMB

osadhibhyah MG · osadhibhyah SG.

kraică varisțham vara âmurim uta RV: kraice vare sthemany âmurim uta SV.

- sam arir (VS SB arīr) rīdām (KS rīdah) VS MS KS SB Nom sing of stem arī; the anomalous VS SB. form is noted in BR, s. v. 2 arī
- adhā jurī (AV. atha jurīr, ApMB athā jūrī) rīdatham ā radūcī (RV. radāthah) RV AV. ApMB Stem jurī (or, with most mss of AV., jūrī). RV. has a dual form; ApMB an isolated sing. from a stem in ī, perhaps due to confusion between the RV. and AV. forms. On the ī of the initial syllable see §544

plāśır (TB °śîr) ryaktah śatadhāra utsah VS MS KS. TB.

ambā ca bulā ca nītatnī. . MS · ambā dulā nitatnir . . . TS,

apo mahi vyayatı cakşase tamah RV: apo mahī vynute cakşuşā tamah SV TB. Here we have a complete change of construction, in addition to (or perhaps rather than?) a change of stem-form

rs te bhinadms takarīm (KS° rsm, AVPpp [Roth] tagarīm, AV mehanam) AV TS KS ApS. See §49 There is no way to determine the original quantity of the z here

§529a. There are also cases in which a nom. sing in $\bar{\imath}$, apparently from a stem in in, varies with one in in from a stem in in:

vyānasīh (SV. °šī) pavase soma dharmabhih (SV dharmanā) RV SV. tan no dantī (TA. °tih) pracodayāt MS TA MahānU Comm on TA. mahādantah

durehetir ındrıyāvān (PB†°yavān) patatrī (PB.°trıh) TS PB TB PG ApMB · dūr° patatrī vājınīvān MŚ. MG

suparno anyather (SV. othe) bharat RV SV

§530. In one variant there is multiple confusion, involving also verb forms:

na ced avedī (BrhU avedi) mahatī vinastih ŚB BrhU. So Conc, with

the printed texts But avedi is only Boehtlingk's emendation; mss avedī The Kānva recension, however, has avedir, and Kena Up (not in Conc) avedīn, a verb-form ('if he has not known [this, it is] a great disaster') avedir would be nom sing of a noun stem avedi 'if not, (there is) ignorance, a great disaster' avedī is taken by comm as nom sing of avedin. 'if not, (he is) ignorant', etc These are surely enough variants, without Boehtlingk's additional one!

- 5 Verb forms containing i \bar{i} and i \bar{i} in the second syllable of dissyllable bases
- §531. This variation occurs in a considerable number of miscellaneous cases in the inflection of the verb, oftenest in root or stem syllables, in which may be included the second syllable of dissyllabic bases. Among the latter we find cases which may plausibly be interpreted as rhythmic or at least phonetic in character. We include with them also nouns which show the same shift in the second syllable of dissyllabic bases, since they are of the same phonetic character:
- suśami śamīşva (TS TB śamişva, KS †śamiāşva) VS TS MS KS TB avanty asya pavīlāram (SV. pavi) āśavah RV SV The shortening of SV. improves the meter (anapest after cesura)
- §532. The next two concern noun forms which may possibly contain dissyllabic bases in their first elements, but they are very obscure.
- antarıkşam purītatā (TS puri°, MS puli°, KSA puli°) VS VSK TS MS KSA
- ulo halikṣno (TS ūlo halī°) . VS TS MS KSA Name of some anımal A theory as to the origin of this ī in Wackernagel, I §39 note
- §533. At least in origin, the *i* of the *i*s aorist represents likewise an IE schwa, the second syllable of dissyllabic bases. For well-known phonetic reasons, it is regularly long in the 2d and 3d persons singular, short in the rest of the inflexion. When we find divergences from this scheme, they are to be regarded as analogical extensions in one direction or the other, of VV I p 189.
- tena (TB. tato) no mitrāvarunāv (MS °nā) avislam (TB avī°) RV MS TB The root av is undoubtedly dissyllabic in origin. The ī of TB is due to the analogy of singular forms like avīt. So in the next
- amīmadanta pitaro (Kauś also patnyo) yathābhāgam () āvrīsāyisata (AŚ °yīṣata) VS VSK ŚB AŚ LŚ Kauś SMB GG KhG Cf prec

- mā tvāgnīr dhvanayīd (TS "yīd, KSA "yed, MS. dhanayīd) dhūmagandhih RV VS TS MS. KSA. This is the converse of the preceding; TS shortens the vowel by analogy with dual and plural forms
- ata ü şu madhu madhunābhi yodhi TS · adah su madhu madhunābhi yodhih RV AV SV AA MS On the anomalous TS form see VV I p 27
- ā gharmo agnım tlayann asādı (TA °dīt) RV. TA: ā gharmo agnır amrto na sādı MS See VV I §84
- §534. Probably rhythmic in character is the $\bar{\imath}$ which varies with \imath in denominative stems before the ya-sign, cf. VV I p 155, and above §478 where the same shift occurs between a and \bar{a} :
- putrīyantah (AV putriyanti) sudānavah RV. AV SV
- janīyanto nv (AV. janīyanti nāv) agravah RV SV AV. AS. ŠŠ
- §535. In some cases we seem to have rhythmic or metrical lengthening of i in stem syllables, at least it occurs in positions where the meter favors a long
- prati şma (SV sma) deva rīşatah (SV rış°, and sopp. of RV. and MS) RV SV MS KS TB The pp readings confirm our opinion that the ī is metri gratia
- avāmba (VS SB KS ava) rudram adımahı (VS SB KS adī°, and so v l of MS KS MS, and p p of MS) VS TS MS KS SB TB KS ApS MS
- §536. But the same shift in root or stem syllables occurs in some cases where it cannot be rhythmic, the explanation varies and is sometimes obscure.
- sarvān patho anṛnā ā kṣīyema (AV. kṣī°) AV TB TA ApŚ The root ksī 'dwell' here presents an exceptional form with ī, perhaps under the influence of the other root kṣī 'perish', from which ī forms are familiar
- yūpāyocchrīyamānāyānubrūhi (MŚ °chriya°) ApŚ MŚ Here the ī, in the passive of śri, is regular, and is probably to be read also in MŚ with most mss
- samīngayatī (ŚB samī°) sarvatah RV ŚB BrhU The root ing appears sporadically as īng in the Brāhmanas, the true reading of BrhU is samīng° in this passage (text emended)
- §537. Jumbled participial forms of the parallel roots ji and $jy\bar{a}$, $j\bar{i}$ and $jit\bar{a}h$ (TA ajītāh, ApMB and one ms of HG ajītā) syāma śaradah śatam TA ApMB HG
- vājino vājajito vājam sasīvānso (KS jigīvānso, TS sasīvānso vājam jigīvānso) . VS TS KS SB

- §538. We have classified the form $\bar{\imath}y\bar{a}na$ 'going', as a reduplicated present from root i; see VV I p 126.
- ıyānah (SV īy°) kṛṣno daśabhıh sahasraıh RV SV. AV KS TA stotṛbhyo dhṛṣnav ıyānah (SV īy°) RV. AV SV.
- §539. The participle $\bar{\imath}d\imath ta$ appears as $\imath d^{\circ}$, probably under the influence of the nouns $\imath d$, $\imath d\bar{a}^{\circ}$
- īdīto (MS KS. id^o, VSK. īl^o) devair harīvān abhişļih VS VSK MS KS
- §540. The present and past passive participles of root *kşi* 'perish', *kşinat* and *kşīna*, are concerned in the following:
- namo whṣinatkebhyah (TS KS wkṣīnak°) VS TS KS ŠB. nama ākṣinakebhyah MS If MS. is right it has a blend of the other two readings, but the mss vary, and it is likely that ākṣīnak° was intended

The 3 plur perfect ending tre appears once as tre:

tāh prācya (Vait. °yah, MŠ prācīr) ujjigāhire (KŚ † °īre, Vait samjigāre) KŚ Vait. MŚ: prācīś cojjagāhire ApŚ

6 Noun suffixes containing i ?

§541. Twice in MS the suffix iya, representing ya after two consonants, appears as iya; but both times the p p. of MS has iya:

namo agrīvāya (VS KS 'gr
yāya, MS 'grīvāya) ca prathamāya ca VS TS MS KS

sahasrıyo dyotatām (TS TB. dīpyatām; MS sahasrīyo jyotatām) aprayuchan VS TS MS KS SB TB.

§541a. We have quoted in §249 (q v.) three variants in which AV. reads varīyah for older varwah:

asmabhyam ındra varıvah (AV. varīyah) sugam kṛdhi RV. AV.: asmabhyam mahı varıvah sugam kah RV

sakhā sakhībhyo varīvah (AV. *varīyah; so one ms of GB; Ppp. varīvah) krnotu RV AV *TS KS. GB

tvaslā no atra varīvah (AV varīyah) krnotu AV. TS

§542. Several times forms in *ina* vary with other forms containing short :

yā sarasvatī vešabhagīna (ApŚ.* vršobh°, KS vešabhagīnī)... MS KS ApŚ -bhagīna, from bhaga, seems to be found only here; KS substitutes a more regular form (fem of bhagīn).

tırascırājē (MS tirascīnarājī) rakstā AV MS Again īna varies with in (weak stem i)

namo yuvabhyo nama āśinebhyah RV ApS: namo yuvabhya āśinebhyaś

- (MS \tilde{ast}° , pp \tilde{ast}°) ca vo namah (MS namo-namah) MS. KS. \tilde{asina} is $\tilde{a\pi}$ $\lambda\epsilon\gamma$ in RV, in MS it seems to be secondarily adapted in form to words in $\tilde{\imath}na$
- §543. The shortening of $\bar{\imath}$ to \imath before suffixal ka may properly be classed with rhythmic shortenings Cf Edgerton, JAOS 31 95 f , 111 $d\bar{u}_{\bar{\imath}}\bar{\imath}k\bar{a}bhii$ $hr\bar{a}dunim$ (KSA † hra°) TS KSA . $hr\bar{a}dun\bar{\imath}r$ $d\bar{u}_{\bar{\imath}}ik\bar{a}bhih$ VS MS

7 Miscellaneous 1 and 2

- §544. Here, first, a few variants which seem to concern what are fundamentally related forms, one being usually more or less suspicious: $\bar{\imath}mk\bar{a}r\bar{a}ya$, and ${}^{\circ}krt\bar{a}ya$ (KSA ${}^{\circ}m$, VS MS SB ${}^{h\imath m}$) VS TS. MS. KSA SB TB ApS
- īryatāyā (TB 11°) akstavam VS TB From the equivalent adjective forms 1170 (RV) and īrya, doubtless ultimately the same, tho the etymology is doubtful (cf Neisser, ZWbch. d RV, s v. 1170)
- ustārayoh pīlvayoh (ApS pilvayoh) MS ApS MS Cf the word pilu or pīlu, name of a tree Obscure
- vīdvīr yāmann avardhayan VS vidvīr yāman vavardhayan TB Comm on TB drdhasaktayah, that is equivalent to vīdu, for which vidu is not recorded
- adhā nvrī (AV atha nvrī, most mss nrvī, which Whitney would restore; ApMB athā nvrī, vidatham ā vadāsī (RV vadāthah) RV. AV ApMB Various theories connect the obscure word with either yyā(n) or nv. The ī in the first syllable in ApMB is isolated and no doubt due to popular etymology, thinking of nv or of the ī forms of jyā or nr (nīra etc) See §529
- anamīvāsa idayā (MS anamīmāsā īdayā, p p idayā) madantah RV MS. TB AS The MS form is probably a mere corruption (due to thought of īd? of the lexically quoted īdā), corrected in p p
- dame-dame sustutyā (TS ° tīr, MS °tī, AS ŠS °tɪr) vāvṛdhānā (AV ° nau, AS ŠS vām vyānā) AV TS MS KS AS ŠS Different case forms of an *i*-stem See §236
- śanderathaś śandikera ulūkhalah ApMB . śāndīkera (PG śaundikeya) ulūkhalah HG PG See §489
- §545. The rest are more definitely lexical in character, but even they occasionally show traces of phonetic relations, thus in the first:
- subhūtāya pīpihi (MS prpīhi) MS TA. ApŠ And others, with ise, ūrje, hrahmavarcasāya, etc In MS always pipīhi, probably from pā 'drink', while pīpihi is from pyā(pī) 'swell' The result, how-

- ever, gives the semblance of a mutual (quasi-rhythmic) shift of quantity; cf $\,$ VV I p $\,$ 182
- sarasvatī tvā maghavann abhışnak (TB ApS abhīşnāt) RV AV VS MS KS TB SB. ApS See §142
- sudītir asī TS PB: sudītir asī KS GB Vait: sudītinādītyebhya ādītyān jīnva MS Boehtlingk: sudītī Anklang an Adītī, sudītī glanzvoll (dī) Sudītī is Rigvedic
- vršvam 1d dhītam (MS dhītam) ānašuh (SV. āšata) RV AV SV MS Ap\$ Roots dhī and dhā
- tıgmam äyudham (AV anīkam) vīdıtam (AV vıdıtam, KS °dham īdıtam) sahasvat AV TS MS KS See §169
- kavır yah putrah sa $\bar{\imath}m$ \bar{a} (TA sā $\imath m\bar{a}h$, Poona ed sa $im\bar{a}$) cıketa RV AV TA N
- ali vā (AV Kaus atīva) yo maruto manyate nah RV AV Kaus Metathesis of quantity
- śam padam magham †rayīşine na kāmam (AA rayışanı na somah) SV AA rayı-ışın· rayı-san (so Keith, or, -sanı)
- ghasinā (ApŚ ghasīnā) me mā sampṛkthāh VSK ApŚ Corruption in ApŚ, perhaps for ghāsinā (RV ghāsī), with metathesis of quantity? Cf Caland's note
- ā yāhi śūra haribhyām (SV KB ŠŠ hariha, AŠ harī iha) AV SV KB AŠ ŠŠ Doubtless read, in all except AV, harīha (=harī iha), with Whitney on AV and Keith on KB
- gaurīr (TB TA °rī, AV gaur ın) mımāya salılānı takşatī RV AV KS TB ApS SMB MG.
- ındrāpāsya phaligam ApMB ındrāyayāsya sepham alīkam HG See §46
- samıddho agnır vrşanāratır (AV °nā rathī, ŠŠ °nā rayır) dıvah AV AB AS SŠ
- rādhānsīt (MS MŚ °si) samprcānāv (MS MŚ °nā) asam° MS ŚB KŚ ApŚ MŚ
- nen na rnān rnava it samānah FA nem na rnān rnavān īpsamānah MS And others, sec §180
- [alikiritam (comm oritam) atidanturam TB So Conc. with Bibl Ind ed, probably misprint, Poona ed comm with text atikiritam]
- [tvañkrīr (so all') asi asya svadhitih sam eti RV VS TS KSA]

8 Final u lengthened

§546 As with the a and i vowels, we include here cases in which the vowel is relatively final, that is, final in its stem as prior member of

compounds, or before the suffix mant, or in the reduplicating syllable. The cases are still less numerous than those of $\imath \cdot \overline{\imath}$, and add nothing further to the subject

§547. Of absolutely final u lengthened to \bar{u} we have noted only four cases, three of the particle u, and one of su All occur before single consonants (once v, twice a sibilant), and in most of them the surrounding syllables are short In only one are both long, but here the original form has short u, and \bar{u} is introduced in a secondary text (MS):

o şu (MS şū) vartta (MS KS varta) maruto vıpram acha RV MS. KS. tam \bar{u} (MS u) sucum sucayo dīdıvānsam RV. ArS TS MS KS

rdam ta ekam para ū (TB † ApS † u) ta ekam RV. AV. SV KS † TB. TA AS ŚŚ ApŚ MŚ (u-ta = uta) On puru: purū, a matter of noun inflexion, see \$555

§548. In the reduplicating syllable the change occurs in reduplicated acrists of root gup; the \bar{u} form is here more usual, and is doubtless a matter of rhythmic lengthening Cf VV I p. 182:

grhān ayūgupatam yuvam AS : grhān (MS grhān) jugupatam yuvam MS MS

prajām me (ApŠ *no) naryājugupah (ApŠ and MŠ. v l °jūgupah) MS KS ApŠ MŠ.

paśūn me (ApŚ *nah) śansyājugupah (ApŚ and MŚ. v. l °jūgupah) MS MŚ ApŚ dhanam me śansyājugupah KS: śansya paśūn me 'jugupas tān me pāhy eva ŚŚ. And others in the same passages ahirbudhnya mantram me 'jugupah (v l 'jū')...MŚ.

§549. There is one doubtful case before the suffix mant

santre tvarbhumate (VS SB tva rbhu°, MS tvarbhū°) VS MS SB TA If MS understands a form of rbhu°, as do the others, we have rhythmic lengthening in it But this would imply anomalous sandhi for MS (see §916), and two mss read svarbhūmate

\$550. In the seam of compounds, we find first several variants of the preposition anu, lengthened to anu. The change occurs before either v or r in every case but one (cf under \$516)

anuroham jinva Vait · anuroho (KS anū°) 'si TS KS GB PB Vait · anurohāya tvā PB Vait : anūrohenānūrohāyānūroham jinva MS (with p p and v. I each time anu°).

anuvrd (KS anū°) ası KS GB PB Vait : anuvrte (KS. anū°) tvā KS PB Vait . anuvrtam jinva Vait : †anūvrtānūvrte 'nūvrj jinva MS panthām anūvrgbhyām (KSA anu°) TS. KSA

- anukāšena bāhyam MS: anūkāšena bāhvyam VS antarenānūkāsam TS KSA.
- §551. Among other compounds, we find several which quite clearly contain rhythmic lengthening of u, in the first two this is the older form, and is shortened in secondary texts
- samdhātā samdhım (MS °dhır) maghavā purūvasuh (TA ApMB and p p of MS puro°, MS puru°) RV AV SV MS PB TA KŚ ApMB
- urūnasāv (TA uru°) asutrpā (AV TA °pāv) udumbalau (TA ulu°) RV AV TA AS
- mıthucarantam (TS mıthuś ca°, KS mıthū°, AV mıthuyā ca°) upayātı (AV abhıyātı) dūşayan AV TS MS. KS
- sındhoh sınsumārah (KSA \dagger sısū°) TS KSA . samudrāya sısumārah VS MS See §305 Whether this is really a compound or not is wholly uncertain
- §552. Aside from one or two compounds where the \bar{u} u concerns noun stem formation or inflexion (§§554 ff), we find further only compounds of su (suyama) and its opposite ku, appearing also as $s\bar{u}$, $k\bar{u}$ (cf also §563).
- brahmanas pate suyamasya (MS s \bar{u} °, p p su°) viśvah \bar{a} RV MS TB The \bar{u} is secondary and not favored by the meter (anapest after cesura)
- suyame me adya ghrtācī bhūydstam svāvrtau sūpāvrtau ApŚ suyame me 'bhūydstam VS ŚB· sūyame me 'dya stam svāvrtau sūpāvrtau MS MŚ
- kuyavam ca me 'kṣītīś (VS °tam) ca me VS MS KS (v l $k\bar{u}$ ° in MS) akṣītīś ca me $k\bar{u}$ yavāś ca me TS

9 Final ū shortened

- §553. Only one variant, concerning the old adverb $k\bar{u}$ 'where?', which appears in SV as ku before a consonant combination, so that it may be regarded as a case of rhythmic, or quasi-Prakritic shortening $k\bar{u}$ stho (read $k\bar{u}$ stho) devāv ašvinā RV ku sthah ko vām ašvinā SV
- küşino (read ku şino) devav asvına Kv ku şınun ko vum asvına S See Oldenberg, Noten on 5 74 1
 - 10. Long and short u in noun stem formation and inflexion
- §554. The words hanu and tanu, compounds of -bhū, and a few others, vary between u and ū forms, in case-forms and in composition hanūbhyām (KSA hanu') svāhā TS KSA TB ApŠ
- nanuonyam (INOA nanu) suana IS INOA ID Apo hanubhyām (TS hanū°) stenān bhagavah VS TS MS KS In this and the prec Tait texts alone have ū, the others u

agne sadakşah satanur (KS.†°nūr) hı bhūtvā TS KS : agnıh sudakşah sutanur ha bhūtvā MS.

 \hat{suraso} ye tanûtyajah (TA. $tanu^{\circ}$) RV AV. TA. Note that two consonants follow the \hat{u} , which opposes the possible theory of rhythmic lengthening

ıyam te yajñıyā tanūh (VSK tanuh) VS VSK SB ApS.

avasyur (VS SB °syūr) ası duvasvān VS. TS' MS KS PB SB SS

śundhyur (VS TS. °yūr) ası märjüliyah VS. TS MS. KS. PB. ŚŚ. Only -yu in RV.

ārādhyai (see §474) †didhişūpatim TB . arāddhyā edidhişuhpatim VS (on the latter see §381)

varenyakratūr (AV. °tur, ApS. īdenyakratūr) aham RVKh AV. ApS. Whitney calls °tūr 'an improvement'. See also §383

vibhūr (PB vibhur) ası pravāhanah VS. TS MS SB. TB PB ApS. MS vibhūr (KSA vibhur) mātrā prabhūh (KSA prabhuh) pitrā VS. TS. MS. KSA. SB TB ApS MS

śambhūr (KS °bhur) mayobhūr abhi mā vāhi svāhā VS. TS MS KS. ŚB. Note mayobhūr even in KS.

ābhūr (VS. TS ābhur) asya nışañgathıh (VS °dhih) VS. TS MS KS samtre tvarbhumate (etc., §549) vibhumate (MŁ vibhū°)... VS MS SB TA

phalgūr (KSA °gur) lohitornī. VS TS MS KSA.

havanasrun (TB hāvanasrūr) no rudreha bodhi RV. TB Comm on TB āhvānasya śrotā san Irregular lengthening of śru in composition

§555. Neuter u stems in the Veda have nom-acc forms, both sing. and plur, in either u or \bar{u}

sa hı purü (SV puru) cıd ojasā vırulmatā RV. SV. Adverbial.

[sam grbhāya purū (TB puru, Poona ed purū-) šatā RV AV. MS KS TB]

Different forms of related stems ayu and ayus.

§556. In the first member of a dual devatādvandva, the \bar{u} may be understood as the dual ending, rather than lengthened stem vowel: $krat\bar{u}dak\bar{s}\bar{a}bhy\bar{a}m$ me varcodā varcase pavasva VS. VSK -SB: $dak\bar{s}akratubhy\bar{a}m$ (sc me etc) TS ApS: $dak\bar{s}akratubhy\bar{a}m$ me varcodāh pavasva MS

§557. The stem dhur regularly appears as $dh\bar{u}r$ before a consonantal ending (Wackernagel III §134c). In the ApS form of the following

variant ur appears before the ending bhih, and conversely in the KS form ur before vocalic endings. Both must be analogical, if textually sound, note that in the 'correct' MS form both dhur and dhur forms Von Schroeder, followed by the Conc, stigmatizes KS dhūro and dhūran (for "am) as corrupt, and Knauer proposes to emend KS on the basis of MS But mechanical form-assimilation may account for all the variants

yathadhuram (KS ms "dhūran) dhuro (KS dhūro) dhūrbhih kalpantām KS MS, vathāvatham dhuro dhurbhih kalpantām ApS

11 Other u v

§558. The remaining variants are so miscellaneous that they seem hardly worth subdividing In verb inflexion there is practically nothing Once TB presents an anomalous uh for the regular 3d plural secondary ending uh, it occurs at the end of a pada, and remains unexplained.

upo ha yad vidatham vānno guh (TB gūh) RV MS TB

\$559. The various forms of the root su, sū, 'beget, enliven' etc. show some confusion as to the quantity of the radical vowel Thus. rasāstah pra suhi (KŚ sūhi, MŚ suva, ApŚ suva pra suhi) AŚ ŚŚ KŚ

ApS MS Both suh and suva are regular forms, and in VV I p 189 it is suggested that suhi is a blend of the two Cf next

ırdhamāsyam prasutāt miryāvatah JB: pañcadasāt prasūtāt miryāvatah Both must apparently be from the same root, of which the regular participle is suita, but suita is recorded otherwise 1 18 has v. l prasūtāt (see Oertel, JAOS 19 [2], 112, 115, delete in Conc. tam ardhamāsam

1st and 2d aorists of bhū.

abhyaşıksı rājābhūm (ApŚ °bhūvam) MS ApŚ abhisikşa rājābhuvam (v 1 °bhūvam) MS

§560. Quite similarly vah (weak stem uh) and ūh are 'in some forms hardly to be separated' (Whitney, Roots), indeed, and meanings Whitney gives some forms (such as passive uhyate) as identical from the Of course they are ultimately variants of each other mā hinsişur vahatum uhyamānam (ApMB † ühyamānām) AV ApMB

Here uh does not fit very well, AV means 'may they not injure the procession as it proceeds' (In ApMB the pple is made to agree with the bride-'as she is being carried off')

samuhyo 'sı vıśvabharāh SS · samūhyo 'sı vıśvabharāh ApS samūhyo Here, contrary to the prec , it is sam- $\bar{u}h$ 'sı vıśvavedā VSK KŠ that is meant, even in SS

phalgunībhyām vy ūhyate ApG phalgunīşu vy uhyate AV Kauś

§561. The present participle of the 'root' ture varies with the related adjective ture:

tūrvan (KS turo) na yāmann elašasya nū rane RV VS TS MS KS

§562. Several times the word varutrī varūtrī, from the dissyllabic root vr 'cover', varies in its two forms.

varūlrīs (vā (KS. varutrīs tvā) devīr viśvadevyāvatīh. . VS. KS SB KŚ: varūtrayo janayas tvā devīr . TS: varūtrī (once, 2 7 6, †varu°, and so v. l in the other passage) tvā devī viśva° MS (bis)

traştur varutrīm varunasya nābhim MS MŚ·varūtrim (VS ŚB °trīm, KS†varutrīm) tvastur var° nā° VS TS KS ŚB

varutrīr avayan KS: varūtrāyas †tvāvayan ApS.

§563. The word sumna or $s\bar{u}^{\circ}$ has been interpreted by some as a compound of su, but can scarcely have been felt as such in Vedic times; yet it is possible that the not infrequent \bar{u} in it may have been due to confusion with compounds of su, which as we saw (§552, cf §547) also appear with $s\bar{u}$:

sumnāya (VS. sū°) nūnam īmahe sakhibhyah RV SV VS TS MS. KS. SB Kauś

dhīrā deveşu sumnayā (AV. °yau, VS sūmnayā) RV AV VS VSK TS MS KS ŚB

The word stūpa, of unknown origin, ordinarily appears in that form; but two variants show that the form stupa was fairly widespread:

vişno (°noh, °nos) stupo (TS. TB. ApŚ stūpo) 'sı VS. TS. MS KS ŚB TB ApŚ MŚ: vişnoh stupah MS. MŚ.

reşmānam stupena (MS stū°, but p p. stu°!) VS MS

§564. The word *ūrva*, on which see last Neisser ZWbch d RV., s v, may be ultimately connected with *uru* At any rate forms which look like derivatives of these two words vary with each other in a confused way which usually suggests textual corruption:

urvīm gavyām parisadam no akran AV : ūrvam gavyam parisadanto agman RV. KS See 846

urv (AS once urvy, once $\bar{u}rvy$) antariksam $v\bar{v}ht$ MS KS SB Vait AS. (bis) ApS MS We might be tempted to see in $\bar{u}rvy$ a phonetic lengthening before r+ consonant (cf Wackernagel I §38), but it is probably only a misprint

ūrva (TB urva) iva paprathe kāmo asme RV †3 90 19c, TB N. Comm. on TB. urva iva, vādavāgnīr īva, connecting the word with aurva, a derivative of ūrva

rudrānām urvyāyām (ApŚ ürmyāyām, ŚŚ omyāyām) . ŚB ŚŚ ApŚ See §228 §565. The word $kuly\bar{a}$ 'stream' is written $k\bar{u}ly\bar{a}$ certainly once, and probably twice, probably under the influence of $k\bar{u}la$ 'bank':

kulyābhyah (TS $k\bar{u}^{\circ}$) srāhā TS KSA. Here the TS comm. takes $k\bar{u}l^{\circ}$ as a secondary adjective from $l\hat{u}la$; but it is probably only an equivalent of kulyā, cf. next. Keith, 'to those of the pools'.

medasah (HG * ājyasya) lulyā (HG kū°) upa tān (AG upainān, SMB abhi tān) sravantu (HG. ApMB kṣarantu) VS AG ŚG Kauś SMB HG ApMB: medaso ghṛtasya kulyā abhinihsravantu MG. Cf also ghṛtasya kulyā(m)... in Conc, and prec Here there can be no question of the precise equivalence of kūlyā and ku°.

§566. The form $p\bar{u}rusa$ for purusa is familiar in all periods of the language, beginning with RV., but is almost if not quite restricted to positions where the first syllable must be metrically long, such as the following variant, where TA Poons ed reads $p\bar{u}^{\circ}$ with v. 1 pu° :

ato (AV. ArS ChU. tato) jyāyāns ca pūruşah (TA. pu°) RV. AV. ArS VS. TA ChU.

§567. Twice the RV writes $\bar{u}gra$ for ugra According to Oldenberg, Noten on 1. 165 6, following an earlier suggestion of Haug's, the \bar{u} would be due to the fact that the syllable has kampa (svarua accent followed by an accented syllable; of Wackernagel I p 293 f) One might think of understanding the particle u plus ugra, but p p hi, ugrah Both pādas occur in the same hymn:

aham hy ugras (RV. \bar{u}°) tacişas tuvişmān RV. MS. KS. TB. aham hy ugra (RV. \bar{u}°) maruto vidānah RV. MS. KS

§568. Other cases concerning different readings of what is apparently the same word or related words.

ūlena parimīdho 'si HG.: ulena pariṣīto 'si ApMB. Followed by. parimīdho 'sy ūlena HG.: pariṣīto 'sy ulena ApMB.: utūla parimīdho 'si PG. The meaning of ula or ūla is unknown. Cf. next.

ulo halikṣno (TS ūlo halī°)... VS TS. MS KSA. Cf. prec Here apparently some animal is meant

godhūmāš ca me masūrāš (TS and KapS masu") ca me VS. TS MS KS Both forms are otherwise known; masūra seems to be commoner

hotā redişad attihir duronasat (VS. dū°, but comm. du°) RV. VS VSK. TS MS. KS AB ŠB. TA. MahānU. KU. NrpU VaradapU. The word dūroņa, for the usual durona 'house', seems to be otherwise unrecorded.

kurkuro nīlabandhanah HG: kūrkuro bālabandhanah (ApMB vāla^o) PG. ApMB The usual form is kurkura, perhaps of Wackernagel I §38 (lengthening before r + consonant). Cf. next kurkurah suhurkurah HG: kūrkurah (ApMB °ras) sukūrkurah PG. Cf prec

kuşmāndāh, °dānı, °dyah, and kuś°, kūş°, kūś°. See §290

mathamava januse bhumanesthah (AV bhuvane", SS bhuma ne") AV. AS. Different but related stems bhuvana and bhūma(n)

ā pūsā civ ā rasu TS : ā pustam eiv ā vasu AV.

āpura stā ŠŠ · āpūryā sthā. TS AŠ

atıkulvam (VSK °külvam) catılomasam ca VS VSK. kulva 'bald', regularly with short u

agnaye dhūnksnā (KSA °kṣā) TS KSA: dhunksāgneyī (VSK °kṣvā° or "ksuā") VS VSK MS. Said to mean a sort of bird; original form and precise meaning unknown

uşo (PB ūṣā) dadṛkṣc (PB dadṛśe) na punar yatīva RV. PB. Conc

suggests reading usā in PB

pūlyāny (ApMB kulpāny) āvapantikā AV. ApMB The latter is secondary if not corrupt (note metathesis of consonants) Cf. §151 §569. The rest concern lexically different words, and are all isolated. except that there are two cases of interchange between the stems uora and ūrdhra.

ugro (HG ūrdhvo, MG. agne) virājann (MG ojam) apa (MG upa-) sedha (AV vrāksva) šairūn (MG šakram) AV. ApMB HG. MG.

ugradhanvā (TS MS KS. ūrdhvadha") pratihitābhir astā RV AV. SV. VS TS MS KS

ud ransam wa yemire RV. SV TS KB'N ürdhvam kham iva menire Mbh

yad annam admı (PranagU agnır) bahudha vırupam (PranagU vıraddham, vv 11 virājam, viruddham) AV TA PrānāgU.

brahmādhıguptah (etc). · brahmābhıgūrtam ... see §742

athā jīvah (KS adhā visitah, VS SB. athaitam, AV. adomadam) pitum (AV annam) addhi prasūtah (TS MS. KS pramuktah) AV VS. TS. MS KS ŠB

aghnyau śūnam (AV. aghnyāv aśunam) āratām RV. AV. śūna 'want': asuna 'unprosperity'

suhutakrtah stha AS subhūtakrta stha ApS

ulem (SV. ūlim) arbhe havāmahe RV. AV SV MS In RV etc ula-īm, in SV acc of ut: But the Samhitas contain no actual variation in quantity of the u vowel, since in all it is fused with a preceding final u

sā brahmajāyā vi dunoti rāstram AV.; sā rāstram ava dhūnute brahmajyasya AV 'Burns up': 'shatters'.

- trīni padāni rūpo anv arohat AV.. paūca padāni rupo anv aroham RV Read rupo in AV, with many mss., comm, and Whitney's Transl udno (AV text ūdhno) divyasya no dehi (AV MS dhātah) AV. TS MS KS ūdhno is a false emendation, withdrawā in Whitney's note Cf §106
- namo vah pıtarah suşmāya (VS SS soşāya, SMB GG KhG sūşāya) VS. VSK TS MS. KS TB AS SS SMB GG KhG Sec §720

CHAPTER XIII QUALITATIVE INTERCHANGES OF A, I, AND U VOWELS

1. Short a and a

§570. The variations between a and i are numerous, but also rather One large group stands out among them as concerning noun suffixes which differ only or chiefly in containing the vowels a and i respectively. These have little phonetic interest. At the opposite pole stands the only other considerable group which appears prommently in this section, namely a i in radical syllables which concern ablaut, or quasi-ablaut That is, the i forms are, or have the aspect of being, reduced ablaut grades corresponding to full-grade forms in a, which vary with them That ir and ur may appear historically in such relations to ar is recognized by all (cf. Wackernagel I §21). Whether the same is true of i in relation to short a (as distinguished from \bar{a}) before other consonants, is a disputed question Cf. Wackernagel I §15 note, where this possibility is denied and the attempt is made to explain otherwise some of the seeming instances

\$571. We shall content ourselves with recording the variants which seem to concern this real or supposed ablaut, it will of course be understood that we do not claim that they prove or disprove either side. We shall begin with one in which an otherwise unrecorded \$ikya\$ appears persistently for the common \$ikya\$ (by which TA comm glosses \$ikya\$) One naturally thinks of comparing \$ikvan\$ and other forms of the sort with \$i\$ (\$ikman, \$ikvas\$); according to Wackernagel (1 c, p 17) \$ikvan\$ would be etymologically unrelated to root \$ik\$, which seems to us doubtful. But the forms in \$i\$ might perhaps be influenced by \$ik\$, \$ik\$ \$ikyah\$ (MahānU \$a^o\$, v 1 \$i^o\$) provācopanisat TA MahānU

A form of siks itself varies with one from sak in

lātum cec chilşān sa (TA chaknuvānsah, or °vān sa) svarga eva (TA eṣām) AV TA See §826

§572. Several variants concern the root or roots sam sim, which certainly are synonymous, but according to Wackernagel (p 18) ultimately unrelated In the variant padas VS uses only sam, TS KS only sim

šamībhih samyantu tvā VS simībhih (KSA †simī°) simyantu tvā TS KSA

kas le gātrāni šamyati (TS KSA śim°) VS TS KSA.

māsā āchyantu samyantah VS: māsās chyantu simyantah TS KSA

śimāh (KSA Conc śimām, ed with v 1 śimāh, VS simāh) krinvantu (VS * śamyantu) śimyantah (VS śamyantīh) VS TS KSA Note that VS denies consciousness of relation between the verb and the noun by reading simāh with s, not ś (comm interprets by sīmā rekhāh)

sūcībhih śamyantu (TS KSA śim°, MS śamayantu) tvā VS TS MS KSA

§573. Next a few variants which either contain or have the aspect of containing ablaut between ir and ar (or ri and ra), cf Wackernagel I §21, but most of the cases are obscure or dubious, only the first is a clearly genuine instance, and there too both forms are familiar, SV has merely substituted a more commonplace synonym (hari) for the old and rarer hiri

hırısmasrum (SV hari°) nārvānam (SV na varmanā) dhanarcam (SV °cım) RV SV

asyai nāryā upastare (ApMB °stire) AV ApMB Infinitive forms, Whitney emends to °stīre with Ppp

śiśirāya vikakarān (KS †vikarān, ApŠ vikirān, vv 11 vikakarān, vikikirān) VS KS ApŠ. Name of an animal, of uncertain form, origin, and meaning

sugantuh karma karanah karışyan JB . sugam tvah karmah karanah karah karasyuh LŠ With karasyu cf. the noun káras, RV?

rudra yat te krayī (VS KS krivi, VSK kravi, MS MŠ giri) param nāma VS VSK TS MS. KS ŠB TB ApŠ MŠ See §47, all the forms are unintelligible

§574. There is a sort of superficial resemblance to these cases in certain verb forms (e g the desideratives mentioned in §583), to be dealt with presently; and ablaut of a different kind (ay for e i) also appears among the verbal variants (§582) Here we shall append a number of variations between words which, while actually of independent origin, simulate the kind of ablaut relation here considered, being usually quasisynonyms and (but for the shift between a and i) nearly or quite homonyms

§575. First, cases in which r follows (cf. §578) Here we find two cases in which pratara, that is pra-tara, a comparative from pra, varies with forms in pra-tir- (verbal or nominal), in which tir is connected with the root tr 'cross' The psychological affinity between this root as commonly used in Sanskrit and the comparative suffix is evident

drāghīya āyuh prataram (TA †pratarām, MG pratiram) dadhānāh (AV. *te dadhāmi) RV. AV. TA AG MG. · dīrgham āyuh pratirad bheşajāni TB.: āyur dadhānāh prataram navīyah AV. Here pratirad is a verb-form (prakarṣena dadātu, comm), pratarām an adverb (comm. prakarṣena); pratiram, if correct, is the Rigvedic mfinitive pratīram, but all but one of Knauer's mss read prataram in MŚ

aganma yaira pratiranta (MG prataram na) ayuh RV, AV, MG

§576. Before other consonants than r (cf. §§570 ff); here might be mentioned, first, the three variants concerning the synonymous roots sam-vas and samus, which are listed in §281 Formally even closer are two variants between k-san 'mjure' and k-si 'destroy', also virtual synonyms'

ındra wārışto akşatah (AV. akşıtah) RV AV.

akşatam asy (SMB omits asy) arıştam SMB SG: akşıtam (akşıtır) ası .. (see §586).

prihivī darvir aksitāparimitānupadastā (ViDh aksatā) ...Kauś ViDh ...yathāgnir aksito...ApMB HG

§577. Other near-synonyms:

yajñam devebhir anvitam (TS TB 1nv°) TS. MS ApS TB †1 4 4.5b 'Accompanied' (anu + 1) 'impelled'

sistle srüge rakşase (AV rukşobhyo) unnkşe (KS unakşe, AV. mss. "nıkşve) RV. AV. TS. MS KS nıkş 'pierce': nas (as if causative) 'destroy'. But no such form of nas is otherwise recorded, and the KS. form is questionable

pavamāno dašasyatī (SV. $di\hat{s}^{\circ}$) RV. SV. Benfey would derive the SV form from stem $di\hat{s}as = di\hat{s}$ (lex, and class in composition).

§578. Since it is impossible to draw a sharp line between these cases and other lexical variants, we shall add here other cases which seem to us purely lexical, concluding with some false-readings or corruptions First, there are a number that concern pronouns (the bases a and i) and particles (ha: hi, etc.):

ato (AV. MahanU. ito, TB tato) dharmanı dharayan RV. AV. SV. VS. TB MahanU.

pūrvo ha (TA. MahānU. hi) jātah (JUB jajñe) sa u garbhe antah VS. TA. MahānU. ŠvetU. SirasU. JUB

rşır ha (SS hı) dirghasruttamah TS MS. KS TA AS. SS.

eşo (TA MahānU. eşa, SırasU. eko) ha (TA MahānU. hi) devah pradišo 'nu sarvāh VS TA MahānU SvetU SırasU.

visvam hi (KS ha) ripram pravahanti (MS °tu) devih RV. AV VS MS. KS. SB.

agnıh sudaksah sutanur ha bhūtvā MS agne sadaksah satanur (KS† onür) hi bhūtvā TS KS

śrestho ha (Savana, AV Introd p 5, hi) vedas tapaso 'dhijātah GB amuti abhūvād adha (AV adhi) yad yamasya AV, VS TS MS KS TAA anūdhā yadı jījanad (SV yad ajījanad) adhā ca nu (SV adhā cid ö) RV. SV Two cases in the same pada.

vācā cit prayalam (AS ca prayutī) devahedanam TB AS ADS duras ca visvā avrnod apa svāh RV turas cid visvam arnavai tapasvān Aν

tāv ehi (AV 1ha, AB. eha, MG tā eva) AV AB AG SG PG MG Others, §888 ehr contains the verb thr, eha is probably corrupt (Weber, ISt 10 160), and eva is certainly secondary

anu manyasva suyajā yajāma (MŚ yaje hi, most mss yajeha) TS MŚ asūrte (TS MS KS °tā) sūrte (TS °tā) rajasi (TS °so) nisatte (MS °tā, KS na sattā, TS vimāne) RV VS TS MS KS N

mā no agne 'va (MG vi) srzo aghāva RV AG MG sūrvo apo vi (MG 'va) gāhate MS ApS MG

Miscellaneous pronominal forms

äre asman (MS NilarU asmın) nı dhehı tam VS TS MS KS NilarU asmat 'from us', asmin 'in it' or 'in him' MS has v l asman, and its p p asmat

prajāyai kam (AV kim) amrlam nāvrnīta RV AV Both forms are used as particles here

yad vā me am (LS 'pı, Vait apa) qachatı AS Vait LS ug gā udājad apa (MS api) hi valam (MS balam) vah RV MS ahır zaghāna (PG dadarśa) kam (AG MG kım) cana AG PG ApMB

HG MG Here true pronoun forms, 'no one'. 'nothing' māmīşām kam canoc chişah RV SV VS marşām kam canoc chişah TS

TB ApS maisam uc chest kim cana AV As in prec

§579. Remoter lexical variants

mā no vidad (KS vadhīd) abhibhā mo asastih AV KS TB ApS These forms are still quasi-synonyms, 'find' (in a hostile sense) 'injure'

dyulāno vānbhir yalah (SV hitah) RV SV 'Guided' 'placed'

jāmim itvā (Poona ed jāmi mitvā) mā vivitsi lokān (Poona ed lokāt) TA jāmım rivā māva patsı lokāt AV See §198

šukrām vayanty asuraya numjam RV Sukrā vi yanty asurāya numje SV.

vālajarair (HG. vālājirair). , see §268 anarsarātım (SV alarsırātım) tasudām upa stuhi RV SV AV N See §292

- hrisu kratum varuno (°nam) vikşv (apsv, dikşv) agnım, see §360.
- mıtrāvarunā šaradāhnām (MS. °nā) cıkıtnū (MS. cıkıttam, KS. jıgatnū, AS. cıkıtvam) TS. MS KS. AS See §45.
- tısro yahvasya (MS MŚ. jıhvasya) samidhah parıjmanah RV. MS. ApŚ. MŚ. See §192.
- visvakarman bhauvana mām didāsitha (ŚB manda āsitha) AB, ŚB, ŚŚ, See §840.
- abhi dyumnam (RV VS. sumnam) devabhaktam yavışiha (MS KS devahıtam yavışihya) RV VS. TS MS KS ApMB
- rāyah syāma rathyo vayasvatah (TB. vivasvatah) RV. MS TB. See §255. yaśo (AŚ diśo) yajñasya dakṣinām (AŚ. °nāh) TB AŚ.
- agnıh pareşu (AS pratneşu, SV VS. SB. priyeşu) dhâmasu AV. SV. VS. SB. AS SS.
- hinvāno heirbhir yatah (SV. hitah) RV. SV
- alıvardāya svāhā KSA: ıluvardāya svāhā TB ApŚ. Followed by balıvardāya (KSA. °vandāya), which suggests that KSA has an assımılated form.
- šam padam magham †rayīşine na kāmam (AA. rayışani na somah) SV. AA See §545.
- vasūni cārur (SMB cārye, ApMB. cāryo, HG cāyyo) vi bhajāsi (SMB bhrjāsi, HG. bhajā sa) jīvan AV. SMB HG. ApMB.
- miham na vāto vi ha vāti bhūma RV.: mahī no vātā iha vāntu bhūmau AV. Metathesis of a and i
 - §580. The following seem to be false readings:
- ahım (RVKh aham) dandenāgatam RVKh AV Both words make good sense; but Scheftelowitz (p. 62) reads ahım for RVKh with his ms.
- tādītnā (TB. Poona ed †tādīknā) satrum (TB satrūn) na kīlā mutse (TB mutse) RV. TB But Poona ed mutse, comm gloss na labhase
- gāvo bhago gāva ındro me achān (AV. ma ıchāt; TB with two AV. mss †achāt) RV AV KS TB achān is the only intelligible reading and is adopted by Whitney, see VV I p 130
- [añnsakthāya (KSA °şak°, Conc °şık°) svāhā TS KSA]
- [namah śaspińjarāya (TS sasp°; Conc wrongly śisp° for MS) tristmate VS TS MS KS]
- [mā no vadhīh (Conc undhīh for TS, wrongly) pitaram RV. VS TS TAA MS]
- §581. In verbal inflexion there are a number of miscellaneous variants. Thus the reduplicating syllable contains variously a or i, included are some noun or adjective forms based on reduplicated stems:

- pra bhānavah sısrate (SV. sa°) nākam acha RV. AV SV VS. TS MS On this and the two next see VV I §272
- vrşāva cakradad (and °do) vanc RV · vrşo acıkradad vanc SV See prec tāh prācya (Vait. °yah, MŚ. prācīr) ujjigāhire (KŚ. °īre, Vait samjigāīre) KŚ. Vait MŚ . prācīš cojjagāhire ApŚ See prec two
- stotāram id didhişeya (SV dadhişe) radāvaso RV AV SV. See VV I p 90
- haslagrābhasya didhişos (AV da°) tavedam (TA tvam clat) RV AV TA Manymss of AV di°, which Whitney would read. Cf however next
- vahā (TB N vaha) devatrā didhişo (MS da°) havīnşi MS KS TB N
 Cf prec The MS reading is not certain, several mss di°.
 - §582. In present formations of different classes:
- suvīrābhis †tirate (SV TS tarati).. RV. SV TS KS Note the following r (§573).
- anāgaso adham it samkşayema TB anāgaso yathā sadam it samkşayema Vait 1st and 4th class presents; VV I p 125 In the latter y is epenthetic
- yac ca prānili (AV °atı) yac ca na AV SB † TB BrhU † 1st and 2d class presents, VV I p 123
- yah prānīti (AV prānāti) ya īm sīnoty uktam RV AV Cf prec
- katı krivah pränatı capanatı ca (SB pranıtı capa canıtı) GB SB Cf prec two
- nı şlani'nı (AV abhı şlana) durılā bādhamānah RV AV VS TS MS KS Cf prec three
- §583. The \imath of the following is of desiderative character, of Whitney §1030.
- na yac chūdreşv alapsata (ŚŚ ali°) AB. ŚŚ An aorist in AB. See VV I p 87
- sa bhilisamāno (SV. bha°) amṛtasya cārunah RV. SV. Both bhilis (a sort of desiderative) and bhaks are derived from bhaj, but function as quasi-independent roots
 - §584. In various miscellaneous verb forms,
- ajīyapata (TS TB "pipata) vanaspatayah TS MS TB MS See VV I p 192 Both are reduplicated (causative) agrists, the form with radical a is influenced by the vocalism of the causative, the other by that of the simple root
- grhā mā bibhīta mā vepadhvam (LŚ ApŚ HG vepidhvam) VS LŚ ApŚ ŚG, HG See VV I p 133
- nābhā samdāyı navyasī (SV °dāya navyase) RV SV. samdāyı is 3d sing passive aor, samdāya gerund (but awkward, with no finite verb)

yenā samatsu sāsahah (SV. °hih, MŚ °hi) RV SV. VS. ApŚ. MŚ 'Whereby thou shalt conquer in battles', RV (perfect subj): 'whereby (thou shalt be) conqueror in battles' SV. (adjective). In MŚ the adjective is made neuter, agreeing with manas '(thy) mind' in prec

sam ındra no (no) manasā neşī (AV neşa) gobhih RV. AV. VS TS MS KS ŠB TB See VV I p 105 pitā no bodhi (TA bodha) VS ŠB TA See VV I p 123

a in noun formation

§586. We begin with the suffixes to ti, and first with those in which the participles stay close to their original meaning, see also §599 below: yam akşıtam (SS N °tım) akşıtayah pibantı TS SS N : yam akşıtam akşıtā bhakşayantı AV · yathākşıtım akşıtayah pibantı (KS °yo madantı) MS KS 'Which imperishable one (imperishableness) the imperishablenesses (AV imperishable ones) drink (or the like)'

akşıtam ası mā pıtrnām (with variants) kşeşihā . ApG ApMB HG.
BDh akşıtam ası mā me kşeşihāh TS: akşıtam asy akşıtam me
bhüyāh MS. akşıtır asi mā me kşeşihā. . VSK AS SS KS And
other variations

apā vrdhi parivrtam (TB Conc °vrtim, Poona ed. text and comm °vrtim) na rādhah RV. TB 'Open up as it were hidden treasure':
'open up treasure, as it were a fence'

bradhnas cid atra (SV yasya) vāto na jūtah (SV. jūtam) RV. SV. jūtah 'speedy', adj with vāto, jūtim 'speed', with change of construction.

pra samrājo (SV °jam) asurasya prašastīm (SV. °tam) RV SV KB atīrātram varşan pūrtīr āvīt (MS vavarşvān pūrta rāvat, KS vavīsvān pūta rāvat) svāhā TS MS KS.

§587. These are supported by other cases in which the participle is used as a noun, practically equivalent to the noun in ti

puşlapale cakşuşe MS puşlipalaye (AS °pale) puşlis AS. ApS pro ayasıd ındur ındrasya nışkılam RV SV PB. • pra va elindur ındrasya nışkılım AV

nyañ (AV nı yan) nı yanty uparasya nışlırtam (AV. °tım) RV. AV KS. ākūtım (MS MŚ MG °tam) agnım prayujam svāhā VS TS MS KS ŚB MŚ MG

vāco vidhrlim (MS °lam) agnim prayujam svāhā VS TS MS KS ŚB In same passage with prec

sviştam (MŚ v 1 °tim) no 'bhi vasyo nayantu KS MŚ sviştim no abhi (KŚ 'bhi) vasīyo (AV. vasyo) nayantu AV. TS KŚ

krnutam nah svistim (MS KS °tam) VS TS MS KS

mayı puşim (AV °iam) †puştrpatır (AV puşia°, KS *puşirpatıī) dadhātu (AG †dadātu) AV MS KS. (four times) TAA MahānU ApŠ AG SMB.

kuyavam ca me 'kşıtıś (VS 'kşıtam) ca me VS MS KS: akşıtıś ca me küyavāś ca me TS

[ādītyās te citim (KS Cone wrongly citam) āpūrayantu KS ApŚ]
punar brahmāņo (AV. brahmā) vasunītha (AV. °nītīr, KS * °dhītam,
v 1 °dhītīm, KS * [38 12b] † °nītha, KapS °dhītam or °tīm, MS
°dhīte) yajnāth (AV MS KS * agne) AV VS TS MS. KS ŠB
°nītha is a variant for °nīta, see §93.

§588. Coming to variants between na and ni, we find in several cases that the i is apparently due to influence of the feminine ending \bar{i}

asapainā sapainaghnī (ApMB °nıghnī) RV ApMB ApG Cf sapainī, for which sapainī is recorded in the Rāmāyana (BR)

gandharvāya janavide (ApMB janī) svāhā ApMB MG Cf the stems janī and janī Here, strictly speaking, the i and the n are both radical, not suffixal (dissyllabic root jan)

somāya janıwide (MG jana°) svāhā ApMB MG In same passage as prec teṣām yo ayyānım (PG 'jyānım) ajītım āvahāt (SMB Cone ajījım āvahāh, but Jorgensen text and comm as others) TS SMB PG BDh teṣām ajyānım (MŚ °nam) yatamo vahātı (KS MŚ na āvahāt) AV KS MŚ a-jyā-nı, 'non-oppression' a-jyā-na id, not recorded lexically, contains properly the suffix ana, which appears as na after ā hıranyapakşah sakunih HG.: hiranyaparna sakune PG : hıranyavarnah sakunah MU

pururūpam suretasam maghonam (TB °nım) VS TB maghonam may be taken either as an irregular acc sing of maghavan (cf. RV maghonas, nom plur) or as from an a-extension of the weak stem, maghonim (masc) can only be from an i-extension of the same TB comm annavantam; VS comm maghavantam dhanavantam

§589. Of the suffixes ra ri we have only noted one variant, of the word tittiri ca The usual form is ca, but ca occurs elsewhere; however in this passage the MS pp reads tittirih.

mandūlo mūşikā tittiris (MS °ras) te sarpānām VS. MS Cf. §598, varsābhyas .

§590. The suffixes ka and ki exchange in patronymics; really the exchange is doubtless between a and i, since probably in all cases the primary noun contained k; all occur in the same passage.

saunakam (SG °hım) AG SG.

kaholam kauşītakam (SG °kım) AG SG mahākauşītakam (SG °kım) AG †SG

§591. Next, a and i as finals in inflexion or composition of heteroclitic stems in an (weak grade a, always used in compounds, and tending to pass into the a-declension) and i, of the type asthan asthi.

asthabhyah (KSA asthi°) svāhā VS TS KSA.

ut iistha purusa harita piñgala lohitāksi (MahānU purusāharitapiñgala lohitāksa) dehi dehi dadāpayitā me sudhyantām TA TAA MahānU And extensions of such stems in suffixal ka (in compounds).

anakşıkāya (KSA °akāya) svāhā TS KSA.

anasthıkāya (KSA °akāya) svāhā TS KSA

\$592. A few cases of interchange between adjectives in 2 and participles (or quasi-participles, mahat) in at

dhruvas tışthāvıcācalıh (AV MS KS° calat) RV AV VS TS MS KS SB TB

parvata wāncācalsh (AV MS KS °calat) RV AV VS TS MS KS ŚB TB

dadhır (SV dadhad) yo dhayı sa te (SV. sute) vayansi RV SV.

enas cakīvān mahi baddha eṣām TS: eno mahac cakīvān baddha †eṣa MS §593. Variations between suffixal ana and in (ina)

tan nau samvananam kṛtam MG: tena samvanınau svake HG samvanana 'concord': samvanın 'concordant'.

manyoh krodhasya nāśanī PG· manyor mṛddhasya (ApMB mṛdhrasya) nāśīnī ApMB HG Feminītes of nāśana nāśīn

- mā no vidad (KS vidhad) vijinā (KS TB ApS. °anā) dveşyā †yā AV KS TB. ApS Both words mean 'deceit', and seem to be otherwise unknown
- śunām agram suvīrınah (ApMB subīranah) ApMB. HG Cf next subīrana srja-srja śunaka ApMB · suvīrınah srja-srja HG Epithets of dogs, of unknown origin and meaning
- §594. Variations between stems in in (in composition i) and stems in a or an (once an by sandhi for at)
- tasya te †vājipītasyopahūtasyopahūto (Vait vājipītasyopahūto, LŠ vājapītasyopahūta [text °hata] upahūtasya) bhakşayāmi AŠ LŠ Vait · tasya te vājibhir bhakşamkītasya vājibhir sutasya vājipītasya vājinasyopahūtasyopahūto bhakşayāmi ApŠ · vājy aham vājinasyopahūta upahūtasya bhakşayāmi VSK KŠ
- vājam tvāgne Vait : vāji tvā . Ap\$ M\$ vājinam tvā vājin KS : vājinam tvā vājedhyāyai (sapatnasāham) VS VSK TS \$B
- ava jyām (HG dyām) wa dhanvanah (HG dhanvnah) AV ApMB HG See §159.
- matsvā suśipra (SV. °prin) harıvas tad (SV. tam) īmahe RV. SV.
- bodhinmanā (SV. bodhan°) id astu nah RV. SV. In SV. pres pple, bodhat
- §595. Before feminine forms of the suffix ka, most commonly i replaces a, see Edgerton, JAOS 31 95 f:
- vidyutam kanīnikābhyām (VS kanīna°) VS MS. KSA. vidyutau kanānakābhyām TS
- vṛtrasyāsı (KS mitrasy°) kanīnikā (VS SB °akah) VS MS KS SB. MS MG: vṛtrasya kanīnikāsi (VSK °akāsi) VSK TS ApS
- agner akşnah kanīnakam (VSK °kām, TS MS KS °ıkām) VS VSK TS. MS KS SB.
- nı galgalīti dhārakā VS. SB·ni jalgulītı (KSA ms †jalgalūtı, em °līti) dhānikā TS. KSA
- masculine form, the i before ka is anomalous, it may be corrupt, or may be based on thought of a form *jihvin, with suffixal in
- §596. The rest are miscellaneous cases of a · i in suffixes and endings tasmin ma indro rucim ā dadhātu AV.: tasmin somo rucam ā dadhātu HG. ApMB Stems ruci and ruc Cf next
- hrrismasrum nārvānam dhanarcam RV harismasrum na varmanā dhanarcim SV. Stems 7c and 7c-1 (possibly with confused thought of arcis?).

- kuvayah (KSA °yıh, VS TS kvayıh) kuṭarur dātyauhas te vājınām (TS. KSA sınīvālyaı) VS TS MS KSA. A name of an unknown anımal, p p of MS also kuvayıh
- andrah (SS °as) patis tunişlamo (AA SS tavastamo) janeşv ā (SS. janeşu) AV AA SS Stems tavas and tuniş- (the latter not used as a separate word)
- tılırlastam (ed mısprınted tılıra°, see Stenzler's Transl. p 83 n) ıravatam AG: tılırla sthanıravatı SG: tılırala sthıravatı MG † 2 11 12b tılırla syad ıravatı ApMB The word is otherwise tılırıla, probably MG is to be emended
- vı sloka etu (AV. etı, TS ŚvetU ślokā yantı) pathyeva (KS. patheva) sūreh (AV. MS † sūrıh, TS. ŚvetU. sūrāh, KS †sūrah) RV AV. VS TS. MS KS ŚB ŚvetU.
- agne varcasvın (VSK °van) varcasvāns (ŚŚ °vī) ivam deveşv ası varcasvān (ŚŚ °vy) aham manuşyeşu bhūyāsam VS VSK ŚB ŚŚ
- pradakşının (AV. °nam) marutām stomam rdhyām (MS aśyām) RV. AV. MS TB The old adverb pradakşınıt, of anomalous appearance, is replaced by a more ordinary form in AV.
- mānasya patnı \$aranā syonā AV \cdot mā nah sapatnah \$aranah syonā HG harşamānāso dhṛṣıtā (TB °atā) marutvah RV TB N. See \$122 and VV I \$86
- kṛkalāsah (KSA kṛki°) pippakā šakunis (TS KSA šak° pr°) te šaravyāyai VS. TS MS KSA. Of uncertain origin; simulates a compound of a stem kṛka- or kṛki-.

2 Long \bar{a} and $\bar{\imath}$

- §597. These variants are few The most interesting group concerns \bar{a} varying with $\bar{\imath}$ as ending of the first part of a compound or seeming compound We seem justified in thinking of the parallel feminine stem-endings $\bar{\imath}$ and \bar{a} in this connexion. These feminine endings exchange themselves a number of times, as we shall see in our volume on Noun Inflection, which we may anticipate here by quoting the following examples.
- samhītāsi viśvarūpā (VS ŚB ŚŚ °pī, TS ApŚ * °pīh) VS TS MS KS ŚB ŚŚ ApŚ (bis)
- upasthāvarābhyo dāśam VS upasthāvarībhyo †baindam (so Poona ed. text and comm) TB
- sukhā saptapadī (ApMB °padā) bhava AG. SG. Kauś SMB ApMB

śivā rulasya (TS. and v. l. of MS. rudrasya, VSK. śiva rlasya) bheşajī (MS. °jā) VS. VSK. TS. MS KS. See §684.

The compounds in question are, however, so obscure that it is hardly ever possible to be sure that they contain such feminine stems, or indeed even that they are really compounds (the last one certainly is not):

- gṛdhrah śitikakṣĩ vārdhrāṇasas te divyāḥ (KSA. vārhī°, ed. em. vārdhrī°, te 'dityāh) TS KSA. The word (otherwise spelled with ī) seems at least to be felt as a compound; cf. vārdhra?
- uṣṭro ghṛnīvān vārdhrīnasas (MS. ghṛṇāvān vārdhrā°) te matyai VS MS. Cf prec; p.p. of MS vārdhrī°. In ghṛ° we have another animal name, of unknown meaning and apparently found only here
- ākhuḥ kašo mānthālas (MS. °thālavas, VSK. māndhālas) te pitṛnām VS. VSK. MS: pānktraḥ (KSA. †pānktaḥ; mss. of both pāmtra-) kašo mānthīlavas (KSA. †man°) te pitṛnām (KSA. †putŗ°) TS. KSA. See §77.
- yā te agne harīšayā (VSK. harī°, MS MS harā°) tanūr...VS VSK. SB. (Pratīkas MS MS) harāšaya is doubtless influenced by haras
- vidyutam kanīmikābhyām (VS. kanīna°) VS. MS. KSA.: vidyutau kanānakābhyām TS Certainly not a compound, but seems to belong psychologically here.
- §598. The other variations of \bar{a} and $\bar{\imath}$ are very miscellaneous; mostly they concern inflexional endings of some sort
- agne tejasvin tejasvī tvam deveşu bhūyāh TS: agna āyuḥkārāyuṣmāns tvam tejasvān deveşv edhi MS See also agne varcasvin etc., §596.
- ındrasyāham devayajyayendriyāvī (KS. °yāvān, MŚ °yavān) . . . TS KS. MŚ
- śirā riśrāha (VS. °hā) bheşajī (TS. °habheşajī; MS. °jā) VS. TS. MS. KS. riśracarşanih sahuriḥ sahārān (AV. sahīyān) RV. AV. MS
- sılpā raisvaderīh (VS °vyah) VS MS: sīlpās trayo vaisvaderāh TS. KSA. Fem and masc forms, nom plur.
- samānī va ākūtih RV. AV. TB. AG: samānā vā (KS. va) ākūtāni MS. KS MG. ī of fem. sing: ā of neut. plur.
- varşābhyas titlirīn (MS °rān) VS. MS KSA. SB. ApS Acc plur of the words which vary in §589
- dhiyā manotā prathamo manīṣī (SV. "mā manīṣā) RV. SV. "The fore-mos"; intelligent one": ... intelligence".
- sā šamtāti (SV. °tā, TB ApŠ. °cī) mayas karad apa sridhah RV. SV. TB ApŠ. šamtāti acc neut, and šamtātā loc sing, from šamtāti; on šantācī see §156

angāni ca me 'sthānı (VS and v. l. of MS 'sthīnı) ca me VS. TS. MS. KS. Stems asthan asthı.

teşām sam hanmo akṣānı (AV sam dadhmo akṣīni) RV. AV. (Ppp has akṣānı) Stems akṣan akṣı.

bahu ha vā ayam avarsīd... MS: bahu hāyam avrsād (KS. °sad) ... TS. KS. See VV I p. 129

tisro ha prajā atyāyam āyan (JB īyuh) AV. JB. Imperfect and perfect of i

In VV I p. 185 are collected some variations between strong and weak verb stems in $(n)\bar{a}$. $(n)\bar{i}$, which we shall not repeat here Add the following:

śrnihi viśvatah prati RV.: †śrnāhi viśvatas pari SV.

§598a. There are a number of cases of interchange between gerunds in tvā and tvī As was to be expected, the form in tvī is regularly the older: avād dhavyāni surabhīni kṛtvā (RV. VS kṛtvī) RV. AV. VS TS. ApŚ. SMB.

krtyaışā padvatī bhūtvā (RV. *tvī) RV. AV. ApMB.

krivī (AV. krivā) devair nikilbisam RV. AV.

kṛtvī (AV. kṛtvā) savarnām adadur (AV adadhur) nvasvate RV. AV. N. pītvī (SV. TS pītvā) sipre avepayah RV. SV AV. VS TS. SB.

vayo ye bhūtvī (AV. °tvā) patayanti naktabhıh RV, AV.

svnnah snātvī (AV. °tvā, VS. SB snāto) malād wa AV. VS. MS. KS SB. TB

hıtvī (SV. hitvā) siro jihvaya vāvadac (SV. rārapac) carat RV. SV.

apālām indra (MG. °ras) trış (trıh) pūtvī (AV pūtvā, ApMB. pūrtvī, MG. pūrty a-) RV AV. JB ApMB MG

3. a and s with shift of quantity

§599. Here are found only a few stray variants: too few to classify. Some of the variants in the preceding sections show shift of quantity as well as quality, these will not be repeated We begin with variants of \tilde{a} and ι , the first two belong with those of a and ι in §586:

prācīm jīvātum aksītām (ŠŠ. ŠG °tīm) AV. TS. MS AŠ ŠŠ ŠG. AG † (Stenzler's Translation, p 36 n) ApMB. N

vyacasvatīsayantī subkūtih AS MS: nišvavyacā isayantī subkūtih (KS °tā) TS KS. In the latter subhūtā is an adjective going with aditir in the next pāda

tan no durgā (TA °grḥ) pracodayāt TA MahānU. Durgi for Durgā seems to occur only here

śrtyo (AV. TB. °yam) vasānaś carati svarocth (TB °cāh) RV. AV. VS. KS. TB.

āngūṣānām (SV angoṣṇnam) avāvaśanta vānīh RV SV. Different caseforms of a and in stems

adhı kşamı vışurūpam (ArS kşamā vıśva°) yad astı (ArS asya, MS† āsta) RV AV ArS MS TB

kara ād (SV 1d) arthayāsa it RV. SV.

anādhrstā .. VS MS KS SB anibhrstā. .TS See §176

§600. Between a and ī the cases are even fewer and equally sporadic. sīrāh (TS MS KS sarāh, AV sarā) patatrinī (TS MS KS °nīh) sthana (KS stha, AV. bhūtvā) RV AV VS TS MS KS Besides the synonymous sarā and sīrā, sirā is also found (RV) All are from root sī, cf §§570, 573

amṛlenāvṛtām puram (TA purīm) AV. TA Equivalent stems pur and (later) purī

yātudhānebhyah kanṭakīkārīm (TB kanṭakakāram) VS TB Both the stem of the first member, and the entire cpd, show shift in gender

nayanto garbham vanām dhiyam dhuh RV: nayantam gīrbhir vanā dhiyam dhāh SV Lexical

āsmınn (KS ā sīm) ugrā (MS ā samudrā) acucyavuḥ TS MS KS ApŚ Lexical

vīrenyah kratur ındrah sušastıh RV. varenyakratūr (AV °tur, ApŚ īdenya°) aham RVKh AV. ApŚ See §§383, 554

4 Interchange of short a and u

§601. Under this head we find a clearly defined group of cases, which seems to have no parallel among the a ι variants, in which a varies with u before a following v, the influence of which must be partly concerned in the shift. To be sure both forms can as a rule be explained historically, the av forms as full ablaut grade, the uv as weak grade forms, representing \bar{u} before a vowel, or—in the few forms concerning roots in short u—epenthesis of v between u and following vowel. Phonetic and morphological matters are no doubt blended here. But the occurrence of some forms which are morphologically anomalous confirms us in the belief that phonetics cannot be entirely excluded. The great majority of the forms concern roots in \bar{u} . There is to be observed a striking tendency to prefer the u forms in SV, and the like seems to be largely true of MS

§602. In VV I §23 we have already collected most of the verb forms which show this variation The following are those from \bar{u} roots. accilerated svapā tha bhuvat (Ppp bhavat, Barret, JAOS 30 244) AV.

Ppp Add to VV Il c

tasma: devā adhi bravan (MS. KS TB † [Poona ed. text and comm] ApS. bruvan) VS. TS MS KS TB. ApS

tasmai somo adhi bravat (KS bruvat) RV AV KS

yatra (SV yatrā) devā iti bravan (SV bruvan) RV. SV

pra bravāma (MS bruvāma, v 1 bra°) šaradah šatam VS. MS. TA ApMB. ApG HG. MG.

sammışlo aruşo bhava (SV. bhuvah) RV. SV.

uta trātā šivo bhavā (SV. bhuvo) varūthyah RV. SV. VS TS MS KS Kaus

nemiś cakram wābhavat (SV MS °bhuvat) RV SV. TS MS

yai some-soma ābhavah (SV. ābhuvah) RV SV.

yad düre sann ıhābhavah (SV. °bhuvah) RV. SV MS N.

tatra pūşābhavat (SV. °bhuvat) sacā RV SV. KS

asapainā kilābhuvam (ApMB. °bhavam) RV. ApMB: asapainah kilābhuvam RV.

samprıyah (TA °yam prajayā) pasubhır bhava (TB TA ApŚ. bhuvat) MS TB TA. ApŚ

marutvantam sakhyāya havāmahe (SV. †huvemahı) RV. †1 101 1-7, SV. [stāvešo anamīvo bhavā (Conc wrongly bhuvā for ApMB) nah RV TS. MS SMB PG. ApMB]

 $\S603$. From roots in short u the cases are much fewer:

abhi pra nonuvur (SV. nonavur) girah RV. SV. (It is not quite clear whether this is originally a short or long u root) Here SV. goes counter to its usual tendency, with av for RV. uv.

upa śravat (MS śruvat, p p. śra°) subhagā yajñe asmın RV. MS. On the anomalous and doubtful MS form cf. VV I p. 106

tad aham nihnave (\$\\$ \circ\$ nuve) tubhyam AB \$\\$ To be added to VV I \\$193, since it is a case of 1st and 2d class presents; the latter (hnute) is more regular.

nediya it sınyah pakvam ā yavan (Ppp yuvan, Barret, JAOS 30 207) AV Ppp (Others, see Conc.) Add to VV II c

§604. The same shift is found in noun formation and declension, both \bar{u} stems (placed first in the list) and short u stems

abhibhuve (MS °bhve, KS °bhave) svāhā MS VS KS TB ApŚ And, in same passage:

vibhuve (MS. vibhve, KS †vibhave) svāhā, same texts

samudram na suhavam (suhuvam, subhuvas) , mahişam nah subhvam (subhavaş) . . ., see §119

ındrah (SS. °as) patıs turıştamo (AA SS tavastamo) zaneşv ā (SS janeşu) AV AA SS Cf. §596 śitibhravo (MS. °bhruvo) vasūnām VS. MS

punsavanam punsavanam AG. punsuvanam ası ApMB The form in av is regular in the earlier language, but that in uv occurs first (in AV.)

tad nprāso npanyavah (SV. °yuvah) RV. SV VS. NrpU VasuU SkandaU ArunU MuktiU.

tā vām gīrbhir vipanyavah (SV °yuvah) RV SV

sumnāyuvah (KS °yavas) sumnyāya sumnam (KS sumnyam) dhatta MS KS MŠ

tasya prajā apsaraso bhīruvah (MS bhīravo nāma) TS MS

§605. Of other variations in radical syllables between a and u, analogous to the variations between a and i treated in §570 ff, we have noted surprisingly little. We might have expected to find a number of cases especially before r (cf §573, and Wackernagel I §21), as in the two forms of the present stem karo kuru. The chief cases we have noted, however, concern adverbs and adjectives in par- pur-, which we shall list below in §615, along with other variations in adverbs and particles. Otherwise the only case we have noted—the first in the following list—is of very dubious character. In it and practically all the others in this section assimilation or dissimilation seems to have been at work.

sukarīrā svopašā (v l svau°) MS · sukurīrā svaupašā VS TS KS ŠB The usual form is kurīra, the etymology is unknown If MS is correct, it may have dissimilation to the preceding u (su)

avabhrtha nicumpuna (TS TB ApS nicaākuna, MS KS MS nicuākuna) VS TS MS KS SB. TB LS MS ApS N See §150 Here dissimilation seems highly likely as an explanation of the a form, despite the obscurity of the words

nucerur ası nucumpunah (TS TB nucañkuna, MS KS nucuñkunah) VS TS MS KS SB. TB. LS Cf prec

samkasuko wkasukah AV. MS · samkusuko wkusukah TA ApŠ The root is kas and the kus forms are certainly secondary, and apparently assimilated to the suffixal u which follows Cf next

asmın vayam samlasuke (ApŚ °kusule) AV ApŚ Cf prec nı nıvariana variayendra nardabuda (KS nandabala) TS KS ApMB

ni nivariana variayendra nardabuda (KS nandabala) IS KS Aphilo See §273. Note that the variant vowel is preceded by b, a labial consonant

etām samkrsya (MS MŠ °kasya, v l °kusya) juhudhi MS ApŠ MŠ Here the original form was neither d nor u, but 7, see §631

tuce tanāya (SV Svidh tunāya) tat su nah RV SV Svidh The SV form is isolated, and probably due to the adjoining and synonymous tuce

Benfey tries to explain it independently, which seems to us highly improbable

§606. Next comes a rather interesting, if somewhat heterogeneous, group in which the a u is found in the second syllable of a word, yet is not clearly suffixal, assimilation or dissimilation may again explain some of the changes, but in one or two, at least, it seems that we are dealing with dissyllable roots, or root-determinatives, in u, of the type laro, laru- (VV I p 116 f, and references there quoted). Most of the other words are obscure; often one is inclined to suspect that the variations in spelling point to a real uncertainty or ambiguity in the pronunciation of an unaccented vowel:

karanam (TS karunam) as TS AS SS Both words occur in the sense of 'religious work'; but karanam is much commoner, and is second-arily substituted for the rarer but original karunam in this variant.

varano vārayālai (and, vārayişyati) AV. varuno vārayāt TA The root vr, like kr, has dissyllabic forms in u It is unnecessary here to consider the old question whether Varuna is derived from it; the god's name (if the reading is correct, Poona ed has varano with v l varuno) is here used obviously with punning intent

So with the verb-forms vanate vanute and the like, on which see VV I p 121; whatever their grammatical classification (discussed l c), they seem ultimately to have a sort of root determinative u.

agnir no vanate (VSK vanute, SV. TS KS vansate) rayim RV. SV. VS. VSK. TS MS KS

tad agnır devo devebhyo vanate (MS SB SS vanutām) TS MS SB TB. AS SS

§607. The rest are more dubious in character:

pitvo (VS MS pidvo, KSA bidvo) nyaākuh kakkaṭas (MS kakuṭhas, TS KSA kašas) te 'numatyai (KSA 'yāh) VS TS MS KSA There may be assimilation in VS or dissimilation in MS, but the forms are wholly obsoure

tad vo astu sucetanam (JB °tunam, SS sajoşanam) AV. AB GB JB SS Here both a and u may perhaps be called suffixal; yet the varint seems to belong in feeling to this group. No uncompounded cetuna is found, but sucetuna is recorded later, and cf. RV cetu

somasya rājāah kulumgah TS · somāya kuluāgah (MS kulaāgah) VS MS : somāya rājāe kuluāgah KSA The usual form is kuraāga, and the medial u is apparently due to assimilation to u of the first syllable. In both this and the next variant MS p p has kulu°; contrariwise VS comm reads in both kula°, glossing kuraāga.

sādhyebhyah kulungān (MS kulangān) VS MS Cf. prec.

- yādase śābalyām (TB śābulyām) VS TB. parā dehi šāmulyam (ApMB śābalyam) RV AV. ApMB Popular etymology has confused two originally distinct words, śāmulya means a kind of woolen garment, and is not connected with śabala 'spotted' A derivative of the latter is concerned in VS TB, whose comms. interpret 'a woman with spotted skin', the u of TB. is either due to vague reminiscence of śāmulya, or to phonetic influence of the labial consonant b. ApMB is clearly thinking of śabala, and intends the meaning 'spotted garment', in RV AV ApMB reference is made to the bridal garment, spotted and impure after the wedding night. Cf §241
- §608. Next we come to cases in which the variant vowels are more definitely suffixal, and matters of noun formation. First a group in which the common synonyms cakşas and cakşus interchange. Note the misreading cakşaşī sāmavedasya in GB Bibl. Ind. ed., which is a mere misprint for cakşuşī as shown by the following s, Gaastra reads correctly cakşuşī. Cakşas is an older form, which later texts tend to replace by cakşus
- namah samudrasya calşase (PB cakşuşe) TS MS KS JB PB LS apo mahı vyayatı cakşase tamah RV. apo mahī vynute cakşuşā tamah SV āyuś ca prāyuś ca cakşaś ca vıcalşaś (ApŚ cakşuś ca vıcakşuś) ca MS ApŚ
 - §609. Other, miscellaneous cases of noun formation
- tarakşuh (KSA†°kşah) krşnah TS KSA Both forms otherwise recorded; original unknown
- sādhu (SV sādhah) kṛnvantam avase RV SV As the accent of sā'dhu shows (see Wackernagel II 1 p 20), it is a noun, not an adjective or adverb It occurs only here, and is replaced in SV by the equally unknown sā'dhas
- tā mandasānā manuşo durona ā RV ApMB sā mandasānā manasā śwena AV Really a lexical variant, even the the words may be related prehistorically, but resembles the case of calşas cakşus, §608, superficially
- dawyā minānā manasā (VS manuşah) purutrā VS MS KS TB sugantuh karma karanah karişyan JB : sugam tvah karmah karanah karanah karasyuh LS Cf. §573
- ārdrah prathasnur (MS †pṛthusnur, v 1 prathasnur) bhuwanasya gopāh TB ApS MS Knauer, note on MS, would understand prathasnu (TB comm. prathanasīlo) as dialectic by-form of pṛthusnu

- samsṛṣiam ubhayam kṛtam (KŚ. abhayam kratum) KS TB KŚ ApŚ Note metathesis of a: u in KŚ, which is poor and secondary; and cf next
- punnkasthalā (KS † punniga") ca krtasthalā (VS ŚB kratu") cāpsarasau VS TS MS KS ŚB Proper names, compounded of krta kratu, of prec Really lexical, since the words are radically not related.
- dhanasprtam (MS. dhanu°, but p p dhana°) śūśuvānsam sudakşam RV MS dhanu° could only mean 'winning by the bow', instead of 'wealth-winning', it is doubtless a blunder, perhaps helped by assimilation to the u vowels of the following
- §610. We have noted only one case concerning noun inflection, a shift between the genitive and vocative forms of the stem savitar ghriavati savitar (MS KS °tur) ādhipatye (TS. °tyaih) TS MS KS AS

'In Savitar's overlordship' or 'in (thru) thy overlordship, O Savitar'

- §611. In verb inflexion, morphological change between a and u vowels is fairly common in shifts between imperative and injunctive (imperfect indicative) endings, $(n)tu^{\cdot}(n)ta$. The instances are gathered in VV I, mainly in §§136, 156, 159, and need not be repeated here, since phonetics are hardly concerned We add a few other stray cases
- adārasrd bhavata (AV. °tu) deva soma AV. TB ApS. bhavata seems uninterpretable and may be a mechanical form-assimilation, see VV I p 283
- ā priaram varšvānaram avase kah (PB kuh! comm akah, glossed kuru)
 PB KŠ ApŠ MŠ kuh is impossible and, if not a misprint, must be a
 gross corruption for kah ('kah), VV I p 283
- §612. The remaining cases of a: u are purely lexical A large group concerns the prefix sa and the particle su, which are practically synonyms as used in composition, and which exchange often with each other, also the pronoun sa, and other exchanges of the syllables sa: su, of various character, are included here
- ye sajālāh samanasah (Kauś su°) TB ApŚ Kauś : ye samānāh samanasah VS MS KS ŚB. TB ApŚ MŚ
- šatam jīvema šaradah sarvavīrāh (TB. savīrāh, ApŚ suvīrāh) AV. TB
- ā tvā vahantu harayah sucetasah (ApMB sa°) MS ApMB HG ādriyāsah sumahasah (SV sa°) krnotana RV. SV
- agnıh sudakşah sutanır ha bhūtvā MS agne sadakşah satanır (KS†°nūr) hı bhūtvā TS KS
- namo vrddhāya ca savrdhe (TS samvrdhvane, KS savrdhvane, MS savrdhvane) ca VS TS MS KS

sajātānām sraisthya ā dhehy enam AV TS.: sa° madhye sraisthyā ā dhehi mā MS: sujātānām śraisthya ā dhehy enam KS

tad vo astu sucetanam (JB. °tunam, SS. sajoşanam) AV. AB GB. JB SS

marutvān astu ganavān sajātavān (AŚ sujātaih) TB AŚ

akah su (TS sa) lokam sukrtam prihivyāh (VS SB °vyām) VS TS MS

KS SB Here and in the next the pronoun sa exchanges with su ayam sa (SS su) vām aświnā bhāga ā gatam AV. AS SS

pra sumartyam (su mṛtyum) yuyotana SMB ApMB. pra sa mṛtyum yuyotana HG Here sa seems uninterpretable; Conc would read su

dadhad yo dhāyı sute vayānsı SV dadhır yo dhāyi sa te vayānsı RV Here and in the next the pronoun sa varies with a syllable su of different character, involving false divisions of words.

samsraşlā sa yudha ındro ganena RV. AV SV VS. TS KS : samsrşļāsu vulsv ındro ganesu MS

nṛcakṣāh (MŚ. sucakṣāh) soma uta suśrug (comm and Poona ed śuśrug, MŚ. sasrud) astu TB MŚ If Poona ed 18 right, TB has śu-, the reduplicating syllable See §145

§613. Similarly, the particle u varies with a- of the augment, or with other a-

yajñah pratyaşļhāt (v 1 praty u şthāt) KS yajñah praty u şţhāt sumatau matīnām MŚ

tam ahve (SV. u huve) vājasātaye RV. SV. In VV I p 26 we have suggested here possible influence of the following v, separated from the vowel only by the aspirate

ırām u ha (AV aha) prašansatı AV SS AG.

§614. The particle nu varies with the negative na, or with other na, sometimes involving false division of words

tam te vi şyāmy āyuşo na madhyāt (MS KS nu madhye) VS MS KS SB. idam te tad vi şyāmy āyuşo na madhyāt TS

varnāvate vā pašuso na (MS nu) vājān RV MS KB

unānasah saparyan RV † upo nu sa saparyan SV

avasyuvātā brhatī (TS °tīr) na (TS nu, AS tu) šakvarī (TS °rīh) TS MS KS AS

mahān ındrah paraś ca nu (SV puraś ca nah) RV AV SV Metathesis

§615. Various adverbs and adjectives in pur-, par- interchange, this goes back to the same prehistoric phonetic relations dealt with in §605, q v Besides the last variant in §614, the following occur.

part pūṣā parastāt (AV pu°) RV AV

yasmāj jātā na parā nawa kim canāsa TA.: yasmāj jātam na purā kim canawa VS · yasmāj jāto na paro 'nyo (ŚŚ anyo) asti JB ŚŚ: yasmāt param nāparam asti kimcit TA. MahānU. N.: yasmād anyan na param kim canāsti Vait. yasmād anyo na paro asti jātah PB.: yasmān na jātah paro anyo asti (NṛpU. 'sti) VS. TB. ApŚ. MahānU. NṛpU

[ye devāh purahsado.. TS MS KS ApŚ MŚ BDh: ye devā agninetrāh purahsadas . VS. ŚB Conc quotes parahsado for TS] §616. Miscellaneous variations involving other particles, adverbs, and light words, sometimes with false division of words

pra na (SV na) indo mahe tane (SV. tu nah) RV. SV.

sarve rādhyāh stha (ŠŠ "yās tu) putrāh AB ŠŠ

devānšo yasmai tvede tat satyam upariprutā (ApŠ apariplutā) bhangena (ApŠ bhangyena) VS ŠB. ApŠ.

ugro (MG agne, HG ürdhvo) virājann (MG virājam) apa (MG. upa-) sedha (AV vīrīkṣva) satrūn (MG. šakram) AV. ApMB. HG MG upaśṛnvate (ŚŚ apa°, corrupt?) tvā AŚ ŚŚ

apa snehitīr etc RV AV. SV KS upa stuhi etc TA. See §110.

tām brahmā tu (AV ApMB brahmota) sundhatı (AV. sumbhatı, ApMB sansatī) RV AV ApMB

§617. The same change occurs in other lexical variants, in words still fairly close in meaning to one another.

mitro yatra (AV no atra) varuno ayyamānah (AV yuyya°) RV. AV.

devebbir aktam (VS TS yuktam) adıtih sajoşâh VS TS MS KSA

vācā cit prayatam (AS ca prayutī) devahedanam TB AS ApS pramade (TB °mude) kumārīputram VS TB

anu stomam mudimahı (PB mademahi) RV. AV. PB

asmın goşthe karışınıh (Kauś °nah, MS purişınıh) AV. MS Kauś. See §152, note p before u

sā samnaddhā sanuhi vājam emam (MS sunuhi bhāgadheyam) AV MG (Others, §52) ā-san: su, near-synonyms

añjanti suprayasam (Ppp yuñjanti suprajasam) pañca janāh RV AVPpp MS See §192

väyosävitra (MS väyusavitrbhyäm) ägomugbhyäm caruh (MS payah) TS MS KSA.

protnāso agna riam āšuṣānāh (AV āśaśānāh) RV AV. VS TS ašīmahı (MS uś°) tvā MS TA

ā rašmīn (RV °mem) deva yamase (TB yuvase) svašvān (RV TB °vah) RV VS SB TB

nı galgaliti dhārakā VS SB·nı jalgulītı (KSA ms †jalgalūtı, ed em °lītı) dhānıkā TS KSA Onomatopoetic forms?

- ye pūrvāso ya uparāsa (AV ye apa°, some mss ya upa°, comm u. parāsah) īyuh RV AV VS TS MS
- [yaje samrādhanīm aham SB BrhU AS SMB ApMB yuje (but read yaje with most mss, Hillebrandt, p 250) †samardham īm aham SS · agnau samrādhanīm yaje HG.]
- §618. And finally, in words that are psychologically more remote pratipam pratisutvanam (AB "satvanam) AV AB SS Boehtlingk regards the reading "sutv" as a corruption of the other But the word is probably a proper name, and may as well contain sutvan as satvan
- svastı nah putrakrtheşu (MG pathyāhrteşu, v. 1 as RV) yonışu RV AB MG
- vasışlhahanıh śıñgīnı kośyābhyām VS oşışlhahanam śıñgīnıkośyābhyām (TA °kośā°) TS TA
- yamasya loke adhırajjur üyat (TA üya, MS loke nıdhır ajarüya) AV MS TA See §401
- adha syāma (MS athā syāta) surabhayo (ApS syām asur ubhayor) grheşu AV. MS KS ApS See §840.

pratisrutkāyā artanam (TB rtulam) VS TB See §651.

śumbhānas (stambho).., see §287

vı no rāşļram unattu . .TB sam te rāşļram anaktu AV See §139 bhakşīmahı (TS MS. KS Vair dhukş°) prajām ışam RV SV TS MS KS PB Vait

rajanı. , rajjunı , see §107

īde agnīm svavasam (AV svāvasum) namobhīh RV AV MS TB AS See §466

ımau stām anupakşıtau (ApMB anapekş°) AV ApMB

āšum jayantam anu (KS yā samjayantam adhı) yāsu vardhase RV VS TS. MS KS ŠB

abhı sprdha usro vedim tatarda ŚŚ vy usridho asro adrir bibheda TB
The TB looks generally secondary Comm asro nirasanakuśalo
priyāny angāni svadhitā parūnşi (Vait angā sulftā purūni) TB Vait
[hotā yakṣat tvaṣṭāram acɪṣtum (TB Conc °ṭam, Poona ed °ṭum, which
certainly read) MS KS TB]

[havir havişşu (SV havihşu) vandyah (SV. Conc wrongly °yuh) RV. SV] [asmākam anšum maghavan puruspṛham SV Conc 'read anšam' for anšum; but cf. Benfey's Glossary, perhaps anšum is correct]

[upa drava payasā godhug oşam (ŠŠ† oşum, AІ payasā goşam) AV AB AŠ ŠŠ Both AŠ and ŠŠ probably contain misprints, as suggested by Whitney on AV]

5. Other interchange of a and u vowels

§619. The variations between long \bar{a} and \bar{u} , and between a and u with shift of quantity, are negligibly few and scattering. We have noted only the following of \bar{a} and \bar{u} .

dwyo gandharvah ketapūh (VSK °pāh) ketam nah (MS KS omit nah) punātu VS VSK TS MS KS SB SMB, 'Purifying (protecting) the will', the verb punātu is cognate with -pūh of the original reading

pıtā devānām janıtā vibhūvasuh (ApŚ MŚ vibhā°) RV SV ApŚ MŚ drapsaś caskanda prthivīm anu dyām (RV. prathamān anu dyūn) RV

AV VS. TS MS KS SB

aghadvıştā devajātā AV Kaus atharvyuştā devajūtāh ApS

yad annam admı (PrānāgU agnır) bahudhā virūpam (PrānāgU mrāddham, vv ll mrājam, mruddham) AV. TA PrānāgU

§620. Besides the last, which also includes a form with short u, we find short u and \bar{a} varying in

sahhā suševo advayāh (Mahānāmnyah vyuh) RV. KS AA Mahānāmnyah Nom sing masc of as u stems

yo nah (AV mā) kadācid abhidāsati druhā (AV. druhuh) RV AV. druhā, instr sing of stem druh, druhuh, nom sing of adj druhu

sā prasūr (ŚG suprasūr) dhenukā (HG °gā) bhava AV ŚG ApMB HG Pronoun sā prefix su

pumānsam u (ŚG ā) dadhad (ŚG †dadhād) 1ha AV. ŚG Add to VV I §§167, 193

§621. Variants of a and \bar{u}

yad adya hotrvarye (SS °vūrye) SB SS ApS °vūrya is Rigvedic, its long ū seems anomalous For the u-vocalism of vurīta etc (VV I §10)

nahih (RV $n\bar{u}$ cit) sa dabhyate janah RV SV $n\bar{u} = nu$

druhah pāšān (TS KS pāšam) prati sa (KS. sū) mucīsļa RV TS MS KS See §612

utsam juşasva madhumaniam ürva (KS MŠ ürmım, VS arvan, VSK sva satadhāram arvan) VS VSK TS KS ApS MŠ See §228

6 Interchanges of short i and u

§622. These variants are not numerous, and chiefly morphological or lexical Of phonetic interest is, however, a small but striking group of cases in which texts of the Taittiriya school show a tendency to substitute u for ι , in various formative syllables These are to be considered in connexion with the tendency of the same school to substitute suffixal

- v for y (§§247-8) The tendency seems to us undemable, even the in nearly every case one or another special consideration may have contributed to the change, so in
- pareywānsam (TA ApŚ pareyu°) pravato mahīr anu (AV $\imath ti$) RV AV MS TA AŚ N (Pratīkas, ŚŚ ApŚ Kauś Rvidh) This form of the perfect active participle of $par\bar{a} + \imath$ is certainly anomalous enough in appearance, possibly the u may be partly due to assimilation to the following v
- hlādike hlādikāvati (TA hlādike hlādika) RV AV TA Here, too, another motive is discernible. The word is felt as a kind of primary derivative of root hlād, 'cooling'. This meaning in the Brāhmana language is expressed by the suffix uka, of Edgerton, JAOS 31 104 ff. But again the form appears only in a Tait text.
- goşv aśveşu śubhrışu (TB °uşu) RV AV KS TB The stem śubhru occurs only here, the surrounding u vowels may have assisted (assimilation)
- made-made ht no dadth (TB daduh) RV AV MS KS TB AS daduh can only be a noun form equal to dadth, and otherwise unknown (a 3d plural verb is not construable) The samhitā mss of MS have a different phonetic corruption, dadrk, ed follows p p
- §623. In other texts i and u occasionally interchange in formative elements of the same type, but in these the u forms are less anomalous acety agains cikituh (SV KS °tih) RV SV KS Perhaps assimilation in SV KS
- dawyā (AV dawā) hotāro (TS °rā, AV °rah) vanuşanta (TS vanış°, KS † vanışan na, AV sanışan na) pūrve (AV KS etat) RV AV TS KS The ancient aorist vanuşanta is based on vanu-, the same element mentioned above in §606, end It is historically quite as justified as vanışanta, which is substituted for it in later texts (TS, contrary to its general trend¹) to bring it into a commoner type of aorist formation
- §624. In two other rather obscure words assimilation or dissimilation may be concerned
- rkşo jatūh suşīlīkā (MS susulūkā) ta itarajanānām VS MS (p p of MS susīlīketī suşī-līkā) See §279
- drše ca (MS dršā ca, RV abhilhyā) bhāsā brhatā sušukvanih (RV šušu°, KS °vabhih, MS sušikmanā) RV VS TS MS KS ŠB See §240 §625. In verb inflexion there are many cases of variation between indicative endings in i and imperatives in ii. They need not be listed here, see VV I, e g §116 Otherwise the remaining variants seem to be

- sporadic and purely lexical, so far as not corrupt, unless one make an exception of the following which shows two mere interjections, him and (commoner) hum:
- paśwnām tvā himkānenābhiyighrāmy (GG °mi, HG hum°) asau . SMB GG ApMB HG
- -§626. In several variants forms of root \$ri exchange with \$ri or sru:
- agne tram sūklavāg asy upaśruti (ŚB AŚ ŚŚ °tī, TB upaśrito) divas (TB divah) pṛthivyoh MS. ŚB TB AŚ ŚŚ upaśrito divah pṛthivyoh TS
- śavasā hy ası 'rutah (AV śritah) RV. AV But SPP srutah for AV, with many mss (other mss śritah), and so Whitney's Transl
- ā tvā parısrutah (MG. °srtah, mss °tam; AG °śrtah) kumbhah (ApMB† °āh) AG PG ApMB MG And others; see §275

§627. The rest are sporadic

- prayāvatīh sūyavasam (AV. °se) rušantīh (RV. TB comm rīš°) RV AV. TB See Whitney's note on AV rūš° 'shining', the no doubt se ondary to rīš° 'grazing', is not impossible of interpretation and is clearly the reading of AV. tradition
- priyo me hrdo (MS hito, v. 1 huto) 'si (MS †bhava) TS MS This, as between i and u, concerns of course only a textual corruption in the mss of MS
- svarvido abhi gā adrim uşnan (SV ışnan) RV SV. See §401
- pāti priyam ripo (and, rupo) agram padam veh RV (both) pāty agnir vipo agram padam veh ApŚ Read rupo in both RV passages, cf. Ludwig ad loc, Bloomfield, JAOS 27 75, and RVRep 184
- apām tvā sadhīşī (MS † sadhīsīu) sādayāmī VS MS KS SB See §353 The MS is mangled, is its ending felt as loc plur? (sadhīsī loc sing)
- upa yajñam asthita (MS astu no, AV comm astrta) vaiśvadevī RV. Kh. AV ApS MS
- ā suse (SV āsise) rādhase mahe RV SV. The RV has a verb form from ā-svas 'I fan (instigate) you unto great bounty' In SV. we have an interesting case of assimilation ir sense to outward form. The ending e suggests a dative matching the following rādhase, hence āsise 'unto blessing', which leaves the sentence without a verb Benfey supplies 'we summon'
- riasyariena mām ula (TA 1ta) TB TA riasya tv enam āmutah (p p tú, enam, mā'm, uliám ma') MS (corrupt in both forms) TA comm takes 1ta as a verb form (= prāpnuta)
- mandāna ud vrṣāyate (SV 1d vrṣāyase) RV SV

şad ıd yamä (TA udyamä) rşayo devajā ıtı RV AV. TA N ud ıt te vasuvıtlamäh ApS ud u tye (MS MS ud-ut te) madhumattamäh

RV AV SV MS GB PB AS SS Vait MS

sarvān it tān anu vidur vasişthāh RV sarvam uktam anuvidur vasişthāh JB

vışvair devai rātibhih samrarānah (MG devair rtubhih samvidānah)

ApMB MG
sugandhim (subandhim) . see §152

lokam (RV ulokam) u (ApŠ 1d) dvc upa jāmī (RV jāmim) īyatuh RV MS ApŠ

[vātāpe pīva id bhava RV KS †—Conc ud for KS id]

nādya satrum nanu (SB † na nu) purā uvutse (SB yuyutse) RV SV See \$255, and other interchanges of v vu in \$805

alıvandāya svāhā KSA ıluvardāya svāhā TB ApS See §579

achidrā usijah padānu takşuh TS achidrosijah kavayah padānutakşişuh (so text, em by Caland, ms † padānutakşişvat) KS

vratānı (MS TB Ap\$ vratā nu) bibhrad vratapā adabdhah (TB \$\$ Ap\$ \$\$G adābhyah) MS AB TB A\$ \$\$ Ap\$ \$\$G

7 Interchanges of long $\bar{\imath}$ and \bar{u} (u)

§628. Here are found only a few stray variants

ūrjam samsūdena (KSA °sīdena) TS KSA Parts of a horse's body, wholly obscure TS comm samsudam samtataksarano nāsikādih visnur āprītapā āpyāyyamānah VS. apūtapā ādhūyamānah TS The passages are rather low bathos

ahır na jūrnām (TB ahır ha jīrnām) atı sa patı tvacam RV SV TB Both participles of the dissyllabic root jr The ī form is regular in Sanskrit, but the Vedic ū form survives in Prakrit (Edgerton, Ind Stud C R Lanman 27)

rkşo jatūh suşılīkā (susulūkā) , see §624

sam îm (SV u) rebhāso asvaran RV AV SV dhūmrā babhrunīkāśāh. VS putrbhyo barhışadbhyo dhūmrān babhrvanūkāśān ApS See §742

CHAPTER XIV VOCALIC LIQUIDS AND OTHER VOWELS

§629. With this chapter we once more enter definitely into the sphere of Prakritism. In a considerable number of cases the variations seem to be, in fact, strictly Prakritic. That is, a, i, or u vowels are historically secondary, and are derived from f (l) by phonetic changes as in the Prakrit dialects. These are flanked by cases of hyper-Sanskritism, in which an older a, i, or u, which is conceived (perhaps wrongly) as Prakritic, is replaced by f in a secondary text. These are not less interesting than the other cases from the phonetic standpoint, as helping to show the wide spread of Prakritism in Vedic times

§630. We also find not a few variations between vocalic r and consonantal r with another vowel, especially when that other vowel is i or u, we are reminded of the later pronunciation of r as ri or ru. On the other hand the not infrequent variations between r and ra or ar are mainly matters of ablaut, in so far as they are not lexical. Perhaps the majority of variants in the entire chapter are indeed in some sense lexical, that is they concern, or at least may concern, lexically independent forms. But even then it is still perfectly possible, and indeed highly likely, that Prakritic influences have been influential in the shift, even the the exact extent of that influence cannot be determined. Cf. our remarks in §20

1 r and a (one anomalous case of \bar{a})

§631. We shall quote first the cases which can with most confidence be classed as purely phonetic (Prakritic), beginning with one in the Rigveda itself

ava sma durhanāyatah (SV. durhṛn°) RV SV The SV. has (secondarily, of course) restored Sanskritic vocalism in the Prakritized form of the RV. The root is originally hṛn, and this form continued to flourish by the side of the early Prakritism han

işām khṛgalyam śavam (ApŚ khagalyam sapham) MS ApŚ An uncertain part of a wagon is meant. The natural presumption of Prakritism arising from the juxtaposition of the two forms is supported by the form khṛgala, RV, if that word (of uncertain meaning) may be assumed to be related

paşthavād (MS prşthavād, p p paştavād) gaur vayo dadhuh VS MS KS

- TB The p p form of MS suggests that its samhitā form may be a hyper-Sanskritism, in any case it is hardly to be doubted that it gives the original form of the word
- etām samkṛṣya (MS MŚ °kaṣya or °kuṣya) juhudhi MS ApŚ. MŚ The MS. MŚ. forms are not incapable of interpretation as lexically independent words, Boehtlingk chooses the form °kuṣya But they are probably Prakritic after all
- achalābhih (KSA °rābhih, MS [m]atsarābhih, VS ṛkṣalābhih) kapiñjalān VS TS MS KSA. See §184. The AV. knows ṛcharā, probably ṛ is older than a
- §632. The following cases seem more or less clearly to contain hyper-Sanskritism in the forms with τ .
- sarvam tam masmasā (VS bhas°) kuru VS TS ŠB sarvāns tān maşmaṣā (MS †mṛsmṛsā) kuru MS KS TA sarvān ni maṣmaṣākaram AV In this onomatopoetic word (cf Eng mash) there is no doubt that the a vowel is original, MS. pedantically tries to make it sound Sanskritic and 'hifalutin'
- attrātram varsan pūrtir āvrt (MS vavarsvān pūrta rāvat, KS vavrsvān pūta rāvat) TS MS KS And various other formulas in the same passages, all containing the same exclamations. Despite the lingual i in MS rāvat, which might be argued to point to an original r, we believe with Keith that āvrt is a mere hyper-Sanskritism, without real standing. Of §168
- vanasade (MS vanarşade, KS vanrşade) vet (TS MS vat) VS TS MS KS SB See §650
- vasūni cārur (SMB cārye, ApMB cāryo, HG cāyyo) vi bhajāsi (SMB bhīj', HG bhajā sa) jīvan AV SMB ApMB HG The SMB form is certainly a hyper-Sanskritism if it is not corrupt, one ms bhajāsi, Stonner 'geniessen' (as if bhaj)
- yajuryuktam sāmabhır āktakham tvā (MS rktakham tā, p p rktakhám tti rkta-khám, tā [unaccented]) MS TA
 varying with r, it is highly problematic See §365
- §633. The remaining cases are more clearly lexical in character In the first we have probably a mere textual error
- jīvasūr devakāmā (HG vīrasūh) syonā ApMB HG prajāvatī tvīrasūr devrkāmā AV vīrasūr devakāmā (AV devr', SMB °sūr jīvasūr deva', GG °sūr jīvasūr) syonā (AV omits, GG jīvapatnī) RV AV SMB. GG PG MG Most mss of AV read deva' both times, and this is doubtless the true AV reading, as Whitney observes Either reading would however make sense

undro nāma śruto grne (TB ApŚ gane) SV TB AŚ ŚŚ ApŚ grne is dubious, Benfey suggests taking it as 3d sing passive, gane is simple enough but may be a lect fac

yālena jālam atī sa pra sarsīte (TB atī sīt pra sīnsate) RV MS TB Comm on TB sīt prasītam, atī prasīnsate 'tīšayena prasītansayaty adhah karotī TB is evidently secondary

§634. In the other lexical changes the two forms are less close to each other in form, the vowel change being accompanied by other changes in the words We omit cases of brhat and mahat, of §241.

vadhūr jajāna (AV jigāya, MS KS mimāya) navagaj (ŚG. navalīj) janitrī AV TS MS KS ŚG ApMB See §46

jagdhā vitrstir (HG vicastir) ApMB HG. jagdho mašako jagdhā vitrstir (HG vicastir) ApMB HG. jagdho vyadhvaro jagdho mašako jagdhā vitrsti svāhā ApMB jagdho vyadhvaro jagdhā vicastir jagdho mašakah HG See §156.

ud usrıyāh srjate (TB sacale) sūryah sacā RV SV TB Sce §3

dadhry (TA dadhad) vidhakşyan (AV °kşan) paryañkhayāte (TA °tai, AV, parīūkhayāta) RV AV TA See §145

ajantı (SV mrjantı) vahnım sadanany (SV oneşv) acha RV. SV

savıtā bhrtyām (KS †manyām) TS KS Soms of KS, ed em bhrtyām yad adya dugdham prihwīm asrpia (TB ApŚ asakia, MŚ abhakia) AB.

TB AS ApS MS See §152

satyaujasā dṛnhanā (MS durhṛnā, KS †drhanā) yam nudethe TS MS KS · sacetasau druhvano yau nudethe AV See §305

somah sutah pāyate ajyamānah (SV suta rcyate pāyamānah) RV SV. See §57.

rasena sam asīksmahī (RV agasmahī, KS LŚ aganmahī, AV. JB. apīksmahī) RV AV. VS TS MS KS JB. ŚB TB LŚ ApMB

yāv (MS. KS yā) ātmanvad bibhrto (KS † °tho, AV visato) yau ca raksatah (AV KS † °thah) AV TS MS KS

deva purašcara saghyāsam (MS devapuraš carasa rdhyāsam) tvā MS TA. ApŠ MŠ But cf §838, it is doubtful if this belongs here.

ye bhakşayanto na vasūny ānrdhuh (TS ānrhuh, MS ānašuh) AV TS MS

āsannıvūn hrisvaso mayobhūn RV AV TS MS KSA N āsann esām apsuvāho mayobhūn SV See §820

2 r and i (once \bar{i})

§635. Here most of the variants can be justified lexically in either form Perhaps the clearest cases of Prakritism are the two following

The first is striking because of the persistence with which the Prakritic form occurs, in three out of four texts, and even in the fourth a v l has it

tejo yasasın sthanıram samıddham (SG samıddham, v 1 samı°) SG PG. ApMB HG See Edgerton, Studies in Honor of Hermann Collitz 34, samıddham is pretty clearly for samıddham

dadhişa ehi ApS dadhrsy ehi MS The forms are voc sing fem, and the first can hardly be anything but a Prakritic form of root dhrs, so apparently Caland, who renders 'Kuhne'

To these may be appended another, in which however \imath for r seems to be a textual corruption

ayam satrūn jayatu jarhrsānah (AŚ † jarhrs°) VS VSK TS MS KS SB TB AŚ But elsewhere AŚ has the vikāra aham sa° jayāmi jarhrsānah, indicating that jarhrs° is corrupt

§636. An interesting case, with a sort of lexical hyper-Sanskritism, is the next, gotrabhrd is probably felt sophistically as 'supporting the gens', but is fundamentally hyper-Sanskritic (the true epithet of Indra can only be the familiar gotrabhid), of Edgerton, Studies in Honor of Hermann Collitz 34

puramdaro gotrabhid (MS °bhrd, all mss , TB. maghavān) vajrabāhuh VS MS KS TB

§637. In words closely related in meaning, when the only or chief difference of form is the shift between ι and r, it is fair to assume some degree of Prakritic influence, even if the forms are both historically correct.

jāmım rivā māva paisi lokāt AV jāmım itvā mā vivitsi lokān TA The roots r and i are synonyms But Poona ed of TA jāmi mitvā

ādstyānām prasstir (MS °sytir) hetir ugrā MS TB TA 'Extension' 'progress' Cf. next two

prayatis ca me prasitis (MS. KS °srtis) ca me VS TS MS KS Cf prec and next

dīrghām anu prusitim (KS samrtim) āyuşe dhām (KS tvā) VS TS KS SB TB . dīrghām anu prasṛtim samspṛśethām MS Cf prec two

tām dhīrāso anudršya (VSK °dišya) yajante (KS. †anudršyāyajanta kavayah) VSK TS KS TB tām dhīrāsah kavayo 'nudišyāyajanta MS tām u dhīrāso anudišya yajante VS SB anu-diš 'assign'. anu-drš 'survey'.

tam ghed (MS. hed) agnir vṛdhāvati (MS vidh^o) RV TS MS In the original there are two words, vṛdhā avati MS. is obscure and probably corrupt, p p vadhā (sic¹), avati

- §638. To this same group belongs the single case involving long $\bar{\imath}$; it is of doubtful validity, since most MS mss read "mpte with the rest, and probably this should be adopted in the text—But the form as printed can be interpreted as a negative past participle of root mi 'change, alter'
- tasmın sīdāmīte pratitistha (MS text sīdāmīte pratitisthan) TB ApS. MS Add to VV I §250
- §639. Still pretty close to each other in meaning are the variants between hia (or dhia), participle of $dh\bar{a}$, in compounds, and bhrta (once hrta), from bhr (hr)
- sa tvā rāsirāya subhrtam bibhartu (Ppp pıpartu) AV. sa no rāsiresu sudhtam dadhātu TB
- gandharvo dhāma vibhṛtam guhā sat VS ga° nāma nihitam guhāsu TA MahānU And others; §855
- devair devāh samāhitāh RVKh (but Scheftelowitz °hrtāh) devīr devaih samāhrtāh (TB °bhrtāh) SV TB
- yad agne pürvam prabhrtam (AŠ prahitam, MŠ nihitam) padam hi te TB AŠ ApŠ. MŠ
- hiranye 'smın samāhıtāh (RVKh Scheftelowitz °hṛtāh, HG °bhṛtāh) RVKh ApMB HG
- garbha wa (SV KU. [Poley's ed] wet) subhrto garbhinībhih (RV sudhito garbhinīşu) RV SV KU
- sūryarasmım samābhtiam TS TB sūryāñ (p p °yāt) sukram samībhttam MS. sūrye santam (KS TA sukram) samāhtiam (KS TA samābhtiam) VS KS SB. TA
 - §640. Rather remoter are the remaining lexical variants
- priyo ma hrdo (MS hito, v 1 huto) 'si (MS †bhava) TS MS.
- ımā (MS ıdam) brahma pīpihi (MS pipīhi, v. 1 pipīhi) saubhagāya VS MS KS SB
- vrşajūtır no 'vṛtah (SV. 'vɪtā) RV. SV. a-vṛ-tah av-ı-tā (nom. ag , root av). hotrāvīdah (RV "vɪda, TB "vṛdha) stomataslāso arkaih RV AV. MS TB mā no vɪdad (KS vṛdhad) vṛṣinā (KS TB ApŚ "anā) dveṣyā † yā AV. KS TB ApŚ
- ındrarlublır brahmanā vāvrdhānah TB Ap\$ indra rbhublır brahmanā samındānah \$\$
- āñjanena sarpışā sam vı
śantu (AV spṛśantām, TA. mṛśantām) RV. AV TA
- atrāha tad urugāyasya viṣnoh (RV. N vṛṣnah) RV VS TS MS KS $\dot{\text{SB}}$ N $\dot{\text{V}}$ Viṣnu is meant even in RV , later texts substitute the name for the epithet

prāntar ṛṣaya sthāvirīr (SV prāntarikṣāt sthāvirīs te) asṛkṣata RV SV vācaspate hṛdvidhe nāman (MS MŚ hinvidhe) MS TA ŚŚ MŚ All mss and p p of MS agree on the strange form Even hṛdvidhe is none too clear (TA comm hṛdayasya vidhātah citaprerakety arthah)

vītrasyāsī (mītra°) see §235.

made-made hi no dadih (TB daduh, MS samh mss dadih) RV AV MS KS TB AS See §622

adrnhathāh śarkarābhis triviştapi (MŠ tribhrştibhih) KS ApŚ MŠ See §222

īśāno vi şyā (= şiyā, TS sījā) drīm AV TS MS KS

upa yajñam asthita (AV comm astria, MŚ astu no) vaiśvadevī RV. Kh. AV ApŚ MŚ

dame-dame suşiutyā (TS °tīr, MS ° tī, AŚ ŚŚ °tɪr) võurdhānā (AV °11111, AŚ ŚŚ vām 1yānā) AV TS MS KS AŚ ŚŚ See §236 [eṣa 1ṣāya (AV Berlin ed 1ṣaye, emendation) māmahe AV ŚŚ Keep 1ṣāya with AV mss]

3 $r(\tilde{r})$ and $u(\tilde{u})$

§641. The not very numerous variants under this head seem to be prevailingly Prakritic in character. We should expect u for r especially in the vicinity of labial consonants, but except in the first variant (before m), we hardly find this to be the case, the only other instances with labials (e.g. bhr and $bh\bar{u}$) are lexical. The most clearly Prakritic cases are

tvaşirmanlas (MS MŚ tvaşiri*, ApŚ tvaşiu*) tvā sapema VS MS KS SB KŚ ApŚ MŚ Cf tvaşirimatī (TS ApŚ and TA Poona ed tvaştī*) te sapeya TS TA ApŚ The Tatturiya form is feminized

ut (Vait adhāma) sakthyā (ŚŚ Vait °yor) ava gudam (TS KSA ApŚ sakthyor grdam) dhehi VS TS KSA ŚB ŚŚ Vait ApŚ Altho grda seems not to be recorded elsewhere, it may be presumed to be the original form of guda

etām samkrīya (MS MŠ °kaşya or °kuşya) juhudhi MS ApŠ MŠ See 8631

rtaprajātā (MŚ uta pra°) bhaga id vah syāma TS MŚ This may be called a lexical variant, since MŚ makes sense, but it is doubtless fundamentally Prakritic

§642. Some variants are on their face hyper-Sahskritic, but probably both are mere textual errors or corruptions

sa nırudhyā nahuşo (TB Conc nahrşo) yahvo agnıh RV TB But Poona ed of TB text and comm nahuşo, the only possible reading

devan manah kuto (AV kṛto) adhi prajātam RV AV Altho all mss of AV apparently agree on kṛto (if we understand Whitney's meaning), it seems that we must read kuto, with Whitney.

made-made hi no dadih (daduh, dadrk), see §§622, 640

§643. More purely lexical variants are

priyo me hrdo (MŚ hito or huto) 'si (MŚ †bhava) TS MŚ See §640 agner (ApŚ devā) akrnvann (RV apunann) uśijo amriyave (RV. °vah, ApŚ amariyave) RV MS.ApŚ

vanışlhor hrdayad (AV * udarad) adhı RV AV (both) ApMB.

upa yajñam asthita (astrta, astu no) . . , see §640

avımuktacakra (°rā) āsīran PG vıvṛttacakrā āsīnāh HG ApMB. Note labial consonants preceding r u

āyurdā deva (AV. agne) jarasam vṛnānah (ApMB. ApG HG gṛn°) AV MS KS MŚ ApMB HG ApG āyurdā (VS ŚB. āyuṣmān) agne havışo juṣānah (VS ŚB ŚG havıṣā vṛdhānah) VS TS ŚB TB TA AŚ ApŚ ŚG

§644. The only cases of long \bar{u} and r concern compounds of the roots $bh\bar{u}$ and bhr, which are practically synonyms here

adbhyah sambhrtah (TA MahānU Ap\$ sambhūtah) pṛthwyat (M\$ K\$†°vyā) rasāc ca (K\$ rasah) V\$ M\$ K\$ TA MahānU K\$ Ap\$ PG

samvešāyopavešāya gāyatryai (PB ŠŠ KŠ also trişļubhe and jagatyai; TS ApŠ gāyatriyās trişļubho jagatyā anuştubhah paūktyā) chandase (TS ApŠ omit) 'bhibhūtaye (TS ApŠ abhibhūtyai, ŠŠ 'bhibhrtyai, KŠ 'bhibhūtyai) svāhā TS PB ŠŠ KŠ ApŠ ariştyā avyathyai samvešāyopavešāya gāyatryā (also trişļubho, jagatyā, anuşļubho, paūktyā) abhibhūtyai svāhā ApŠ

Once \bar{r} is corruptly written \bar{u} in a single ms.

tāsām svasīr ajanayat (MS svar ajanan, KS ms † svasūr [ed em svasīr] ajanan) pañca-pañca TS MS KS

4 land u

§645. There are two cases, both concerning the same very interesting form. A perfect middle participle of root klp appears twice in ApS with u for l. There is no doubt whatever of the correct interpretation of the form, which is established by the KS variant, with correct Sanskrit vocalism. It is the clearest kind of Prakritism, but seems not to be recorded in any grammar or lexicon, nor in Whitney's Roots

- §649. In various participles and gerundives.
- atırātram varşan pūrtır āvrt (MS vavarşvān pūrta rāvat, KS vavrşvān pūta rāvat) svāhā TS MS KS See VV I p 147.
- jāgaritāya (KSA jāgrtāya) svāhā TS KSA Both equivalent participles adhā te viņno viduņā cid ardhyah (TB rdhyah) RV TB Gerundives, cf Whitney §963b, 4
- dāma grīvāsv avmokyam yat (TS avicartyam) AV TS pāśam grīvāsv avicartyam (VS ŚB °crtyam) VS MS KS ŚB Cf. prec AVPpp according to Whitney has °crtyam
 - §650. In other noun and adjective formations
- sam methir (ApMB sam te methī) bhavatu sam yugasya tardma (ApMB tṛdma) AV ApMB No stem tṛdman is otherwise known
- atandrāso yuvatayo tvibhriram (TB vibhartram) RV TB Poona ed of TB text and comm bibhartram Agni is referred to, TB comm poşakam
- aprajasiām pautramṛtyum ApMB HG aprajasyam pautramartyam SMB Comm on SMB repeats the form, glossing putrasambandhimaranam
- pra sa (tead su?) mṛtyum yuyotana HG · pra sumartyam (ApMB su mṛtyum) yuyotana ApMB. SMB prathamam artım yuyotu nah MG.
- agner (ApŚ devā) akṛnvann (RV apunann) uśijo amṛtyave (RV. °vah, ApŚ amartyave) RV MS ApŚ In ApŚ a blended stem -martyu (fused from marta, martya, and mṛtyu), cf prec
- jīvātave na mṛtyave (PB martave) RV PB Infinitive in PB
- sarūpavarsā ehi MS . sarūpa vṛṣann ā gahi SV JB
- vanasade (MS. vanarşade, KS vanrşade) vet (TS MS vat) VS TS MS KS SB The stem vanar, equivalent to vana, is found in RV. in compounds It does not occur independently, and vanr is not recorded even in compounds except here. The next preceding phrase in KS is nrṣade vet, the r of nr has perhaps been responsible for vanr°
- devāh pāntu yazamānam nyarthāt (AV. nurthāt) RV. AV TS. Synonyms, both meaning 'perdition', nurtha also Rigvedic
- [nışkartā (RV KS 15°, ApMB Conc wrongly nışkrtā) vıhrutam (PB TA. ApMB. vıhrtam) punah RV AV. SV MS PB TA KS ApMB]
 - §651. Miscellaneous and apparently unrelated words
- pratišrutkāyā artanam (TB rtulam) VS TB artanam, comm. duhkhinam, BR. 'reviler', rtulam, comm dešarājavārtākathanašīlam

 $sarn\bar{\imath}k\bar{a}ya$ $tv\bar{a}$ TS $srd\bar{\imath}k\bar{a}ya$ $tv\bar{a}$ MS Both words wholly obscure, said to mean 'water'

dvişas taradhyā (ApŚ ° yai) rnayā na īyase (SV. īrase) RV. SV KB AB ApŚ dvişas tad adhy arnaveneyase AV.

7 r and ār

§652. Here we find only a few cases, in most of which $\bar{a}r$ shows the vriddhi of secondary derivation, varying with the primary word with r Once a form with prefixed preposition \bar{a} varies with the same form without \bar{a}

aprajāsivam mārtavaisam AV aprajastām pautramriyum ApMB HG Others, §650

ārtavā (MS KS rtavo) adhipataya (MS KS 'dhī') āsan VS MS KS SB ārtavo 'dhipatir āsīt TS

rtavo 'srjyanta VS TS ŚB ārtavā asrjyanta MS KS agnir grhapatīnām (MS KS gārhapatyānām) VS TS MS KS ŚB ārtyai (TB rtyai) janavādinam VS TB Stem rti, from r ārti, from $\bar{a} + r$

8 r and vr, ur, ur

§663. Here are found only a handful of cases, almost all of which seem highly questionable or certainly corrupt Even corruptions are interesting in such a case, however, as signs of phonetic tendencies in later times at least As to r ir, we find just two cases in which the samhitā mss of MS (the same text each time!) read r for proper ir In both cases the p p points to the reading ir Von Schroeder inconsistently retains r in one case and emends to ir in the other, there is as much, or as little, justification in one as the other

nama ānırhatebhyah (MS ānr°, p p ānır°) VS TS MS KS SB anuttam ā te maghavan nakır nu (MS mss nakrnu, ed em nakır nu, p p nakıs, tu) RV VS MS KS

§654. Under r. ur we also find only a couple of cases, equally dubious again dvārā vy ravati RV TB Cone quotes uravati for TB; but Poona ed text and comm ra without v 1

satyaujasā dīnhanā (MS durhīnā, KS †dīnhanā) yam nudethe TS MS KS And others, see §305

nābhimṛśc (MS KS nābhidhṛṣc) taniā (TS tanurā) jarbhurānah (TS MS KS jarhṛṣānah) RV VS TS MS KS SB Might also be classed in §643

§655. Of τ : $\bar{u}r$ we find only the following, in which the root τ varies with the so-called 'root' $\bar{u}rnu$, really a form of $v\tau$ tresas te dhūma $\tau nvati$ (AV $\bar{u}rnotu$) RV AV SV. LS KS MS

9. r and ra, rā

§656. In so far as this variation is properly phonetic, it is mainly a matter of that form of ablaut which is called by modern westerners 'Samprasārana', with a misapplication of a term used differently in Hindu grammar. On this see Wackernagel I pp 69-71, and cf. the similar variations of i and i with i and i with i and i in the next chapter. There is one case, also, of i varying with i a which stands for i before i plus consonant, by the phonetic law formulated in Wackernagel I p 212 f. There are likewise a few variants which concern morphology (verb inflexion, and noun formation) and a few that are purely lexical, with some border-line cases which seem to be half-lexical, half-morphological

§657. The cases of so-called Samprasārana concern to some extent roots which are familiarly known in both forms (such as grah, grabh), to some extent rarer and more doubtful cases which are not recorded in Wackernagel's excellent treatment of the subject. They thus supplement our previous knowledge on the point. We begin with several variations of grabh, grbh, on which see especially VV I §281

agrbhīt VSK . agrabhīt VS AS SS

agrbhīşata VS · agrabhīşata KS

udgrābhenod agrabhīt (MS azigrabhat, KS azīgrabham, and azīgrbham) VS TS MS KS ŚB

agnaye tvā mahyam pratigrahītre (SS °grhnate) VS VSK MS SB SS prāno dātra edhi pratigrahītre (SS °grhnate) VS VSK SB SS The same with hayo dātra.

Similarly ablaut grades of another root, in various verb forms. use usam aprhthāh (aprāg apı) AV (both)

§658. In radical syllables of various noun formations the same change is familiarly known. Most of the following cases are sporadic and are not recorded in Wackernagel 1 c, some of the forms are so obscure that no theory of historic origin can be regarded as certain, and the phonetic shift may perhaps be secondary and analogical

hradam (MS hrdam) na hi tvā nyrşanty ūrmayah RV MS 'Like streams to a pool, flow down to thee (the hymns, brahmāni)' The ultimate etymology of hrada is not clear, but surely hrda can be nothing but a phonetic variant for it, presumably samprasārana Cf next.

- namo nīveṣyāya (p p ni°) ca hṛdyāya ca MS · namo hradayyāya (VS. hrdayyāya, KS hradavyāya) ca mveṣyāya (TS °ṣyyāya) ca VS TS KS See §248 The MS and VS forms simulate derivatives of hṛd and hṛdaya, but these can hardly be in place hẹre; the adjoining word means 'whirlpool' and apparently we must think of the same form hṛda = hrada found in MS in the preceding variant
- pṛkṣasya (ArS prakṣ°) vṛṣno aruṣasya nā sahah (ArS mahah) RV ArS AB KB AS SS Svidh pṛkṣa is a name or epithet of a horse, its etymology is obscure, and pṛakṣa has not been recorded elsewhere
- numrado (ApŚ numrdo) 'sı MS KS ApŚ MŚ Apparently different grades of root mrd, Wackernagel p 71
- avātīratam brsayasya (TB prathayasya) šeşah RV TB See §69.
- bhrjas chandah MS bhrajas chandah VS TS SB bhrājas chandah KS † (but v 1 bhra°) The word is said to mean 'fire', and apparently comes from the root bhrāj, which is not mentioned as such by Wackernagel 1 c but may be related to bhrajj, Wackernagel p 69, cf also bhargas etc There is much confusion in the forms of this root or these roots Cf next
- kşuro bhrajas (TS bhr.jvāñ, MS bhr.jas, VS, bhrājas, stigmatized by Conc as erroneous, hardly with justice) chandah VS TS MS KS SB Cf prec
- ārdrah prathasnur (MŠ †pṛthusnur, v l pratha°) bhuvanasya gopāh TB ApŠ MŠ See §609, and Wackernagel p. 71
- svasty apsu vrjane svarvati (MG tvrajane svarvatah) RV AB MG Really a lexical variant, vrajana 'way' is suggested by pathyāsu of the preceding pāda But some MG mss read with RV
- [digbhyas cakravākah (KSA Cone cakrav with the sole ms. ed em cakrav) TS KSA This is probably a mere corruption, if genuine it would have to be a purely phonetic variant, for the meaning is certainly the same l
- §659. The roots $r\bar{a}dh$ and rdh, the separated in the history of the language, and the often regarded as unrelated, are at least quite possibly of identical origin, and certainly the repeated variation between them belongs phonetically with this group Cf also §806
- rdhyāsam adya makhasya sırah MS TA, Ap\$ · makhasya te 'dya sıro rādhyāsam devayajane pṛthwyāh VS \$B [The references to MS MS ın Conc seem to be erroneous]
- tan me rādhyatām VS TS SB TB TA SS MS Kaus SMB tan me samṛdhyatām (Kaus samṛddham) TB SMB Kaus

harıvato graham rdhyāsam KS : harıvato harıyozanasya harıvantanı graham rādhyāsam MS

§660. The single case noted of r varying with ra for ar before s plus consonant (Wackernagel I p 212 f) is.

sams
rṣṭāsu yulsv ındro ganeṣu MS : samsraṣṭā (AV. v l samsrṣṭā) sa yudha ındro ganena RV AV SV VS TS. KS

§661. From the root δr , also quoted as $\delta r\bar{a}$ 'boil', are found the two participles $\delta r ta$ and $\delta r\bar{a} ta$, which exchange in the following, in which $\delta r ta$ happens to be secondary, but it is equally old otherwise subratam (AV subrtam) manue tad rtam navivah RV AV.

susraiam (AV susriam) manye lad riam naviyah RV AV.

 $\S662$. The remaining variants cannot be called purely phonetic In verb inflexion forms in r vary repeatedly with other forms in which a morphological a (thematic vowel, or part of a different personal ending) is added, producing ra.

āpo grheşu jāgrata HG · āpo jāgrta MS KS MS āpo havihşu jāgrta ApS āpo deveşu jāgratha PG See VV I p 123

ye ca bhūteşu jāgratı (KS jāgrtha) AV. KS See VV I p 221

yajamānāya jāgrta ApŚ: saputrikāyām jāgratha PG See VV I p 96 te na ātmasu jāgrati (KS † jāgrta) AV KS

yat pasur māyum akrta TS SS. KS ApS. MS SMB GG · yad vasā māyum akrata Kaus See VV I p 257.

yatra-yatra vibhrto (KS bibhrato) jātavedāh AV KS Both forms are textually uncertain (for variants see VV I p 158), and obscure as to interpretation

§663. Similarly in noun formation, a stem in r varies with a derivative in suffixal a

hotralānām (MS hotrh°, v. l hotrak°) camasādhvaryavah. ApS MS The words hotrka 'secondary hotr' and hotraka 'pertaining to the sacrifice (hotra)' are finally synonymous names for a certain priest See Caland on ApS 12 23 4

\$664. Finally, we find similar shifts in words which are lexically quite unrelated, notably three between the stem kratu and forms of the root kr. Both are important in the ritual, and the repeated interchange may well signify an association of them in the minds of the Vedic poets, by popular etymology

puñjikasthalā (KS †puñjiga°) ca kṛtasthalā (VS ŚB kratu°) cāpsarasau VS TS MS KS ŚB Proper names, and so naturally flexible

samsışlam ubhayam krtam (KS abhayam kratum) KS TB ApS KS.
ındra kratvā (MS ındrah krtvā) maruto yad vasāma RV MS KS The

MS, which is certainly secondary and poor in indrah, reads the

gerund $krtv\bar{a}$ for $kratv\bar{a}$ by a phonetically easy slip, which is banal to the point of senselessness

maınā arvā renukakā(ah pṛnak (MS † [v 1 pṛnak] KS pṛanak) MS. KS TB pṛa-nak, from nas, 'attaın', with pṛa; pṛnak from pṛc

indrāya tvā sīmo 'dadāt (ŚG śramo dadat) MS MŚ ŚG SMB See §277 §665. The other lexical variants are more remote from each other in sound, and the resemblance becomes very vague.

drapsas caskunda prihivīm anu dyām (RV prathamān anu dyūn) RV. AV VS TS MS. KS SB Vague assonance only

tam tvam višvebhyo devebhyah kratūn (KS °bhya rtūn) kalpaya KS ApŚ sā (read sa?) nah prajām pašūn pāhy aranīyamānah (p p aháh, ánī, yámānah) MS . sa no rucam dhehy ahrnīyamānah TA The MS is hopelessly corrupt, probably read ahrnīyamānah

atrā te bhadrā raśanā apasyam (KS bhadrā vrsanā agrbhnām) RV VS TS KS.

ıdāsmān anu vastām ghrtena ApŚ MŚ: ıdawāsmān (RVKh ılawa vām) anu vastām vratena RVKh AV Scheftelowitz reads ghrtena in RVKh

ıdam aham sarpānām.. grathnāmı (MŚ mss kṛtsnāmi) TS ApŚ MŚ. See §47, MŚ perhaps corruption for grath°

nadayor vıvratayoh süra ındrah RV na devo vrtah süra ındrah SV See \$828

vısvaır devai rātibhih samrarānah (MG devair rtubhih samındānah) ApMB MG.

āvitte dyāvāpṛthɪvī ṛtāvṛdhau MS KS āvɪnne dyāvāpṛthɪvī dhṛtavrate TS TB. In this and the next, TS has interchanged the two old adjectives ṛtāvṛdh and dhṛtavrata (both RV)

āvīttau (TS āvīnnau) mitrāvarunau dhṛtavratau (TS °nāv ṛtāvṛdhau) VS TS MS KS ŚB Cf prec

10 r and ri, rī

§666. Since r and r have been pronounced alike for centuries by most Hindus, it follows on the one hand that such variations are especially open to the suspicion of corruption, and on the other that genuine variations of this sort may be expected to occur fairly early, as forerunners of the later change of r to r (which occurs, sporadically but not seldom, in the middle Indic dialects). On the whole subject see provisionally Wackernagel I pp. 31 ff. It is a well-known fact that Hindu mss, including those of Vedic works, show much fluctuation in this regard. As a single instance, which might be multiplied indefinitely,

we call attention to Whitney's note on AV. 5 14 3, apropos of the pādariśasyeva parīšāsam So the Berlin ed prints it But Whitney informs us that most miss read rśasyeva, and observes that this is a common phenomenon in them In this case Whitney advises adopting their reading into the text; we agree with him. Against most miss, but with some of them and with the comm, Whitney, would also read rśyapadīm vrṣadatīm in AV. 1 18 4a, where both editions have riśya.

§667. These AV cases do not differ in principle in the slightest degree from the following readings of MS, which presents trisu for trisu (adverb 'eagerly', from root trisi) and trisit for the god-name trisit. We agree with Von Schroeder's judgment in keeping the readings of his mss, despite the unquestionable meaning of the words. In short, we believe that the Maiträyaniyas pronounced the words in this way, and that we are dealing with real phonetic (dialectic) variants, not 'corruptions' in any proper sense of that word:

trşu (MS trışu) yad annā vevişad intişihase RV SV. MS ApS trşucyavaso (MS trışu') juhvo nāgneh RV. MS

tvaşirmantas (MS MŠ tvaşiri°, ApŠ. tvaşiu°) tvā sapema VS. MS. KS SB KS ApS MS Others, see §641

§668. Similarly, but in a very much more wide-spread and insistent fashion, the word for 'worm' is frequently and in many texts written krimi, althouts original form seems to have been krimi (Wackernagel I p 33, Uhlenbeck, Etym Wbch, s v) Several variants show both forms of this common word.

hatas te atrınă krımıh (GG kr°) SMB. GG atrınă tvă krime hanmı TA ApS atrıvad vah krımayo hanmı AV.

hatāh krimayah (but Jörgensen text and comm kr°) sāśātikāh sanīlamakṣikāh SMB · āśātikāh krmaya (but Poona ed. krr°, v. 1 kr°) wa TA Note that different editions differ on both texts! nīlamgoh (MS °gave) krmih (TS kri°) VS. TS MS KSA.

§669. So far we have mentioned only cases in which it appears that the regular or original form had r, not r. But the opposite is also not uncommon. It may be regarded as a kind of hyper-Sanskritism, or at least, it presupposes a tendency to pronounce r and r in a similar manner, at any rate in certain linguistic spheres. In some cases, to be sure, as in the preceding group, the tradition of the mss is confused and we may be confronted with late corruptions. But it would be very rash to make this assumption as a general explanation of the most of such cases. The fact seems to be that this pronunciation of r as r is much more ancient than has often been supposed, and must have had some

sort of existence in Vedic times, however limited geographically or socially

§670. Take for instance the proper name Trita, which is quite definitely established in that form as prehistoric (Avestan Thrita) Yet thrice in a single hymn of AV (6 113 1 and 3) it is spelled Trita, according to all mss known to both editions. In such cases we should not emend, as Shankar Pandit does, even tho the TB parallel for two of the pādas (the third is not recorded elsewhere) gives the usual and proper form Trita. In short, we feel no right to assume that the Atharvan tradition had any other form than that presented by all mss tria enam (read enam. TB trita etam) manuscress manning (TB mā°)

iria enam (read enan, TB trita etan) manuşyeşu mamrje (TB mā°) AV TB

trte (TB trite) devā amrjataitad enah AV TB

§671 There is little doubt that the MS form $\bar{a}paprv\bar{a}n$, which evidently gave Whitney considerable trouble in his *Roots*, is simply a phonetic variant for $\bar{a}paprv\bar{a}n$ (perfect active participle to $pr\bar{a}$) instead of an independent participle of pr, as Whitney questioningly suggests The MS p p has pr

āpaprīvān (MS āpaprīvān) rodasī antarīksam RV VS TS MS KS ŠB

§672. The verb sredhati makes it clear that sridh is the proper form of the stem found in the next variant. In fact many AV mss read sridhah, which Whitney regards as the true AV reading at inho at sridhah (AV MS srdhah) AV VS TS MS KS

§673. In the next krivi is the only form known to RV, and so may perhaps be assumed as the original, both etymology and meaning of the word are unknown

ā va ındram krıvım (SV Svidh krvım) yathā RV. SV ŠŠ Svidh adha tvışīmān abhy ojasā krıvım (SV krvım, v 1 krıvım) yudhābhavat RV SV

§674. According to Wackernagel I §180b, r was regularly replaced by ri before y, by phonetic law, when r appears before y, as in the majority of texts in the next variant, it would then be due to analogy. In the second variant the original (AV) reading was pronounced $pitriy\bar{a}c$, and for this TA $pitry\bar{a}c$ is merely a phonetic variant, with r for proper ri vayam $r\bar{a}sitre j\bar{a}gry\bar{a}ma$ (MS † KS † $m\bar{a}$, TS and p p of MS $j\bar{a}griy\bar{a}ma$) $purohit\bar{a}h$ VS VSK TS MS KS ŠB

dyaur nah pıtā pıtryāc (TA pıtryāc) cham bhavātı (TA bhavāsi) AV TA

Cf the next where the RVKh reading is doubtful.
āvvusam jāgriād aham AV dvyusam jāgrijād aham RVKh Aufrecht:

but Scheftelowitz $\bar{a}vyu$ şam $j\bar{a}gry\bar{a}m$ (em , for ms $^{\circ}y\bar{a}my$) aham Cf VVI p. 102.

§675. The epithet of Rudra concerned in the next is of wholly obscure origin and meaning, presumably MS is secondary

vikirida (KS °da, VS °dra, MS vyakrda) vilohita VS TS MS KS.

§676. Finally a few corruptions and false readings

ya rte (TA ApŚ ApMB yad rte, PB †yakşate) cıd abhışrışah RV AV SV PB TA KŚ ApŚ MŚ Kauś GG ApMB yarı cetid (mss cetid, pp cya iti it) abhışışah MS (grossly corrupt, cf §193)

sam tvā rinanti (Vait rnanti) LS KS Vait Note the anomalous sandhi in Vait, sam-r and sam-ri would be virtual synonyms, but a 9th class present from r is anomalous (allowed by the Dhātup, but not known in literature according to Whitney's Roots). The Vait reading is therefore doubly suspicious See §992

[1mau te pakṣāv (°sā) ajarāu patatrīnau (VSK TS KS °nah, Conc wrongly quotes TS as patatrīnah) VS VSK TS MS. KS ŚB §677. Twice r varies with $r\bar{\imath}$, both forms are morphologically justi fiable in both cases

śrtas tvam srto 'ham ApŚ śrītas tvam śrīto 'ham KS Participles of the root which appears somewhat confusedly as śr, śrā, śrī 'cook, mature'

adbhir viśvasya bhartiibhih ApMB adbhih sarvasya bhartiibhih SG In ApMB a distinctively feminine stem bhartii is used, to agree with adbhih, SG uses the stem bharti as of common gender

11 r and ru

§678. The shift between r and ru is only slightly less frequent than that between r and ri. There is equally good reason to regard it as having genuine phonetic bearings. In standard modern Marāthī the r of Sanskrit is regularly pronounced with an u coloring (practically ru, instead of ri as in most other vernaculars). That this tendency is very ancient is proved by RPr 14–12 (796), which states that some erroneously 'make the r-vowels like the labial vowels' (svarau kurvanty osthyanibhau sarephau). There are, to be sure, not so many variants that seem to be purely phonetic in character as was found to be the case with r ri. They seem to tend to associate with neighboring labial consonants, and perhaps justify an assumption that the vocalic r in conjunction with labials was apt to have u coloring

§679. Among the clearest phonetic variants are

bhrmim (TB. bhrumim) dhamanto apa gā avrnata RV TB Note that the sound occurs between two labial consonants. The original bhrmi is not very clear, one of Sāyana's theories is that it means 'cloud', which is the meaning assigned to bhrumi by TB comm, who derives it from root bhram

druāsi VS. drbāsi KŚ drubāsi VSK An obscure word, note the following b There is no way of determining the original form §680. A clear case of hyper-Sanskritic r for original ru is the stem prsvā, found several times in Tait texts for regular prusvā, note the preceding p BR call prsvā a 'falsche Form', but it is too persistent to be thus lightly dismissed. TA comm explains by jalabinduh It seems clear that it was the established Tait school form of prusvā, tho there has been much confusion about it among interpreters, see e.g. Keith on TS 7 4 13 1

pruşvā aśrubhih VS MS · aśrubhih pruṣvām (TS pṛṣ°) TS KSA pruṣvābhyah (TS pṛṣ°, KSA ed pruṣṭābhyas, ms praṣṭā°, read probably pruṣvā°) svāhā VS TS KSA

śam u prsthāva (read with Poona ed text and comm prsvāva) šīyatām TA śam te prusvāva šīyatām AV

§681. Hyper-Sanskritic, again, is the r in the following cases; we do not venture to say whether the following labial bh (part of an inflexional ending) is concerned in the change. At least the r form seems quite well established in the Tait school, the MS is more seriously corrupt pura jatrubhya (TA APMB jartrbhya, MS cakrbhya, p p vaktrbhyah) ātrdah (MS °da) RV AV SV MS PB TA KS APMB

§682 The remaining variants contain at least a semblance of independent lexical interchange. Thus, the roots of and or are virtual synonyms, and their derivatives of and or the both mean 'course, way' die stuti (VS KS SB Brhu KS oft, and so TB Conc, but Poona ed stuti) as fravam prinam RV VS MS KS SB TB Brhu SS KS ApS MS. (Von Schroeder needlessly emends KS 38 2 to stuti)

namah srutyāya (KS srt°) ca pathyāya ca VS TS KS namah pathyāya ca srutyāya ca MS Derivatives of the words concerned in the pree ā tvā parisrutah (AG °śritah, MG °srtah) kumbhah (ApMB † °āh) AG PG ApMB MG enam parisrutah kumbhyā ŠG · emām parisrutah kumbhah AV pūrnān parisrutah kumbhān ŠB No form parisrt is otherwise recorded, despite the equivalence of the two roots, it is probable that MG (all mss) has a phonetic variant or corruption for parisrutah

hiranyam astriam (SB BrhU. GP asrutam) bhava SB. BrhU KBU AG SMB PG ApMB HG MG Here sru varies with str; 'indestructible' or 'unmolten' (gold)

Cf mṛgasya sṛtam (HG sṛtam, ApMB vv. ll srutam, śrutam) akṣnayā ApMB HG See §278

§683. Similarly hr with w becomes a synonym of hru with w, the participles of both, exchanging twice, mean 'confounded, gone astray' or the like A third variation between hr and hru is merely a textual corruption

avinaşlan avıhrutan (AS °hrtan) MS KS AS ApS SG

- işlartā whrutam punah RV KŚ · nişkartā (Conc wrongly °krtā for ApMB) whrutam (PB TA ApMB vihrtam) punah AV. SV. MS PB TA ApMB In TA there is a v l whrutam, adopted in the text in Poona ed, but the comm even there reads whrtam, and glosses visesena bhagnam
- aslonā (comm asronāh) angair ahrutāh svarge AV. aslonāngair ahrutā svarge TA But Poona ed text and comm ahrutāh, v. l °tā, for TA, and this is the only possible reading. The simple hr is not a synonym of hru, ahrta would make no sense, comm kauļutyarahītāh (=ahrutāh).
 - §684. Miscellaneous cases, largely suspicious:
- ruvad dhokṣā (TB nṛvadbhyo 'kṣā) paprathānebhir evaih RV MS KB TB The original has ruvad dha-ukṣā 'the bull roared' This is misunderstood and corrupted in TB
- śwā rutasya (VSK śwa rtasya, TS and v 1 of MS śwā rutasya) bhesajī (MS °jā) VS VSK TS MS KS. Original is certainly rutasya. 'healer of what is injured' Rutasya, 'Rudra's healer', is an obvious lect fac, and rtasya, 'healer of the rta' or 'the rta's healer', while formally intelligible, is clearly a stupid change conditioned by the phonetic relations between r and ru
- satyaujasā drnhanā (MS durhrnā, KS †drhanā) yam nudethe TS MS KS.. sacetasau druhvano yau nudethe AV Multiple confusion, see §305, etc
- mayobhūh samtamā yad dhrudo (comm dhrdo) 'sı TB So Conc, but Poona ed text with comm dhrdo.

CHAPTER XV. THE I AND U DIPHTHONGS AND SAMPRASĀRANA

§685. In most of the variants collected in this chapter, phonetics can be said to be only an ancillary motive in the shift That is, nearly all of them present interchanges between forms both of which can be iustified by recognized principles of morphology or levicography They mostly concern ablaut, in radical or suffixal or inflectional syllables. or various details of the inflection of nouns, pronouns, or verbs, with a sprinkling of purely lexical variants Yet in some parts of the chapter, dialectic (Prakritic) phonology is certainly suggested as a contributing This is especially true as regards the exchanges of the short and long diphthongs. e at and o. au, and the interchange between e and aya, o and ava, and the like Altho some sort of independent interpretation of both the forms is regularly possible, their number is too large to make it reasonable to ignore the corresponding (the purely phonetic) shifts between Sanskrit and the Middle Indic dialects, in view of the now well established fact that Prakritic phonology played a large rôle in the speech of Vedic times

1 2 · e

§686. The not very numerous cases collected here are mostly matters of ablaut in the radical syllables of nouns and verbs, or of different case-endings of the same or related noun stems, with a residuum of lexical variants. We begin with those which present different ablaut grades in the radical syllables of the same or related nouns and adjectives.

atra (ŚB atrā) jahīmo 'śwā ye asan VS ŚB atrā jahāma (AV jahīta) ye asann aśevāh (AV *aśwāh, *asan durevāh) RV AV. TA The meter properly requires aśevāh if the word be final (VS ŚB transpose)

yā sarasvatī višobhagīnā (MS ApŠ * veša*, KS vešabhaginī) . . . MS KS ApŠ višo- is gen sing of viš

dıvyah losah samukşıtah MS davvyah kosah (AV SırasU. devalosah) samubjıtah AV TS KS SırasU

divo jyote (KS *jyotir) vivasva (MS devajūte vivasvann). .MS KS vivasvān aditir devajūtis TS

devya (ApŠ dwyā, v 1 devyā) āpo nannamyadhvam . . PB KŠ ApŠ

- sūryo dīvo (TS KS * devo) dīviṣadbhyah (TS KS. °bhyo...) TS. KS * MŚ
- punse putrāya rettavai (SB BrhU vittaye) SB TB BrhU ApMB ApS HG.
- pra suvānāso (SV. svā°) bṛhaddweşu (SV. °deveşu) harayah RV SV. lekah salekah . . TS salılah salıgah . MS KS See §49
- §687. Of different origin and only superficially resembling these cases is the numeral adverb $tredh\bar{a}$, which is originally trissyllabic and therefore probably to be regarded as representing a contraction of something like $trayadh\bar{a}$ (cf. §§744 ff below, Wackernagel I p 53, III p 347).
- tridhā (MS tredhā) baddho vṛṣabho roravīti RV VS MS KS GB TA ApŚ. MahānU. N
 - §688. In the stem-syllable of verbal forms
- maişām uc cheşi kim cana AV: maişām kam canoc chişah TS TB Ap\$ · māmīşām kam canoc chişah RV. SV VS.
- yah prānato nīmīsataš (v 1 KS nīmēs°) ca rājā MS KS yah prānato nīmīsato (VS. nīmēs°) mahītvā RV. AV VS TS KSA Present participles for 6th and 1st class present stems of nī-mīs, the 1st class stem seems not to be otherwise recorded Add to VV I §197.
- vāmī te samdrši višvam reto dhiṣīya (MS dhe°).. MS KS. višvasya te vāmīr anu samdrši višvā retānsi dhiṣīya TS Cf next The form dheṣīya seems to be established in the Maitr school. It can hardly be interpreted except as an aorist of dhā 'place', yet is highly anomalous if so understood (as if the root were dhi, with guna dhe! perhaps by confusion with root dhī?) See VV I p 186
- somasyāham devayajyayā suretā (MŠ viśvam) reto dhişīya (MŠ dhe°) TS ApŠ MŠ
- §689. In inflectional endings of verbs i and e exchange very commonly as between active and middle-passive forms and elsewhere See VV I §§39–79 and 82 et passim.
- §690. Coming to noun case forms, we find first a little group of datable plur forms in *ibhyas*: ebhyas, from stems in i(n) a
- dwācarebhyo (MG. °cāribhyo) bhūtebhyah (sc namah) MG. ViDh · ahaścarebhyah (sc namah) ŚG
- nakiamcarebhyah SG V1Dh: nakiamcārībhyo bhūtebhyah MG
- marudbhyo grhamedhibhyo (MŚ °dhebhyo) 'nubrūhi ŚB. MŚ marudbhyo grhamedhibhyo (MŚ °dhebhyo) başkihān (MŚ. vaş°, ApŚ bāşkān) VŚ MŚ ApŚ
- svāhestībhyah (Kauś °tebhyah svāhā) KS Kauś 1stebhyah svāhā vasad anīstebhyah svāhā TB ApŚ

- §691. The others are miscellaneous case-forms, since they are of slight interest here we shall content ourselves with a few examples, referring to our volume on Noun Inflection for full lists
- pūṣne śarase (MS † °si) svāhā MS TA ApS. svāhā pūṣne śarase VS. SB KS The majority reading (dat) is certainly not easily intelligible (labored and worthless explanations in the comms.); but the loc of MS is also difficult and may be only an attempt to rationalize an unintelligent passage
- hrranyapakşah śakunıh HG hrranyaparna śakune PG. Nom: voc pra vo mahe mahividhe (SV PB mahevidhe) bharadhvam RV SV AV. PB AS SS The SV seems to have a mechanical form-assimilation to the surrounding datives (note especially the identical form mahe preceding)
- vı sloka etu (AV. eti, TS ŠvetU slokā yanti) pathyeva (KS patheva) sūreh (AV MS.† sūrih, TS ŠvetU sūrāh, KS † sūrah) RV. AV VS TS MS KS ŠB ŠvetU Nom gen.
- agnır hotā vetv agnır (AS agner) hotram vetu (vettu) . TB. AS SS: agnır hotā vettv agner hotram vetu . SB Nom gen.
- kratvā varış|ham vara āmurım uta RV AV : kratve vare sthemany āmur|m uta SV
 - §692. Oddities of noun stems.
- agner agneyāny (KS agnī) ası (MS v. l and p p agner agner yāny ası)

 MS KS devānām agneyāny ası TS agner yāny ası TS MS. KS

 Ap\$ M\$ See §357, and cf vāyosāvitra ., §716
- frudhi fruta fraddhivam (AV fraddheyam) te vadāmi RV AV See §248, both forms have the force of gerundives
- §693. The remaining variants are lexical, but in the first we have a shift which simulates ablaut, as in §688
- sa idhāno (KS edh°) vasuş (MS vasuh) kavıh RV SV. VS TS MS KS The roots idh and edh are quite independent, but superficially the change looks like a change from ml-grade to guna
- ā yāhi (and, ā no yāhi) tapasā janeşu (ŚŚ °şv ā, MS janişva) MS AB AŚ ŚŚ ApŚ The MS form could be interpreted as a 2d sing impv from jan but for the accent (jánişva), which seems to call for emendation
- no (AV enā) višvasya bhwanasya gopāh RV. AV N ino, nom of stem ina, enā, adverbial pronominal form.
- utem (SV ūtim) arbhe havāmahe RV AV SV MS uta-īm acc sing
- krīdī ca lākī cojjeşī (ApŚ sālī †corjişī ca) VS VSK ApŚ See §407.

āsannışün h_ītsvaso mayobhün RV. AV. TS MS. KSA. N: āsann eşām apsuvāho mayobhūn SV. See §820

[vācā mendrīyāviša TS. KS MS. Conc. vācam indro for KS., so ed. reads at 4 14, but at 31. 15 (p 18, n 1) it is corrected]

§694. Several times a word beginning in \imath varies with the same word preceded by \bar{a} :

ındram (SV. endram) agnım ca vodhave RV SV

iha (MS AS ŠŠ eha) gatır vāmasya TS MS TB ŠB AŠ ŠŠ †1 14 19 tve ışah (KS. viśve; MS. tva eşah) samdadhur bhūrvarpasah (TS † bhūrrretasah) RV. SV VS TS MS KS ŠB See Von Schroeder's note If correct, MS must intend tve, ā, ışah, but the pp reads tve iti tve, ışah.

tāv (tā) ehi (eha, cva, AV. iha) . , see §§578, 888

rnān no narnam ertsamānah AV nen na rnān rnava it samānah TA See §180

ādītyānām patvānv (PB °mānv) ihi (KSA †ehi) VS. TS. MS KSA PB SB TB MS ApMB.

2 7: e

§695. Here the variants are few and scattering, except for a considerable group concerning case-endings of the same or related nouns and adjectives. Often the stems presupposed by the case-forms involved are slightly different.

višo yantre (KS yantrī) nudamāne arātim KS TB ApŠ Duals from stems yantrā and yantrī

samgayī (MS. SB "gavī, TB "gaye) zīradānū (SB. zīva") MS SB TB. AS SS. Also femmine duals.

vairājī (KSA†°je) puruṣī (so KSA†) TS KSA. Also fem duals; there seems no reason to emend KSA as von Schroeder would do. rātri (TB. °rī, KS v l °rih) stomam na jigyuṣe (KS†TB °ṣī) RV. KS. TB

mahī višpatnī sadane (KS °nī) riasya KS. TB ApS MS Here sadane is loc sing. '(come) to the seat of the ria' KS makes sadanī fem dual, 'as two seats of the ria' (addressed to the aranis), the other reading is simpler and most likely original

vaisvānarāya matir navyasī (ArS °se) sucih RV ArS Nom. sing fem . dat sing mase (with agnaye in next pāda).

nābhā samdāyı navyasī (SV. °dāya navyase) RV SV. As prec.

rāyas poşam cıkıtuşe (AV °şī) dadhātu (SS dadātu) AV. TS MS KS SS As prec

lālīlāya (MahānU lāle°) dhīmahī TAA † (not TA.) MahānU. Names of Agm, of unknown origin Hardly to be classed as ablaut The two comms have different and equally ridiculous explanations. aṣādhāya sahamānāya vedhase (TB. mīdhuṣe) RV. TB. N Lexical

In the reduplicating syllable

aindrah prāno añge-añge ni dīdhyat (TS ni dedhyat, VSK nidhītah) VS. VSK TS MS KS SB The reduplicating syllable with e should mark an intensive, and probably the isolated form of TS is felt as such, of VV I pp 149, 160

§697. Cases concerning verb inflection An aor ind varies with a present opt But the KS ed reads as ApS, with v 1 as Conc..

grāvāvādīd (Ap\$ grāvā vaded) . KS Ap\$ VV I p 86

anu stomam mudīmahı (PB made") RV AV PB. Optatives of different verbs

mā tvāgnīr dhvanayīd (TS °yīd, KSA. °yēd, MS dhanayīd)...RV VS. TS. MS KSA

§698. Twice the presence or absence of the preposition \bar{a} is responsible for the variant, of §694.

vāmam pitrbhyo ya idam samerire (AV samī°) RV. AV. ApMB.

rnān no narnam erisamānah AV nem na rnān rnavān īpsamānah MS. See §180

3 1. ai

§699. Nearly all the variants noted here concern derivative noun and adjective stems with the vriddhi of secondary derivation, varying with primary or secondary formations without the vriddhi

varśvānara uta vrśvadāvyah AV KS: yo varśvānara uta †vrśvadāvyah (ApŚ varśvadevyah) MS ApŚ Whitney's Transl. adopts for AV vrśvadevyah, which he states is the reading of Ppp, but this is an error, Ppp (Barret, JAOS 32 358) has °davyah, intending °dāvyah Only ApŚ has a derivative of vrśvadeva.

dıvyah kośah samukşılah MS . daivyah kośah (AV ŚırasU devakośah) samubjılah AV TS KS ŚirasU.

achınno dıvyas (KS ApŚ daıvyas) tantur mā mānuşas (KS ApŚ. manuşas) chedi MS KS ApŚ

brhanto dawāh (VS dwyāh) VS MS Ap\$

nırbādhyena (AV naır°, Ppp nır° according to Whitney) havışā AV TB ApS

brhatā tvā rathamtarena traisļubhyā (KS trisļubhā) vartanyā...MS KS: brhadrathamtarayos tvā stomena trisļubho vartanyā TS.

aghorena cakşuşā mitriyena (ApMB. maitreņa, KS ApS. calşuşāham bivena) AV KS ApS ApMB

ındrasya vaımrdhasyāham (KS ındrasyāham vimrdhasya) devayayyayāsapatno (ApS. but not †MS adds vīryavān) bhūyāsam KS ApS MS

kapota (MS °tā) ulūkah sasas te nırrtyaı (TS. KSA. nairrtāh) VS TS MS KSA.

nırriyaı svähā MS: naırriyaı (sc dise) svāhā VāDh

vihāyaso (PG. vaih°) 'dhi bhūmyām HG. PG vi°, abl of vihāyas, vai°, nom of adj vaihāyasa.

ındrasya suşmam îrayann apasyubhıh RV. SV.: aındrah suşmo visvarüpo na ağan AV.

vaivasvato (AV vivasvān) no abhayam krnotu AY. TB TAA SS ApS SMB. PG HG vai°, of course, means Manu

harranyanābhah (SS. hir') Lausalyah SB SS

indropānasyakchamanaso (MŚ aindro°). ApŚ MŚ The formula is so obscure, that emendation of MŚ to indro°, while tempting, is hardly safe

§700. Otherwise we find only miscellaneous cases, two concerning noun inflection

undrādhipatih (MS KS "patyaih) piprtād ato nah TS MS KS AŚ 'O Indra, as overlord (by overlordships)' etc

tam (MS. tan) mã devã avantu śobhāyan (MS °yı) TS MS TA The form in yan is dat of stem śobhā, 'unto splendor' The yı form would seem to be acc neut. of a stem śobhāyın (cf §247), perhaps used adverbially

Two concerning agrist verb forms

āpo malam ıva prānaikṣīt (ApS prānijan) AV ApS See VV I p 129 pitur ıva nāmāgrabhiṣam (ApMB °bhaiṣam) ApMB HG See VV I pp 139, 186

And one in which ai contains the augment yam aichāma (ApŚ ichāmi) manasā so 'yam āgāt RV ApŚ

4 ī ar

§701. Most of the few variants noted here concern interchange between instr plur, and nom-acc plur (fem) forms. indrena devīr (MŚ devair) vīrudhah samvidānāh TS MŚ devīr devīr (ApŚ devair) abhi mā nivartadhvam MS ApŚ MŚ sapta ca vārunīr (PG °nair) imāh AG PG ŚG MG sapta ca mānuşīr imāh ApMB HG Followed in all by

- tısras ca rājabandhavīh (HG °vaıh) HG ApMB prajāh (this word belongs to prec pāda) sarvās ca rājabāndhavaıh (MG °vyah) PG. MG sarvās ca rājabāndhavīh (SG † °bāndhavaıh) AG ŚG
- ā dadhnah kalaśair (ApMB °śīr, MG °śam) aguh (AG ApMB ayan, SG. gaman, PG upa, HG ayann wa, MG airayam) AV AG SG PG ApMB HG MG
- §702. There are three cases of vriddhi of the first syllable, the first two (especially the second) anomalous, and one agrist verb form, also anomalous
- straışüyam anyatra dadhat AV . strīşüyam anyān sv (read anyāsv) ā dadhat ŚG
- madhvā yajām nakṣatı (VS TS nakṣase) prīnānah (AV prai^o) AV VS. TS MS. KS In the pres mid pple the vriddhi is quite out of place, 'blundering corruption', Whitney
- yad adīvyann (MS davyam) rnam aham babhūva (AV. krnom) AV. MS. TA BDh adīvvyann rnam yad aham cakāra TB The original is adīvvyan 'not gambling', MS has a stupid lect fac Add to VV I §231
- ndra enam (TB ApS enam) parāšarīt AV TB ApS cf. indro vo'dya parāšarait AV. But for the last SPP. with most mss and Ppp. sarīt, the regular form See VV I p 186

5 e: at

- §703. Altho both forms can be defended morphologically in most of these variants, it seems to us very clear that the Prakritic change of at to e must be largely concerned in them. They are fairly numerous, the great majority fall into three classes, to wit: dative (or locative) forms in e at, forms with e at in the root syllable, in which at is generally the vriddh of secondary derivation, and verb forms, chiefly indicative and subjunctive endings
- §704. First, there is a large group of interchanges between the pronominal forms asme (dat or loc) 'for, to, in us', and asmai 'for him, it'. asmai (TB asme) dyāvāprthivī bhūri vāmam (Conc divides AV before vāmam) AV TB asme is secondary
- asme devāso vapuşe cikitsata TS ApŠ: śrad asmai naro vacase dadhā'ana VS KŠ Keith assumes that TS intends asmai
- asmaı (MS asme) rāstrāya mahı sarma yachatam TS. MS AS asmaı ıs certainly simpler
- suppppalā oşadhīh kartanāsme (AV kartam asmaı, VSK kartam asme) AV VS VSK MS 'For him' 'for us', equally possible

- savitrā prasavitrā . indrenāsme (VSK °smai) . VS VSK As prec asme (AV. asmai) dhārayatam (MS °tām) rayım RV AV. MS Different contexts, both possible
- asme (AV. asmaı) dhatta vasavo vasūnı AV VS TS MS KS SB N Equally possible
- asme (KBU asmai) prayandhı maghavann rjīşın RV KBU AG PG N asme rāşļrānı dhāraya (KS rāşļram adhısraya) MS KS asme kşatrānı dhārayer anu dyūn RV TS MS KS asmın rāşļram adhı sraya TS · asmaı kşatrānı dhārayantam agne AV. Kaus Different contexts
- asma: (MS asme) karmane jālah MS Ap\$ 'For our rite' 'for this rite'. Probably lect fac in Ap\$
- asme (AS asmai) indrābrhaspatī RV. TS MS KS AS Probably misprint in AS.
 - §705. Other dative forms in $e^{-\alpha t}$, including infinitives
- tā (VS ŚB yā, TS te) te (RV KS N vām) dhāmāny (RV. KS N vāstūny) ušması gamadhyaı (TS °ye) RV VS TS MS KS ŚB N The TS form is anomalous, cf Keith's note and Whitney, Grammar §976a Infinitives
- havyāyāsmai vodhave (KS °vai) jātavedah TS MS KS Kauś Infinitives
- sugam meşāya meşya
ı (RV °ye) RV VSK TS MS KS LŚ \cdot sukham meş
āya meşyaı VS ŚB
- agne samrād ışe rāye (ApŚ rayyai) AŚ ApŚ ışe rāye. . VS MS SB TB Cf §396
- ābhış (vāham . . sūtave (HG °vai) HG ApMB
- kuhvai (KSA kuhve, ed em °vai) trayo 'runaitāh TS KSA
- punse putrāya vettavai (SB BrhU vittaye, KS †kartave, MG kartavai, v 1 °ve) KS SB TB BrhU. ApS ApMB HG MG
- šakrāya sunavai (JB °ve) tvā RV JB
- śriyai (MG śriye) putrāya vettavai (MG vedhavai) ApMB MG śam tokāya tanuve (SMB tanvai) syonah TS TB ApŚ SMB PG
- parıdhāsyaı yasodhāsyai PG parıdhāsye yaso dhāsye MG · cf parīdam
 - vāso adhithāh (HG °dhāh, ApMB adhi dhā) svastaye AV. ApMB HG These forms are taken as datives by the PG comm, followed by Stenzler and Oldenberg It is uncertain whether this is cor-
 - rect, or whether they are verb forms, see VV I p 112 §706. Another stray case or two concerning noun endings (loc sing
- and instr pl).

 ghrtavatī savitar (MS KS "tur) ādhipatye (TS "yaih) TS MS KS AŠ

avyo (SV avyā) vāre (SV.*vārash) pars prsyah (and, prsyam) RV SV. punar brahmāno (brahmā) . . yajñash (agne), see §339

§707. When e and ai vary in radical syllables of nouns, it is generally a matter of secondary formations with vriddhi varying with other related forms without vriddhi.

dawīm (VS devīm) nāvam svarıtrām anāgasam (AV. °sah) RV. AV. VS. TS MS KS

devih (AV dai*) sad urvir uru nah (TS ApMB nah, and so Whitney for AV with most mss) krnota RV. AV. TS ApMB

dawībhyas (KS. devebhyas) tanūbhyah (KS °yas) svāhā KS TB. ApS. Kaus

brhaspatır devānām (ŚŚ dawo) brahmāham manuşyānām (ŚŚ mānuşah) VSK TB ŚŚ KŚ ApŚ MŚ

devān mā bhayād iti SMB daivān mā bhayāt pāhi SS.

ımā yā devīh pradiša
ś catasrah AV yā daıvīś catasrah pradišah TB. ${\tt ApMB\ HG}$

sam devena savıtrā TA: sam daivena (and, daivyena) savıtrā VS SB dıvyah kosah samulışılah MS daivyah kosah (AV. SırasU. devakosah) samulyılah AV TS KS SırasU

vācā tvā hotrā pañcabhır dawyaır (MŚ devair) Ţtvıgbhır uddharāmi ApŚ MŚ

mā devānām (TA davvyas) tantus chedr mā manusyānām (TA manusyah) MS KS TA ŠŚ

ındro jyeşthānām (MS KS jyaışthyānām, VS ŠB jyaışthyāya) VS. TS. MS KS ŠB PG

vaiśvānaram kṣaitrajītyāya (TB kṣetra*) devāh VS TB

somaindrā (KSA †saumendrā) babhrulalāmās tūparāh TS. KSA

adhvanām adhvapate śreşthah svastyasyādhvanah (ApMB śreşthasyādhvanah, MG śransthyasya svastasyādhvanah, read svastya° with most mss) pāram ašīya AŚ ApMB MG

meghyā (VS. marghīr) vidyuto vācah VS TS MS KSA

§708. A couple of cases with e as in the first syllable of nouns seem to differ from the preceding, it is very questionable whether the as form has secondary vinddhi or is in any morphological way different from the form with e In short, it is at least likely that these are pure phonetic variants

avārāya kevariam VS pāryāya kawariam TB. The usual form is kai° , evidently of non-Aryan origin, and it is, to say the least, very possible that ke° is a Prakritism

veśaniabhyo daśam TB vaiśaniabhyo baindam VS Here again we have

a word probably of foreign origin, but this time the usual form is ve° Perhaps hyper-Sanskritism in VS

§709. Several cases are complicated by the possibility that the form e, where ai seems to be expected, may be due to elision instead of contraction of final a (Wackernagel I §269c). The same phenomenon occurs with o for au, §731. Wackernagel, I c (small print), thinks of the possibility of influence of the Prakritic change of ai, au to e, o, besides this, it should be remembered that in Pāli and Prakrit any final vowel may be elided before any initial vowel, without regard to the quality of either. Thus there are two different tendencies of Middle Indic phonology which may possibly have been at work here. But furthermore, in some of the cases independent lexical or morphological explanations are conceivable for the e form

adhı na ındraışām (VS ındreşām) RV VS Here there can be no doubt that the intention of VS is ındra-eşām This is the most certain case

neva manse na pibasi AV nawa mansena pivari PG The AV pp reads na, wa, according to Barret JAOS 26 205, Ppp also reads neva (contrary to Whitney's note) Yet it is possible that AV really intended nawa, which certainly is a more natural reading

jagatyanam (AS 'tyenam) vikşv ā vešayāmah (MS KS 'mi, AS 'ni)
TS MS KS AS In VV I p 75 we have stigmatized jagatyenam as erroneous, which is unnecessarily harsh, to be sure the edition of AS inspires little confidence But it may be a phonetic variant of the sort here considered, or even—possibly—a real morphological change (voc jagaty instead of instr jagatyā)

enāhnedam ahar ašīya svāhā KS (prec by -mānā, actual text, -mānar-nāhne°) the MS version quoted in Conc as idāhna id āharam ašīya is Knauer's emend of corrupt mss which begin [-mān]-enāhned-, doubtless intending the same as KS

See also anāmayardhi etc. §344

§710. In verb inflection there are a number of cases in which indicative or subjunctive endings in e vary with subjunctives in at, see VV I p 28

vı sakhyānı srjāmahe (SS °haı, MS vısrjāvahaı) AS SS Vait ApS MS PG

yam jīvam ašnavāmahai (MS °he) RV AV VS TS MS KS devān yajūiyān iha yān yajāmahai (TS havāmahe) TS MS KS rayim yena vanāmahai (SV °he) RV SV sacāvahe (MS °hai, p p °he) yad avīkam purā cit RV MS

- brahmāham antaram kṛṇve (KŠ. karave, read °vaī) AV. KŠ. (? the proper subjunctive form would be °vaī, °ve either corruption or purely phonetic variant).
- anu nau śūra mansate (TS. ctar) RV TS. KSA.
- yā na ūrū uśatī viśrayāte (AV °tı, ApMB. HG. visrayātaı) RV AV. ApMB HG
- parı şvajāte (AV. ctai) libujeva irksam RV AV. N.
- pra yaḥ satrācā (TB. sa vācā) manasā yajāte (TB °tar, text and comm. ın Poona ed.) RV TB.
- dadhad vidhaksyan paryañkhayālai TA. dadhṛg vidhakṣyan paryañ-khayāte (AV. vidhakṣan parīnkhayātai) RV. AV.
- manaı (MS manve) nu babhrūnām aham RV. VS. MS. KS. \pm N yayā gā ākarāmahe (SV. °hai) RV. SV.
- varunetı sapāmahe (MS†°hai; AV. yad ūcıma, LŚ †?ayāmahe) AV. VS. TS MS KS. SB. TB AŚ ŚŚ LŚ.
- §711. There are a few cases in which the ai is due to the preposition ā preceding e, cf. §§694, 698; or, in the first two cases, to the augment: mṛtyoh padam (MG. padānī) yopayanto (AV cta, MG. lopayante) yad (AV. omits) eta (RV. aita, TA. aima) RV. AV. TA. MG.
- vācaspate 'chidrayā...hotrām airayat (KŠ. 'yant, TA. erayasva, ŠŠ. airayasva) svāhā ŠB TA. KŠ. ŠŠ Augmented forms in ŠB. KŠ.; the ŠŠ. is uninterpretable.
- ā te garbho yonım etu (AG. aitu) AG. ApMB. HG: ā te yonım garbha etu AV ŚG. ā yonim garbha etu te AV: ā garbha yonim etu te ApMB HG. The preceding ā proves AG. secondary
- arşu (AS eşu) dyumnam svar yarnat AV AS. SS Perhaps misprint in AS, as Whitney on AV. suggests.
- etat ie agne rādha artı (MS. KS. eti) somacyutam TS. MS KS.
- grhan armı (LS. HG emi) . . AV. VS. LS. ApS. SG. HG.
- abhyaitı (SV. abhyetı) na ojasā spardhamānā RVKh. SV. VS §712. Miscellaneous cases:
- he 'lavo he 'lavo SB.: hailo hailo SBK. Interjections,
- mā bheh VS. TS. SB. TB KS. ApS.. mā bhath MS KS. MS. Aorist verb forms, see VV I p 129, and next.
- mā bher mā .. VS. VSK. TS. SB: mā bhar mā ... MS KS. See prec. uṣnena vāya (ApMB. vāyav) udakenehi (SMB. GG 'naɪdhi, MG. vāyur udakenet) AV. AG. SMB GG. PG. ApMB. MG. See §122; and on the MG. form, VV I p 87.
- uttamam nākam (VS. MS. KS ŠB uttame nāke) adhi rohayemam (VS. MS. KS. ŠB. °ya:nam, TA. °rohemam) AV. VS. TS. MS. KS ŠB. TA. Pronouns imam: enam

tatra rausthām anu sambharaitam (MŚ °retām, AŚ, °bhavatām) TB AS ApS MS. In TB ApS fusion of sambhara and etam, in the others dual verb forms

satruhanam ametrahanam (KS satru° ası satruhanam) biratruyahanam asurahanam ivaindram (ApŚ text ivendram) vajram sādayāmi KS ApS Here tvendram, if not a corruption or misprint, can only be a phonetic reduction of traindram (tva + aindram)

[endram (TB, aindram, but comm and Poons ed text endram) acucuavuh TB Ap\$1

6 4 0

- §713. The variants under this head are relatively not numerous, and quite miscellaneous in character A fair number have to do with ablaut in stem syllables, thus, in nouns and adjectives

namo vah mtarah susmāya (VS SS sosāya, SMB GG KhG sūsāya) VS VSK TS MS KS TB AS SS SMB GG KhG See \$720

matuai śrutāva (mahe śrotrāva) caksase AV (both)

ā mā stutasya stutam gamyāt (Vart gamet) TS Vart ā mā stotrasya stotram gamuāt PB

duścyavanah prianāsād (°sāl) ayudhyah (AV MS ayodhyah) RV AV t19 13 7c. SV VS VSK TS MS KS Gerundives

deva gharma rucitas tvam devesv ā MS rocitas tvam deva gharma devesv as TA Causative and simple participles Cf next

riletto gharmah MS KB SB TA etc rocito gharmo ruciva TA Cf

ānandā modāh pramudah AV.: ānando modah pramodah TB modah pramoda ānandah TB. mudah pramuda āsate RV Stems (pra)mud and (pra)moda

drunā (SV drone) sadhastham asnuse (and āsadat) RV SV Stems dru and drona

714. With these may be grouped certain other cases which are really lexical, and partly involve different word divisions, but which in their external form simulate ablaut relations.

dyumnī šlokī (KS šuklī) sa somyah (TB sau°) RV AV SV MS KS TB sukevam somapitsaru (TS. sumatitsaru) VS TS MS KS SB VāDh susīmam somasatsaru AV See §180

sumıtrah soma no (Kaus sumano) bhava RV TS MS KS SB KS Kaus An obvious lect fac in Kaus

§715. Ablaut relations also occur in the inflection of the verb tions between no and nu as strong and weak stems of 5th and 8th class

- presents have been collected in VV I p. 185, and need not be repeated In the radical syllable different Ablaut grades are found in perfects, and are especially frequent in acrists
- yan me mātā pralulubhe (ApMB HG pralulobha) ŠG ApMB. HG.
 MDh
- sūryasya cakşur āruham (VS āroha) VS TS MS KS SB ApS. MS. Aonst and present, see VV I p 82.
- ādītya (AV also sūrya) nāvam ārukşah (SMB. ārokşam) AV SMB See VV I p 130
- amocı (AV amulthā) yakşmād durıtād avartyaı (AV. avadyāt) AV. TB. ApMB
- mā bher mā roñ (VSK mo rơñ, TS māro) mo ca nah (TS. mo eṣām) kim canāmamat VS VSK TS ŠB: mā bhair mā ruñ mo ca (KS. rauñ mā) nah kim canāmamat MS KS See VV I p. 129.
- mā dyāvāpṛthīvī abhī śocīh (TS śūśucah, KS śucah, MS. hīnsīḥ) VS. TS MS KS SB. See ibid p 128
- devasya (°syāham) savītuh.. ruheyam (GB. roh°) VS. VSK. TS. MS KS SB. TB GB Vart MS ApŠ LS See ibid p 132
- sa yathā tvam rucyā rucṣṣ̄ya (MS rocṣṣ̄ya) AV MS. See VV I p 186 On the following form see VV I p 281, the MG form is quite uninterpretable by regular grammar, and must be understood as a phonetic variant or corruption for tiṣṭhatu.
- antas tışthatu (MG °to) me mano 'mrtasya ketuh SMB. HG. MG.
- §716. In several cases, the o pertains to the genitive ending of noun stems in u, either as independent words or in composition.
- vasuh (TS ApMB vasoh) sūnuh sahaso apsu rājā RV. VS TS MS. KS ApMB. Nom and gen forms, the former an adjective, the latter a noun ('son of Vasu, of Strength' etc)
- dyumattamā supratīkasya sūnoh (AV °tīkah sasūnuh) AV. VS. TS. MS KS ŚB See §189
- āyuşkrie (ApŚ āyoş°) svāhā KS. ApŚ Both 'maker of life'.
- vāyosāvitra (TS pp °trah, MS vāyusavitrbhyām) āgomugbhyām caruh (MS payah) TS MS KSA TPr 6. 8 explains vāyo° by vāyusavitrbhyām, it is a secondary adj. in suffix a, and evidently the o is due to influence of the genitive form vāyos, cf agner agneyāny etc., §692
- uror ā no (VS SB LS pururāvņo) deva rīşas pāhī VS TS MS KS. SB TB LS See §371a
- madhu reto (TS madhor ato, KS † madhur ato) mādhavah pātv asmān TS MS KS AS See §837

§717 The stem puru in composition varies with puro, for puras, cf below, §721

samdhātā samdhīm (MS °dhīr) maghavā purūvasuh (TA ApMB MS p p puro°, MS text puru°) RV. AV SV MS PB TA KS ApMB puru višvām jūrvan RV puro rakṣānsī mījūrvan AV

§718. Twice the o is due to a prefixed \bar{a} , cf §§694, 698, 711

obhe pṛnāsı (TS ubhe pṛnalṣi) rodasī RV TS MS. pṛnalṣi rodasī ubhe RV SV VS KS SB

ā yā dyām (MS dwam) bhāsy ā pṛthwīm orv (KS urv) antarıkşam VS TS MS KS SB

§719. The remaining variants are miscellaneous, and certainly for the most part lexical. The first may be some sort of phonetic variant sajūr devair vayonādhaih (MS MŚ vayu°) VS TS MS KS. ŚB MŚ vayunā-dha is certainly a compound of vayuna, vayo° is ordinarily taken as a cpd of vayas with a derivative of nah, which seems highly improbable. The form is difficult and may be based on vayuna- with a phonetic alteration, perhaps due to some obscure analogy.

ye devā manojātā (MS KS MŚ manu°) manoyujah (KS manu°, ViDh manujuşah) VS TS MS KS ŚB BDh ViDh ApŚ Stems manas and manu

agnır havyānumanyatām (MŚ havyā no man°) TB ApŚ MŚ

pra nu (TA. ApMB HG nu, Kaus no with all mss but one, and the two paddhatis, but probably read nu) vocam cilituse janāya RV TA SMB Kaus GG ApMB HG MG

pra nu vocam (ArS no vaco) vidathā jātavedasah (ArS °se) RV ArS yas te stanah śaśayo (AV ° yur) yo mayobhūh RV AV VS MS AB SB TA BrhU AS Equivalent stems, śaśaya °yu

yā codītā yā ca nodītā (TA yā cānudītā) MS TA na-udītā an-udītā yatheyam strī pautram agham na rodāt SMB PG ApMB HG yathedam strīpautram aganma rudrīyāya MG See §801

agnaye tvā mahyam .āyur (MS mayo) dātra VS VSK MS ŠB ŠŠ Near-synonyms

rudrānām urvyāyām (ApS ūrmyāyām, SS omyāyām) SB SS ApS See §228

sīdanto vanuşo yathā RV SV LŚ · sīdantu manuşo yathā RV See §227 larma kṛnvantu (MŚ °to) mānuṣāh AV MŚ The MŚ form can only be construed as a participle hanging in the air, without finite verb It is really a phonetic variation

[ato (TB tato) no rudrā uta vā †nv (Conc no, TB nuv, Poona ed 'nv, comm anu) asga RV TB]

7 1 0

- §720. The majority of variants in this group concern forms which resemble shifts of ablaut, but only partially are the forms in question really related to each other in this way. Some, such as jyotis and jūti, are quite unrelated words but quasi-synonyms. Others are wholly obscure, and while the change of vowel is probably due to some sort of phonetic consideration, the precise nature of it is problematic. One is tempted to think of the fact that in some Prakrit dialects u is a phonetic shortening of o, implying that the relation of o to u is not far from the same as that of \bar{u} to u (cf. Pischel, Gram d. Pkt. Sprachen §84)
- abhı tyam devam savıtāram onyoh (TS ūnyoh) kavıkratum AV SV VS TS MS KS KB AB SB AdB AS SS The isolated TS stem ūni must mean the same as the regular oni
- namo vah pıtarah suşmāya (VS SS soşāya, SMB GG KhG sūşāya) VS VSK TS MS KS TA AS. SS SMB GG KhG Comm on SMB sūşa ıtı balanāma
- sam pūṣā (ApŚ. adds sam dhātā, MS.* poṣā) sam brhaspath (KS dhātā) AV MS (bis) KS ApŚ poṣā is either a textual corruption or due to the analogy of guna forms of root puṣ The mantra is repeated in fragments in a Brāhmana passage immediately following its quotation with poṣā, and in the Brāhmana pūṣā is read Cf next.
- apı (PG. 1ha) pūsā nı şīdatu (AV ŠŠ * °ti) AV ŠŠ (b1s) LŠ SMB PG HG rāyas poşo nı şīdatu ApMB ApŠ Cf prec; rāyas poşo 1s here evidently secondary, but sensible
- kukūnanānām (KS kūtanānām, MS pūtanānām) tvā . VS MS KS SB lotanāsu TS Wholly obscure words
- yamasya pātūrah (KSA pāto°) TS KSA. yamyai pātūrah TS yamyāh pātorah KSA Uncertain part of the horse's body
- angoşınam (RV angüşanam) avavasanta vanıh RV SV Cf §490 and next
- aāgoşinan (RV āāgūsyam) pavamānam sakhāyah RV SV Cf prec. mano jyotir (VS ŠB LŠ jūtir) juşatām ājyasya (TS TB Vait ājyam, AŠ ājyam me) VS VSK TS MS. KS ŠB TB AŠ Vait LŠ. KŠ ApŠ MŠ Unrelated words but quasi-synonyms
- divo jyote (KS *°tir) invasva (MS devajūte invasvann) MS KS ·
 vivasvān aditir devajūtis TS
- *vivasvān adıtır devajūtıs TS §721. The stem purū, for puru in composition, varies with puro for puras, in the first variant quoted in §717, q v, and also in tam sakhāyah purorucam (SV purū°) RV SV

§722. The o is due to a prefixed \bar{a} , cf. §718 etc.:

yat kım canıtam odima (TA üdima) MS TA

yad vācānītam odima (TB TA ūdima) MS TB TA

devatrā havyam ūhişe (RV ohişe and ohire) RV. SV. TB. A complicated case, on which see RVRep 131 f, VV I p 237 f.

§723. The rest are miscellaneous

amo 'ham asmı sā (AB sa) tvam AV KS AB. SB BrhU. JUB AG SG Kaus PG MG amūham asmi sā tvam TB ApS ApMB HG: sā (AB sa) tvam asy amo 'ham (SB BrhU. PG. aham, ApMB amūham, MG asy āpy amo 'ham) KS AB JUB SB BrhU. AG SG PG. ApMB MG. amo, for amas, stem ama; amūham, peculiar sandlu connecting some form of stem amu (amū? amus, amūs?) and aham; see Winternitz. Introduction to ApMB, p xxvii

aūghrinā vişno (KS vişnū, twice; ms once vişnu) mā tvāva (KS vām ava) kramişam VS KS SB: agnāvişnū mā vām ava kramişam TS TB ApS See Von Schroeder on KS 1 12 and Keith on TS 1 12 1 vişno, voc sing; -vişnū in TS devatādvandva, in KS elhptic dual (note vām in KS.); but note also the phonetic resemblance between aūghrinā and agnā of TS

tapūnsy (MS tapobhir) agne juhvā patamgān RV. VS TS MS. KS. Different case forms of related stems tapus and tapas.

tanūpā ye nas tanvas tanūjāh AV.: tanūpārānas tanvas tapojāh AB. AŠ sa tū (SV. sato) dhanam kārine na pra yansat RV. SV.

mā mā yūnarvā hāsīt (JB yono vām hārasīh) PB JB. LS Both forms obscure

S. u au

§724. Nearly all the few variants recorded here seem to concern the vriddhi of secondary derivation as regards their au forms; but one or two of them are strange forms. (For the sorts forms ruk, rok, rauk, see §715, mā bher etc.)

suślokyāya (ApMB. sau°) srastaye ApMB. AG PG. MG.

māham pautram (KBU. putryam) agham rudam (AG. niyām, read nigām, with SMB *; SMB *nigām, *riṣam) AG. SMB ApMB HG. KBU.

ulūkhalā (ApMB aul°) grāvāņo ghoşam akrata (MG. akurrata) ApMB HG. MG : aulūkhalāḥ sampravadantı grāvāņah SMB.

udbhinnam (ApS audbhidyam) rājnah MS ApS

āšīr na (nā, ma) ūrjam ula suprajāstvam (AV. sau°) AV. TS MS. KS
KS Whitney rightly calls the AV. form 'anomalous'.

kumbhīnasah (KSA laum°) puşkarasādo lohtāhis te tvāṣṭrāh TS. KSA. Here, as in the last, it is hard to account for the vriddhi, the meaning seems to be the same as that of the primary noun

vāce krauācah (VS kruācah) VS TS. MS KSA Again the two forms are apparently synonyms. In this case the form with vriddhi is commoner, at least in the later language. The origin and primary form of the word are unknown

dyusamantasya ta ādriyo 'nrīkhyātā BDh ; dyauh samā tasyādriya upadrastā ... HG See §833

vyam eva sā yā prathamā vyauchat (ŚG vyuchat) AV TS. MS KS TB. ApŚ ŚG HG ApMB Augmented and augmentless forms. vy uchā (and, aucho) duhitar divah RV SV (both in each). As prec.

9 ũ au

§725. Here we find, first, a number of cases concerning vriddhi of secondary derivation

taındrāsūrāh syetalalāmās (KSA taındrāsaurāh tsyāmalalāmās) tūparāh TS KSA

pauşno (VSK püşü) vıspandamāne (sc mahāvīrah) VS VSK. svarmaurdhnyāya svāhā KS. svarmūrdhā vauyašano vyašyann.. MS. dhruvāya bhūmāya (PG bhau°) svāhā TA MahānU.PG. ūrvaih ŠŠ Vait aurvaih LŠ With both sc pitrbhih

§726. There are several variants of the participles $dh\bar{u}ta$ and dhauta, from roots $dhu(dh\bar{u})$ and $dh\bar{u}v$ 'rinse', which are no doubt related in origin the they are kept distinct in the history of the language $nrbhur\ dh\bar{u}tah$ (SV dhautah) suto asvarh RV SV.

nrbhir dhūto (SV. dhauto) vicaksanah RV SV.

apsu dhautasya (AS SS dhā°) TS MS KS PB AS SS. ApS. MS. apsu dhāto (SV dhautam) nrbhih sutah (SV. sutam) RV. SV

\$727. In one case the au is due to prefixing of the augment.

praty auhatām (MS 'ūh') aśvīnā mrtyum asmāt (AV. asmat) AV. TS VS. MS. KS 'TAA.

10 o au

§728. Here again the largest group concerns the widdhi of secondary derivation

dyumnī ślokī (KS śuklī) sa somyah (TB sau") RV AV SV MS KS TB namo mauñjyāyormyāya vasuvindāya GDh namo mauñjyāyaurmyāya Svidh

yat somyasyāndhaso (ApMB sau°) bubodhatı RV. ApMB. Juşantām somyam (TB sau°) madhu VS MS TB. somaındrā (KSA †saumendrā) babhrulalāmās tūparāh TS KSA somāpauṣnāh (KSA sau°) syāmalalāmās tūparāh TS KSA yadı somasyāsı rūjňah somāt Kaus yadı sauny ası somāt AG

Rvidh yady ası saumī somāya GG

caurasyānnam (TAA BDh cor°) navasrāddham TAA MahūnU VıDh. BDh

[tvam rauhinam (AV misquoted roho in Conc) vyäsyah AV SS]

§729. Several times the two diphthongs interchange in the radical syllable of agrist stems

 $\it{m\bar{a}}$ (VS SB add vayam) rāyaspoṣena v
r yauṣma VS MS SB $\it{m\bar{a}}$ ham rāy° v
r yoṣam TS. KS TA ApŚ.

ıhawa slam mā vı yauşlam (ApMB yoşlam) RV AV ApMB mā bher mā etc., see §715

§730. Once the au form is due to prefixed a, of §722 etc

 \bar{a} no (VS SB $m\bar{a}$) goşu vı
śatv \bar{a} tanüşu (TS auşadhīşu, MS oşadhīşu) VS TS MS KS SB

§731. A few cases, not all textually certain, concern the elision of a before o instead of fusion These are parallel to the similar cases of e ai, §709, q v

upayāmam adharenauşihena (TS °noşihena, KSA adharoşihena) VS TS MS KSA See TPr 10 14

saha ojah (VS sahaujah, VSK sahojah) VS VSK AB GB AS Vait Adverb saha plus ojah in VS VSK, the latter with irregular sandhi, the other texts sahas + ojah

ya āvvešosadhīr (MS °śausadhīr) yo vanaspatīn AV MS There is a v 1 °ausadhīr in AV , which Whitney adopts in the text

[sukurīrā svaupašā VS TS KS ŚB sukarīrā svopašā MS But several mss and p p of MS svaup°, which should probably be read in the text The second part of the cpd is certainly opaša, and the first probably sva, tho it is sometimes assumed to be su, doubtless this was Von Schroeder's assumption when he printed svopašā in MS] §732. Miscellaneous

asthuri nau (nau, no, no) etc, see §950 Dual and plural pronouns nau and no (nas)

[ye ke cobhayādatah (TA cau°, Poona ed correctly co°) RV VS TA ye ca ke cobhayādatah AV]

anupauhvad (ApMB anu po 'hvad) anupahvayet (ApMB anuhvayah)

HG ApMB The ApMB surely means po for vo, comm says p
is 'chāndasa' for v, cf Winternitz, p xxi The HG seems to
intend a form containing upa, but it is corrupt and obscure

devī dvārau (Vait devīr dvāro) mā mā samtāplam TS AŚ Vait The dual verb shows that the plural of Vait is impossible

sūryo rūpam krnute dyor (MS dyaur) upasthe RV AV VS MS TB Only a gen can be construed here On dyauh as abl-gen see Wackernagel, III p 224, infra

yaırādhi sūra udīto vibhāti (TS udītau vyeti) RV VS VSK TS Others, §63

mā tvā nı kran pūrvacıto (AV °cıttā, MS °cıttau) nıkārınah AV VS TS MS KS See §399

ımau (Kauś yau) te pakṣāv (VSK MS KS °ṣā) ajarau patatrınau (VSK TS† KS °no—so all texts, before following sonant) VS VSK. TS MS KS SB Kauś Nom dual gen sing

11 'Samprasārana', i(i) ya, yā, and the like

§733. We have already referred in §§656 ff to the phenomena of so-called samprasārana as they concern r in variation with ra, $r\bar{a}$ Similar exchanges occur between i and ya, but in almost every case they concern morphologically or lexically independent forms. There is hardly a trace among them of the genuine ablaut relations that exist in such roots as yaj ij, etc. The phonetic importance of these variants is therefore secondary and contributory. They show that fluctuation occurred between such sounds or sound-groups, and so tend to support the ablaut relations of i ya as a live factor in the language. Indeed so live was this factor that it was capable of producing secondary and analogical developments where it did not belong historically, as in the following case, which is the most interesting of all these variants from the phonetic standpoint

agne yat te tejas tena tam prati titigdhi (KS tityagdhi, AV tam atejasam kṛnu) AV MS KS ApS For the 'adventurous' tityagdhi, irom root tij but apparently influenced in form by thought of tyaj or the like, see VV I p 191

§734. All our other variants are morphologically or lexically quite independent, except possibly the following

prapīnam (MŚ v l °tam, TS ApŚ prapyātam) agne sarırasya (MŚ sahlasya) madhye VS TS KS ApŚ MŚ The 'roots' pī and pyā are ultimately one

yatrāsate sukrto yatra te yayuh (AV ta īyuh) RV AV VS SB TA 'Roots' yā and ı, the latter form here metrically poor

vikirida (KS. °da, VS °dra, MS vyakrda) vilohita VS TS MS KS It is barely possible that the first syllable of this obscure epithet of

- Rudra may show a variation which properly belongs here; but nothing is really known of the word
- agne devānām ava heda vyakşva (KS ıkşva) KS ApS ıyakşva is a desiderative from yaj; possibly for metrical reasons, KS presents a sort of contraction of it, which in VV I p 123 we have doubtfully classed as a root present
- dhanāni šakro dhanyah (AŚ. dhanāh) surādhāh TB AŚ The reduction of the commonplace adjective dhanyah to the monstrous dhanāh can only be a phonetic corruption or blunder (or should we read dhanā, from dhana?).
- §735. Of the lexical variants, several concern monosyllabic forms like id, $\bar{i}m$, varying with yad, yam; or the like.
- apām payasvad it (KS yat) payah RV KS -apām payaso yat payah AV. TS. TB MS
- gomān id (SV. yad) indra te sakhā RV SV
- muşkāv 1d (VSK °kā 1d, LS °kau yad) asyā ejatah AV. VS VSK SS LS
- mıtram na yam (TB īm) sımyā goşu gavyavah (TB °vat) RV TB
- samyak (TS MS TAA ApŚ * MS sam it, KS * sarit, all mss) sravanti sarito (TAA. °tā, Poona ed °to) na dhenāh RV VS TS MS KS * SB TAA KŚ ApŚ * MŚ
- yadı tvam atra (Vait tvam tatra) manasā jagantha VS AŠ ŠŠ Vait .

 yad-yat tvam atra manasānuvettha LŠ
- iti cid dhi (AV. *yadi cin nu) tvā dhanā jayantām RV AV (both)
- §736. In others the variation is accounted for by the presence or absence of the augment or a particle or the preposition \bar{a} before a verb form or derivative noun, and after a preposition ending in i.
- mā dhenur atyāsārīnī (HG atīsā°) HG ApMB. The true reading is manifestly that of ApMB, HG has a phonetic reduction (it should mean 'having diarrhea!')
- yajña praititṣṭha sumatau suśevāh TB ApŚ yajñah praiyaṣṭhāt (v l praiy u ṣṭhāt) KS yajñah praiy u ṣṭhāt sumatau matīnām MŚ
- toyena jīvān tusasarja (TA. text vya ca sarja, comm v 1 vyasasarja) bhūmyām TA MahānU The only possible reading in TA is vyasasarja, which is itself anomalous enough, see VV I p 140
- abhyaşıkşı rājābhūm (ApŚ °bhūvam) MS ApŚ abhısıkşa rūjābhuvam (v l °bhūvam) MŚ
- §737. Stems or endings in i varying with extensions in (y)a agnir grhapatīnām (MS KS gārhapatyānām) VS TS MS KS SB sūpasthā asi vānaspatyah MS sūpasthā devo vanaspatih TS ve 'gnayah purīsyāh (purīsinah), and others, see §907

- antimitras (TS antyam°) dūre-amitras (MS 'mitras) ca ganah VS. TS. MS KS. Both probably mean 'having near friends', anti and adj antya. Weber and Keith follow the comm on TS in dividing anty-amitras, 'with foes within,' which is less plausible
- agnır havyam (RV KS. havıh) samıtā südayātı (AV svadayatu) RV AV. VS. TS MS. KS
- ahāh śarīram (TB ahāc char°) payasā sametı (TB °tya) TB Vart (also AVPpp) The correct reading is doubtless the gerund sametya; the 3d sing sameti may almost be considered a case of genuine 'Samprasārana'. Cf VV I p 164
- kım it te vişno parıcakşyam bhūt (SV parıcakşı nāma) RV SV TS MS N. The SV form is scarcely interpretable (see Benfey's Glossar for two suggestions), and is probably a sort of phonetic corruption of the other.
- tāh prācya (°yah, prācīr)..., see §387. Equivalent case-forms; others will be found in the volume on Noun Inflection
 - §738. Remoter lexical variants and corruptions
- satyam vadanty anv 1cha (KS anu yacha) etat TS KS PG anu-13 'seek after': anu-yam 'follow'
- yebhir viśvam (SV. vy aśvam) airayah RV. SV Vy aśvam doubtless a corruption, favored by this sort of phonetic shift Benfey takes aśva as a proper name
- anyām icha pitṛṣadam vyaktām (ApMB vittām) RV ApMB . jāmim icha pitṛṣadam nyaktam (read °tām) AV vittām is certainly secondary. Note that in jāmim anyām we also have a kind of samprasāraṇa in the final syllable
- acittapājā (TA acyuta°) agnīt MS TA. SS. Also. acittamanā (TA acyuta°) upavaktā, same texts Here yu: i vary, cf the second variant in §736, and next
- bhujyuh (MS. bhujī) suparno yajño gandharvah VS TS MS KS SB. yu: ī, cf prec
- pāhi mā didyoh (TS. TB mādya dwah) VS. TS SB. TB.
- ayam yo'sı (MS. yo asya) yasya ta idam sırah KS ApS MS. The latter certainly secondary
- yena bhūyas ca rātryām (ApMB. carāty ayam, MG caraty ayam, PG bhūris carā dwam) AG PG. ApMB MG See §61
 - 12 Samprasārana $u(\bar{u})$ va, $v\bar{a}$, and the like.
- §739. Here, as in the preceding division, there are very few purely phonetic variants, almost all of them involve lexical or morphological divergences. The most clearly phonetic cases are

- svar (KhG. sur) abhıvyakhyam KS ApŚ GG KhG: svar abhıvyakhyam (MS MŚ °kśam) jyotir vaiśvānaram MS KS MŚ sur is certamly for star, cf the Dhātupāṭha root sur 'shine'
- kati dhāmāni kati ye vivāsāh MS. ko asyā dhāma katidhā vyuştīh AV. Different ablaut grades of the root vas 'shine'
- agnir havyam (RV. KS havsh) śamstā sūdayāts (AV. svadayatu) RV. AV VS TS MS KS The roots sūd and svad are distinct historically, but no doubt related prehistorically
- agnır havyānı sışıadat RV . agnır havyā suşūdatı RV.
- ayā no yajāam rahāsi KS ayasā havyam ūhise ApS ApMB HG And others; see §502 Related roots vah and ūh

And similarly in suffixal elements.

- vidyullelheva bhāsiarā (MahānU bhāsurā, v I bhāsvarā) TA MahānU Both these stems are familiar adjectives
- madhuntamānām (VSK madhrant", MS madughānām) tvā patmann ādhūnomi VS VSK SB MS The VS form is a kind of superlative to madhu, modeled upon madin-tama, which occurs in the preceding formula The VSK. form is a variation on the other, suggested by suffixal forms in van(t)
- sugantuh karma karanah karışyan JB.. sugam tvah karmah karanah karanah
- §740. Several times the AV. presents the word abhisastipā(h), 'protector against imprecation', followed by the particle u, while other texts read abhisastipāvā, as nom of a suffixal form in -van; cf Lanman's note in Whitney on AV 19 24 5, which suggests that AV. is secondary bhavā kṛṣṭīnām (AV. gṛ°) abhisastipāvā (AV °pā u) AV. PG ApMB HG. abhūr gṛṣṭīnām (AV *vašānām in text, mss vāpīnām, HG āpīnām,

ApMB āpīnām) abhisastīpāvā (AV. °pā u) AV HG. ApMB

rşīnām putro abhısastıpāvā (AV. °pā u) AV. VS SB

And similarly, the particles vā and u interchange once.

yad vā (RVKh u) detī sarasvatī AV RVKh

- §741. The prefix su exchanges a number of times with the stem sva in composition, just as both of them exchange with sa-(§§364, 612) nāraš caranti svasica iyānāh VS TS SB.: nāvo viyanti susico na iānāh MS. KS
- ımam yajñanı sıudhayā ye yajante (KS dadante) KS AS · ımam ca yajñanı sudhayā dadante MS · ya ımam yajñanı svadhayā dadante (SS bhajante) VS. TS SS

- sugā (TS ApŠ svagā) vo devāh sadanā (TS N. sadanam) akarma (MS krnomi, KS Kaus ApS sadanāni santu, KS devās sadanedam astu) AV VS. TS MS. KS SB KS Kaus ApS N
- sunītī svayašastaram (SV su°) RV. SV.
- avabhrthas ca svaaākāras (KS su°) ca MS KS. So the one ms of KS; but ed em svagā°, no doubt rightly; cf. ava° ca me svagā° ca me. in Conc
- ekauā ca dašabhiš ca svabhūte (AV cā suhūte) AV. VS MS ŠB TA AŠ. SS See §119
- privāny angāni svadhitā parūnsi (Vait angā sukītā purūni) TB. Vait §742. The rest are sporadic lexical variants
- urudrapso visvarūpa induh TS ApS: purudasmo visurūpa (KS °dasmavad visvarūpam) induh VS KS. SB KS Other cases of visu vršva in \$291
- dhūmrā babhrunīkāśāh pitrnām somavatām VS: pitrbhyo barhişadbhyo dhūmrān babhrvanūkāšān ApŚ babhru + nīkāša (anūkāša)
- brahmādhiguptah (PG brahmābhi°) svārā kṣarāni (PG surakṣitah syām) svāhā AG PG brahmābhıgūrtam svarāksānah (most mss svarāraksānah) MG For AG Stenzler says: 'moge ich Lieder ergiessen',
- asmān (MS KS asmān) u devā avatā havesu (MS KS bharesv ā) RV. SV. VS TS MS KS asmān devāso t'vatā havesu AV
- svādhyo (TB °dhiyo) vidathe apsu zījanan (TB apsv az°) RV. TB
- purutrā te manutām (AV vanvatām, comm vanutām) visthitam jagat RV AV. VS TS MS KSA N Sing . plur : see VV I p 266
- ındrah (SS. °as) patih tuvıştamo (AA. SS tavastamo) zaneşv ā (SS zaneşu) AV AA SS
- ā yāhı (and, ā no yāhi) tapasā janeşu (ŚŚ.º sv ā, MS janışva) MS. AB AS. SS See §§693, 826
- §743. A number of times, in lexical or morphological variants, vi or $v\bar{\imath}$ is found varying with u or \bar{u}
- vidyutām (PG MG udyatām) wa sūryah SS AG. PG MG
- adyā krnuhi vitaye (SV. °hy ūtaye) RV. SV.: nrvat krnuhi vitaye (SV. 'hy ūtaye) RV SV The variation may also be considered one
 - between $y\bar{u}$ and $v\bar{i}$ (§805)
- achıdram parayışnum (SMB 'yışnvim) TS SMB Fem acc of u stem dršāno rukma urvyā (RV. KS urvyā, MS uruyā) vy adyaut (MS v bhath) RV VS TS MS. KS SB. ApMB Cf. - §791, and next variant The form uruyā seems to be characteristic of MS
- cakşur ma urvyā (KS urvyā, MS uruyā) vı bhāhı VS TS MS KS SB Cf. prec.

dhışane vidü (vidvi) . . , and others, see §169

yatrādhi sūra udito vibhāti (TS uditau vyeti) RV VS. VSK TS: yasmini adhi vitatah sūra eti MS KS· yasyāsau sūro vitato mahitvā AV See §63

13 ayare and the like

§744. On this general subject see Bloomfield, AJP 5. 27 ff; Wackernagel I p 53 f It is clearly Prakritic in character. The variants are few, and mostly capable of different lexical or morphological explanations. Perhaps the only purely phonetic variant is the following, the MS form is not otherwise recorded and is reasonably supposed to be merely a dialectic form of the other

namah kınsilāya ca kşayanāya (MS kşenāya) ca VS TS MS KS Epithet of land

§745. In several verb forms we find the same variation, where the aya forms may (with more or less forcing) be explained as causatives, or as 1st class presents, the alternative forms being derived from the non-causative, or from root-class presents, but undoubtedly the phonetic tendency in question is involved in them:

arejetām (TB arejayatām) rodasī pājasā girā RV TB Cf VV I p. 154; a sort of hyper-Sanskritism in TB., which spoils the meter

uttamam nākam (VS MS KS ŠB uttame nāke) adhī rohayemam (VS MS KS ŠB "yainam, TA rohemam) AV VS TS MS KS ŠB TA See VV I p 152 The contracted form of TA is unmetrical

sed u rājā kṣayatı (TB kṣeti) carṣanīnām RV. MS TB The contracted form is again unmetrical Cf VV I p 123

agnır (also vāyur, prajāpatir etc.) dīkşıtah...dīkşayatu (JB dīkşeta) JB. Ap\$ See VV I §160

§746. Otherwise we find a few miscellaneous cases, concerning noun inflection or particles:

pibāt somam mamadad (AŠ SS. °mam amadann) enam ışle (AS. SS ıstayah) AV. AŠ SS See VVI p 88

tasyed (AV tasya yad) āhuh prppalam svādv agre RV AV The AV expansion is hypermetric, according to Whitney, Ppp agrees with RV

§747. As showing analogous tendencies, we append a miscellaneous group of cases of variation between e(ai) and avi, ayi, iye, iya, \bar{a} - $y\bar{a}$ For e: va, $v\bar{a}$, see §803.

samsrāvabhāgā (VS SB. samsrava°, MS °gāh, KS. Kauś °gās) stheṣā (Kauś tanṣā) bṛhantah VS. TS MS. KS. SB. Kauś. See §96

TS. pp stha, iṣāh; and accordingly Keith, 'well-nourished'; but this is implausible The original doubtless means stha iṣā 'ye are great by food'; Kauś, 'by strength'.

tebhyo ghrtasya kulyaitu (TA dhārayitum) AV. TA. The AV. form intends kulyā-etu; TA suggests dhāraitu (dhārā-etu) as an intermediate stage between AV and its secondary reading

āruroha tve sacā (KS tvayy api) KS TB AS. Vait ApS MS

revati predhā yajñapatım ā viša MS. KS.: revati yajamāne priyam dhā ā viša VS. ŠB: revatīr yajñapatım priyadhāvišata TS. ApŚ. The old adverb predhā (doubtless original), 'kindly', becomes priyadhā in TS, and this is further broken up into priyam dhāh, 'establish the pleasant', in VS

vi dhūmam agne aruşam miyedhya (MS medhya) RV VS TS. MS SB. TA miyedha and medha, both RV, are synonyms, it is a disputed question whether there is any ultimate relation between them. agnir developah sundatriyebhyah (TA sundatrebhyah) RV AV TA N.

In the original form odatryebhyah stands for odatryebhyah (suffix ya). pratravebhyah (TA pratrebhyah) svāhā MS TA. The correct reading is certainly that of MS; pratrava in the soma ritual means the 'echo-hole', otherwise called uparava. TA comm pratrebhyo 'bhvvddhhetubhyah prānadevebhyah (as if pra-tra 'extending' [life]). ā yāta (SMB GG ViDh eta) pitarah somyāsah (HG somyāḥ) AV SMB

GG HG ViDh ā-yā and ā-1, synonyms

Compare the interesting case agnim (SV agnim u) śresihaśocisam RV SV, see §843

14. ava: o and the like

 $\S748$. See the references quoted in $\S744$ The variants are even fewer than those concerning aya and e The most clearly phonetic instance shows the peculiar pronominal genitive form to (Wackernagel p 54)

to-to (MS KS MŚ tava-tava, TS ApŚ to-te) rāyah VS. TS. MS. KS. ŚB KŚ ApŚ MŚ

§749. Other stray cases which involve the same phonetic tendency. yatra yanti srotyās (KS sravatyas) taj jitam te AV. TS MS. KS The fuller form of KS improves the meter RV. knows the stems srotyā (found here) and sravantī = KS sravatī, both meaning 'stream' But note that several mss of KS read sravatyās, which points to a hyper-Sanskritic form based on srotyās.

sā nah priyā supratūrtir maghonī TS.: sā nah supratūrtih priyā nah

- suhār naḥ prıyavanır maghavanır antā ehi MS In TS the regular fem of maghavan, based on the weak stem maghan, in MS an i-extension of the strong stem
- svāhā tvā subhava (VSK TS ApŠ °vah, KS subho) sūryāya VS VSK TS MS KŠ KB ŠB ApŠ The KS probably has really a phonetic contraction, but may be understood as from stem su-bhu (-bhū), parallel to -bhava(s)
- anābho mṛda dhūrte (read °ta with some mss of MS and all of MS) MS MS anārbhava mṛda KS ApS Cf p w 5 Nachtrāge, s v Possibly here also forms of root bhū may be involved, as in the last, but the readings are very obscure Epithets of Rudra KS ms reads anānbhava, KapS anār°
 - §750. We append a stray lexical variant of ava and \bar{u} ,
- avamaıs ta ūrvaıs te kāvyaıs te pıtrbhır bhakşayāmı PB LŚ · ūmaih pıtrbhır bhakşayāmı AB ŚŚ Vait It is possible that the latter form intends avama 'nether', instead of ūma 'helper', which does not fit pıtrbhıh so well We should then have a sort of Prakritic reduction Caland does not translate the word in Vait

For o va, vā, see §804

CHAPTER XVI INSERTION OR EXPULSION OF VOWELS

1 EPENTHESIS OF VOWEL BETWEEN TWO CONSONANTS

§751. In this chapter we shall consider mainly two kinds of variation One, the more extensive, is the writing of $\imath y$ for y and $\imath v$ for v, it is, as we shall see, primarily a matter of orthography, since it occurs almost exclusively where y and v have vocahe function. The other, which we shall take up first, is epenthesis of a vowel (usually \imath) between two consonants. It is dealt with in Wackernagel I §\$49-53, also, in so far as it concerns agrist verb forms containing $-r\imath_{\bar{s}}$ - or- $r\imath_{\bar{s}}$ -, in VV I pp 189-191. As Wackernagel says (p. 57), this epenthesis is clearly related to the Prakritic tendency to avoid a succession of dissimilar consonants by a similar epenthesis.

§752. In the variants it is almost always a matter of genuine epenthesis, that is insertion of a vowel which was originally absent. The older form of the variant is regularly that which lacks the vowel, and moreover in most cases the history of the word justifies the assumption that the original form of the word lacked it

§753. Perhaps the only two cases in which beyond any question an original vowel is expelled in one form of the variant are the following, on which see VV I pp 190-1, and Wackernagel I p 60 As Wackernagel observes, the forms without the vowels are hyper-Sanskritic. They show a straining to avoid what is felt as dialectic and incorrect, carried to the point of dropping vowels which properly belong in the words pra na (MS nā, SV PB na) āyūnşi tārişat (VS*TS*KS*SŠ N*tārişah, Kauś tārsat) RV AV SV VS*TS*MS KS*PB. TB

TA AŚ ŚŚ ApŚ Kauś N* The Kauś form is bad metrically. āchettā te (TB ApŚ*vo) mā rişam (KS rişat, MS and all mss of MŚ mārsam) TS MS KS TB ApŚ MŚ Since the root is riş, the Maitr form (to be read also in MŚ) is formally impossible, except as a purely phonetic (hyper-Sanskritic) variant for mā rişam

§754. In the next group of variants, acrists of the root car, both forms with and without i are otherwise known, but at least in two of the three cases the older forms of these particular variants show forms without i, so that they may also be counted as hyper-Sanskritisms

apo (RV AŚ āpo) adyānv (TS TB JB ApŚ anv, AV dwyā) acārişam (JB † acārṣam, AV acāyiṣam) RV AV VS TS MS KS ŚB TB

JB AS. IS ApS. MS. ApMB ApG MG Add to VV I §286a, p. 190. Note that JB. is unmetrical

agne vratapate vratam acārişam (MS MŚ. v. l. acārşam), VS. TS MS. KS.† ŚB ŚŚ. ApŚ MŚ HG

vratānām vratapate (Kauś °patayo) vratam acārīşam (MS. acārşam) MS. TA. Kauś

§755. The original form of parasu or parsu is uncertain; Wackernagel §51 behaves that it was parsu, but parasu seems commoner and is apparently supported by Greek $\pi \ell \lambda \epsilon \kappa \nu s$. In the variant which follows the meter is indeterminate (reading suastile, the form parsur can be made to fit metrically); but note that in TS. both forms of the word occur in the same pāda, which makes parsu suspicious:

parasur (TS parsur) vedih parasur nah svasti (TS. otih) AV. TS

§766. There are other cases in which double forms, with and without the vowel, are more or less familiar in the language generally. But it appears that in most if not all the other variants, these particular formulas originally contained the form without the vowel, so that the form with epenthesis may be regarded as secondary at least in the context considered

§757. The vowel inserted is regularly ι , seldom a or u. It is found commonly before or after a liquid, generally τ , and most frequently of all between τ and a sibilant or h. In addition there are a number of cases in which the epenthetic vowel ι seems to be inserted before a labial consonant, especially v, this principle is not recognized in Wackernagel, nor, so far as we know, elsewhere. The insertion is as a rule injurious to the meter, to make the text metrical it has to be omitted

§758. First, between r and sibilants the only certain cases except that mentioned in §755 are acrist forms. We have mentioned above those in which the vowel ι is certainly or probably original. Those in which it is secondary are (see on them all VV I, l. c.)

yad rātriyā (MahānU TA v l rātryā) pāpam akārşam (TA v l akārisam) TA. MahānU

dıleh putrānām adıler akārşam (MS akārışam) AV MS tan nah parşad (MS parışad) alı dvışah TS MS

dakşam te bhadram ābhārşam (AV ta ugram ā bhārışam) RV AV

§759. The only other case is probably no genuine variant, since the Poona ed of TB. text and comm reads dhūrṣadam. It is therefore probably to be deleted in Wackernagel I p 56, likewise delete there the form dhūruṣāh-, which is supported by only one ms in TS 1 2 8 2; the other mss. all read dhūrṣāh-.

ghṛtapratīkam va (TB ca) ṛtasya dhūrṣadam (TB. Bibl Ind. dhūruṣadam) RV TB. ApŚ.

§760. There is one variant vowel between l and a sibilant; most mss of MS (in three occurrences) and of MS. (in two) read with epenthesis -valisā, which should no doubt be read in all the Maitr. passages, altho Von Schroeder, for no apparent reason, reads twice -valsā and only once -valsā:

sahasravalšā (MS * MŠ v l °vališā) vi vayam ruhema RV. VS. TS MS * KS SB TB. ApŠ MŠ The epenthetic i is bad metrically.

§761. Between r and h, there are two instances of the same word. The variation is really lexical $(sp\bar{a}rha^-sv\bar{a}ruha)$, but is certainly helped along by the tendency we are considering:

spārhā (TB svāruhā) yasya śriyo drśe RV KS TB

spārho (TB svāruho) deva negutvatā RV SV VS TB.

§762. A single instance between l and h:

etad brahmann upa valhāması (AŚ apa°, LŚ upabalıhāmahe) tvā VS AŚ. ŚŚ LŚ

§763. Likewise one between h and r.

dahram (v 1 daharam) vipāpmavaravešmabhūtam (TA Poona ed vipāpam [v 1 vipāpma] vara", MahānU. vipāpmam varam [v. 1. vara-] vešma") TA MahānU Both dahara and dahra are known; the latter is required by the meter here.

§764. Before labial consonants, generally v.

puru tvā dāśvān (SV. dāśvān) voce RV SV The inserted i in SV is doubtless meant to improve the meter. In RV dāśvān was trissyllabic (probably dāśvān, Oldenberg)

sutah sudaksa dhanva (SV dhanva) RV. SV. Read dhanua in RV the i of SV is to be explained as in the prec

asının gharmam pātam hārdvānam (TA. hārddivānam, read with Poona ed hārdi") VS SB TA. SS And others, see §267

varşmā (VS varşımā) ca me drāghmā (TS drāghuyā, MS drāghmā, KS drāghvā) ca me VS TS MS KS The 1-forms of VS are exceptional Interesting is the TS form, which suggests a middle stage *drāghwā (blend of KS drāghvā and VS drāghmā), which has suffered metathesis of vowel and semi-vowel (vv uy)

Here we may also mention the common forms prthvī and prthvī. In the one variant noted, the meter requires the shorter form. It is a disputed question which is the original; Wackernagel thinks prthvī (I p 58), but there is something to be said on the other side (cf. e.g. Avestan parathwī):

pṛthwī (VaradotU pṛthwī) suvarcā yuvatıh sajoṣāh TB. VaradotU. §765. Finally, an isolated corruption

yad asyā anhubhedyāh (LS anuhodbhyāh) AV VS GB. SB AS SS. Vait LS The LS form is an uninterpretable corruption. The word anu doubtless floated before the mind of whoever first spoke or wrote it.

2 WRITING OF 1y FOR y AND uv FOR v

§766. The fullest previous account of this subject is found in Wackernagel I §181a, note, a briefer statement in Whitney 129d. The Prātišākhyas seem to take no note of it, not even the TPr, althouthe resolution is peculiarly characteristic of TS, and other Tait texts. In the commentary on TPr 2 25 Whitney believed he detected a reference to it in the term sphurita, but the passage is by no means clear

\$767. The arbitrary and capricious nature of the Vedic tradition comes out nowhere more clearly than here Certain broad general tendencies appear, the most striking is the tendency just mentioned of all Taittiriva texts to prefer the spellings iy and uv Yet even this is cut across by counter-currents in individual cases. The participle of the root ksz, which in all non-Tait texts beginning with RV itself is regularly spelled kswant with resolution, in Tait texts alone keeps or rather restores the historically 'regular' spelling ksuant, in defiance of meter which shows that even there it must have been pronounced ksiyant (§795) In some other cases where resolution is regular. That texts perversely show the unresolved form, thus going counter to their general practice. For instance, in two variant formulas (§797) they read promvätham (this time with VSK) against promuvo of all other texts, which is the regular form in the present of the fifth class when the present-sign nu is preceded by a consonant (Whitney 697a) the word which in most texts is written kuvala seems to have in the Tait school the definitely established form kvala (§782), nor can this be explained as due to metrical considerations, since it is found in prose Brāhmana passages Similarly the adverb urnyā 'so RV. always) is spelled urvyā in TS (also in VS, §791), and kuvayi or va of MS KS is written kvayn in TS and VS A Tait text (TA) even contains one of the three cases (nyemur, for ni-yemur) in which the final vowel (i or u) of a preposition is suppressed before the related semi-vowel (y or v) which follows it, thus leaning over backward to avoid even the semblance of the resolution of which the Taxt school is otherwise so fond (§770) \$768. Nor is the Tait, school the only one which displays this capricious character. KS. in general does not favor vy for y or uv for v. Yet in the case of the single word which all other texts write tryavi, KS in three different variants shows the invariable spelling triyavi (§776). The RV itself is guilty of one strange anomaly the pres mid participle of the root su 'press', is always written suvana, despite the fact that, as the meter shows, it was always pronounced svāna; the SV in the case of this word writes always svāna, in accord with the actual pronunciation (§794)

§769. Generally speaking, this matter is one which concerns orthographic convention alone, not phonetics in a proper sense. This is proved by the fact that in practically all metrical passages the y or v was syllabic. Thus the writing vy or v represents the actual pronunciation of all texts better than the other writing. Nevertheless it is almost invariably secondary. In nearly every case the older version writes vy or v, and a secondary text (generally of the Tait school) substitutes vy or vv

§770. To such an extent was y or v felt as a proper way of writing the actual sounds iy or uv that in three variant texts we find an original i or u, as final vowel of a preposition, suppressed in certain texts before a following initial y or v Cf. Wackernagel I p 59 These three cases are curious enough to be worth special mention. They are

mā tvā ke cin ni (AV ke cid †n) yaman vim (SV ke cin ni yemur in, TA ke cin niyemur in) na pāšinah RV. AV. SV VS TA The TA form, which defies meter as well as etymology, can only be interpreted as standing for ni yemur; so the comm There is, to be sure, a v. l. ni yemur, but nyemur is well attested and appears to have been the actual reading of TA

graha visvajanīna myantar (KS nyantar) . MS KS. This and the next passage are prose KS can only intend m-yantar.

anvāsī PB: anuvāsī . TS KS (not GB. Vait, see §255) anuvāya MS Here PB can only have in mind anu-vā.

§771. In a handful of cases this resolution is attended by false divisions which lead to real lexical variations in secondary texts, as when $apsv\ \bar{a}$ is resolved to $apsuv'\bar{a}$ which is then read $apsu\ v\bar{a}$ in TS (°§778), or when an original $nya\bar{n}$ (from $nya\bar{n}c$) is broken up into nv yan (thru the middle stage $nvya\bar{n}$) in a secondary reading of AV (§778) Again the adjective $apy\bar{a}$ is made into the two words $apv\ y\bar{a}$ in SV (§785), and the RV abhvam (two syllables, not *abhvam) is revamped by TB into ab-bhvam, thinking of ap 'water' (§790) Other variants which have lexical bearings are $suv\bar{a}\bar{n} \cdot sv\bar{a}n(a)$, §778, nv for nv varying

with 'nv for anu (wrongly printed nuv in TB Bibl. Ind ed, §778); and the few cases in which suffixal forms in $\bar{\imath}ya(n)$, with $\bar{\imath}$, vary with forms in ya(n), the $\bar{\imath}$ proving that we are not dealing with mere resolution of y to y (§786). With these exceptions, all the cases listed here are purely phonetic, or rather orthographic

\$772. The variants fall into five clearly defined groups First, i or u final (either absolutely or in the seam of compounds), written iy or uv as well as y or v before an initial vowel; most commonly after more than one consonant Second, non-final y and v in radical (initial) syllables; chiefly the one word svar (suvar) and its compounds, plus several words beginning in k- (in which the iy or uv form seems to be more primary). Third, the suffix ya pronounced iya, and written so in secondary texts; in practically all cases after more than one consonant Fourth, the stem-final of noun stems in long or short i or u, before inflectional endings beginning with a vowel; again the y or v, even when not written iy or uv, is regularly pronounced syllabically, but written so only in secondary texts Fifth, a few miscellaneous verb-forms, either finite verbs or participles

§773. In all of these groups except the last, the writing *iy* or *wi* is secondary to *y* or *v*, but accords with the actual pronunciation as shown by the almost unvarying testimony of the meter. Again in all except the last, it is regularly Tait texts which show this secondary writing. Typical is their treatment of the word *svar*, which they practically always write *suvar*; the few exceptions are mostly instances in which ancillary texts of the Tait school have borrowed formulas from other, non-Tait texts (such as KS., from which ApS frequently quotes), and have retained the characteristic spelling of those other texts. It would not be unreasonable to see in the writing of *iy* and *wi* an attempt to represent the actual pronunciation. The same tendency may be noted occasionally in other schools, and in the reverse change, as when SV always writes *svāna*, in accord with the meter, for the unmetrical RV *swāna* (§794). Yet, as we saw above, changes in both directions are sometimes introduced in defiance of meter.

A. uv and vy for v (u) and y final before vowels

§774. Most of the variants are metrical, and of course the y or v is always syllabic. We begin with the particle u, which in the RV etc is always written not v but u before a following vowel when it is preceded by a word ending in a vowel (or in y for final i), but v when preceded by a consonant (Wackernagel I §270a).

ghrie śrito ghriam v (TA. uv) asya dhāma RV. VS. TA AŚ MŚ. praty u (TB. uv) adarśy (TB †adrśy) āyatī RV. SV. TB ŚŚ. AŚ.

na vā u (TS TB. ApŠ uv) etan mrīyase na rīşyasī RV. VS TS. KSA. SB. TB ApŠ

sa u (TS uv) ekavnnšavartanih TS MS Prose

§775. The spelling uv was regular from RV times in the word suvita (svita). It is therefore not surprising to find it not limited to Tait. texts: sarad dhemantah suvite dadhāta (MŠ °tu) KS MŠ. sarad varsāh svite (TS. SMB suvitam) no dadhāta (TS. SMB astu) AV TS. SMB. The meter requires uv, but even with that is poor in TS SMB. because of their change to astu

sunte mā dhāh TS MS KS ŠŚ LŚ ŚG. N.: sinte etc VS. GB. ŚB AŚ. Vait. Prose

§776. The word tryan, so spelled in nearly all texts, is thrice spelled triyan in KS, altho this text rarely resolves y to iy, and altho Tait. texts write this word tryan(1) Two of the variants are prose, the other requires syllabic y or iy.

tryavır (KS triyavır) gaur vayo dadhuh VS MS KS TB.

tryavır (KS. triya°) vayah VS. TS MS KS. SB. ApS Prose

tryans (KS triya°) ca me tryan (KS triya°) ca me (MS MS omit me twice) VS TS MS KS MS Prose

§777. The rest are sporadic

sutudrı stomam sacatā paruşny (TA °nıy) ā RV. TA MahānU N. In a jagatī stanza, RV. certainly pronounced °nıy-ā

asıkny (TB °nıy) asy oşadhe AV. TB.

dhārāvarā maruto dhṛṣnvojasah (TB dhṛṣnuvo°) RV AB. KB TB

§778. False divisions resulting in lexical variations or corruptions are found in the following:

yad oşadhīşv apsv \bar{a} (TS apsu $v\bar{a}$) yajatra RV VS TS SB apsu $v\bar{a}$ clearly based upon the intermediate stage apsuv \bar{a} As a matter of fact, this may be what TS really intends, but p p divides apsu $v\bar{a}$, and so Weber and Keith

nyañ (AV. ni yan) ni yaniy uparasya nişkriam (AV. °tım) RV. AV. KS.

The AV. has a corruption based upon nivañ for nivañ

svāna bhrājā°.. VS TS ŠB KŠ ApŠ svān nabhrād KS.. svāna bhrāļ .TA . suvān nabhrād . MS MŠ In the latter su-vāk (vāc) is meant

[ato no rudrā uta vā †nv asya RV . tato no rudrā uta vā nuv (but Poona ed 'nv, and comm anu) asya TB We assume that the Poona ed is right, so that the variant does not belong here]

We have listed above (§770) the three variants in which just the reverse tendency occurs, namely, a final \imath or u is suppressed before an initial y or v

B Non-final y (v), in radical (initial) syllables

§779. These mostly concern the one word svar and its compounds Numerous variant pādas begin with this word itself. They can be got so easily from the Concordance, and show so little interest individually, that we have not taken the space to copy them out here. It will be seen that the form suvar is practically limited to Tait texts, but that in them it is nearly universal. The rare cases in which Tait texts write svar are generally due to quotations (in such texts as Ap\$) from non-Tait sources, retaining the non-Tait spelling. We note that in the variant $s(u)varge\ loke\ samprornvāthām\ TS\ KSA\ TB$, the true reading of KSA is †svarge loke †samprornuvāthām, correct Conc

§780. In addition to formulas beginning with svar we find for example (the list is far from complete)

parı lokān parı dışah parı svah (TA MahānU swah) VS. TA MahānU dıvı mürdhänam dadhışe svarşām (TS TB swo) RV VS. TS. MS KS

hıranyavāšīr ışırah svarşāh (TB. suv°) RV TB —The compound stem svarsā occurs also once initially, viz

svarṣām (TB suv°) apsām (TB Poona ed twice †apsvām, text and comm) vrjanasya gopām RV VS MS TB

§781. There is, finally, at least one variant in which a Tait text (TB) reads svar contrary to metrical requirements, if it was quoted from some other text, that text has not been discovered. The later texts of the same Tait school, TA and MahānU, write suvar.

tapasarşayah (MahānU °rşayah) suvar (TB svar) anvavından TB TA MahānU

§782. Next we come to three words, all etymologically obscure, in which an apparently older or more regular form in $\imath y$ or $\imath v$ (always preceded by k, is this accidental?), is replaced by y or \imath alone. Most curious of all, in each case a Tait text has the secondary reading with y or \imath alone, and in the first of the three this form seems to be known only in the Tait school and to be regularly used there in this particular word—despite the obvious inconsiste ay with the usual Tait tendency Meter evidently has nothing to do with any of these variations pakṣmāni godhūmaih kuvalair (TB kvalair) utāni VS MS KS TB

sman goanumum kusuum (12) surely states of the form kvalaur makes better meter But this

cannot account for the change, since the word seems regularly to appear as kvåla in the Tait school, and is so written e.g. in a prose Brāhmana passage, TS. 2. 5 3 5—The same word in

ajo dhūmro na godhūmaih kuvalair (TB. kvalair) bheşajam VS MS. TB. kiyāmbr atra rohatu RV : kyāmbūr atra rohatu (TA jāyatām) AV TA

Here the later texts go counter to the meter by expelling i kurayah (KSA and p p of MS °yıh) MS KSA · kvayıh . . VS TS §783. Of the remaining cases under this heading one concerns the somewhat doubtful participle samdhurānā, which TS substitutes (in defiance of meter) for samdhvānā of other texts We take it to be merely a phonetic or orthographic variant for samdhvānā, differing from Whitney, Roots, who quotes it under root dhu (dhū).

samdhrānā (TS. °dhurānā) rātā abhi no grnantu TS MS KS. AS

The other presents a lexical variation involving false word division, see §S32; the word bhiyah 'from fear', is evolved out of the case-ending -bhyah (KS, or -bhih AV.).

rıśvā amīvāh pramuñcan mānusībhih (KS. °sebhyah) AV KS: viśvā āśāh pramuñcan mānusīr bhiyah VS. TS.. vy amīvāh pramuñcan mānusānām MS

C. Suffixal y in noun formations, pronounced and sometimes written iy

§784. Here we include chiefly nouns and adjectives in suffixal ya, but also a few forms in $(i)ya\bar{n}c$, (i)yac, where the y is treated in the same way. In all genuine instances of this variation, the y follows two consonants, and was pronounced as a vowel in all texts (the cases listed §786 are different in character). In practically every case the writing iya, the in accord with metrical requirements, is obviously secondary. It occurs almost exclusively in Tait texts. The following are the metrical pādas concerned, beginning with the few $(i)ya\bar{n}c$ stems asmadryak (TS "driyak) sam mimīhi śravānsi RV. TS. MS KS asmadryay (TS TB "driyag) vārīdhe vīryāya RV. VS TS MS KS.

ŠB. TB.

te pāyavah sadhryañco (TS sadhriyañco) nişadya RV TS MS KS

mā te mano viṣvadryag (TS °drıyag) vi cārīt RV TS MS KS vi mucyadhvam aghnyā (TA ApŚ aghnıyā) devayānāh VS MS KS. ŚB TA ApŚ MŚ

rājam arvaisu payo aghnyāsu (TS aghniyāsu) TS KS. payo grheşu payo aghnyāyām (TB Ap\$ aghniyāsu) AB TB A\$ Ap\$ yad āpo aghnyā (TS. TB aghniyā) iti (omitted in TS TB MS KS L\$.) AV. VS. TS MS. KS SB TB. AS SS. LS: yad āhur aghnyā str VS. SB.

ni vīram (TS. vīravad) gavyam ašvyam (TS. ašviyam) ca rādhah RV. TS MS KS. Several mss. of MS ašviyam

sugavyam no vājī svašvyam (TS °vryam) RV. VS. TS. KSA AŠ

parā duşvapnyam (TB TA Ap\$ MahānU. °niyam) suva RV. SV. TB. TA, Ap\$ Kaus. MahānU.

achā devāri ūcişe dhışnyā (TS dhişniyā) ye RV. VS. TS MS. KS. SB. sa budhnyā (TS TB. TA budhnyā) upamā asya vişļhāh AV. SV VS TS MS. KS. SB TB. AS. SS. TA

pra budhnyā (TS. °niyā) va īrate (TS īrate vo) mahānsi RV. TS MS KS AS. SS.

ahim budhnyam (TS. oniyam) anu rīyamānāh (MS KS anv īyamānāh, TS. anu samearantīh) VS. TS. MS. KS. ŚB.

sväyäm tanü (ApMB.†MG †tanün) rtviye (RV.† rtvye) nädhamänäm (ApMB nätha°, MG. bädha°) RV ApMB. MG.

sa yo vrsā vrsnyebhih (TB °nıyebhih) samokāh RV. AB. KB. TB tam sadhrīcīr ūtayo vrsnyāni (TB vrsnyāni) RV. MS KS. TB.

brhat sāma kṣatrabhrd vṛddhavṛṣnyam (MS °nam, see §315; TS °niyam) TS. MS KS. AS

\$785. There is one case of a false division resulting in a lexical variant (cf. \$771):

ya usriyā apyā (SV. apı yā) antar asmanah (SV. °ni) RV. SV The adjective apyā, pronounced apiyā, is falsely divided in SV

§786. In several variants suffixed y, of various kinds, varies with $\bar{\imath}y$; that is, the epenthetic vowel is long. The forms concern secondary noun formations in $(\bar{\imath})ya$ sometimes; the rest are either comparatives in $yans \bar{\imath}yans$, or denominative participles. In some cases the form in $\bar{\imath}y$ is shown by the meter as well as by text history to be original, that in plain y secondary; note that, most curiously, one of these secondary forms without $\bar{\imath}$ occurs in TS!

apo rmānah pavate kavīyan (SV.† °yān, TS kavyan) RV. SV. TS KSA In SV. nom. of a comparative stem; in the others, of denominative participles

turīyādītya (VSK turyā°) savanam (RV. hav°) ta indriyam RV VS VSK TS. MS KS SB.

But in others the longer form is secondary, at times even unmetrical, and is twice found in Tait texts alone.

tam trā grnāmi tarasam atavyān (TS °rīyān) RV. SV. TS MS KS. N. Comparatives

sanım gäyatram navyānsam (TA. navīyānsam) RV. SV. MS TA. Comparatives In the next case the meter is ambiguous:

derā devebhyo adhvaryanto (KS adhvarīyanto) asthuh VS. TS KS. SB. svişļīm (°ļam) no abhi ('bhi) vasyo (TS KŠ. vasīyo) nayantu AV. TS. KS KS. MS. Here the meter shows that y was vocalic, tho the spelling vasyo seems older.

yathā no rasyasas (TS "sah, LŚ. rasīyasas) karat VS. TS. MS. KS SB LŚ.

unnetar rasīyo (KS. vasyo) . . . MS. KS. Ap\$. Prose.

namo dundubhyāya cāhananyāya. (MS. dundubhaye cāhananīyāya) ca VS. TS MS. KS. Prose.

pāra ikṣavo 'vāryebhyah (KSA.† 'vārīye') pakṣmabhyaḥ svāhā TS. KSA.: avāra ikṣavaḥ pāryebhyaḥ (KSA pārīye') TS. KSA Prose

§787. The following are the prose variants of ya and (short) iya. etām te aghniyi (PB. 'ghnye) nāmāni TS PB.: etā te aghnye nāmāni VS SB. MS. In the latter form quasi-meter.

ā pyāyadhvam aghnyā (TS. TB. ApŚ. aghnyā) . . . VS. TS. MS. KS. ŚB. TB ApŚ. MŚ.

yāsyā aputryā (\$G. °triyā) tanūs . . . \$G. SMB

ahir asi budhnyah (TS. Ap\$ budhnyah) VS. TS MS. KS. PB. \$\$ Ap\$ ahirbudhnya mantram me pāhi M\$. ahe budhniya mantram me gopāya TB. Ap\$.

ahir budhnyo (TS. oniyo) devatā TS MS KS.

namo jaghanyāya ca budhnyāya (TS °nıyāya) ca VS. TS. MS: namo budhnyāya ca jaghanyāya ca KS.

namo agriyāya (VS. KS. 'gryāya, MS 'grīyāya) . . . VS. TS. MS. KS. namo rātyāya ca reşmyāya (TS. °mryāya) ca VS. TS. KS.

namo vidhryāya (MS °riyāya, p.p. °ryāya; TS. nama idhriyāya) cālapyāya ca VS. TS MS. KS.

namaḥ śīghryāya (TS. °rıyāya) ca śībhyāya ca VS. TS.: namaḥ śībhāya ca śīghrāya ca MS. KS.

sumitrā (VS SB. MahānU. SS KS. °triyā, AS. LS. sumitryā) . . . VS. TS. MS. KS. SB TB. TA MahānU. AS. SS. LS. BDh. ApS. KS MS. And similarly durmitrās etc., see §315.

asrībhyām tiroahniyānām (MS. tirohnyānām) ... ApS. MS. tiroahniyān (MS. asrībhyām tirohnyān) somān ... ApS. MS.

D. Stem-final of nouns in 1 or u, long or short

§788. Here again the meter shows that the y or v was in nearly every case pronounced as a vowel, so that the resolution to iy or uv is in

accord with the pronunciation Yet it is always secondary and is practically limited to Tait texts. The variants fall naturally into four groups. First, monosyllabic (radical) $\bar{\imath}$ and \bar{u} stems. In these we expect regularly iy and uv before vocahe endings in the uncompounded stems, and in compounds after two consonants (Wackernagel III §§91a, 100a); consequently there is opportunity for this variation only in compounds after a single consonant, where the regular forms show y,v, but Tait texts (and rarely others) show iy,uv. Second, derivative $\bar{\imath}$ stems of the $dev\bar{\imath}$ type, and very rarely \bar{u} stems in forms that imitate the $dev\bar{\imath}$ declension (see Wackernagel III §97d; only one such variant has been noted). Here the only cases that occur show the variation after two consonants. Third, gentive-locative duals of short i and u stems (see §792). Fourth, \bar{u} stems of the $vrk\bar{\imath}s$ type; the variants are practically limited to the one word $tan\bar{u}$

§789. Monosyllabic (radical) stems in $\bar{\imath}$, $\bar{\imath}$ Most of the variants are metrical; we call attention specifically to the prose ones. They nearly all concern compounds of the stems $dh\bar{\imath}$, $bh\bar{\imath}$, and $p\bar{\imath}$ svādhyam (TS °dhiyam) janayat sūdayac ca RV. VS TS MS svādhyo (TB. °dhiyo) manasā devayantah RV. MS KS AB TB. PG svādhyo (TB. °dhiyo) vidathe apsu jījanan (TB. apsv ajī') RV TB. tam tvā vayam sudhyo (TB. sudhiyo) navyam agne RV. MS. KS TB pāhi mām yajāanyam (TS TB. °niyam) VS TS MS. KS ŠB TB. ŠŚ vaneşu citram vibhvam (TS vibhuvam) nise više RV VS TS MS KS ŠB vibhuve (MS vibhve, KS † vibhave) svāhā VS MS KS TB ApŠ Prose abhibhuve (MS abhibhve, KS abhibhave) svāhā VS MS KS TB ApŠ

šatam yasya subhvah (SV. subhuvah) sākam īrate RV SV

mahişam nah subhvam (AVPpp ms subhavas, Barret JAOS 35 46 subhuvas) tasthıvānsam AVPpp MS samudram na subhvah svā abhışlayah RV.: samudram na subhuvas tasthıvānsam AV. Others, see §119

ghriena no (MS KS. mā) ghriapvah (TS. °puvah) punantu RV. AV VS TS MS KS SB. According to Roth, AVPpp also °puvah

deras írā savitā punātu vasoh pavitrena . . supvā (ApŠ supuvā) VS ŠB ApŠ . devas tvā savitotpunātu . . . supvotpunāmi Kaus Prose.

§790. A peculiar case which may involve lexical reinterpretation of the variant word is the following:

arhann idam dayase viśvam abhvam (TA abbhvam) RV TA. The pāda occurs in a tristubh verse, and abhvam was undoubtedly a dissyllable in RV. In TA it is reinterpreted as ab-bh(u)vam 'originating in water', according to the comm, see §392

§791. Derivative $\bar{\imath}$ and \bar{u} stems of the dev $\bar{\imath}$ type The stem-final is here always preceded by two consonants, and the y or v has vocalic function in nearly all metrical cases. The first is the only case of an \bar{u} stem

samrājāī śvasrvām (ApMB °ruvām) bhava RV SMB ApMB On this form of Wackernagel III p 189, 1 1

asıknya (TA °nıya) marudvṛdhe vıtastaya RV TA MahānU N sūro rathasya naptyah (ArS naptryah, TB °trıyah) RV. AV ArS KS TB

ubhayor ārtnyor (TS oniyor) yaām VS TS MS KS

devyo vamryo (VSK vamriyo) VS VSK SB KS Prose

drsāno rukma urvyā (RV KS urvyā, MS uruyā) vy adyaut (MS vi bhāti) RV VS TS MS KS ŠB. ApMB This adverb is always spelled urvyā in RV, the spelling uruyā (§743) seems to be peculiar to MS, cf next

calşur ma urvyā (MS uruyā, KS urvıyā) vı bhāhı VS TS MS KS SB Prose Cf prec

apīparo mā rātriyā (MŚ rātryā) ahno mā pāhi TA ApŚ MŚ Also apī° māhno rātriyai (rātryai) etc., same texts

yad rātriyā (MahānU and v. l of TA rātryā) pāpam akārşam (TA v. l akārişam) TA MahānU yad rātriyāt kurute pāpam TAA Here by exception the meter favors the unresolved form

rātryai (TB °triyai) krşnam pingākşam VS TB

rātryai (TS rātriyai) tvā TS KS PB Vait

rātryaı (TA ApŚ rātrıyaı) mā pāhı TA ApŚ MŚ

rātryaı (TS TB rātrıyaı) svāhā TS MS KS KSA TB

viśvapsnyā (TS °psniyā) viśvalas pari SV VS. TS MS KS Kauś Here, by exception, the meter favors the unresolved form

samvešāyopavešāya gāyatryai (TS ApŚ °triyās).. TS KS PB. ŠŠ KŠ. ApŚ

 8a gāyatryā (TS TB $^{\circ}trıy\bar{a})$ trış
!ubhā . VS TS MS KS ŚB TB AŚ Kauś

gāyatryai (TS °triyai, MS KS °triyā) gāyatram VS TS MS KS SB mano gāyatryai (TB ApŚ. °triyai) VSK TB. KŚ ApŚ

§791a. The following case is peculiar

viliptī yā (vilipiyā) brhaspate AV (both) In two nearly adjoining stanzas, 12 4 44 and 46, which except for this change are practically identical Whitney would emend viliptyā to viliptī yā, but this is unnecessary, viliptyās would be a correct gentitye form, depending on aśnīyāt of pāda c. 'of the viliptī (cow) the non-brahman shall not eat'

§792. Genitive-locative duals of short \imath and u stems. On these cf. Wackernagel III §22b, which is not quite accurate in stating that all texts write -yoh and -voh (rather than -vyoh and -vvyoh) 'durchweg'; the occurrence of the Tait spellings in the following variants, at least, seems to have been overlooked. As Wackernagel observes, the y and v in these forms is regularly vocalic in RV..

indrāgnyor (TS. ApŚ °gniyor) (prose formulas, see Conc) VS TS.

MS KS SB KŚ ApŚ MŚ

ayād agnīr indrāgniyos TB ayād indrāgnyos . MS

bāhuvor balam TS TAA bahu bāhvor balam AV bāhvor balam Vait MS PG

bāhvos (TS bāhuvos) tava hetayah VS TS hetayas tava bāhvoh MS KS patāti didyun naryasya bāhvoh (TS bāhuvoh) RV TS MS KS ūrvor (TS TAA ūruvor) ojah AV. TS TAA Vait MŚ PG

§793. The stem $tan\bar{u}$ and its type The only form from another stem than $tan\bar{u}$ itself is the fem accus sing sudrvam (from * $sudr\bar{u}$, fem to su-dru), which is of course pronounced sudruvam and is so written in SV—The very numerous cases in which uv for v is written in forms of $tan\bar{u}$ in Tait texts alone are not listed in full

nemim tasteva sudrvam (SV sudruvam) RV SV

yasyaı bahvis tanuvo vilaprşihāh TB . yasyā bahvyas tanvo vilaprşihāh MS

na dhvasmānas tanvī (TS tanuvī) repa ā dhuh RV. TS

tanūs tanvā (TS TAA tanuvā) me saha AV TS TAA PG Vart tanūr me tanvā saha MS The AV mss read ome sahed antāh or the like, the vulgate presents a violent emendation, abandoned by Whitney in his Transl Properly speaking this passage is cadenced prose, rather than verse

śam tokāya tanuve (SMB tanvai) syonah TS TB ApŚ SMB PG Note that PG has the characteristic spelling of TS from which it

here quotes (there is a v 1 tanvai).

tayā nas tanvā (TS ŠvetU tanuvā) šamtamayā VS TS MS KS ŠvetU NīlarU Here the meter is intended for anustubh, and the resolution makes it even worse than the original form

tanıam (TS Ap\$ ApMB HG tanıvam) me pāhi VS TS MS KS AB \$B JB \$\$ Ap\$ PG HG ApMB Prose

E. Verbal forms

§794. The materials here are scattering and miscellaneous A large group contains the participle suvāna, from su 'press', which is always

written thus in RV altho pronounced svana, SV. changes the spelling to match the pronunciation:

pra suvānāso (SV. svā°) brhaddīveşu (SV. °deveşu) harayah RV. SV.

brhat somo vävrdhe suvāna ınduh (SV svāno adrıh) RV. SV.

soma u şuvānah (SV. PB svā°) sotrbhih RV SV PB.

mitrāh suvānā (SV. svānā) arepasah RV SV

ındre suvānāsa (SV svā°) ındavah RV AV SV.

ā soma suvāno (SV. svāno) adrībhīh RV. SV.

parı şya suvāno ahşāh (to be read akṣāh, cf. Oldenberg Noten ad loc)

RV parı sya svāno akşarat SV: cf. parı sya suvāno avyayam RV. parı suvānas (SV svā°) calşase devamādanah RV. SV

parı suvānāsa (SV svā°) ındavah RV. SV.

parı suvāno (SV PB svāno) gursṣṭhāh (to be read °ṣṭhāh) RV. SV. PB. suvānā (SV. svānā) devāsa ındavah RV SV.

suvāno (SV. svāno) arşa pavıtra ā RV SV.

suvāno (SV. svānair) yāti kavikratuh RV. SV

§795. We have already referred (§767) to the Tait. spelling kṣyant for regular kṣiyant, participle of root kṣi (kṣeti, kṣiyanti etc.), in defiance of meter

prati kşiyantam (TS kşyantam) bhuvanāni viśvā RV. VS TS MS KS. SB

ādityasya watam upakşiyantah (TB °kşyantah) RV MS TB.

§796 Conversely to this, but more in accord with the general usage of the school, Tait texts show viyantu for vyantu (root vi) in numerous variants, conforming to the meter always in those which are metrical. samudho agna ājyasya vyantu (TB. viyantu) MS KS TB

aktam (MS MŠ aptubhī, KS *artham) rihānā vyantu (TS TB KhG. viyantu) vayah TS. MS KS. TB. MŠ. GG. KhG · vyantu vayo 'ktam (VSK ripto) rihānāh VS VSK ŠB. KŠ The comms on both VS and TS, followed by Keith, take the verb form from vi + root 1.

vasuvane vasudheyasya vyantu (TB vyantu) VS. MS KS TB AŠ ŠŠ vyantu (TS vyantu) devā havrso me asya TS MS KS.

vyantu (TS vyantu) devīr ya rtur janīnām RV AV TS MS. N

vyantv (TB viyantv) āzyasya VS MS KS TB

uta gnā vyantu (TB vryantu) devapatnīh RV AV. MS TB. N

pībantu madantu (MS °tām) vyantu (TB viyantu somam) VS MS TB. prati na īm surabhīni vyantu (TS viyantu) RV. TS. MS. KS

lekah salehah viyantu TS · sahlah saligah . vyantu MS KS

§797. In two prose variants Tait texts, with VSK, read prornvāthām for the more regular prornuvā" (above, §767)

- svargena lohena samprornuvāthām Vait svarge lohe prornuvāthām (MS °tām, VSK prornvāthām) VS VSK MS ŠB suvarge (KSA† svarge) loke samprornvāthām (KSA†°nuvā°) TS KSA TB
- ghriena dyāva prithivī prornuvāthām (VSK TS Ap\$ prornvāthām; MS M\$† prornuvātām) VS VSK TS MS ŠB KS Ap\$ M\$ vapayā dyāvā° prornuvāthām Kau\$
- §798. Finally, we find two cases of forms of the root $h\bar{u}$ (of the 6th, tud-class?) with v exchanging with uv The latter are commoner in most texts
- mano nv ā huvāmahe (Vait °hi, VS, ŠB, KŠ Kauš hvāmahe) RV VS VSK TS MS KS, AB ŠB AŠ ŠŠ Vait. LŠ KŠ ApŠ Kauš See VV I §2
- tam ahve (SV u huve) vājasātaye RV SV.

CHAPTER XVII. METATHESIS, HAPLOLOGY, AND DITTOLOGY

1 Metathesis

- §799. On metathesis in Sanskrit in general see Wackernagel I §239, and references The cases we have noted are almost entirely lexical, but are not without interest as evidence for the extensive operation in the Vedic tradition of this wide-spread linguistic phenomenon Even when the metathetized form gives a different sense, the fact that metathesis has taken place in a repeated formula remains unquestionable and has linguistic importance
- §800. We begin with metathesis of consonants, and first with a small group in which a single consonant is moved from one place to another pūlyāny (ApMB kulpāny) āvapantīkā AV ApMB Here mss of both texts present both readings, and the variation between lp and ly may be considered graphic
- asmaddātrā devatrā gachata madhumatīh TS asmadrātā (MS KS SS add madhumatīr or °tī) devatrā gachata (KS gacha) VS MS KS SB SS The TS is doubtless secondary 'having us as givers' means 'given by us' (so Keith translates; this is of course the meaning of the other variant)
- yasyedam ā rajo yujah AV ArS yasyedam ā rajah AA yasyedam oja ārujah SS See §244
- endram vagnunā vuhata PB · vagnunendram hvayata TB. Ap\$
- §801. Interchange in position between two adjoining consonants occurs a couple of times
- yad enati jagati yac ca ceşiati nāmno (MahānU nānyo) bhāgo yan (TAA Poona ed 'yam) nāmne (MahānU yatnān me) svāhā TAA MahānU In MahānU v 1 mānyo for nānyo, and yan nāmne for yatnān me The comm understands 'let that (all) be my (ātmanah) portion by effort—no otner' TAA comm says nāman = paramātman'
- yatheyam strī pautram agham na rodāt AG SMB PG ApMB HG yathedam strīpautram aganma rudriyāya MG The latter is simply a bad corruption original, 'that this woman may not weep over harm to her children'
- adhā juvrī (AV atha juvrīr, mss jīrvīr; ApMB athā jūvrī) vidatham ā tadāsi (RV vadāthah) RV AV ApMB See §544

- §802. More frequent is interchange in position between two not adjoining consonants:
- yena turyeno brahmanā bṛhaspataye 'pavathās tena mahyam pavasva JB.:
 yena rūpeņa prajāpataye j'vapathās tena mahyam pavasva KS. The
 original is 'vapathās, as shown by the preceding formula in KS,
 trir vasubhyo 'vapathās etc. (see Conc.). If the JB. reading is
 correct, it contains metathesis of p and v, with assimilation to the
 following pavasva.
- mitrāya kulīpayān (MS. pulīkayān) VS. MS. See §149, and next nākro makarah kulīpayas (TS. kulīkayas, MS. pulīkayas, KSA. pulīrayas) te 'kūpārasya (KSA.† kūvarasya) VS. TS. MS KSA. See under prec.
- evasti nah putrakṛtheşu (MG. pathyākṛteşu, v. 1. as RV.) yonişu RV. AB. MG.
- viivasmai bhūtāyādhvaro (KS. MŚ. bhūtāya dhruvo) astu devāḥ (TS. °dhvaro 'sī) TS. KS. ApŚ. MŚ.
- abaddham mano daridram calışulı süryo...TS. KS. BDh.: adabdham mana işiram calışulı (MS. adabdham calışur arişlam manal) süryo...MS. SG.
- gharmam iocantah (AS. °ia, SS. °iam) pravanezu (AS. SS pranavezu) bibhratah AB. AS. SS.
- chandonāmānām (VSK. chandomānāmām, TS. °mānām) sāmrājyam gachēti (VSK. gachatād iti, MŚ. gached 1ti)...VS VSK. TS SB. MŚ.
- jari cetid (mss cetid, p p. cya iti it) abhisisah MS: ya (TA. Ap\$. ApMB yad) rte (PB. †yakşate) cid abhisisah RV. AV. SV. PB TA. K\$. Ap\$ M\$. Kau\$ GG. ApMB. See \$193.
- ye no drişanly anu tān rabhasva AV.: yo no dresti tanūm rabhasva MS: yo no dresty anu tam ravasva ApS. Here MS. transposes the syllables nu-la.
- apa snehitīr (SV. snīhitim) nrmaņā adhatta (SV. adhad rāh, KS Ţ nrmaņām adadhrām) RV. AV. SV. KS.: upa stuhi tam nrmnām (Poona ed. ɛnuhi tam nrmanām) athadrām TA. See §110. The KS reading looks like a metathesis of adhad rām
- agne dakşaih punīhi nah (TB. mā, MS. punīmahe) RV. MS TB. The MS. reading may be a metathesis of that of TB., which is secondary to RV
- lam te hiranyam lam u sanlv (ApMB. eam u lanlv) āpah AV. Kaul ApMB. See §277.
- brahmādhiguplah (PG brahmābhi", MG. brahmābhigurlam) svārā l.sarānt

(PG surakşıtah syām, MG svarākşānah, most mss svarārakşānah) AG PG. MG. Evident corruption in MG.

dwas (SV dwah) prziham adhi tizihanti cetasā (SV †rohanti tejasā) RV SV With change of surd c to sonant j, cf. §57.

vājaš ca prasataš vasuš (TS suvaš) ca...TS KS. The syllables va-su exchange position yielding suvaš (=svar)

§803. When a vowel and an adjoining semivowel are interchanged, the result, if the vowel is a, is a diphthong in one of the forms. These cases are related to §§747 and 748ff above, q v. The following are instances of $e (=ay, \bar{a}y)$ varying with $ya, y\bar{a}$:

arthas ca ma emas (VSK. me yāmas, MS. ca mā ema) ca me VS VSK TS MS KS.

vrşiıdyāvānam (ApŚ vrşiım devānām) amriam svarvıdam MS. KS. ApŚ. ahā yad dyāvo (AV. devā) asunītım ayan (AV. āyan) RV. AV.

āyur vasāna upa vetu (AV. TA yātu) šeşah (TA. šeşam) RV. AV. TA.

ıtıdam vısvam bhuvanam sam eti (AV. vı yātı) RV. AV. N. Synonymous and related roots \imath and $y\bar{a}$

ahorātre ūrvastīve (VS. °sthīve, TS ahorātrayor vrstyā) ..VS. TS MS See §840

iyam pıtryā (AB vaı pıtre, AS SS pitre) rāştry ety (AV. GB. etv) agre AV. AB GB AS SS

tvayāyam vṛtram vadhyāt (VSK ba°, VS ŚB badhet) VS VSK TS MS. KS ŚB Cf VV I §175, and next

 \bar{a} mā stutasya stutam gamyāt (Vaxt gamet) TS Vaxt \bar{a} mā stotrasya stotram gamyāt PB See prec

vanaspatīnr osadhī rāya eşe (rāye aśyāh) RV (both)

ghriam eva (BDh. ghriam yavā) madhu yavāh BDh. V1Dh

§804. Instances of $o \ (=av, \bar{a}v)$ and $va, v\bar{a}$

sāmānı cakrus tasarāny otave (AV onı vātave) RV AV

vasışthahanuh singini kosyābhyām VS \cdot osışthahanam singinikosyābhyām (TA °kosā°) TS TA.

sam ela viśvā (AV †viśve) vacasā (SV ojasā) patīm dīvah AV. SV Roth quotes Ppp as reading oham ā-, evidently for ojasā See §52

parı ghransam omană (TB parıghransa vām mană) vām vayo gāt (TB gām) RV MS TB N Bad corruption in TB

§804a. A special case of this interchange involves alternative genitiveablative forms of u-stems, such as madhoh madhvah. While this concerns noun inflection more than phonetics, we quote the following examples here

madhvah (SV madhoh) pavanta ūrmayah RV SV

madhvah (SV madhoh) pavasva dhārayā RV SV madhoh pibalam aśvinā VS MS SB TA LS madhvah etc RV VS

as ss

madhvah (SV madhoh) pibanti gauryah RV SV AV MS madhos cakānas cārur madāya AV SV madhvas etc AS SS

vasvah (TB TA MahānU vasoh) kuvid vanātī nah RV KS TB TA MahānU

§805. Instances of vi, $v\bar{i}$, and yu, $y\bar{u}$

achā ma (SV va) ındram matayah svarvıdah (SV svaryuvah) RV AV SV GB Vait

adyā (also nrvat) krnuhı vītaye (SV °hy ūtaye) RV SV Cf §743 āvıtsı (MS āyukşı) sarvā osadhīh RV VS TS MS KS

nādya šatrum nanu (ŚB †na nu) purā vīvītse (ŚB yuyutse) RV. ŚB vīvalam (MS KS yuvalam) chandah VS TS MS KS ŚB

mā te vyoma (=viyoma or vioma, AV yuyoma) samdrši (AV ° šah, LŠ † °šah or °še) AV AA TA AŠ LŠ MG

yajñam pranaya (TS pra suva) devāvyam (TS MS devāyuvam) VS TS MS KS SB

devebhyas tvā devāyuvam (KS devāyuvam) pṛnacmı etc MS KS ApŚ MŚ devebhyas tvā devāvyam (VSK devāyuvam) gṛnhāmı etc VS VSK ŚB pṛāsmān ava pṛtanāsu pṛra vikṣu (TB yulsu) RV TB

ukthebhyas tvokhāvyam grhnām: KS ukthyebhya ukthyāyuvam ApŠ varşmā (VS varşmā) ca me drāghmā (TS drāghuyā, MS drāghmā,

KS drāghvā) ca me VS TS MS KS See §764 TS apparently has a metathetized form for *drāghivā

§806. With the following interchanges of ar and $r\bar{a}$ are to be compared §§656ff In fact the ar forms in the following concern the τ vowel, either directly (as containing sandhi of $a+\tau$), or as guing derivatives of a root in τ

tena rādhyāsam VS. MS SB TB AS ApS MS Kaus tenardhyāsam KS SMB The latter stands for tena rdh°, cf §659

agnau samrādhanīm yaje HG yaje samrādhanīm aham ŚB BrhU AŚ SMB ApMB yuje (read yaje with most mss, Hillebrandt p 250) †samardham īm aham ŚŚ

ahā avartım (AV arātım) avıdat (AV °dah) syonam AV TB ApMB

2 Haplology

§807. On this general subject see especially Bloomfield, PAOS 16 xxxiv, AJP 17 418, Wackernagel I pp 278ff, where further references may be found, we may add Lanman in Whitney, AV 4 5 5, and other

references below. We shall content ourselves here with merely printing the variant cases, arranging them in three groups: those in which the longer reading seems to be the original, so that we may assume haplology; those in which it seems to be secondary, involving dittology; and those in which the question of originality is too uncertain to make classification advisable

- §808. The following are the cases which seem to involve haplology: pṛthưu ribhūvari (ApŚ bhūvari). .KS. ApŚ This is a very clear case On the strength of the isolated ApŚ form Boehtlingk (pw 6 304) set up a goddess Bhūvarī, who is nothing but a ghost, the shade of the adjective ribhūvari after pṛthivi
- viśvasyām viśi praviviśwānsam (KS †pravivišānam) īmahe TS MS. KS. viśo-viśah praviśwānsam īmahe AV Lanman, in Whitney's Transl, has already suggested that the lack of reduplication is due to haplology But it may be noted that it improves the meter, also
- ya äste yaś ca caratı (AV. yaś caratı) RV AV. The haplology is again noted by Lanman.
- trīṇi padāni (TA. MahānU padā) mhītā guhāsya (TA MahānU. guhāsu) AV. VS TA MahānU. The ms of Ppp. padāmhatā guhās-, em Barret JAOS 30 195 to the AVS reading Clear haplology in TA. MahānU.
- agne 'dabdhāyo 'śītatano ('śīrtatano, 'śītama) pāhi , see §353
- yāni kāni ca cakṛma (ApŚ mss omit ca, by haplology) MS ApŚ cf duritāni yāni kāni ca cakṛma MS · duritā yāni cakṛma TS TB TA. (here not really haplology, ca is needed only after kāni)
- ye vā (MS omits vā) vanaspatīnr anu (MS NīlarU °patīnām) VS TS MS. KS SB NīlarU. ApMB Supposed to be metrical even in MS., which is clearly haplological In the same verse
- ye vāvaļeşu (MS †KS ye 'vaţeşu) serate, same texts Here the shorter version can be read metrically by pronouncing avaţeşu, but is nevertheless certainly haplological
- tena vardhasva cā ca pyāyasva (MS vardhasva cā pyāyasva) VS MS. SB. TA: cf eṣā te agne samt tayā (MS tayā tvam) vardhasva cā ca pyāyasva VS SB SS. MS ApS SG. ApMB. ApG HG The second ca is clearly required
- yad era kım ca pratıjagrahāham (TA *jagrāham) AV TA The TA. form (also found in Poona ed) is indefensible formally and metrically, and is obviously haplological.
- nyag vāto 'ra rātı (AV. tāto vātı) RV. AV Lanman notes the haplology yuyuyātām ito rapo apa sridhah RV yūyātām asmad rapo apa sridhah. TB. ApŠ. The loss of a syllable leaves its trace in the long \bar{u}

- anhomuce pra bharemã (AV bhare) manīṣām AV. TS MS KS See VV I p 253.
- anādhrṣṭā apasyo vasānāh VS MS KS ŚB anibhrṣṭā apasyuvo vasānah TS See Keith on TS
- chandonāmānām (VSK °mānānām, TS °mānām) sāmrājyam gacheti (with variants) VS VSK TS ŚB MŚ 'Lordship of the meters' names' or even of their 'measures' (on VSK see §802) is better than 'of the Chandomas', a ritualistic slip
- yad tapsaradrūr uparasya (ApS apsararūparasya) khādati KS ApS The latter corrupt
- guhā hītām nīhītām (KS† omīts nī°) gahvareşu KS MŠ
- namah samgave (TS† samgāya, for °gayāya?) . VS TS MS KS See §250
- yasyedam \bar{a} rajo yujah AV ArS. yasyedam \bar{a} rajah AA Others, see §244
- vrśvāny anyo bhuvanābhrcaşle (MS °nã vr°) RV MS TB . vrśvānyo bhuvanā vrcaşle AV
- parīdam vājy ajınam (PG °dam vājınam) dadhe 'ham (HG ajınam dhatsvāsau) SG PG. HG ApMB The PG is not construable
- [yo no agne nistyo yo 'nistyo KS ApS Conc quotes ApS as omitting the second yo, a modern haplology!]
 - §809. The following cases are less certain.
- mama ca nāma tava ca (KS once omits ca) jātavedah KS (both) The reading with ca is prose, the other metrical; this may account for the change, omitting ca (before jā-)
- puru visvām jūrvan RV.: puro rakṣānsi nijūrvan AV (Ppp msvāmijūrvan) Whitney suggests visvā nijūrvan for RV; Lanman, visvām ni°, assuming haplology As Oldenberg (Noten on 1. 1919) points out, this would make poor meter for a second pāda, he would read jūruan
- suvāū nabhrād aūghāre bambhāre MS svāna bhrājāūghāre bambhāre VS TS ŠB: svāna bhrāl, anghārir bambhārih TA: svān nabhrād anghāre bambhāre...KS. See Keith on TS 1 2 7 1, he suggests svāna nabhrāj as the original

3 Dittology

§810. The following variants contain the reverse of the preceding, in that the shorter version seems to be the original, and dittological influence has produced the variation

kukūnanānām (KS kūtanānām, MS pūtanānām) tvā VS MS KS SB kotanāsu TS Note double dittology in VS SB

- namo babhluśāya vyādhine (TS vivyā°) VS TS. MS KS Either form makes good sense, we assume that the majority have the original athem enam pra hinutāt pitrbhyah (AV. †pitīnr upa); and:
- athem enam (AV athemam enam) pari datlet putrbhyah RV. AV. TA.

 See Whitney on AV. 18 2 4, 5. There is no doubt of the dittology in AV. (note the meter); in 18 2 5 it seems textually certain, being read by nearly all mss. and both editions. In 18. 2. 4 there is more variation in the mss, and SPP. reads athem enam with the comm
- devā (AV devā vā) etasyām avadanta pūrve RV AV The meter proves AV. secondary, and Ppp. (Barret, JAOS 42 127) also omits vā(i)
- namo gırisaya (VS. °śayaya) VS TS. MS KS The stems -śa and -śaya are both unexceptionable, probably the majority indicate the original.
- na sīm adeva āpat (SV. āpa tat) RV. SV. ŠŚ. The RV. has an aorist of āp, to be read as a trissyllable SV tries to improve the meter; cf. VV I p 138.
- nırıtim nirjarjalpena (MS nırjalpena, TS nırjālmakena, KS. nirjālmāka-) šīrṣnā VS TS. MS KS Obscure word; VS. simulates an intensive from jalp
- ye te agna (MS agnā) ındavo yā u nābhayah (TA urnunābhayah, but Poona ed u nā° with v l urnunā°) MS KS. TA The absurd corruption of some TA. mss seems to be read by the comm. also; perhaps it was influenced by thought of ūrnanābhi 'spider', but this would be as inappropriate as possible here
- anhaspatyāya (VS ŠB. KŠ anhasaspataye) tvā VS TS MS ŠB TB. KŠ. ApŠ Stem varying with genitive case form in composition.
- rtur janitrī tasyā apas (GB apasas) par RV GB. If GB is correct it attempts to improve the meter and at the same time furnish a form which can be governed by pari (in RV. apas is governed by a verb in the next pāda, and pari governs tasyāh) But Gaastra reads apas, with v I apasas
- tanūpāś (TB Poona ed text and comm tanūnapāc) ca sarasvatī VS. KS TB. See §195.
- trır asmai sapta dhenavo duduhre (SV Svıdh °hrıre) RV SV. Svıdh. See VV I p $\,170$
- vrṣā pawtre adhi sāno avye (RV * avyaye) RV. (both) SV TA MahānU.

 N Both avya and avyaya (from avya? or avi?) are well known, and both are metrically possible; they are tristubh and jagatī forms of the same expression But the latter occurs in a verse

- (9 86 3) which seems to be a patchwork of older materials (RVRep 453), so that avye is probably original
- ājim na girvavāho jigyur aśvāh SV ājim na jagmur girvāho aśvāh RV For metrical reasons Grassmann considers SV the original Against this Oldenberg, *Noten* on 6 24 6 The SV form is unique, the other familiar, and Grassmann's suggestion is unlikely

§811. Vaguer dittologies seem involved in the following.

- nıdhedhāsı puruspārham (so KS and TB Poona ed, and pp of MS, MS text puruşaspārham) yaśasvat MS KS † TB †
- tato $v\bar{a}k\bar{a}$ (TS tatah $p\bar{a}vak\bar{a}$) $\bar{a}siso$ no juşantām VS TS MS KS SB 'Holy words and prayers' or 'purifying prayers', TS spoils the meter Dittology with p for v
- tena yo 'smat (TA * tenānyo 'smat) samṛchātai (MS mss samṛtsātām)
 MS 'TA The variation is deliberate and intelligent, and scarcely
 belongs here TA repeats a verse in successive stanzas, with this
 purposeful change, the first version means 'whoever comes against
 us therewith', the second 'whoever else' etc
- ındrāpāsya (v l °yāsya) phalıgam ApMB ındrāyayāsya sepham alīkam HG Kırste, 'read ındra āyāsya'

4 Haplology or Dittology

§812. In a smaller group we find either haplology or dittology, but it is not certain which, because the original form of the variants is hard to determine Several of these contain variations between the accusative personal pronouns $m\bar{a}$ and $m\bar{a}m$

āuur brhat tad ašīyo tan māvatu (MŚ mām avatu) ApŚ MŚ

tan mām āvīt TA TU tan māvīt MG

tan māvatu PB TA TU Ap\$ tan mām avatu M\$ AG MG

punar mām aitv (AV Vait Kaus maitv) indriyam AV SB TA BrhU SS Vait AG Kaus SMB GG HG MG

SS Vart AG Kaus SMB GG HG 8813. Other, miscellaneous cases

vājantyāyar (KS °ntyar) tvā TS MS KS ApŠ MŠ Stems niyā and nit While the majority agree on the longer form, this is hardly conclusive KS is probably on the whole the most original YV text; only two other schools differ from it, and nit is a much commoner stem than niyā, which latter seems to be found only in composition with vāja and āji

Sısırāya vıkakarān (KSA † vıkarān, ApŚ vıkırān, vv ll vıkakarān, vıkıkırān) VS KS ApŚ Original form and precise meaning unknown (seemingly some bird) Cf the preceding formula,

hemantāya kakarān (KSA † kakūrān)

- anesann asya yā ışavah (TS KS NîlarU asyeşavah) VS TS MS KS NîlarU The presence or absence of the articular relative makes little difference, and the meter is no better in one reading than in the other
- bharatam uddharem anuşı \tilde{n} ca (MŚ uddharema vanuşantı) TB ApŚ MŚ. See §236, end Either haplology in TB ApŚ , or dittology in MŚ. which is in any case corrupt, with v for m
- anu no mārşļu (VS TS SB TA anu mārştu) tanvo yad vīrīstam (vīlī) AV VS TS MS KS SB. TA SS

CHAPTER XVIII. FALSE DIVISIONS AND PATCH-WORDS

- §814. Except for Sandhi, to be treated in our final chapter, we have now concluded what may be called phonetic variants in the strict sense. In this chapter we shall deal chiefly with variants involving different divisions of words. It may be questionable whether they belong strictly in this volume. Yet they certainly deserve mention, as revealing, perhaps as well as any other groups of variants, the general break-down of sound and sense alike in the Vedic tradition (see §16). There seems no better place than this volume to present these materials, which do not exhaust the subject but illustrate the main types sufficiently.
- 1 A compound word divided, or vice versa, without further change
- §815. In a considerable number of cases the difference between the variant words consists solely in this, that what in one form of the variant is a single compound word appears in the other as two separate words. There being no change in the form of either part, we can sometimes tell only by the accents whether one word or two is intended, and sometimes, indeed, we can not tell at all with confidence. At other times other changes in the formulas suggest a reinterpretation
- §816. We begin with cases in which the original and true form of the variant has one word, the separation into two being secondary, and sometimes uninterpretable
- jagāma sūro adhvano vimadhyam (AV vi madhyam) RV. AV Whitney rightly says that the AV reading is a corruption of the other
- oşışthahanam kıñgınıkokyābhyām (TA °kokābhyām) TS TA vasışthahanuh kıñgını kokyābhyām VS The VS reading is very poor and perhaps should be emended
- yatheyanı sirî pautram agham na rodāt SMB PG ApMB HG · yathedam sirîpautram aganma rudrıyāya MG See §801
- aghoraghoratarebhyas ca MS. ghora ghoratarebhyah TA MahānU
 Preceded by aghorebhyo 'tha ghorebhyah The forms of Rudra are
 meant The tradition is unstable One ms of MS has two
 accents, but MS pp takes it as one word, which seems likely to be
 original TA has two accents, yet its comm understands one
 word, 'more terrible than the terrible', and Poona ed prints it so
 (but with two accents') Comm on MahānU, however, takes
 ghora as a separate vocative, addressed to Rudra

- rianasaspala imam deta yajñam (KS devayajñam srāhā rāci) srāhā rāte dhāḥ VS. KS. ŚB. The variants in AV. 7. 97. 8 and TS. 1. 1. 13 3, 4. 44. 3, have deteşu yajñam, which supports KS in meaning The separate deva yajñam is secondary, if indeed it is really the intention of the texts (so comm. on VS, but the accentless voc. is indistinguishable from deva- as part of a epd)
- rācaspate 'chidrayā rācāchidrayā juhvā divî devāvrdham (ŠS devā rṛdhan) hotrām airayat (KŠ. °yant, TA. erayana, ŠŚ airayana) svāhā SB TA. KŠ. ŠŠ. The ŠS. is uninterpretable.
- §817. In the rest it seems more likely that the form with two words is original, altho in some of them there is little to choose
- yajur yuktam (TA.† yajuryuktam) sāmabhir āktakham tvā (MS. rkta-khamtā) MS. TA. Comm. on TA., 'provided with the yajus'. In MS. two accents- 'the yajus is joined' or the like.
- madhu saspair (MS. madhusaspair) na teja indriyam VS. MS. TB In either case the word madhu is a quasi-adjective, modifying either the preceding bhesajam, or saspair. MS. p.p. divides madhu saspair as two words; Poona ed. of TB prints it as one, but with two accents! (and against the comm.)
- modhu havir (MS. madhuhavir) asi MS. TA. Apś. Mś. So according to the accents of MS. and TA Probably Mś. must be read madhuhavir like MS.; Knauer separates the words because of the parallel hutam havir in Mś. 4. 3. 34; but MS. also reads hutam havir in its version of that passage and follows it immediately with madhuhavir, as one word. Cf. prec.
- derabarhih (KS. dera barhis) sataralsam vi roha TS. KS. TB ApS.:
 atas tram dera vanaspate sataralsa (MS tram barhih sataralsam)
 viroha VS. MS. SB. The latter version suggests taking dera barhih
 as two words, as von Schroeder does in KS. The words are voc,
 so that the accent proves nothing; TS. pp. takes it as one word.
 But Poons ed. of TB. prints it as two.
- arīvarata vo hi kam (TS. hīkam; so printed also in KS.†) AV. TS. MS. KS. Comm. on AV. (as also that on TS.) as a single, compound particle.
- upa prakse (AA. SS. upaprakse) madhumati ksiyantah SV. AA. SS. Svidh. This is hard to interpret, whether as one word or as two For various guesses that have been made see Keith, AA. Transl., p. 285 n. 7. Keith's text of AA. prints upa prakse with most mss., but against comm., who understands upaprakse as a prepositional cpd., 'near the praksa'. Cf. also the infinitive (?) upaprakse, RV 5. 47. 6.

- namas te rudra rūpebhyo namah MS namas te astu rudrarūpebhyah TA MahānU. 'Homage to thee, O Rudra' to (thy) forms homage' 'homage be to thy Rudra-forms (terrible forms)'
- ระงนี ชาร์งนี้คล bheṣajī (TS "habheṣajī, VS "hā bhe", MS "ha [p p , "hā] bheṣajā) VS TS MS KS There is no difference in the meaning, whether the adverb be taken as compounded with the next word or not
- devih (AV dawih, KS trayīs) sad urvīr (TS pp sadurvīh, and so Cone assumes for ApMB HG) uru nah (TS ApMB nah, KS† nas) hinola RV AV TS KS ApMB HG The words are voc and there are no accents RV and AV pp interpret as two words, which seems more natural No doubt all-texts except possibly the Tait school separate sad urvīr
- deva purascara saghyāsam (MS devapuras carasa 7dhyāsam) tvā MS TA ApS MS See §147, and §838 MS p p divides deva from punas (which it reads by error for puras)
- ımām su nāvam āruham TS KS ApS sunāvam ā ruheyam VS (pratika PG)
- pra su (HG. sa, read su) mṛtyum (SMB sumartyam) yuyotana SMB ApMB HG The reading of ApMB is original
- apa (AV ava) śveta padā jahi AV AG ŚG, PG ApMB HG apah śvetapad ā gahi MG Read apa śveta padā in MG, there is no good ground for Kanuer's editing of the text See his note and comm, and our §134
- 2 A compound word divided, or vice versa, with change of form in the prior member
- §818. Next we come to cases in which the prior part of what is a compound word in one form of the variant appears in the other with somewhat altered form. Again we begin with the variants in which it appears that the original form contained a compound, which is broken up in secondary texts.
- stomatrayastrınse bhuvanasya patnı TS KS AS stomas trayastrınse bhuvanasya patnı MS The latter corruptly turns the vocs into noms, apparently making stomas subject and patnı predicate, despite the divergence in gender
- vānmanascalsuhsrotrajihvāghrānaretobuddhyākūtisamkalpā (TA TAA °ākūtih samkalpā) me sudhyantām TA TAA MahānU See §383 sarīram yajnasamalam (MahānU yajnah sa°) lusīdam tasmin sīdatu yo 'smān dvesti TS KSA TA MahānU The latter is clearly second-

- ary, comm makes sarīram yajñah a sentence, 'the sacrifice is the body' On the interpretation of the original, which is troublesome, see Keith on TS
- gaur dhenubhavyā (HG dhenur bhavyā) ApMB. HG The meaning is the same, 'that is to become a milch cow', but the compound dhenubhavyā seems to be the standard expression
- tām ndyām brahmayonım svarūpām (VaradapU. brahmayonısra^a) NrpU. VaradapU. 'The identical womb of brahman', or 'which is identical with the womb of brahman', either is possible
- adhrstam dhrsnvojasam (SV dhrsnum ojasā) RV AV. SV. 'Of irresistible strength': 'irresistible in strength'.
- mıthucarantam (KS mıthū°, TS. mıthuś car°, AV mithuyā car°) upayātı (AV. abhıyāti) dūşayan AV. TS MS. KS. There is really no way of deciding the original
- agner (TS devānām) agneyāny (KS agnıyāny) ası TS. MS. KS. One ms and p p of MS agner agner yāny ası. Cf agner yāny ası TS. MS KS ApS MS See §357.
- devajūte vivasvann āditya te no devāh. MS: vivasvān aditir devajūtis te na ādityā. TS. divo jyote (and, jyotir) vivasva āditya te no devā. KS Both parts of the cpd are changed to different, tho quasi-synonymous, words.
- syonā māvišaterammadah (TS °terā madah) TS. MS. KS. The TS. may be original, as it certainly seems simpler and more natural: 'kindly enter into me as food and drink'. But it is probably a lect. fac for the other: 'kindly enter into me as Irammada (Agni, lightning?')'
- rtaprajātā (MŚ uta pra°) bhaga id vah syāma TS MŚ The latter is secondary but intelligible, §641
- sarvasmād devakılbışāt (LŠ eva kī°, VS. devakılv°) RV. VS MS LŠ. ApŠ · viŝvasmād deva° AV.MS The LŠ is secondary but sensible, §402
- [†aındrāsūrāh (KSA †aındrāsaurāh) śyetalalāmās (KSA.Ţ śyāmala°) tūparāh TS KSA Conc quotes KSA as aındrāh saurāh]
- [anyarratasya (TA anyádvra°, printed by Conc as anyad vra°, the accent proves that it is a cpd, tho the comm seems to take it as two words) saścima (RV saścire, TA saścimah, Poona ed. °ma) RV VS MS ŚB TA]
- §819. In the following, on the other hand, it seems more likely that the version with two separate words is the original
- svāhā yajñam manasah (KS 2 3 yajñamanasah) VS MS. KS. †2 3 and

- 23 5, SB. ApS KS MS. A verb like ā rabhe is understood, the accus yajāam is necessary to the sense, and KS. 2 3 should be so corrected. In 23 5 KS has correctly yajāam ma° (not noted in Conc.). '(I take) sacrifice from mind'
- māgadhah punscalī kitavah klībo 'sūdrā abrāhmanās (VSK punscalī klīvah kitavo 'sūdrābrāhmanās) te prājāpatyāh VS VSK
- satal saras chandasānusļubhena ApŠ satāl sarachandasā jāgatena Kaus In Kaus v l. satāl sarah The original reading of ApŠ (cf §511) makes the adjective agree with ayam sruvo preceding, with change to satā, having a totally different meaning, it is drawn into composition with chandasā
- dahram (v 1 daharam) vipāpmavaravešmabhūtam (MahānU vipāpmam varam vešma°) TA MahānU The Poona ed. of TA reads vipāpmam vara°, with v 1 vipāpmavara° MahānU also has v 1 varavešma° The most plausible original seems to be dahram vipāpmam varavešmabhūtam This is stylistically better than vipāpmavara°, an awkward compound
- dadhad ratnam (AS ratnā) dalşam putrbhya (AS. SS dakşapıt°) äyum (AV āyūnşı) AV AS SS Doubtless AV. 18 original The edition of AS separates dakşa from pi°, evidently regarding it as a voc
- ındrah päsena tsıktvā vah (HG päsena vah tsıktvā) ApMB HG ındrapäsena sıtvā PG. See note in Oldenberg's Translation of HG
- aslonā (AV comm asro°) angair (TA °nāngair) ahrutāh (TA ahrtā, Poona ed ahrutāh, v l °lā) svarge AV TA 'Not lame in their limbs', or 'with not-lame limbs'. AVPpp agrees with TA, but this is the kind of error that occurs very commonly in Ppp, meter indicates that the other version is original
- rudra yat te krayī (VS KS krivi, VSK kravi, MS MŚ giri-) param nāma tasmai (VS MS ŚB tasmin) hutam asi VS VSK TS MS KS ŚB TB ApŚ MŚ See §47
- yasya (ApMB vy asya) yonim prati reto (SG patireto) grhāna (SG grbhāya) SG ApMB HG patireto looks like a secondary adaptation, tho a very natural one
- şad ıd yamā (TA şad udyamā) rşayo devajā iti RV AV TA N Apparently TA must understand udyamā as an adjective
- 3 A compound word divided, or vice versa, with change of form in the second member
- §820. In other cases the form of the variant containing two separate words shows a change in the form of the second member (sometimes

in the first one too) when compared with the form containing a compound. The second member of the compound, when used as a separate word, has a different inflectional ending, or is otherwise changed in form, sometimes it even appears as a different part of speech (a verb). We begin as before with those variants in which the original form seems to be that containing a compound word

- vrşindyāvānam (ApS vrsim devānām) amriam svarvidam MS. KS ApS The original of MS KS means 'nectar of the dwellers in the rainsky, heaven-finding', the sacrifice is referred to In ApS by a lect fac the sacrifice is called 'rain, nectar of the gods', etc
- parā svapnamukhāh śucah AV parah svapna mukhā kṛdhī KŚ 'Away the dream-faced pains'. 'away, O sleep, put (thy) faces (appearances) 'But KŚ may intend a compound
- andrāsūrā janayan višvakarmā TB andrah sūrah prathamo višvakarmā AŠ Comm on TB takes indrā sūrā as two words (and they are so printed in Poona ed), interpreting as noms sing But they must surely be acc dual of a devatā dvandva, object of janayan The whole verse is pretty low bathos AŠ has a lect fac
- bhuvanam ası sahasrapoşapuşı (ApS sahasrapoşam puşa) MS. ApS 'Thou art ground prospering with thousand-fold prosperity': 'prosper thou with thousand-fold prosperity'. Verb form introduced secondarily, cf next
- agne tvāmkāmayā (SV tvām kāmaye) girā RV. SV. VS The original means 'O Agm, with thee-desiring song' By a lect fac SV. introduces a verb form, as in the preceding and next. 'O Agm, I desire thee with song'
- revatı predhā , revatı yajamāne priyam dhā . , revatīr yajā
apatım priyadhāviśata, see §747
- Gre satrūn (AV † Gresatrum) krnuh sarvavīrah (AV °ram) AV TS AS SS MS 'Make him one whose enemies are remote,' AV., doubtles original 'make [his] enemies remote,' lect fac The AV. comm stumbles over the form and understands two words
- ugrampaśyā (MS ugrām paśyā'c, TB dūrepaśyā) ca rāṣṭrabhṛc ca tānī MS TB TA ugrampaśye ugrayitau tad adya AV In this and the next MS is hopelessly corrupt; note accents
- ugrampasye (MS ugrám paśyéd) rāstrabhrt kılbısānı AV MS TA Cf prec
- āsannısūn hṛtsvaso mayobhūn RV. AV TS MS KSA N · āsann cṣām apsuvāho mayobhūn SV The latter misunderstands and simplifies the strange cpd āsann-iṣūn 'having arrows in the mouth' SV means 'carrying water in their mouths

- mama padyāya vi rāja ApMB. mayi dohah padyāyai virājah (MG adds kalpatām) AG HG MG. mayi padyāyai virājo dohah ŠŠ SG PG. The original is virājah, gen of virāj
- [subhagamkaranī mama AV: subhāgam karanam mama SMB But Jorgensen properly prints SMB subhāgamkaranam as one word] §821. In the rest it appears that the form of the variant with two words is the original
- sarūpa vrṣann ā gahi SV JB.. sarūpavarṣā ehi MS In the latter nom. of stem sarūpavarṣa (with sandhi peculiar to MS) The other texts, most likely original, have two vocatives
- parı ghransam omanā (TB parıghransa vām manā) vām vayo gāt (TB gām) RV MS. TB N. Hopeless corruption in TB See §828
- agnır hotā prihivy antarikşam AS ApS agnihotram prihivim antarikşam MS The latter has a careless assimilation to the accusatives of the preceding pāda ukhām sravantīm agadām akarma
- parı doşād udarpıthah KS. parītoşāt tad arpıtha ApS See §63
- mā rudrīyāso abhī gulbadhānah (TA gur vṛdhānah) MS TA. mā no rudrāso adhīgur vadhe nu (mss nuh) MS See §§209, 260, MS has a gross corruption
- sahasradhāram vrsabham divo duhuh (SV divoduham) RV SV Verb form in RV.. 'the thousand-streamed bull of heaven they milked' SV 'the thousand-streamed heaven-milking bull'
- uror \bar{a} no (VS SB. LS pururāvno) deva rīṣas pāhī VS TS MS KS SB. TB LS See §371a
- 4 Last syllable of a word, not a compound, replaced by a patch-word, or vice versa
- §822. In not a few cases the last syllable of a word (not an independent member of a compound) is replaced in a secondary text by a separate word, generally a light word (preposition, particle, or pronoun), which may be called a 'patch-word' ('Flickwort'), or the reverse The cases recorded here differ from those included in the separate sections (§§841–850) on Patch-Words below only in that the degree of phonetic resemblance is here greater, there is no hard and fast line between them
- §823. Since the change in both directions is quite common, it is at times hard to tell, unless on the ground of general text-chronology, which form of the variant is the more original. In the following cases we do not venture to decide this question
- apsarasāv anu dattām rnām (AV rnam nah) AV TB TA. apsarasām anudattān rnām MS (p p. anu, dattām, rnām) Either the plur rnām, or the sing rnam with the pronoun nah, is quite satisfactory

- vratānı (MS TB ApS vratā nu) bibhrad vratapā adabdhah (TB ApS SS SG adābhyah) MS AB TB AS SS ApS SG. In MS etc the older or hieratic form vratā is patched by the particle nu, in the other the alternative form vratānı is used
- mā mā yūnarvā hāsīt (JB yono vām hārasīh) PB JB LS Both forms incomprehensible
- §824. In the following the form of the variant with the longer word seems to be the original, being replaced in a secondary version by a shorter word plus a patch-word. Here may be mentioned RV 4 20 9b (also in KS, where there is no evidence as to the division intended), yayā krnoti muhu kā cid rīvah, read muhukā with Ludwig and Conc, cf Oldenberg, Noten ad loc
- jāmim (KS †cami) mā hinsīr amuyā (MS anu yā) sayānā KS. TB. ApS MS mā jāmim moşīr amuyā sayānām AV Acc to AV comm the darbha-grass used in strewing the vedi is addressed, amuyā is adverbial The MS variant makes sayānā refer to jāmim, conjectured by Ludwig and Henry to mean the uttaravedi, so that in general sense it agrees
- gaurīr (AV gaur ın, TB TA gaurī) mımāya salılānı tal.şatī RV AV TB AA TA N
- dhruvāsah (TB ApŠ dhruvā ha) parvatā ime RV. AV KS TB ApŠ SMB MG
- stavāno (VS TS KS ŚB avā no) devyā kṛpā (VS ŚB dhıyā) RV. VS TS MS KS ŚB
- mā rudriyāso abhi gulbadhānah (TA gur vṛdhānah) MS TA mā no rudrāso adhigur vadhe nu (mss nuh) MS Altho the MS reading is by all means the most reasonable, it is probably only a lect fac TA accents wrongly vṛdhā'nah, and its comm takes the apparently uninterpretable singular quite calmly as a plural (vardhamānāh)! Cf §821
- yo raywo (SV rayim vo) rayintamah RV. SV. KB SS SG VHDh Benfey ignores the uninterpretable vo in his translation, taking rayim as accus of specification
- rşīnām putro abhisastipāvā (TB. °pā ayam, AV °pā u) AV VS SB TB. See §740
- bhavā kṛṣṭīnām (AV. gr°) abhisastipāvā (AV ${}^{\circ}p\bar{a}\ u$) AV. PG. ApMB. HG See prec
- abhūr gṛṣṭīnām (ApMB āpīnām, HG āpīnām, AV mss *v āpīnām, em wrongly vaśānām) abhīśastīpāvā (AV °pā u) AV HG ApMB See prec but one

- ya usrıya apya (SV api ya) antar asmanah (SV °ni) RV. SV. See §785 SV misunderstands and misdivides the epithet appa 'of the waters'
- achāvam eti (KS °vam yanti) śavasā ghrtena (AV ghrtā cit, KS ghrtācīh) AV VS. TS MS KS The AV. reading looks secondary to that of KS, which has an adjective agreeing with srucah, the subject of yanti; ghrtā can only be construed as an accus of goal after etc. whose subject is Agni
- dwaś cid antād (RV, antān) upamām (RV, omān, TA upa mām, so AV v 1 adopted by Whitney, and comm) ud anat RV. SV. AV TA While RV, is of course original, the AV TA reading is not bad: 'even from the end of heaven he has attained unto me' This should doubtless be read in SV
- te brahmalokeşu (TA °loke tu) parantakale TA. MahanU MundU. KaivU
- vıprasya dhārayā kavıh RV.: vıprah sa dhārayā sulah SV. See §189 somah sulasya madhyah RV.: somah sulah sa madhuman SV. See §189 na var śvetasyādhyācāre (AG śvetaś cābhyāgāre, others all śvetasyā-) AG. PG. ApMB HG MG. Secondary but intelligible reading in AG.: see §188.
- ubhāv ındrā (SB. ındro) udithah sūryas ca VS. SB: aya(h)sthūnam (°nāv) udītā (°iau) sūryasya RV. TS MS. KS See §188
- ūrvam gavyam parisadanto agman RV. KS . urvīm gavyām parisadam no akran AV.
- aganma yatra pratıranta (MG. prataram na) āyuh RV AV. MG
- sugantuh karma karanah karisyan JB.: sugam tvah karmah karanah See §739. karah karasyuh LS
- apa snehttir (SV. snihitim) nrmanā adhatta (SV. adhad rāh, KS †nrmanām adadhrām) RV. AV. SV. KS · upa stuhi tam nymnām athadrām (Poona ed varies) TA
- sam takşā hantı cakrī vaḥ (HG. cakrıṇah) ApMB EG Very obscure passage, HG seems to approach closer to a sensible reading
- rtena (MG. rte 'va) sthūnām (onāv, onā) adhı roha vansa (MG vansah) AV. AG. ApMB. HG MG. Kaus Knauer says 'wohl meht ria ua', yet that would seem to give better sense than rte ava In any case MG is secondary.
- startaj (AV. svar yaj) jyotir abhayam svasti RV. AV.
- grāmyamankīradāšakau Ap\$ grāmyam mangīradāsakau MS. vyāghram mañaīradāsa gauh Vait See §49.
 - §825. In verbal endings (cf §827).
- stasti rāye maruto dadhātana (MG dadhātu nah) RV. KS AB MG See VVIp 281

- pna su (HG sa) mṛtyum (SMB sumartyam, MG prathamam artım) yuyotana (MG yuyotu nah) SMB ApMB HG. MG
- vısvam tu tvāhutayah sarvā . PrānāgU · vısvantu tvām āhutayas ca MU Read vısantu, see §371
- krıyanta (TB prıyā ta, so dıvıde) ā barhıh sīda RV. AV KS TB
- dawyā (AV °vā) hotāro (TS °rā, AV °rah) vanuşanta (TS vanı°, KS †vanışan na, AV sanışan na) pürve (AV KS etat) RV AV TS. KS
- vasūnı cārur (cārye, cāryo, cāyyo) vı bhajāsı (SMB bhrjāsı, HG bhajā sa) jīvan AV. SMB APMB HG Cf VV I p 96
- jātavedo nayā hy (read nayāsy?) enam sukrtām yatra lokah JB.. jātavedo vahemam (ŠŠ vahasvainam) sukrtām TA ŠŠ
- §826. In the rest it seems that the form containing two words is the older, a secondary version joins a short word on to the preceding word, usually with some further change:
- samudrena (and °dre na) sındhavo yādamānāh RV (both). Read samudre na in both, Bloomfield, JAOS 27. 77 ff, RVRep 197; Oldenberg, Noten on 3 36 7.
- tinsim indre na (MS indrena) bhesajam VS MS TB Bathos in either case; but MS pp indre, na. VS comm says that na means ca!
- spardhante dhiyah (divah) sürye na (SV süre na, TS KSA.† süryena) visah RV SV TS KSA Change to instr in TS KSA because this is the case naturally construed with spardh.
- neva mānse na pībasi AV. naiva mānsena pīvari PG.: na mānsesu na snāvasu ApMB Perhaps PG. should be divided mānse na; at least this is the original reading
- samsraṣṭā sa yudha ındro ganena RV AV SV. VS TS KS.. samsṛṣṭāsu yutsv ındro ganesu MS 'This Indra the joiner of battle' 'Indra ın the joined battles'.
- trīm padām (padā) mhitā guhāsya (TA MahānU. guhāsu) AV VS TA MahānU Pronoun asya replaced by loc ending -su
- māteva putram bibhrtā sv (VS SB °tāpsv) enat (TS KS enam) VS TS MS KS SB The verse is addressed to waters, hence the secondary reading apsu
- ıdam aham rakşo 'bhı (MS *rakşobhıh) sam ühāmı (TS sam dahāmı) TS MS (bıs) KS. MS See §383
- āvat tam (TA Conc prāvartam, comm and Poona ed. text āvartam) indrah sacyā dhamantam RV AV SV KS TA The sole ms of KS also reads āvartam (ed emends) TA comm interprets as a gerund (āvrtya)
- samıd dısam asaya nah (MS asáyanah) svarvıt (TS suvar°) TS MS

- KS AS ApS Both accent and sense show that no pres mid pple (mase) can be intended, altho MS pp does not divide the word
- yajā no (MS yajāno) devo (TB AŚ ApŚ devān) ajarah suvīrah MS TB. AŚ ApŚ. bhavā no dūto ajarah suvīrah ŚŚ. ŚG. Again (cf prec) the accent shows that MS pp is wrong in not dividing the word, tho this time the participle would be interpretable
- vi ca našan na iso arātayah RV · vi cid ašnānā isayo arātayah SV Benfey renders SV 'devoured' (root aš 'eat', middle pple in passive sense) It is a Verballhornung, the orig itself is rather obscure; vi-naš is peculiarly used
- yato bhayam abhayam tan (KS 35 1c †abhayatvam) no astu (AV ed astı, misprint) AV KS * TB ApŚ MŚ
- imam indra vardhaya kṣatriyam me (TB kṣatriyānām) AV TB Kauś viṣnūvarunā (TB °nāv) abhisastipāvā (TB °pā vām) MS TB Followed by devā yajanta haviṣā ghṛtena 'O V and V, let the 'gods' (TB comm rtvijah) sacrifice to you two as protectors from imprecation' etc The variant form must be dual, and as MS can be so interpreted only by understanding it in a bizarre way (stem °pāva, or irregularly from °pāvan), we assume that TB is orig
- brhaspataye (MS °pate) mahışa (TS mahı şad) dyuman namah AV TS MS. Comm on AV. agrees with TS, which has the correct reading, see §392
- dātum cec chikṣān sa svarga eva AV dātum cec chaknúvānsáh (so, with double accent, Calc ed) svarga eṣām TA For the latter read chalndvān (or better °vān) sá with Poona ed, see VV I p 165
- purasiāt (AB puras tvā) sarve kurmahe AB SS See §365
- sumitrah soma no (Kaus sumano) bhava RV TS MS KS SB KS Kaus
- slomo yajñaś ca (TB yajñasya) rādhyo havişmatā (TB. °tah) RV TB See §188
- arepasah (ApS adds samokasah) cite goh (SV citā goh, ApS cidākoh) SV AV ApS MS See §47
- turas cid visvam †arnavat tapasvān AV · duras ca visvā avrnod apa svāh RV
- tam 1d arbhe havışy ā samānam 1t RV.: tvām arbhasya havışah samānam 2t SV. KS TB ApS
- anupūrvam yalamānā yati siha (AV stha, TA yatisia) RV. AV. TA.
- agne vitatam antar ā (LS antaram) RV VS MS KS TB. LS VHDh Assimilation in LS to vitatam

- ā no yāhi (also, ā yāhi) tapasā janeşu (MS jánişva, ŠŚ. janeşv ā) MS. AB AŠ ŠŠ The accent proves MS wrong, it seems to presuppose janeşv ā.
- yad ultaradrāv uparaš ca khādatah AV yad †apsaradrūr uparasya (ApŚ apsararūparasya) khādati KS ApŚ In AV complementary sing after elliptic dual (Edgerton, KZ 43 110 ff) See VV I p. 270 f §827. Verbal endings are concerned in the following (cf §825).

srucā juhuta no (SS juhutanā) havih TB SS ApS

- tigmāyudhāya bharatā šrnotu nah (TB śrnotana) RV TB N Assimilation of form to the preceding bharatā in TB
- yatheyam strī pautram agham na rodāt AG. SMB PG ApMB HG yathedam strīpautram aganma rudrīyāya MG See §801.
- āprno 'sı samprnah (ApS āprnoşı samprna) SS ApS The latter
- ramadhvam mā bibhīta mat (Kauś bibhītana) AV Kauś pratno hi (TA. pratnoṣi) kam īdyo adhvareşu RV AV TA See §299
- 5 First syllable of a word, not a compound, replaced by a patch-word, or vice versa
- §828. Fairly numerous also are the cases in which a light word replaces the initial, instead of final, syllable of a longer word, or vice versa. In the list now following the form with one word is original, the 'patched' form secondary
- śūro nṛṣātā śavasaś (SV. MS śra°) cakānah (SV ca †kāme) RV. SV. TS MS Assimilation in SV to the preceding loc nṛṣātā: 'hero in men-winning and in desire for glory'
- vasavas cātīsihan vasudhātaras ca AV . vasus cetīsiho vasudhātamas ca VS TS. MS KS The bad meter and feeble sense of AV show that it is a corruption of the other, moreover Ppp agrees with the other texts (Barret, JAOS 42 108)
- sukrām vayanty asurāya nırnıjam RV · sukrā vı yanty asurāya nırnıje SV 'They weave a bright garment for the Asura'. 'the bright (soma-drops) stream variously for the adornment of the Asura'.
- nadayor vıvratayoh süra ındrah RV na devo vıtah süra ındrah SV The 'uncontrolled bulls' of RV seem to be Indra's horses, lect fac ın SV
- asūrte (MS KS °tā) sūrte rajası nişatte (MS. °tā; KS na sattā) RV VS MS KS N· asūrtā sūrtā rajaso mmāne TS Here na seems to be the comparative particle, it is of course secondary
- aryo nasanta (SV nah santu) sanışanta (SV.†°tu) no dhıyah RV SV.

- Again a lect fac in SV (santu taken with preceding, 'devoured . be our foes').
- ūrjam bibhrad vasuvanıh (VS LS SG ApS *vah sumanāh, ApS *vah suvanıh, ApS *vasumanāh) sumedhāh AV. VS KS. LS. ApS (thrice) SG. HG See §227
- ailabrdā (MS °mrdā, KS aidamrdā) yavyudhah (VS āyuryudhah, MS vo yudhah) VS. TS MS KS See §241
- parı ghransam omanā (TB parıghransa vām manā) vām vayo gāt (TB. gām) RV MS TB N. The original 'he shall go thru the heat by your aid unto strength' Corruption in TB
- dame-dame suşlutyā (TS °tīr, MS. °tī, AŚ. ŚŚ °tır) vāvīdhānā (AV °nau, AŚ ŚŚ. vām ıyānā) AV TS MS KS. AŚ ŚŚ. See §236

amanmahīd anāšavah (PB °hīt tad āšavah) RV AV PB

brāhmanebhyo 'bhyanujñātā (MahānU hy anu') TA MahānU.

tam ahve (SV u huve) vājasātaye RV. SV

- tilvilā (misprinted tilvalā) stām irāvatīm AG. tilvilā sthājirāvatī ŠG. tilvalā sthirāvatī MG tilvilā syād irāvatī ApMB A desperate passage, all forms corrupt Oldenberg (on ŠG, p. 144) suggests something like sthāvarāvatī for the original In ApMB a mistaken rationalization, a third person verb is out of place here, since there is a direct address
- [pra yah satrācā (TB. Conc sa vācā) manasā yajāte (TB °tai) RV. TB But Poona ed of TB text and comm satrācā]
- §829. In the rest the form with two words seems to be the original: adyā mamāra sa hyah samāna (MS sahyah samānah; p p sah, hyah, sam, āna) RV AV SV MS TA N The MS makes no sense, and its p p gives the true reading
- yas tā vijānāt (TA * MahānU yas tad veda, AV.* VS yas tāni veda) sa pitus (VS. MahānU pituh, TA savituh) pitāsat RV AV VS TA MahānU N See §198
- sa dahan (GB sadanān) pradahan nv (GB v) agāh GB Vait One ms of Vait has the same absurd reading as GB
- sā prasūr (ŚG suprasūr) dhenukā (HG °gā) bhava AV ŚG ApMB. HG garbhe '(MS °bhah) sañ (VS ŚB san, KS MS sam') jāyase punah RV VS TS MS KS ŚB But it is likely that MS KS really intend san (MS pp)
- sa eva ja...h (T' MahānU sa vijāyamānah) sa janişyamānah VS TA. MahānU ŠvetU ŠirasU.
- svasāra āpo abhı gā viāsaran (SV udā°) RV SV See §60 agne yāhı dūtyam mā -ışanyah (TB °yam vārışenyah) RV MS TB AS. See §225.

- tan mā jinva TS MS tan mārjitvā KS. See §354. KS probably secondary
- amum ma ışāna, and sarvalokam ma ışāna VS. amum manışāna, and sarvam manışāna TA. The form ışāna can properly only mean 'send', but is doubtless felt confusedly as meaning 'wish', as if from *icchati* 'send (as if, 'wish') me that (world)',... 'every world'. TA has a monstrous quasi-imperative middle (with ending āna'), as if from the aorist of root man, comm prayaccha
- ā samudrā (KS ā sīm ugrā, TS ApŚ āsmınn ugrā) acucyavuh TS MS. KS ApŚ Obscure and difficult with any reading, but MS seems clearly secondary
- apām na yanty (SV apo nayanta) ūrmayah RV. SV. 'Like streams of water go (the somas)' '(the somas) lead on the waters'.
- upākriam sasamānam yad asthāt (MS sadhasthāt, v 1 sad asthāt) AV. TS MS MS If sadhasthāt is right (see Knauer's note), it must depend on upākriam
- parisital kvesyasi ApMB · parisidal klesyasi HG The true reading is kva isyasi, or more properly esyasi, 'whither wilt thou go?' The HG. has foolishly attempted to rationalize the reading by connecting it with the quasi-root klis (thinking of klis).
 - 6. Dissyllable words broken up into two 'light words', and vice versa
- §830. Next comes a group which may be said to belong to both the two preceding classes at once That is, a dissyllabic word is broken up into two light words, or vice versa; often with further changes. We begin as before with cases in which the dissyllabic word seems to be the original:

tad vipro abravīd udak (SS u tat) AV. SS See §65

ava (RV abhı, MS ā vah [text vah preceded by havışā], VS SB vācā) somam nayāması (RV mṛśāması, VS SB avanayāmı) RV AV VS TS MS KS SB

sanvan (KŚ sa tvam) sanım suvımucā vımuñca KŚ ŚŚ ApŚ The secondary KŚ reading may be graphic

yamasya dūtah śvapād vidhāvasi TA yamasya dūtaś ca vāg vidhāvati MS See §145

satyam (SV ApŠ sa tvam) vrşan vrşed ası RV. SV. ApŠ vrām u ha (AV aha) prasansatı AV SS SG.

pra na(SV na) indo mahe tane (SV tu nah) RV SV

samyak (TS MS TAA Ap\$ * M\$ sam it, KS * sarit) sravanti sarito

- (TAA Conc °lā, Poona ed. text and comm °lo) na dhenāh RV VS. TS MS KS * SB TAA KŚ ApŚ * MŚ The second reading of KS, sarit, tho given by all mss, is evidently a mistake for sam it, which is secondary to samyal:.
- nyañ (AV ni yan) ni yanty uparasya niskitam (AV ctim) RV. AV. KS tarī mandrāsu prayaksu AV sa īm (TS ī) mandrā suprayasah (TS mandrāsu prayasah, MS mandrā suprayasā starīman) VS TS MS: starī mandras suprayaksuh KS As all commentators realize, the passage is hopelessly corrupt, but sa īm (ī) looks like a secondarv lect fac for some single word (as in AV. KS)
- §831. In the following the version with two light words seems to be original.
- idam ta ekam para ū ta (TB ApS, but not KS, uta) ekam RV AV SV. KS † TB TA. AS SS ApS MS Comm on TB uta, api ca, but the text leaves the word accentless, which, as well as the bad sandhi (uta ekam, with hiatus), indicates that the true reading was u ta (tc).
- sa tū (SV. sato) dhanam kārıne na pra yansat RV SV 'He verily shall give wealth to the singer'. 'he shall give wealth to the virtuous, to the singer'. The genitive, followed by a dative in the same construction, is an indication of the badness of SV.
- kavır yah putrah sa îm ā (TA Conc sā ımāh, Poona ed text and comm sa ımā) cıkcta RV. AV. TA N Comm on TA ımā, ctānı dṛšyamānānı sarvāṇi bhūtānı
- vidyām yām u ca (SS ula) vidmasi AB SS.
- ā yam (MS MS āyan) narah sudānavo dadāšuse RV TS MS KS AS MS The corruption of MS is indicated by the fact that the verb ácucyavuli in the next pāda still has the accent, tho it is no longer in a relative clause, and there is no other reason for the accent
- ku şihah ko vām akına SV.: kūşiho devāv akına RV. It is universally recognized that RV. must be read kū şiho
- utem (SV. ūtim) arbhe havāmahe RV AV. SV. MS uta-īm· ūtim, 'aid' mahī no vātā tha vāntu bhūmau AV: miham na vāto vi ha vāti bhūma RV ā tiā (AV. emām, ŚG enam) parisrutah (AG °sritah, MG °sritah) kumbhah (ApMB †kumbhāh, ŚG kumbhyā) AV AG. ŚG PG. ApMB MG.
- tre ā (SV. tvayā) bhūṣanti vedhasah RV SV Note resolution of e to ay siahpalir yadī vrdhe SV.: svarpatīm yad īm vrdhe RV. AV
- sariah sarvā vn caratu prajānan MS: sa vah sarvāh sam carati prajānan AV The MS pp sah, sarvāh; in the samhitā text stupid assimilation to the following word

- yatrāspṛkṣat tanvo yac ca vāsasah (ApMB tanuvam yatra vāsah) AV. ApMB yatrā vṛkṣas tanuvar yatra vāsah HG. Probably yac ca of AV is original and yatra due to assimilation to the preceding yatrā
- [ā tvam (GB ātmam, but Gaastra correctly ā tvam; LŚ ā svam) ındrāya pyāyasva VS TS MS KS AB GB SB. AS SS Vait LŚ]
- [name tad upadambhişar MS MS na ma idam upadambhişag ApS We must read ná me in MS MS, there is no p p here, and náme is simply bad editing]
- [m gā ındra vıcaran spāśayasva TA ApŚ In TA, text printed vigā, but both syllables accented, clearly vigā(h) is intended, so comm]
 - 7 Longer words, not compounds, broken up into two or more shorter words, and vice versa.
- §832. We come next to a group of variants in which a word of more than two syllables, generally at least four, is split up into two or more shorter words, or vice versa Excluded are divisions of compounds into parts, which have been treated above First come cases in which the longer word is original
- balım ıcchanto vıtudasya (AG. vı tu tasya, v 1 vıdurasya) preşyāh (MahānU AG preşṭhāh) TAA MahānU AG See §65
- upānasah †saparyan RV upo nu sa saparyan SV Indra is meant, SV has obvious earmarks of secondariness
- yad ındra cıtra mehanā (SV PB ma ıha na) RV SV. PB AŚ ŚŚ N As in the preceding, a rather obscure word (mehanā, adv) is broken up into a series of harmless particles in SV.
- na me (so read, §831) tad upadambhişar ..MS MS na ma idam upadambhişag (once erroneously udam bhişag) . ApS A simple and obvious blunder, possibly only a misprint
- mā (AG MG ā) tvā prāpann aghāyavah (MG. adyāyavah) AG ŞG ApMB MG See §868
- akṣānām vagnum (AV em ganam, true reading probably gatnum with SPP, see Whitney's note, MS †vagmum) upayighnamānah (AV upalipsamānāh, MS avayighram āpah) AV MS TB TA The MS is corrupt, its pp, yet worse akṣnā, avagmam ity ava-gmam, avayighram ity ava-yighram, āpah But the original is obscure enough
- viśvā amīvāh pramuñcan mānuşībhih (KS *şebhyah) AV. KS viśvā ašāh pramuñcan mānuşīr bhiyah VS TS: vy amīvāh pramuñcan mānuşānām MS Evidently VS TS are secondary, the interpretable, cf §783

yasya te visvamānuşah (SV. visvam ānuşak) RV AV SV It is surprising to find the simple and commonplace RV reading distorted in SV. into one that is much more recondite, and hard to interpret See Benfey's note in Translation, p 259

anvādīdyāthām tha nah sakhāyā TB TA manmā dīdhyānā utā nah sakhāyā MS. The latter seems clearly corrupt, p p dīdhyānām, the nasal perhaps preserving a trace of the original, which means: 'make us shine here, O ye two friends (Mitra and Varuna)'.

yebhyo madhu pradhāvatı (AV. pradhāv adhı) RV AV TA The AV. comm, followed by SPP and Whitney's Transl, reads pradhāvatı, correctly

tvam no devatātaye (AV deva dātave) RV AV SV - See §61.

prathamāya januse bhūmanesihāh (AV bhuvane°, ŠŠ. bhūma nesihan) AV. AŠ ŠŠ If ŠŠ intends this division, it would seem to mean 'that thou shalt lead the world' Obscure

yajñah pratyaşthāt (v l praty u sthāt) KS . yajñah praty u sthāt (v l pratyasthāt) . . MŚ. yajña pratitistha TB ApS

apāmītyam (AŠ apām ittham) īva sambhara MS KS AŠ A graphic error in AŠ

ubhe yatete ubhayasya (AV ubhe asya) pusyatah RV. AV Cf next ubhe 1d asyobhayasya (AV asyobhe asya) rājatah RV AV In same verse as prec; here Whitney adopts the RV reading See §911

§833. Next cases in which the reading with one long word is second-

ava tara (TS avattaram) nadīṣv ā VS TS MS KS ŚB. avattaro nadīnām AV ava tara 'descend in the rivers' is original, in TS AV there is no verb, and one must be awkwardly supplied. The double t is suspicious (cf §401), BR take it, following the Indian tradition, as from the participle of root av, which is not at all likely to lead to 'the original sense (however it may have been felt in TS AV) Keith rejects the comm and connects with ava, while Whitney follows the tradition MS pp avataram

prāntar rṣaya sthāvīrīr (SV prāntarīkṣāt sthāvīrīs te) asīkṣata RV SV pra dhārā yantu madhunah AB pra dhārayantu madhuno ghrtasya AG (corrupt, abandoned by Stenzler for the other reading)

dyusamantasya ta ādıtyo 'nukhyātā BDh dyauh samā tasyādıtya upadrastā HG The BDh reading seems like a secondary adaptation of HG, which is typical stylistically—The next two variants are in the same passage

antarıkşasamantasya te väyur upaśrotā BDh . antarıkşam samam tasya väyur upadraştā HG As prec

- pṛthivīsamantasya te 'gnir upadrasṭā BDh.: pṛthivī samā tasyāgnir upadraṣṭā... HG. See prec two
- sutarası tarase (MahānU. sutarasıddhatarase) namah RVKh. TA MahānU The latter has a v l like the others, but its comm reads the recorded version, which is obviously a secondary attempt to make the meaning simpler Sutarası is voc sing fem, and tarase an infinitive
- šīte vāte punann wa (AŠ LŠ, mss of Vait, most mss of ŠŠ, and v 1. of KSA punarnīva) VS TS MS KSA ŠB TB. AŠ ŠŠ Vait LŠ Doubtless a graphic corruption, but its wide spread is curious
- antarā dyāvāprthīvī apah suvah TB ApMB HG antarā dyāvāprthīvyor apasyuh MG Is apasyuh understood as apa-syuh, from apa-as 'be away'? It is hard to construe a nom-sing. of apasyu. In any case it is secondary.
- anupauhvad anupahvayet HG: anu po 'hvad anuhvayah ApMB. See §732
- yajñapataye (SS adds vasu; TA yajamānāya) vāryam ā svas kah (TA. ā suvas kar asmaı, SS āsamskarase) MS TA SS The latter secondary
- tanūpā ye nas tanvas tanūjāh AV: tanūpāvānas tanvas tapojāh AB AS. The AV. is probably original. See §254.
- ayam sahasram ānavo dṛśah kavīnām matır yyotır vidharma (ApŚ °mā) SV. ApŚ. MŚ: ayam sahasram ā no dṛśa . vidharmanı AV. Benfey is forced to interpret the corrupt SV. reading sahasramānavo as one compound word, against the accents: 'der tausendbewachende'. Probably AV is original, tho it too is not very sensible
- agnır hotrenedam (hotrena, agnıhotrenedam) havır . ., see §354
- vande därum vandamāno vivakmi RV: vandadvārā vandamānā vivastu SV On this troublesome and disputed passage see references quoted in VVI p 218
 - 8 Different divisions of two or more independent words
- \$834. Finally we come to a large class in which two or more independent words are involved in both forms of the differently divided variant. They fall into three subdivisions. Perhaps the simplest (a) are those which concern different resolutions of a final or initial vowel between the two words, so that in one form of the variant the vowel belongs exclusively to either the preceding or the following word, while in the other it (not necessarily the same vowel) contains a fusion of the final of one word with the initial vowel of the next. Secondly, (b)

there are cases in which a final consonant is detached from one word and affixed to the next. And thirdly, (c) cases with more extensive alterations, at least one entire syllable being detached from one word and attached to another, sometimes a whole series of words-is affected, resulting in complete revision of the passage

(a) Different resolution of final-initial vowels

§835. We begin with the cases concerning final-initial vowels. In one form of these variants a vowel at the end of one word or at the beginning of the next belongs exclusively to the one word, while in the other it (not always the same vowel) contains a fusion of a final with an initial vowel. Either form may be the older; we begin with those in which sandhi, combination of two vowels, seems to be the original reading, which is much more frequently the case

avakrakşınam vrşabham yathajuram (SV yatha juvam) RV AV SV. ajuram 'ngeless', nuvam 'swift'

- na mānsam ası nodalam (HG no dalam) ApMB HG If the division is so intended, HG must mean 'thou art not flesh, nor a fragment' The comm on ApMB (Winternitz, Introduction, p xxiv) takes nodalam for na-udaram, 'nor a (part of the) belly'
- ya ājagma (N°muh) savanemā (TS KS savanedam, N savanam udam, VS MS SB ya ājagmedam savanam) juṣānāh AV VS TS MS KS SB N Cone suggests savanemā (savanā-umā) for AV, and Whituey notes that the AV text (p p savane, mā) is a corruption of this, tho he translates 'ye that have come enjoying me at the libation'
- samıdhyamānah prathamānu †dharmā (TB ApS prathamo nu dharmah)
 RV TB ApS The later texts stumble over the antiquated forms
 prathamā dharmā (neut plur) of RV 'According to ancient
 ordinances' 'as the very first law'

prasthäyendrägnibhyäm somam vocatopo (KB vocato yo) asmän brähmanän brähmanä hvayadhvam KB AS SS As Keith says in liis Transl, KB must be read vocatopo A graphic corruption

- 3thvā pavitram asvināsan (TB °nā sam) sarasvatī VS MS KS TB The original, of which TB is an uncomprehending corruption, contains āsan in his mouth
- viśvalopa visvadāvasya tvāsañ juhomi TS GB Vait ApŚ viśloka viśvadāvye tvā samjuhomi svāhā MŚ Precisely like the prec, except that here the secondary reading is verbally intelligible

gāra upavalāvalam (SV upa vadāvate) PV SV See §60

- yatrāspṛksat tanvo yac ca vāsasah (ApMB tanuvam yatra vāsah) AV. ApMB. yatrā vṛkṣas tanuvai yatra vāsah HG The latter corrupt; see §198
- rdhag (RV AV dhruvam) ayā (AV. ayo, TS MS. KS ayād) rdhag (RV AV dhruvam) utāšamışthāh (MS KS °şṭa, AV. utā šavışṭha) RV AV VS TS MS KS ŚB N. See §234
- yat tvemahe (SMB te mahe) prati tan no (Kauś prati nas taj) jusasva RV.

 TS MS Kauś SMB. PG ApMB Original has tvā-īmahe
 SMB comm alternatively takes mahe as a verb, pūjayāmi, or as a
 noun, utsave, supplying pūjādikam karma with yat. All mss agree
 on it
- āśum tvājau (ApŚ ākhum tvā ye) dadhire devayantah KS ApŚ MŚ hariśmaśrum na varmanā dhanarcim SV.: hiriśmaśrum nārvānam dhanarcam RV
- dhātā vidhātā (MS dhartā vidhartā) paramota samdīk (KS paramo na samvīk) RV VS TS MS KS. N. Graphic change in KS, §871 hotā vistīmena (SS vistvī me) jaritar AV AS SS Vait See §367.
- tenemām upa sincatam RV. AV. TA N tena mām abhişincatam \$\$ SMB Different contexts, imām or mām.
- tena tvam agna ıha vardhayemam AV. tenāgne tvam uta vardhayemam (MS °yā mām) TS MS KS ımam or mām
- puteva putram jarase nayemam (MS ma emam) MS. KS ApMB. HG. The corruption of MS is indicated by its p p: jarasera. ā, imam, pointing to the other reading
- yaded (KS ād id) antā adadrhanta (TS adadrnh°) pūrve RV VS TS MS. KS
- yenākşā (SMB °kşān, PG °kşyāv, SS yenā kşām) abhyaşıcyanta (SS SMB abhyaşıñcatam, PG °tām) AV. SS SMB. PG For the original 'dice' SS. lamely substitutes 'earth'.
- [tvayāvasena (\$G text tvayā jvasena) sam ašīmahı tvā TS KS TB A\$ M\$ Kaus \$G. SMB PG The \$G seems to be a misprint]
- §836. We come now to the much fewer cases in which the original reading assigns the vowel exclusively to one of the two variant words, the form with vocalic sandhi being secondary
- yadārāghatī (read yadā rā°) varadah Vs.t.. yadā rākhāļyau vadalah ApŚ yad adyārādhyam vadantah MŚ See §70
- praty eva (ŠŠ pra iveva, 1 e ivā-iva) grbhāyata AV AB GB JB ŠŠ
- grāvāvādīd (ApŚ grāvā vaded) abhī somasyānsum (ApŚ °sunā) KS ApŚ But KS ed prints the ApŚ reading, with v 1 °rādīd
- śrutakak so aram (SV "kaksāram) gave RV SV Nom voc

- vīhi svām āhutim jusāno manasā AV: vīhi svāhāhutim jusānah TS. TE The ritualistic exclamation svāhā is always allowable, but is her secondary
- višvasmai bhūtāyādhvaro (KS MŠ. bhūtāya dhrui) astu devāh (15 °dhvaro'si) TS KS. ApŠ MŠ adhvara dhruva, it is not certain tha the latter is more original
- mā na āyuh param avaram mānadonath MS mā nah param adharam mā rajo 'nath (MŚ †param adhanam mā rajo nath) TA. MŚ The MS is corrupt, and its p p is worse mā, anat, ā, unath Cf VV p 93
- ā māšişo (or ām āšişo, so MS understands) dohakāmāh MS KS emā agmann āšişo dohakāmāh TS ApŚ. It is possible that KS also intends ām (interjection) āšişo It seems that TS ApŚ (ā-imās) have a lect fac.
- [ātmāsy ātmann ātmānam (GB ātmanātmānam, but Gaastra as the others) me mā hīnsīh GB Vait Kauš]
- (b) Final-initial consonant transferred from one word to another §837. Next there are a few cases in which a consonant is mobile between words, being attached to the preceding word in one form of the variant, to the following word in another. This process may be illustrated within the RV itself, in the pada traditionally recorded as agner avena marutam na bhojyā, 1 128 5b. Here we must surely read agne ravena, see Cone and Neisser, ZWbch d RV I 127. This is commonly recognized, altho Oldenberg, Noten, has some slight doubts Similarly, it is commonly recognized that for nybhir yad yukto nive rapānsi, RV 1 69 8, we must read viver apānsi, and for muṣāyas cakram avive rapānsi, RV 6.31 3, aviver apānsi. Also in AV 6 116 1a, yad yāmam cakrur nikhananto agre, read probably yady āmam; see Bloomfield, AJP 17 428, SBE 42 457, and Whitney ad loc

āsann ā (SV PB āsan nah) pātram janayanta (KS tu) devāh RV SV VS TS MS KS PB ŠB

madhu reto (TS madhor ato, KS †madhur ato, AS text printed madhureto) mādhavah pātv asmān TS MS KS AS Keith on TS thinks the KS reading is correct. He calls the MS 'nonsense', which is a little strong considering that we are dealing with a yajus formula; madhu and reto might be taken as coordinate with either subject or object. But the MS p p reads madhuh, amiah, pointing towards the KS reading

revati ramadhvam, revatir amedhyam, see §255

- ā māšişo (MS text ām āšişo) dohakāmāh MS KS And others; see \$836 MS and KS, may intend the same reading
- agor arır ā cıketa RV nāgo rayır ā cıketa SV. Benfey understands na-ago(s), from agu 'mcht preisend' = 'bos' Doubtful, the SV is hardly interpretable
- ubhayor ārtnyor (TS ārtnyor, Nīlar U. ubhayo rājnor) jyām VS TS MS KS Nīlar U. An absurd corruption in the last; it can only refer to the two ends of the bow, and so the comm calmly takes it
- satyād ā (ApŠ satyā tā) dharmanas patī (ŚŚ dharmanā, and so mss of MS, Vait MS parī, ŚŚ omits patī) AŚ ŚŚ. Vait ApŚ MŚ.
- purovāto varsañ jinvar āvrt svāhā TS ApS: purovāta (KS °to) jinva rāvat (KS °vat) svāhā MS KS And other formulas in same passage, see §168 TS is secondary
- yam asvinā namucer āsurād adhi (ŚŚ †namucāv āsure dadhi) VS MS KS ŠB TB ŚŚ Vait LŚ. Followed by: sarasvaty asunod indrivāya Some verb, probably a form of su, is understood 'which (soma) the Aśvins pressed out (Caland on Vait enthalmen) from the asuric N' ŚŚ is secondary and poor, dadhi 'sour milk' conceals adhi, to which is affixed the d of the abl which preceded in the original form. For the myth in question see Bloomfield, JAOS 15 144-63

(c) More extensive false divisions between separate words

§838. In the rest the alteration involved in the false division is more extensive at least one syllable is detached from one word and attached to another — Sometimes a whole series of words is affected, as in.

śatāpāṣṭhādya (read with Poona ed of both °thā gha) viṣā pari no vṛnaktu TB TA śarā vāṣṭād dhaviṣā vārnah MS (corrupt)

- pītā bhāsvaty anūpamā TA pītābhā syāt tanūpamā MahānU In MahānU a v l agrees with TA but for anūp°, but the comm keeps to the text as printed He explains pītābhā by pītavarnā, and tanūpamā by sūkşmenopamīyate kundalinīti yām naigamā āhuh The TA makes pītā bhāsvatī = pītavarnā, and anūpamā is explained by laukikānām tanūnām sūkşmavastūnām upamā bhavitum yogyā
 - acıkradat svapā iha bhuvat AV · adıdyutat sv apāko vibhāvā RV MS Whitney says the AV has 'an adaptation, or corruption, or both' of the other reading Ppp bhavat for bhuvat (§602).
- deva purascara saghyāsam (MS devapuras carasa 7dhyāsam) tvā MS TA ApŠ The MS. 18 corrupt pp deva, punar 111 punah, carase See §817.

- dvişas taradhyā (ApŚ. °yai) rnayā na īyase (SV īrase) RV SV KS. AB ApŚ. dvişas tad adhy arnaveneyase AV 'A simple corruption' (Whitney) in AV
- riasyariena mām uta (TA 1ta) TB TA · riásya tv enam ā'mútah MS (p p tú, enam, mā'm, utiám ma, in part pointing to the TB reading). MS is corrupt, in TB. supply muñcata from preceding pāda
- graha viśvajanīna niyantar viprāyāma te (MS p.p. viprāya, 'mate, KS nyantar vipra ā †satī) MS KS
- §839. In several instances the prefix su exchanges with su as locative ending
- made suśipram (SV madeşu śipram) andhasah RV. SV
- tarī mandrāsu prayakşu AV sa īm (TS î) mandrā suprayasah (MS °sā starīman, TS mandrāsu prayasah) VS TS MS stanī mandras suprayakşuh KS
- mandūky apsu šam bhuvah AV.: mandūkyā su sam †gamah (TA gamaya) RV. TA The familiar association of the frog with waters leads to the secondary reading of AV
 - §840. The rest hardly need classification
- yas te soma prajāvat so 'bhı so aham MahānU yās te soma prajā vatso 'bhı so aham TA Both are obscure, and the far-fetched interpretations of the comms give little help. For instance, the TA comm explains soma as sa + uma, from umā = brahmavidyā, so that soma = paramātman'
- viśvakarman bhauvana mām didāsitha (SB manda āsitha) AB SB SS. didāsitha is taken as a desiderative from dā 'O V Bh, thou didst seek to give me (the earth) away': 'thou wast slow of wit (so comm, mandamath)' Either meaning is possible
- bhrātāntarīkṣam abhīsastyā nah (TA abhīsasta enah) AV TA Comm on TA yad eno 'smābhīh kṛtam tad abhīsastah satrusthānīyam' It would be better to understand abhīsaste, 'upon the accursed one (may) the sin (light)'. Whitney understands a verb 'save' in AV
- samudrād udajam vah (ApS udacann wa) srucā MS ApS The ApS. reading seems better
- yā samjayanlam adhi yāsu vardhase KS āsum jayanlam anu yāsu vardhase RV VS TS MS ŚB
- mänasya patnı saranā syonā AV mā nah sapatnah saranah syonā HG See §189
- yyeşthasya dharmam dyuksor anīle SV yyesthasya vā dharmani kşor anīle RV. The bad form dyukşor is taken by Benfey as for dyukşayor, from dyukşu

- brahmādhiguptah (PG brahmābhi°, MG. brahmābhigūrtam) svārā kṣarām (PG. surakṣitah syām, MG svarākṣānah, most mss. svarārakṣānah) svāhā AG PG. MG. The original is probably AG, see §742 PG has a simple lect fac, MG is corrupt
- yena bhūyas ca rātryām (ApMB. carāty ayam, MG caraty ayam, PG bhūris carā dwam) AG PG ApMB MG See §61
- sarasvalyaı vāco yantur yantrıye (VSK. vāc ua 'urye turyam) dadhāmı VS VSK SB Corruption in VSK
- āyuhpatı rathamtaram (MŚ āyuh pratıratham°) tad asīya . ApŚ MŚ. Caland would read °patī (nom) ın ApŚ , and observes that MŚ ıs yet more corrupt
- ud vansam wa yemre RV SV TS KB N . $\bar{\text{u}}\text{r}\text{dhvam}$ kham wa menwe Mbh
- k_{l} aivā varīziham vara āmurīm uta RV AV $\;\;$ kratve vare sthemany āmurīm uta SV
- ruvad dhokṣā (TB $\,$ nrvadbhyo 'kṣā) paprathānebhir evaih RV. MS $\,$ AB. KB $\,$ TB $\,$ See §684
- prath. achad (KS parama°) avarān (TS paramachado vara) ā viveša RV VS TS MS KS Keith takes paramachado as a gen depending on vara (vare) The result is close to nonsense
- ā devo yātı bhuvanānı paśyan (TS MS bhuvanā vıpaśyan) RV VS TS MS
- tena samhanu krnması AV. tena sann anugrhnäsi HG See §47.
- pathā madhumatā bharan (MS °mad ābharan) VS. MS TB. Either makes good sense
- ahorātre ūrvaştīve (VS °sthīve, TS ahorātrayor vṛṣtyā) bṛhadrathamtare ca me yajñena kalpetām (VS †kalpantām) VS TS MS Cf §803, TS secondary.
- pumānsam vardhatām mayı SG.: pumān samvartatām mayı PG. pumān garbhas tavodare SMB See §97 Despite the Conc, SG is quite correct, and may well be the original reading
- jāmım ıtvā mā vıvıtse lokān TA · jāmım rtvā māva patsı lokāt AV See §198
- hıranyavad annavad dhehı (ApS annam adhyehı, read annamad dhehı) mahyam KS ApS
- utem anamnamuh (KB SB SS KS. uteva nam°) TS MS AB KB. SB AS SS KS ApS MS
- athem ava sya vara \bar{a} pṛthưyāh TS AS SS MS . athemam asyā vara \bar{a} pṛthưyāh AV See §236
- utānyo asmad yajate vi cāvah (TB vicāyah) RV MS TB N. See §254

- anūdhā yadı jījanad (SV. yad ajījanad) adhā ca nu (SV. adhā cid ā) RV SV.
- pra su (HG sa) mṛlyum (SMB pra sumartyam, MG prathamam artım) yuyotana (MG yuyotu nah) SMB. ApMB. HG MG. The lastis secondary.
- yaśasendrābrhaspatī (ArS yaśo mendrā°) ArS. PG MG Graphic change
- dyumatlamā supratīkasya sūnoh (AV °tīkah sasūnuh) AV VS TS MS KS SB See §189
- dhıya martah sasamate (SV. martasya samatah) RV SV See §189
- yaśo bhagaś ca mā rıdat (MG. rışat, most mss rışak) PG MG · yaśo bhagasya vındatu ArS See §189.
- yunajmi tisro viprcah sūryasya te (MS vivitah sūryah save, or savah) TS ApS MS. See §189
- pragāyāmasy agratah PG ApMB · pragāyāmy asyāgratah MG †prajāyāmasy agratah HG asya in MG is to be taken in a cosmic sense, it is of course secondary
- yamasya loke adhırajırı äyat (TA äya, MS loke nıdhır ajarāya) AV MS TA Whitney describes the MS as a 'corrupt guess'
- māvādevā avalaran HG., adevā devavatlaram ApMB See §401
- ā gharmo agnīm rtayann asādī (TA asādīt) RV TA. ā gharmo agnīr amrto na sādī MS The latter is of course secondary
- adha syāma surabhayo (ApŚ syām asur ubhayor) gṛheşu AV. KS ApŚ athā syāta surabhayo gṛheşu MS The ApŚ is worthless; Caland tacitly adopts the other reading
- [ssur nāvīrastāram SS 15um na vīro astā AV RWh. by emendation, but mss as SS except for 15um]
- [pātam mā dyāvāprihīvī adyāhnah (Kauś text aghān nah) TS ApŚ Kaus Read adyāhnah in Kauś, cf critical note, p 295, n 4 of ed In the reading quoted for ms Bū hna should be read for dna]

9. Patch-words

§841. In the earlier parts of this chapter, and especially in §§822-31, we have met many cases of variation between a longer word and a shorter word 'patched' by a light word. We shall now add a group of variants involving such light words—'patch-words', Flickworte, Luckenbusser—to which 'false division' in the strict sense seems not to apply, because the phonetic resemblance between the variant words is insufficiently close. There is no hard and fast line between the two groups, however, and we are far from regarding the separation we have

made as absolute. Doubtless many of the variants which follow might with justice have been classed above. At least they all belong in the same chapter

§842. For instance, in a pāda like

syonam patye (AV. patibhyo) vahatum kṛnuṣva (AV. kṛnu tvam) RV. AV SMB ApMB MG. N,

it is clear that AV has substituted an active imperative form for a middle, filling out the meter with the pronoun tvam. There is still a certain resemblance in sound between the syllables tvam and -sva. This resemblance approaches the vanishing point in

na no rayım subhojasam yuvasva (TS yuveha) RV VS TS. MS KS, where TS likewise uses an active for a middle imperative, patching the pāda with the adverb iha And in a pāda like

āpas tad ghnantu sarvadā (MG. te sadā) MG YDh,

it would obviously be impossible to speak of 'false division', since $sarvad\bar{a}$, if it is the original reading, cannot be thought of as divided into $te \; sad\bar{a}$, rather, the synonym sada is substituted, and the line is then patched by inserting the light word te. If, as we suspect, the original form of this pāda was that of MG, the order of change is reversed, but the principle is the same

- §843. Prevailingly these variants are concerned with metrical requirements, as is clearly suggested by the above examples. The use of a patch word is designed to fill out a metrical unit which would otherwise be defective. This comes out very interestingly in a small group of cases where the original reading had or seemed to have defective meter, and in a secondary text this is corrected by inserting a patch word.
- agnim (SV agnim u) śresthaśocisam RV SV. In RV śrestha-constituted three syllables (Wackernagel I p 51) The SV has lost consciousness of this fact, feels that a syllable is lacking, and inserts the harmless u
- vise visam aprkthāh (aprāg api) AV (both) The shorter form (with ending read as two syllables?) was probably the original
- yatah sürya udeti AV yatas codeti süryah SB. BrhU Kathal †4 9a äsün huve suyamān ütaye TS MS KS. āsūn ıva suyamān ahva ütaye
 - AV Here the longer form of AV may be original, at least it is better not only metrically but in sense
- §844. There are, however, a few cases in which the addition of a patch word spoils, or at least injures, the meter. In one of these the form without the patch word is probably historically secondary, and due to an attempt to improve the meter by omitting (instead of adding) a light word:

tasmar no (AV mā) devāh paradatteha (AV PG odhatteha, KS MS odhatta) sarve (MS visve) AV. TS KS MS SMB PG BDh Even the KS MS form, lacking tha, is not really good in meter §845. But in most cases of this sort the light word appears to have

been added secondarily, to the detriment of the meter

šatena pāšair varunābhi dhehi KS: šatena pāšair abhi dhehi varunainam The reading of Ppp (Barret, JAOS 37 298) is that of KS. and this is doubtless original

tam aham vunar ädade KS. PG · ımam tam vunar ädade 'yam (read 'ham, as Kirste suggests) HG

tasmā u rādhah krnuta prašastam (AV krnuhi suprašastam) RV AV The superfluous su is ignored by AV Anukramani and omitted in Ppp (Barret, JAOS 41 266)

§846. Once SV omits a pronoun from a good and simple pada of RV, thereby spoiling the meter, the change was possibly conditioned by the use of the hieratic case form sutasah (straining for archaic effect), which made the pada too long, altho the omission of ime leaves is too short tubhuam somāh sutā ime RV tubhyam sutāsah somāh SV

§847. Change of meter makes both forms passably metrical in the following

anumale 'nv idam manyasva AV: anumate 'nu (KapS †anu) manyasva na idam KS. Cf anumate 'nu manyasva (prose) GG KhG HG

apām napātam asvinā huve dhiyā (TS thayantam) AV. TS The mss of AV read asvinā (accented) and dhiyah. Neither text makes sense as presented in the mss, but both are metrically correct See Whitney's and Keith's notes

§848. In the next AV by a later resolution gets two syllables out of one of RV, and to save the meter omits the light word u:

agnır vidvan sa yazat sed u hota (AV Kaus sa id dhota) RV AV TS See §996 MS KS SB

· §849 In the remainder the variants with and without patch word are metrically equivalent We shall begin with those in which the form with patch word is probably secondary, they are, as we should expect, far the more numerous group

ımam (AV. *tam u) me agadam kıta (AV kıtdhı) RV AV * VS TS anu manyasva suyajā yajāma (MŠ yaje hı, most mss yajeha) TS MŠ tam manyeta (ViDh tam var manyet) pıtaram mātaram ca Samhitopani-

şadB VāDh VıDh asmān (AV sā nah) sīte payasābhyāvavrtsva AV VS TS MS KS SB

- upa yajñam asthita (MS astu no) vaisvadevī RVKh AV. ApŚ MŚ apasedhan (SV†°dham) duritā soma mrdaya (SV. no mrda) RV SV See VV I §194 In RV r in mrdaya is long, in SV. it was pronounced short, and the change with insertion of no is intended to improve the meter
- marutām pitas tad aham grnāmi (MS grne te) TS MS marutām pitar uta tad grnīmah KS
- tasya doham asīmahı (KS asīya, AS asīya te) VS MS KS TB SB TA AS SS In KS prose
- ivaşļā sudatro (TA no atra) vi dadhātu rāyah RV VS MS KS SB TA SS N
- sa nah pito madhumān ā višeha (Kauś viveša) KS Kauś sa no mayobhūh pitav (TS TB pito, MŠ pitur, SMB Jorgensen pitav) āvišasva (AŠ āvišeha, MŠ āviveša) TS TB AŠ MŠ SG SMB PG
- añgırobhır ā gahi yayñıyebhıh RV TS MS añgırobhır yayñıyaır āgahīha AV
- dadhad ratnām (RV once ratnā vi) dāsuse RV (thrice) SV VS TS MS KS TB dhattam ratnām dāsuse RV dadhad ratnā dāsuse vāryām RV VS
- tvışır apsu goşu yā puruşeşu AV tvışır asveşu puruşeşu goşu TB The Ppp agrees with TB (Barret, JAOS 30 204)
- anāgā devāh šakuno grheşu (AV grham nah) RV AV MG The Ppp according to Roth agrees with RV., and the AV text makes poor sense as Whitney observes
- abhūn mama (KS nu nah) sumatau vrsvavedāh TS KS PG.
- ahnā yad enah kriam astı pāpam (AS astı kımcıt, SS enas cakrmeha kımcıt) AS SS ApS MS ApMB
- edam barhır nı şīdata (AS SS şīda nah) RV VS KB AS SS Change of context in AS SS requires a singular verb, and the pāda is neatly patched with nah
- devebhyo havyam (MS MŚ MG havyā) vahatu (TB * AŚ ŚŚ ApŚ vaha nah, Kauś *vaha) prajānan RV AV VS TS MS KS ŚB TB * AŚ ŚŚ Vait ApŚ MŚ Kauś * MG In one form Kauś is unmetrical, lacking nah
- pra tad voced amriasya (VS amriam nu, TA MahānU voce amriam nu) udvān AV VS TA MahānU
- vīryebhir (MS vīrebhir, AV yau vīryair) vīratamā šavisthā (TB šaci°, Poona ed šavi°) AV VS MS ŞB SB TB AS SS
- punantu viśvā bhūtāni (MS bhūtā mā) AV VS MS KS Is the MS. reading a reminiscence of viśve devāh punīta mā, which is the RV. form of this pāda?

- Satam pavitrā vitatā hy (MS vitatāny) āsu MS ApŠ ApMB Undoubtedly MS is original, form assimilation to pavitrā in the others hvayāmi (AV. SV. TS MS. huve nu) šakram purvhūtam indram RV AV SV. MS VS TS KS MahānU
- apriye (AV *apriyah) prati muñcatām (Kauś†°tam, AV. *muñca tat) AV (bis) Kauś
- sarvān agnīnr (AV. śwān agnīn) apsusado huve vah (MS omits vah, AV havāmahe) AV. TS. MS TB See VV I p. 253
- §850. The much fewer cases in which the form with a light word seems to be the older are:
- rsīnām ca stutīr (SV. susļutīr) upa RV SV VS TS MS KS.
- agnım ındram (TB agnī indrā) vṛṭrahaṇā huve 'ham (TB. vām; MS 'hanam huvema) AV MS TB.
- yā antarılşyā (TB ApS. °kşa) uta pārthwāsah (TB ApS AG pārthwīr yāh) KS AG TB ApS. Since the adjectives are feminine (agreeing with āpah), the KS form is less regular (Wackernagel III §62), but it may nevertheless be the original
- yā akrntann avayan yā atanvala (AV. yāś ca tatnīre) AV SMB. PG ApMB HG: yā akrntan yā atanvan MG Discussed in VV I §§46. 218
- jarām gachāsi (PG gacha, AV. su gacha) parī dhatsva vāsah AV. PG ApMB HG Only the relative antiquity of AV favors greater originality of its reading; and perhaps this is not conclusive

CHAPTER XIX RIME WORDS

§851. A large majority of all the variant words treated in this volume are rime words, in so far as they are not different forms of identical words. But in addition to these, there are found not a few other variants which rime with each other and tend to be associated, at least partly on that account. It seems worth while to present some examples of such variants, the list includes, of course, only words which do not seem to be explicable by any of the phonetic changes treated above, nor yet by graphic confusion. Even so restricted, the list could no doubt be extended. We hope, however, that we have included at least all cases of the repeated occurrence of such rime words in variation. They are sufficiently numerous to illustrate the phenomenon as a whole. It is to be noted that the words are as a rule fairly close to one another in sense as well as sound; that is, they are mostly quasi-synonyms.

§852. We begin with the roots jinv and pinv, closely associated from early times, and semi-synonyms 'inspire' and 'make to prosper'. The ease with which they interchange is illustrated well by the first two formulas, which follow one another in the Samhitās, both verbs are found in all texts that have both pādas, but the two are exchanged in different texts.

mano me jinva (MS KS pinva, Vait mano jinva) VS TS MS KS Vait Followed by.

vācam me pinva (MS KS ŚŚ zinva) VS TS MS KS ŚŚ. tad indrāgnī zinvatam (MŚ † pinvatām) sūnrtāvat TB ApŚ MŚ

nnva (AS †pinvam, read pinva) gā nnvārvatah TB. ApS AS Cf pinvatam gā nnvatam arvato nah RV. KS

§853. Other verb forms are.

ūrjā pṛthivīm gachata (MS yachata) TS MS KS TB

paramam padam ava bhātı (VS SB. bhārı) bhūrı (TS bhūreh) RV. VS. TS MS KS SB N The comm on VS calmly says. avabhārı avabhātı, takārasthāne chāndaso rephah! BR derive from root bhr, as aor. pass 'wurde eingedruckt', which is at least possible

trikadruhebhih putati (AV pavate) RV AV KS TA. ApS Cf Hillebrandt, Ved Myth. I 500

pratilāmīti (AS °nīti, TS KSA TB pra sulāmīti) te pitā VS TS MS KSA ŠB TB AS ŠŠ Derived by the comms. from roots til and sul, both with obscene meanings, and both unknown otherwise.

- sam bāhubhyām dhamatı (AV bharatı, TS TA. namatı, KS namate, MS "bhyām adhamat) sam patatratı (KS yajatratı) RV AV VS TS MS KS TA MahānU ŠvetU sam-dham and sam-nam praetically synonyms here, 'weld together' Note also the noun forms patatra yajatru (graphic change)
- asadan (TS asanan) mātaram purah (TS punah) RV AV SV ArS VS MS KS SB Practically synonyms: 'has seated himself' 'has reached'.
- yābhyām svar ajanann (TB suvar ajayann) agra eva MS TB MŚ yābhyām ajayan svar agra eva AV 'By which they created (won) light in the beginning'
- sam grāvabhir nasate (SV vasate) vite adhvare RV SV Both 'umte with', SV lect. fac (sam-nas was obsolete)
- rasena sam asrksmahı (RV agasmahı, KS LŠ aganmahı, AV JB aprksmahı) RV. AV VS TS MS KS JB SB TB LS ApMB sam-srj and sam-prc practically synonyms Cf sam-prc and sam-sprs, \$375
- añgād-añgāt sambhavası (SMB. *samśravası) SB. BrhU KBU AG SMB * GG ApMB HG MG N Mahābh In SMB a synonym is introduced in one occurrence for the sake of variety 'thou flowest together' for 'thou arisest' The pāda is immediately repeated with the reading of the other texts. In both cases some ms. of SMB have the alternative reading
- pra ketunā bīhatā yāty (AV TA bhāty) agnīh RV AV SV TA 'Agnī goes (shines) forth with mighty beam' Perhaps graphic?
- śocasva (VS * rocasva) devavītamah (KS °vittamah) RV. RVKh VS * TS MS KS TA Synonyms
- tataś (RV ataś, KS tatra) cakṣāthām (RV °the, MS KS cakrāthe) adıtım dıtım ca RV VS TS MS KS ŚB Root cakṣ perfect of kṛ
- adhı skanda vīrayasva AV abhı kranda vīlayasva SG Quasi-synonyms AVPpp also reads kranda, which therefore may be original, the skanda seems more appropriate ('mount', of sexual approach)
- nā chetthā (v 1 bhetthā) mā vyathişihāh KBU
- [varṣmā rathasya nı jıhīṣate (SS jıhīlate) dıvah AV SS So RWh , but the mss of AV read jıhīdate, which should be kept]
 - §854. Riming participles occur in the following
- pratyag enam šapathā yantu tṛṣṭāh (AV sṛṣṭāh) RV AV Comm and one ms of AV tṛṣṭāh, for which sṛṣṭāh may be called a lect. fac: 'Let the curses go back upon him, the harsh ones', or 'those emitted (by him)'

- yā dabhrāh parısasruşīh SG: yā †ārdroghnīh pari tasthuşīh ApMB Pples of roots sru and sthā
- āyurdā deva (AV agne) jarasam vṛnānah (ApMB ApG HG gṛn°) AV. MS KS MŚ ApMB ApG HG āyurdā (VS ŚB āyuṣmān) agne havişo juṣānah (VS ŚB ŚG haviṣā vṛdhānah) VS TS. ŚB. TB TA ÁŚ ApŚ ŚG. The ApMB etc readings are an interesting blend of those which contain vṛnānah and juṣānah Perhaps gṛnānah was felt as meaning 'praising' rather than 'devouring', even this would be none too sensible in the context Oldenberg adopts vṛnānah for HG Still a different version ('thriving by the oblation') is adopted in VS etc, this is an easy lect fac in a passage relating to Agni
- ā sutrāvne (MS KS bhūyışthadāvne) sumatım āvrnānah AV MS KS oşışthadāvne sumatım grnānāh TS 'Choosing to myself (praising) his kindness'
- §855. Among riming nouns and adjectives, the pair dhāman. nāman stands out In the mystical religious language of the Veda they are easily interchangeable; the 'name' and the 'station' of anything both mean its mystic essence. In some cases the change from one to the other is due to the influence of adjoining words, as in
- yat te'nādhṛṣṭam nāma yajñıyam (KS nāmānādhṛṣyam, MS dhāmānādhṛṣyam) tena tvādadhe VS TS MS KS ŚB The change in MS. was suggested by ādadhe
- sedam priyena dhāmnā priyam sada tāsīda (VSK priyenu nāma priye sadas sīda) VS VSK SB Also:
- priyena dhāmnā (TS TB ApŚ nāmnā, VSK nāma) priyam sada āsīda (VSK TS TB. ApŚ * priye sadasī sīda) VS VSK. TS ŚB TB KŚ ApŚ In this and the prec (which are variants of each other) only the VS texts have dhāman, and it is reasonable to suppose that it was substituted there for nāman because it is a synonym of sadas
- vidmā te nāma (AV vidma te dhāma, Ppp gandharvo nāma) paramam guhā yat RV AV VS TS MS KS ŠB ApMB. gandharvo dhāma paramam guhā yat (VS vibhrtam guhā sat) AV. VS gandharvo nāma nihitam guhāsu TA MahānU. Here two different pādas have become confused, one began originally with vidmā te nāma, the other with gandharvo dhāma The AVPpp reading (not in Conc) occurs in the verse where AV has vidma te dhāma
- puruşlulasya dhāmabhıh (MS nã°) RV AV MS Vait
 - §856. Twice the RV phrase pratiena manmanā 'by ancient hymn'

- is changed in SV to pratinena janmanā 'by ancient generation (birth) much to the detriment of the sense In one case TB follows SV aham pratiena manmanā (SV. jan°) RV. SV. AV.
- agnih pratnena manmanā (SV TB jan°) RV SV MS KS AB T. AŠ MŠ
 - §857. Other nouns and adjectives:
- aktam (MS MŚ aptubhĩ, KS *artham) rehānā vyantu (TS TB viyantu vayah TS MS KS * TB MŚ. GG. KhG · vyantu vayo 'lta: rehānāḥ VS A very obscure passage, the isolated artham ma possibly be due to graphic confusion
- sarīram me vicarşanam (RVKh vicakşanam) RVKh TA TU. pratīkai me vicakşanam PG 'My body (face) be active (glorious)' Schei telowitz on RVKh reads vicakşana, but it seems that 'nam must' the true reading
- paktā (KSA panthā) sasyam TS KSA The latter is called 'ludicrous by Keith. On paktā see Wackernagel III p. 204, he takes it as masculine form used as neuter, rendering 'die Saat pflegt reif zi werden'; of Oertel, Syntax of Cases I p 171
- kuhūm aham (AV Vait kuhūm devīm) suvītam (AV MS KS sukītam TS subhagām) vidmanāpasam AV TS MS. KS AŠ SŠ N Quasi synonyms
- dyumnā suksatra manhaya RV dyumnam sudatra manhaya SV
- dhanamjayam dharunam dhārayışnu RVKh bhūmıdrnham acyutan pārayışnu AV.. bhūmıdrnho 'cyutas' cyāvayışnuh AV The ev dently secondary cyāv° 18 suggested by 'cyutas: 'unshaken (but shaking (others)'
- aslono 'piśācadhītah ApMB. anandho 'ślono 'piśācadhīrah HG The latter is a strange corruption, the original means 'not sucked by demons'
- adroghavācam matibhih śavistham (RV * °bhir yavi°) RV * AV See RVRep 275 f
- abhı dyumnam (RV VS sumnam) devabhaktam yavıştha (MS KS devahıtam yavışthya) RV VS TS MS KS ApMB Quasisynonyms
- nagnahur dhīras (KS vīras) tasaram na vema VS MS KS TB. Synonyms
- pāh no agna enase (SG edhase) svāhā TA MahānU SG. edhase is certainly right 'protect us unto prosperity' TA comm quotes the text as enaso, tho both editions print enase. The corruption is due to recollection of other phrases in which enasah or the like is

- associated with the root pā in the sense of 'protect from evil' or 'sın'
- nunar brahmāno (AV brahmā) vasunītha (AV. onītir, KS odhītam and tonitha [so 38 12b], MS odhite) yannath (AV MS KS,* agne) AV. VS TS MS KS SB The form with n is apparently original: in MS KS it is contaminated from such forms as vasudhā, vasudhiti kuvîn no asya sumatır navîyasî (SV bhavîyasî) RV SV. 'Hıs verv fresh
- (abundant) favor'.
- sthirā cin namavisnavah RV drdhā cid yamayisnavah SV Practically synonyms, 'bending'. 'subduing'
- aūdhi kham vartavā panim (SV pavim) RV SV Benfey and Grassmann would read panm in RV. The emendation is exceptionally tempting, but one must be cautious about it; cf Oldenberg's judicious remarks (Noten ad loc) It is easy to see how pann could be substituted for an original panim under the influence of kham, a reason for the reverse change in the tradition is not so apparent
- tās tvā višantu manasā šīvena (TB. mahasā svena) AV. TB. The English words 'mind' and 'might' substantially reproduce the rime, and are derived from the same roots Cf next.
- ul salvanām māmakānām manānsı (TS mahānsı) RV SV VS TS. Cf prec
- dvişadbhyah prati muñcāmi pāśam (HG. pāpam) SMB, ApMB, HG The two words are near-synonyms, pāšam is clearly original
- upa śresthā na āśisah (MS āśirah) AV TS MS KS
- panasyuvah samvasanesv (SV °varanesv) akramuh RV SV. Quasisynonyms, 'at the dwelling-places (enclosures, sanctuaries?)'.
- asya (AS mama) snusā švašurasya prašistim (AS pravistau) TB AS Complete change of meaning as well as syntax
- svāhā tvā sūryasya (MS vātāya sūr°) vīsivanaye (MS.° sanaye) MS TA ADŚ

CHAPTER XX. GRAPHIC VARIANTS

§858. There are not a few variants in which it seems at least possible that graphic confusion between letters written similarly may have been a contributing cause Some of them, such as variations between b and v, th and dh, t and th, p and v, have been treated above, as having also phonetic aspects Those which follow in this chapter would appear to be purely graphic We have no doubt that the list could be considerably extended, especially with the help of experts in Indian pileography, a title to which we lay no claim We have merely noted down such variations as have struck our attention between certain letters which resemble one another in well-known modern Indian alphabets Even so limited, the collection seems to us important enough to suggest that graphic confusion must have played a considerable part in the variants of the Vedic tradition. It will be seen that different manuscripts and even different editions of the same work not infrequently vary regarding words of this group, which confirms that conclusion, it may be fairly assumed that in many other instances, where no manuscript variants are recorded, we nevertheless may be dealing with phenomena of the same sort. At the same time we would emphasize the fact that we do not mean to assert that all the variations here collected are due solely or even chiefly to graphic confusion course, there are many cases where neither phonetic nor graphic matters We mean only that this is one feature of the Vedic can be concerned variants which cannot be ignored

§859 The largest number of variants here collected concerns the letters n and r. Fairly numerous, also, are shifts between p and y, c and v, gh and dy, d and v, s and m, t and n. The rest are more sporadic. We shall present the cases in the approximate order of their frequency.

n and r

\$860. The variation between n and r is fairly common, and may certainly be due to graphic confusion. The signs for these two letters when not combined with other consonants are not very dissimilar in the principal Indian alphabets. They are still more similar in Devanagari, for instance, when they follow other consonants in combined characters. When in such consonant combinations they precede other consonants,

the Devanagari, to be sure, clearly distinguishes between n and r, so that a misreading would be unthinkable. But this is by no means true of all Indian alphabets. Notably in Sarada n and r before other consonants are written almost alike, and confusion is very easy and frequent. §861. We present first cases of n and r not combined with other

consonants

- endhāna enam jarate (MS KS janate, but MS pp jarate, KS v. 1 jarate) svādhāh RV. VS TS MS KS ŠB ApMB N One ms of KS. reads jarate, and the pp of MS jarate, this is clearly the proper reading
- mritike hana (MahānU. hara) me pāpam TA MahānU Here the change is facilitated by the nearly equivalent meanings of the roots han and hr in such a context ('destroy' and 'take away')
- asadon (TS. asanan) mātaram purah (TS punah) RV AV SV ArS VS TS MS. KS. SB.
- avımuktacakra (v. 1°rā) āsīran PG.: nvrttacakrā āsīnāh HG ApMB tarī mandrāsu prayakşu AV stanī mandras suprayakşuh KS Others, §830.
- tanur varşişihā gahaneşihā MS: mahāntain gahvareşihām SV.
- nerriho (MS °to) yas ca nesianah (AV. °rah) AV MS TA
- nigalgalīti dhārakā VS. SB.: nı jalgulītı (KS † jalgalūtı, mss , em °līti) dhānıkā TS KSA
- deva purascara saghyāsam (MS. devapuras carasu rdhyāsam, p p deva, punar iti punah, carase, etc.) tvā MS TA. ApŠ MŚ The text of MS is corrupt in both readings.
- mā na āyuḥ param avaram mānadonash MS. mā nah param adharam (MS. param adhanam) mā rajo 'nash (MS nash) TA MS Two cases, adhanam: adharam, and mā rajo 'mānado- (corrupt)
- ruvad dhol.şā (TB nīvadbhyo 'kṣā) paprathānebhir evaih RV MS. AB KB TB. But r may be regarded as a phonetic substitute for ru; §684.
- §862. Next, n and r before other consonants, note one case in RV itself:
- višvāny anyo (RV.*KS aryo) bhuvanā jajāna RV (both) MS KS TB In different contexts
- balitardāya (KSA. °vandāya) svāhā KSA TB Ap\$ Apparently balitardāya is intended
- ıluıardāya (KSA alıvandāya) svāhā KSA TB ApŠ Follows the prec gaurīr (TB. TA gaurī, AV gaur in) mimāya salılānı takṣatī RV AV. TB AA. TA. N

widyur (ApMB vidyun) me asya devāh RV AV KS ApMB Set Winternitz, Introduction to ApMB, xxiv vidyun is doubtless corruption due to unintelligent thought of vidyut, it is read by all mss and confirmed by the comm, who says that t for visarga is chāndasa! vidyur is 3d plural verb form

šīle vāle punann wa (AŠ LŠ, mss of Vait., most mss of ŠŠ, and v 1 o KSA. punarnwa) VS TS MS. KSA. ŠB TB. AŠ ŠŠ Vait LŠ The persistence in the mss of the impossible punarnwa is striking ni nivarlana varlayendra nardabuda (KS nandabala) TS KS ApMB See §273

adyā tvā vanvan (KS vardhan) sureknāh RV. KS TB ukhām sravantīm agadām aganma (MŚ akarma) KŚ MŚ

anārbhava mrda KS. Ap\$ The ms of KS reads anānbhava, em v Schroeder, see p w 5. Nachtrage Cf anabho mrda dhurte (read dhūrta with some mss of MS and all of MS) MS MS See §749 §863. As to n and r after other consonants, most of the variants contain forms of the stems agni and agra. A special historic, and as it were romantic, interest attaches to this variation on account of the famous falsification of RV, 10 18 7d, a robantu janayo yonim agre, into which by substituting agnet for agre there was introduced a justification for widow-burning. 'Let the women mount upon the (proper) place in the beginning' was made to mean 'Let the women mount into the seat of In the Vedic occurrences of this pada, which is found also in AV and TA, there is no authority for this change. There are, however, a number of other Vedic passages where a like change occurs, always, with one exception, between the locative agre and the vocative agre It is noteworthy that in most instances the stem agra is evidently original, and the stem agni secondary The explanation is that the context is regularly one that concerns the god Agni, whose name is secondarily introduced by a natural confusion

§864. The list is as follows, the first is the only variant which does not concern the forms agre and agne.

dhvāntam vātāgram anusamcarantam (PB abhisam^a) TS PB TB PG ApMB: dhvāntā vātā agnim (mss of both vātāgnim) abhi ye samcaranti MS MG Clearly agnim is secondary.

agre wksu pradidayat RV. agne wksu pratidayat TB (Poons ed agre without v l., but comm he agne)

tubhyam agre (MG agne) pary avahan RV AV PG ApMB MG agre (MS *KS.*MŚ agne) bihann uşasām ürdhvo asthāt RV VS TS -MS *KS *ŚB ApŚ, and Pratikas AŚ ŚŚ KŚ MŚ Rvidh BrhD.

- tenemam agra (TB agna) tha varcasā †samaāgdhi KS TB. Here, by exception, agna (=agne) may be the original reading, one accented ms of KS. leaves agra unaccented, suggesting that a vocative (which could only be agna) was intended.
- tavāham nāma bibharāny agne (AS agre) TS AS: tavāham agne bibhārāni nāma MS. Here it seems even more probable that agne is the older reading
- [agre (TB. agne, but Poona ed text and comm agre) yanasya socatah (KS TB. cetatah) RV KS TB.]
- [agne (AV agre) samidham āhārṣam AV Kauś agre is only an emendation in the Berlin ed, which is rightly withdrawn by Whitney in his Translation]
- §865. Aside from variants of these two stems, we have noted only the following
- akṣāṇām vagnum (MS tvagmum) upajīghnamānah (MS avajīghram āpah) MS TB TA The MS is certainly wrong TB. comm upahatam kurvan
- gırā ca (AV mrājah) śruştih sabharā asan naḥ RV. AV. VS TS MS KS SB Whitney on AV adopts śnuştih with most mss; Ppp suniştas See §57
- ürdhvacıtah (MS KS °śritah) śrayadhvam (VS † śna°) VS TS. MS KS SB. TA Doubtless corruption, if not misprint, see §195

c and v

- §866. Under this heading we find first a few cases of shift between the roots *vi-crt* and *vi-vrt*, in all of which the sense is more favorable to *vi-crt*, 'unloose', also a few, the majority being of very doubtful authenticity, between the synonymous bases śac and śav. The others are sporadic
- agnum hotāram antarā vivītiāh AŚ hotāram agnum antarā vicītiāh ApŚ. 'Bonds' are referred to, which are 'loosened' by this stanza, so that vicītāh is very natural, but it may for that reason be regarded as a secondary lect fac. It is not necessary to the sense, as the following pāda declares that the bonds shall 'bind the fool, but the wise shall go past them'.
- rtasya tantum vitatam vivrtya (VS vicrtya, AV drše kam) AV. VS TA.

 MahānU The true reading is probably vicrtya So Poona ed of
 TB text and comm, tho with v. l. vivrtya; comm gloss gurušāstramukhān nišcitya, which looks as if he had read vivrtya and taken it
 from vi-vr 'elucidate', a meaning which can hardly be right in any

case MahānU. reads vvvtya without recorded variant, comm. gloss vvtī sandīpena sandīpya, which is obscure to us

[vi pāšam madhyamam crta (TB and MŠ v 1 vrta) RV KS TB MŠ So Conc, seemingly erroneously, MŠ has crta without recorded variant, and Poona ed of TB. likewise crta text and comm with no v 1]

śabalı prajānām śacışthā vratam (ApŚ śavışthā vrajam) anugeşam svāhā PB ApŚ

[vīryebhir (MS vīrebhir, AV. yau vīryair) vīratamā šavisthā (TB šaci*) AV VS. MS ŞB ŠB TB AS ŠS But Poona ed of TB šavisthā in text and comm without v 1]

[devānām devatamā śamṣthā (TB śaci*) MS TB Again Poona ed of TB śawi* without v 1]

vicili (or viviți) svāhā MahānU vivişiyai svāhā TA TAA There is also a v. l civiți in MahānU The word is meaningless Comm vicili, which he does not explain; he quotes also a v I vidhijňa Poona ed of both TA. and TAA vivitiyai, explained by comm as for vivişiyai by Vedic license

vakratundāya (TAA cakra°) dhīmahı TA TAA † MahānU

sam arvanto raghudruvah (VSK °drucah) RV. SV. VS VSK MS Meaningless corruption in VSK

ghriapratīkam va (TB ca) riasya dhūrşadam (TB dhūruş°, Poona ed dhūrş°) RV. TB ApS The sandhı shows that TB is secondary and poor

yaira cābhimṛśāması (HG vābhi) ApMB HG

p and y

§867. A miscellaneous but fairly numerous group

ındrāpāsya (two mss ındrāyāsya) phaligam ApMB ındrāyayāsya (corrupt, Kırste suggests ındra āyāsya) šepham alīkam HG

hrıyaı salyakah (VS salpakah) VS MS The p is a false reading, VS comm svāvit

brhaspataye sitputah (KSA † simyutah) TS KSA An otherwise unknown word, said to be a kind of cat

prasthāyendrāgnibhyām somam vocatopo (KB vocato yo) asmān KB AS SS Read in KB. as the others (Keith).

sam bāhubhyām dhamatı (etc., §853) sam patatraıh (KS. yajatraıh) RV AV VS TS MS KS TA MahānU ŠvetU

prapunvanta upa spršata prapunvadbhya svāhā ApMB prayunvanta upaspršata prayunvadbhyah svāhā HG Both anomalous forms and scarcely interpretable

- susasyāh (VSK °pāh) krşīs krdhi VS VSK ŚB KŚ· krşyai tvā susasyāyai (KS †sumanasyāyai, bis) TS KS ApŚ. With the VSK reading cf śaspa
- pūlyāny (ApMB. kulpāny) āvapantikā AV ApMB The mss of both texts vary between lp and ly
- anadvāns tapyate vahan (MŚ talpate vahān) ApŚ MŚ If MŚ is correct (it occurs in an unedited part of the text), it is a mere corruption tvam hi rādhaspata (text 'yata, wrongly) eka īśise ŚŚ.
- ubhe ca no (etc)...anhasah (°sas) pātām (TB Conc syātām, Poona ed anhasah spātām, AŠ text †anhasa syātām) MS SB TB AŠ SŠ The true reading can only be anhasah (or °sas) pātām
- [tanūpā (TB °yā, Poona ed °pā) bhışajā sute VS MS KS TB]
- [vahishebhir viharan yası (TB Conc pāhi, comm and Poona ed. text yası) tantum RV TB KS AS ApS]
- [tvaştā turīpo (TB turīyo, Poona ed text and comm. °po) adbhutah VS. MS KS TB]
- [āpataye (GB āya°, Gaastra āpa°) tvā gṛhnāmi VSK TS MS GB Vait ApŚ MŚ]
- [varuneti sapāmahe (MS†°hai, LS †sayāmahe) VS TS MS KS SB TB AS SS LS Probably a double misprint in LS]
- [viśvutohasta uta viśvataspāt (TA °tah syāt, but Poona ed correctly °taspāt) TS MS KS TA]

gh and dy

§868. The variants are again miscellaneous, tho fairly frequent mā (AG MG ā) tvā prāpann aghāyavah (MG adyāyavah) AG. ŚG ApMB MG The correct reading is mã...aghāyavah 'Let not the malicious ones reach thee' It is strange that apparently all miss of AG MG read ā at the beginning, preceded by anusvāra at the end of the preceding pāda (Stenzler assumes mā) The further corruption in MG seems an attempt to patch up a bad job, it implies adya-āyavah 'may lives today reach thee'

magham (MS, but not KS, madyam) indrāya jabhrire VS MS KS TB 'Brought a gift (liquor) unto Indra' Indra's well-known bibulous habits are responsible for the secondary change in MS, involving the misreading of gh as dy Cf next

sa bibheda balam (VS and Poona ed TB. valam) magham (MS madyam)
VS MS KS TB Cf prec

śaiāpāṣihādya viṣā (read with Poona ed of both sihā gha viṣā) parī no vīnaktu TB TA . śarā vāṣiād dhaviṣā vārnah MS (Poona ed of

- TB. records v. l. 'dya, and comm v. l. adya.) The MS is hopelessly corrupt but has another graphic corruption, ddh for gh, ci. §875; see also §838.
- pālam mā dyārāprihirī adyāhnah (Kauś. aghān nah, read adyāhnah) TS. ApŠ. Kauś. See §S40
- ¡læalāgho (TB. keralādyo, but Poona ed. text and comm. °lāgho) bharali keralādā RV. TB. N. Gloss in TB. comm.: pāpam eva sampādayali na tu kimeid api punyam.]
- [sa ghā (TB. sadyā, read with Poons ed. text and comm sa ghā) no dwah sarītā sahāvā (TB. savāya) RV. MS. SB. TB. AS ŠŠ]
- [yad vā chā (TA. vādya, but Poons ed. vā ghā, and comm. vā gha) saiyam uia yan na rīdma RV. TS MS. KS TA. There is a v. l. vādya m TA. Poons ed., but gloss in comm (yad cra kimad) proves that he read vā ghā.]

\vec{a} and \vec{v}

- \$869. Under this head we find principally a group of variants between the stems dis and ris; both stems always appear in the plural number, of Wackernagel H. 1 p 48, foot These are of course rime words. In every case except the first mentioned the original form seems to contain ris. There are, in addition, a couple of other miscellaneous variants between d and r.
- devānārā palnīr (VS. palnyo, MS palnayo) dišaḥ (MS. KSA. †rišaḥ) VS. TS. MS. KSA. The 'wives of the gods' must apparently be the 'directions', not 'tribes'. This is the only case of original dis, and even it is perhaps not certain.
- ye vã nûnam surjanāsu rikşu (AV. dikşu) RV. AV. Av. 1 rikşu occurs in AV., and so Ppp. reads
- sasond risah (TB. disah) saritur dairyasya RV. TB. The change in TB was perhaps due to assimilation in meaning to the parallel bhuvanāni in the next pāda.
- risāri (TB. dišāri) patir abharad rājinīvān MS. TB. Indra is referred to, and the original is doubtless risām.
- rišo (SV. dišo) rišvā anu prabhuh (TB. prabhu) RV. SV. MS TB Agni is meant.
- hilsu kratuń varuno (MS. varunam) viliso (RV. apsv., MS. diksr) agnim RV. VS.† TS.† MS. KS. ŚB.†
- ana durhārddišo jahi Kaus. (read durhārdrišo, Cone)
- ul parjanyasya chāmabhih (TS. TA. ApMB. susmena, MS dhāmaā, KS. rrsiyā, PG. drsiyā) VSK. TS. MS. KS. TA. AS. PG ApMB

- dhātā vidhātā (MS dhartā vidhartā) paramota samdrk (KS paramo na samvrk) RV VS TS KS MS N. samvrk perhaps 'seizer', certainly inferior
- avasphūrjan vidyud (TS didyud) varşan...TS MS KS
- bhūmır iti tvābhıpramanvate janāh AV. yām tvā jano bhūmır iti pramandate VS MS KS SB The latter secondary and poor, Mahīdhara, stauti, which the verb can hardly mean

s and m

- §870. Here the variants are quite miscellaneous:
- kṛṣyai tvā susasyāyai (KS †sumanasyāyai, bis) TS KS. ApŚ Others, see §867. The original is clearly susasyāyai
- agne yān devān ayād ..tām sasanuṣīm (KS ms tān samanoṣīnr, ed em samanaɪṣīr) hotrām ..MS KS TB The corrupt ms reading of KS seems to point towards the reading of MS TB., rather than towards Von Schroeder's emendation, which should probably be replaced by the other version
- prlsasya (ArS prak°) vrsno aruşasya nữ sahah (ArS mahah) RV ArS AB KB AS SS Svidh Synonyms
- athā jīvah (KS adhā viṣitah, VS SB athaitam, AV adomadam) pitum (AV annam) addhi prasūtah (TS MS KS pramuktah) AV VS TS MS KS SB
- graha viśvajanīna niyantar viprāyāma te (MS. p. p. viprāya, mate; KS nyantar vipra ā †satī) MS KS
- yaśasendrābrhaspatī (ArS yaśo mendrā°) ArS PG MG.
- mā brāhmanasya (3c sā br°) rājanya AV. 5 18 1c, 3c In the Berlin ed. mā is misprinted for sā in 3c, hence this is not recorded in Conc But it is a deliberate variant with change of meaning, not a graphic error
- mahas te sato mahimā panasyate (SV panistama) RV AV. SV. VS. mahāns te mahato mahimā AV. The related words in the context have, of course, helped in the secondary change to mahato.
- vahāsı mā (KS †vahānsı sā) sukrtām yatra lokāh (KS. lokah) KS TB Certainly KS. is secondary and inferior, but sā may refer to the juhū
- tvaştā devaih sahamāna indrah MG.: tvaştar devebhis sahasāma indra ApMB.
- nīlāgalasālā AV nīlagalamālah sivah pasya NīlarU See §512 Some copyist tried to correct the reading in NîlarU., thinking of nīla-gala and mālā

t and n

§871. The variants we have noted are less numerous than might hav been expected from the frequency of the sounds and the similarity of the forms of the letters Our list may be incomplete

sa tvam (SS. ApS sanvan) sanım suvımuca vımuñca KS SS ApS See §830

tan mā jinva (KS mārjitvā) TS MS KS See §§354, 829

dhātā vidhātā (MS dhartā vidhartā) paramota samdīk (KS, paramo na samvīk) RV VS TS MS KS N See §835

yad ejatı jagatı yac ca ceşlatı nämno (MahänU nänyo, v 1 mänyo) bhägo yan (TAA Poona ed 'yam) nämne (MahänU yatnän me, v 1 yan nämne) svähä TAA MahänU.

upa stuhi (Poona ed snuhi) tam nṛmnām (Poona ed nṛmanām) athadrām TA (Other forms, see §110.) The mss of the comm vary between stuhi and snuhi, gloss bhūmau prasrāvaya, pointing to snuhi.

yām apītā upatīsthanta āpah LŠ. yām āpīnām upasīdanty āpah AV prapīnam (MŠ v l °tam, TS ApŠ prapyātam) agne sarīrasya (MŠ salītasya) madhye VS TS KS ApŠ MŠ

ghrtam duhānā višvatah prapītāh (TB ApMB prapīnāh, AVPpp pravīnāh) RV AV VS TB ApMB

āvitte dyāvāpṛthivī ṛtāvṛdhau MS KS.: āvinne dyāvāpṛthivī dhṛtavrate TS TB

āvillau (TS āvinnau) mitrāvarunau dhṛtavratau (TS °nāv ṛtāvṛdhau)
VS TS MS KS SB Others with āvilla âvinna, see Conc 188
grāmam sajānayo †gachanti ApMB. grāmān sajātayo yanti HG
jāmim itvā mā vivitsi lokān TA: jāmim ṛtvā māva paisi lokāt AV
vīrān mā no rudra bhāmito (°no)..., mā no vīrān rudra bhāmino...,
see §209

savitā bhrtyām (KS ms † manyām) TS KS See §242

s and p

§872. The variants are few:

atho (LS ApS nir mā) yamasya padbītāt (VS °vītāt, LS. †şadvintāt) RV AV VS LS ApS. See §217

vājinam šepena VS · šeso vājinena MS But MS p.p šepah, read certainly šepo

ye tālryur (TB tālrpur) devatrā jehamānāh RV. AV. MS TB. AS SS. Kaus 'Thirsted'. 'delighted'

ā and prā

§873. In Devanāgarī, at least, these letters are easily confused It is interesting that we find one variant here within the RV. itself:

āvo (and prāvo) yudhyantam vṛṣabham daśadyum RV. (both)

āsmā asmvann āsāh AV: prāsmā āsā asmvan TA

āvat tam (TA Conc prāvartam, comm āvartam, Poona ed. text and comm āvar tam; so also KS ms) ındrah sacyā dhamantam RV. AV. SV KS TA

s and p, pt, pr, bh, t

§874. The remaining graphic variants are more sporadic and we shall group them in our arrangement. In this paragraph are included various other letters exchanging with s (on s and m see §870).

susīmam somasatsaru AV · suševam somapitsaru (TS sumatītsaru) VS MS KS ŚB VāDh See $\S180$ s and p(t)

rasena sam asrkşmahı (RV. agasmahı, KS LS aganmahı, AV JB aprkşmahı) RV. AV VS TS MS KS JB. SB. TB. LS ApMB. s and p

[āptam manah TS MS KS TB MS ApS. So read in TB, for which Bibl Ind ed has āsam]

sacyutım (AS. pracyutım) jaghanacyutım MS TB. AS Preceded by a pāda ending in sacyutım (MS hastacyutım) Perhaps the AS variant (s pr) is not so much graphic as deliberately stylistic (for the sake of variety)

anugrāsas (PB anugrābhas) ca vṛṭrahan RV AV. PB. The original is a nom pl of an-ugra PB misunderstands and rationalizes it, with graphic change of s to bh.

yad adya dugdham pṛthwīm asṛpia (TB ApS asakta, MS. abhakta) AB. TB. AS. ApS MS Agam bh is secondary to s

agne svam (TS TB. svām, SB. tvam) yonım ä sīda sādhyā (VS SB sādhuyā) VS TS·MS KS. SB TB sv: tv, the latter secondary.

gh and dh and other similar letters

§875. The only common graphic interchange of gh, that with dy, has been treated in §868. The shift between dh and gh has phonetic aspects, see §147 The rest are sporadic

grhānāngāny apve (SV. aghc) parehi RV. AV SV VS N. The SV. is certainly corrupt, see Benfey's Nachtrage to SV text, p 258 Benfey curiously retains aghe in his Glossary, but in his Translation substitutes the proper name $Apv\bar{a}$ $gh \cdot pv$.

agdhād eko 'hutād ekah . . TS adhvād eko 'ddhād eko hutād ekah M\$ gdh dhv or ddh.

ıma udvāsīkārına ıme $% \left(1\right) =0$. TB. ApŠ , ımā uddhāsıcārına ıme $% \left(1\right) =0$ MŠ ddh dv

ruvad dhokşā (TB nrvadbhyo 'kṣā) papratnānebhir evaih RV MS AB KB TB The TR is secondary, ddh dbhy

v and j, s, tr, th

§876. Compare §§866, 869 for v and c, d

pra vislīminam āvisuh AV VS ŠŠ pra samhrstinam ājisuh LŠ The whole passage is obscure, LŠ doubtless secondary, with j for v usrāv (VSK usrā) etam dhūrsāhau (VSK, MŠ dhūrvāhau). VS VSK

TS SB MS. Others, \$122 s v

[vairājī (KSA†°je) puruṣī (so also KSA†, Conc wrongly puruvī) TS KSA]

[pra yah satrācā (TB sa vācā, but comm and Poona ed text satrācā) manasā yajāte (TB °tai, Poona ed text and comm °te) RV TB] [šam te pruṣvāva šīyatām AV sam u pṛṣthāva (read pṛṣvāva with Poona ed text and comm., tho v 1 pṛṣthāva) šīyatām TA]

y and s, th

§877. For y and p see §867, for dy and gh, §868

rṣvāh satīh kavaṣah (KSA kavayah) šumbhamānāh VS TS MS KSA See Keith's note on TS While the meaning of kavaṣah is quite uncertain, kavayah (found also in some TS mss.) is probably only a graphic lect fac

tad asya priyam abhi pātho asyām (TB asthām, Poona ed asyām) RV MS AB TB AS See §287

apāmītyam (AS apām ittham) īva sambhara MS KS AS The AS is an absurd graphic blunder

samıddho agnır vrşanāratır (AV °nā rathī, ŚŚ °nā rayır) dıvah AV AB AŚ ŚŚ Here the reverse error, y for th, has occurred in ŚŚ see §93

Miscellaneous

§878. Other miscellaneous variants which may be graphic in character

āptye (AV *aprıye, *dvışate) san nayāması RV AV * The AV comm reads āptye for aprıye But the variant dvışate suggests that aprıye must have been known in very early times, and indeed Ppp reads

- apriye (Barret, JAOS 30 220) The RV. says 'We collect and heap (evils) upon (the scapegoat, Trita) Āptya'. The AV charmmonger knows little and cares less about this old mythological character, with characteristic practicality he heaps evils on 'the enemy' Without this intermediate step, in which the graphic resemblance to pty to pr may have shared, the further change to dvisate would be unintelligible.
- tāsām wisisnānām (KS visisnyānām) MS. KS: tesām visipriyānām (VS ŠB °nām vo 'ham) VS TS ŠB \$n(y): pr. Both words are obscure, Keith renders 'without handles' and conjectures that MS. KS meant the same.
- pratiŝrutkāyā artanam (TB. τ tulam) VS TB $n\cdot l$ Possibly phonetic, cf §273
- khanyābhyah (KSA khalyā°) svāhā TS KSA Vor Schroeder suggests reading with TS. $n \cdot l$, cf. preceding
- anarsarātim (SV alarşırātim) vasudām upa stuhi RV. SV. AV. N. See §292 $n \cdot l$.
- śaśvat parıkupıtena (HG °pılena) ApMB HG $t\cdot l$. Oldenberg abandons the HG reading
- abhi yo na irasyati (AV. no durasyati) RV AV. The AV. reading (found also in Ppp as durasyatu, Barret, JAOS 26 210) is nearly a synonym for that of RV, which is antiquated and limited to RV. du i
- acışyāma (p.p. amı, for abhı, syāma) vijane višva ūtī MS: abhı şyāma vijane sarvavīrāh RV. KS. c: bh (note p.p. of MS)

CHAPTER XXI SANDHI

§879. In the great mass of variants concerning phonetic relations of various individual sounds, already treated, not a few really relate to sandhi. This has been pointed out in individual instances as we have come to them. They are, however, mostly so sporadic that they can hardly be said to throw much light on the rules of sandhi as applied in the texts in general. As instances we may refer to §§142 and 145 (gutturals and dentals), 148 (gutturals and labials), 308 f (nasal as Hiatustilger'), 338 ff and 359 ff. (y and v as 'Hiatustilger'), 709 and 731 (clision of final a before initial e and o), and various parts of Chapter X, on internal consonant assimilation

§880. We shall now present, as an appendix, a collection of variants showing different treatments of vowels or consonants in sandhi, which are sufficiently numerous in each rubric to make worth while an investigation of their bearings on the rules of sandhi. We believe that the results of this investigation will be found very fruitful, not a few new principles have come out of the study

§881. Regarding the interpretation of these materials, a general word of caution will not be out of place Changes in external sandhi In actual speech they are matters of great delicacy and finesse probably always varied to some extent, in different communities, in different speakers, perhaps even in the same speaker at different times On a number of points the Vedic grammatical authorities, the Pratiśākhyas, ieflect this variation by their apparent confusion of statement The manuscripts on which our editions are based are in general at least Modern editors sometimes increase the confusion equally confused And if they are conscientious and desire to bring order into the chaos, they are often (quite naturally and inevitably) at a loss how to proceed Shall they treat each occurrence of a given sandhi-combination as a separate problem without reference to similar cases, and print what the best manuscript evidence seems to suggest for each individual word? Shall they, on the other hand, try to determine the usual procedure of their text, by considering all analogous cases together, and then standardize by printing them all alike? To what extent shall they be influenced by the usual procedure of other Vedic texts, of the same or

different schools? These are some of the problems which confront every conscientious Vedic editor. Different scholars have chosen different solutions; and in some cases a rather careful study of their critical notes is necessary to determine the actual usage of the texts.

§882. For these reasons the variants gathered from our actual printed texts in certain of the sections on sandhi are of doubtful value. At times they tell us less about Vedic usage than about the ideas of some modern editor. We refer particularly to such matters as the treatment of final s before sibilants, §§969 ff. But in spite of such considerations, for which we have tried to make all due allowance, there is no doubt of the value of most of the sections which follow. And they frequently add a good deal to our knowledge of the usages of various Vedic schools. This is notably the case, for instance, with the 'abhinihita' sandhi (initial a after final e and o).

§883. The following matters of sandhi will be taken up, in the order indicated First, final au and o before initial vowels (except, in the case of o, initial a) Next, the 'abhinihita' sandhi, final e and o before initial a. This is one of the most interesting sections. The variants seem to us to indicate clearly that an attempt was made, at some time or other, to standardize the writing of a after e and o in accordance with the pronunciation in metrical passages; for details see the section itself. The only other case of vocalic sandhi is that of final a vowels followed by initial vocalic r, here new and interesting results regarding the usage of various Vedic schools appear

§884. Coming to consonantal sandhi, we take up first the treatment of final n, before vowels, and then before consonants Then the change of dental to lingual n, in which again the various schools are shown to have individual rules or tendencies Next the cases of final s before initial t, lingualized after non-a vowels in most texts, but regularly retained in the Taittiriya school (often also in KS) Regarding final s before initial k and p, the Taittiriya school is again exceptional in that it usually has h, as in classical Sanskrit, especially after a vowels. After afew cases of final r before k and p, we come to final s before an initial sibilant alone, and then before initial sibilant plus consonant; here, as stated above, we are more than usually doubtful of the value of the No clear school tendencies appear in the matter of initial s after final non-a vowels (sometimes kept, sometimes changes to s). We conclude with a section on secondary crasis or double vocalic sandhi, and its converse, hiatus between vowels, which proves to be in considerable part due to metrical considerations

FINAL QU AND O BEFORE INITIAL VOWELS

- §885. Here are treated variants concerning au before all initial vowels and o before all except short a (abhimhita sandhi), which is treated in the next section We find very definite school rules observed in this matter, to wit
- (a) AV. writes $\bar{a}v$ for au, but a for o, without regard to the character of the following vowel This is required by APr 2 21 f But once, in a passage inherited from RV. AVS shows \bar{a} for au before u, Ppp has the regular $\bar{a}v$
- (h) All other schools treat au and o in a quite analogous manner Thus Maitrāyanīya and Kāthaka texts, and VSK, write ā for au and a for o before all vowels. This is prescribed by VPr. 4. 124; for the practice of VS see just below. The rule is not quite without exceptions in Maitr. texts; cf. Linutām tāv adhvarā jātavedasau MŠ 5. 1.3. 27. So, at least, Knauer reads with no report of v. 1. On the other hand, at MŠ 3. 5. 14c Knauer reads yatra cuścutad agnāv evaitat, without any ms authority, the corrupt mss are closer to agnā, the expected form.
- (c) Taittiriya texts write $\bar{a}v$ and av before all vowels. This is contrary to TPr 10 19, which prescribes \bar{a} and a. But 10 21 adds the opinion of another teacher who says $\bar{a}v$ and av should always be written, this is favored by the comm on TPr, and is according to Weber the regular usage of the mss of TS. The variants indicate that it is also the regular usage of Tait school texts, at least in their mantra materials
- (d) Other schools—that is, those of RV, SV (very few instances), and VS—write \bar{a} and a before u-vowels, but $\bar{a}v$ and av before other vowels. So RPr 129 (29) and 135 (211), and so VPr 4 125 gives the opinion of 'some', opposed to its own rule 4 124, quoted above
- (e) To summarize before u-vowels, Tait texts write $\bar{a}v$ and av, AV, writes $\bar{a}v$ for au but a for o, others \bar{a} and a
- (f) Before other than u-vowels, Maitr texts, KS, and VSK write ā and a; AV writes āv but a, all others āv and av.
- (g) In a few sporadic instances the final o of voc sing, forms is retained without change before a following vowel Cf Wackernagel I §273b, the variants show that the phenomenon is not quite so limited as Wackernagel represents it
- §886. The variants of au before u-vowels are the following asvinau dvyakşarena (MS KS °rayā) prānāpānāv (MS KS °nā) ud

ajayatām TS MS KS asā (Ap\$ asāv-asāv) upahvayasva \$\$ Ap\$ asmākam yonā (Ap\$ yonāv) udare suševāh MS Ap\$

- ımam yaıñam zuşamānā (TB °nāv) upetam MS TB.
- upasthe mātuh surabhā (TS °bhāv) u loke RV TS. MS. KS
- ubhā (AV ubhāv) upānšu prathomā pibāva RV. AV.
- urūnasāv (TA uru°) asutrpā (AV. TA. °pāv) udumbalau (TA. ulu°) RV. AV. TA AS
- kā (TA. kāv, AV. VS kım) ūrū pādā (TA † pādāv) ucyete RV AV VS TA The only exception to the rule in AV Ppp. (Barret, JAOS 42 113) reads pādāv, regularly
- danyā hotārāv ūrdhvam (VS MS °rā ūrdhvam, KS hotārordhvam) VS TS MS KS †18 17a In KS the form hotārā, not °rau, is concerned
- na yonā (TS yonāv) usāsā° VS TS MS
- rakşohanau (VS SB °nau vām) valagahanā (TS. ApŠ °hanāv) upa° VS VSK TS KS SB ApŠ
- syone kṛnudhvam surabhā (TS °bhāv) u loke VS TS MS KS \$B §887. The variants of o before u-vowels are.
- uşnena vāya (ApMB vāyav) udakenehi (with varr) AV SMB ApMB. AG GG PG
- deva vişna (ApS vişnav) urv PB KS ApS MS
- dwo vā viņna (TS viņnav) uta vā pṛthivyāh VS TS KS ŚB dwo viņna etc AV MS.
- maho vā viṣna (AV maho viṣna) uror antarikṣāt (TS viṣnav uta vāntarikṣāt) AV. VS TS KS ŚB
- vişna (TS ApS vişnav) urukrama VS TS MS SB ApS MS §888. The variants of au before other than u-vowels are
- agnāv (VSK MS KS MŚ agnā) agnis carati pravisļah AV VS VSK TS MS KS ŠB AŠ ApŠ MŚ SMB , pratīka, Vait KŚ Kauś GG agnīsomāv (MS KS MŚ °somā) imam su me RV TS MS KS TB
 - vîşomâv (MS KS MS "şomā) ımam su me RV TS MS KS TF AS ApS MS SS
- azasya nābhāv (MS KS nābhā) adhy ekam arpıtam RV VS TS MS KS asāv (MS KS MŚ asā) anu mā MS KS LŚ MŚ ApŚ
- āyur dadhad yajñapatāv (MS KS °tā) avıhrutam RV SV ArS VS MS. KS LS ApS
- ımau bhadrau dhuryāv (MS °yā) abhı SV MS JB
- usrāv etam VS TS SB MS ApS KS usrā etam VSK KS In MS the rule is violated, no v 1 reported
- gošaphe šakulāv (VSK °lā) īva AV VS VSK ŠŠ LŠ
- tāv (KS. tā) ehr sam TS KS SB TB ApS HG BrhU tāv rha sam AV tāv ehr (MG tā eva) vr AG SG PG MG tāv eha sam AB

dīksito 'yam asā āmusyāyanah MS. MŚ. adīksistāvam brāhmano 'sāv amusya. ApS.

darvyā hotārāgnā (KS. AS. °ana, SS. °rā agna) ājyasya vītam MS KS AS. SS Since SS., if it stands for hotarau, is contrary to the rule which requires "rav, we should perhaps read hotaragna also in SS. or consider it a case of histus between hotara and agna; the other texts of course have the form hotara, not rau No v I reported for SS

nabhaś ca nabhasyaś ca vārşıkāv (VSK. MS KS °kā) rtū VS VSK. MS TB SB, KS

namucāv (VSK MS KS °cā) āsure sacā RV. AV VS VSK MS KS SB TB ADS

pañcabhir dhātā vi dadhāv (MS KS. dadhā) idam TS MS KS. But MS. p p. dadhe

putram wa prtarāv (VSK. MS KS °rā) asvnobhā RV AV. VS VSK MS KS SB TB AS ADS

praişān sāmidhenīr āghārāv ājyabhāgāv (KSA āghārā ājyabhāgā) ākrulam TS KSA

madhavyau stokāv (MS °kā) apa tau rarādha TS. MS

muşkāv (VSK. muşkā) id asyā ejatah AV. VS VSK ŠŠ

yajñasya yuktau dhuryā (TB. ApŚ °yāv) abhūtām (MS °thām) MS KS † TB ApŚ

yadā carışnü mithunāv (MS. °nā) abhūtām RV. MS N

yo 'sāv (MU. 'sā) āditue puruşah so 'sāv (MU 'sā) aham VS MU

rādhānsīt samprācānāv (MS MŚ °sı °nā) asam MS. ŚB KŚ ApŚ

vışnuh sıpıvışta †üräv (VSK †ürä) äsannah VS VSK . sıpıvışta †ürä āsūdvamānah KS

sacetasāv (VSK °sā, MS samokasau sacetasā) arepasau VS. VSK MS SB.: samokasāv (KS °sā) arepasau TS KS. Ksuš

samıddhe agnāv (VSK. MS KS agnā) adhı māmahānah VS. VSK TS MS KS SB

samrājāv (MS °jā) asya bhuvanasya rājathah RV MS

sarasvatīm ašvināv (VSK MS KS °nā) indram agnim VS VSK MS KS SB. TB

sahaś ca sahasyaś ca harmantilāv (VSK MS KS °kā) 7tū VS VSK TS MS. KS SB.

upa (MS utā) no mitrāvarunāv ihāvatam (MS °nā ihāgatam) MS TB TA

ApMB HG MG' rtena sthūnāv (MG. rteva sthūnā) adhi

tena (TB, tato) no mıtrāvarunāv (MS. °nā) avışţam (TB. avī°) RV MS TB

madhus ca mādhavas ca vāsantīkāv (VSK MS KS °kā) rtū VS VSK. TS. MS KS ŠB.

vişnüvarunā (TB °nāv) abhisastipāvā (TB °pā vām) MS TB.

yāv (MS KS yā) ātmanvad .. AV. TS. MS KS

agnım sve yonāv (VSK. MS. KS yonā) abhār ukhā VS. VSK TS MS KS SB

ahāv (MS KS ahā) anadatā hate AV TS MS KS.

ā tasthāv (VSK. MS KS tasthā) amrtam dwn RV. VS VSK TS MS. KS SB

ındravāhāv (KS °hā) rbhavo vājaratnāh RV -KS

mıtrāvarunāv (VSK °nā, MS ındrāvarunā) algābhyām VS VSK MS vāsantilāv (KS ıme vās°, MS KS °tıkā) rtū abhıkalpamānāh VS. MS KS TB.

śaiśirāv (MS °rā, KS ime śaiśirā) rtū abhikalpamānāh TS MS. KS. ŠB işaś corjaś ca śāradāv (VSK MS KS °dā) rtū VS VSK TS. MS KS ŠB

ubhā dālārāv (VSK MS KS °rā) ışām rayīnām RV VS VSK. TS MS. KS SB

ko nu vām mitrāvarunāv (MS °nā) τ tāyan RV MS. KB ŚB

tapaš ca tapasyaš ca šaiširāv (VSK MS KS °rā) $\gamma t\bar{u}$ VS VSK TS MS KS SB.

devī uşāsāv (VSK MS °sā) asmnā VS VSK MS TB.

dawyāv (VSK. °yā) adhvaryū ā gatam VS VSK ŚŚ

dhanasātāv (VSK MS KS °tā) zhāvatu VS. VSK TS MS KS

praharşıno (KS ms °nam, ed em) madırasya made mrşāsāv (KS °sā) astu KS. ApŚ

mahāntāv (MS °tā) ındrāvarunā mahāvasū RV MS

yajñasya pakṣā (TS °ṣāv) rṣayo bhavantī TS MS KS.

yat pṛthwyām yad urāv (VSK MS KS urā) antarīkṣe VS VSK TS MS KS. SB

yā (AV omits) rājanye dundhubhāv (KS.†°bhā) āyatāyām AV KS TB yo no mitrāvarunā abhidāsāt sapatnah (TS °varunāv abhidāsati) TS MS imau (Kauś yau) te pakṣāv (VSK MS KS pakṣā) ajarau patatrinau

(VSK TS†KS °nah) VS VSK TS MS. KS ŠB Kauś. rāgānah samītāv (VSK MS KS °tā) wa RV VS VSK TS MS KS

vāyava ārohanavāhāv (KSA °hā) anadvāhau TS KSA.

venubhāram girāv (KSA girā) īva TS KSA TB

śacyā harī dhanutarēv (KS °rā) ataşta RV KS

śukraś ca śuciś ca graişmāv (VSK. MS KS °mā) rtū VS VSK TS MS KS. ŚB

sūdrāryāv (VSK MS KS °yā) asrjyctām VS VSK TS MS KS \$B. śriś ca te lakṣmīś ca patnyāv (VSK °nyā) [ahorātre] VS VSK sam yāv apnastho (MS yā apnahstho) apaseva janān RV MS sajoṣasāv (VSK °sā) aśvnā dansobhih VS VSK \$B

sahasrasā (RV also °sām) medhasātāv (VSK °tā) wa tmanā RV (bis)

VSK KB (This RV. repetition is omitted in RVRep) somārudrāv (MS °drā) iha su mṛdatam nah RV AV MS staumi devāv (MS KS devā) asvinau nāthito johavāmi TS MS KS hatāghaśansā (TB °sāv) ābharadvasū MS KS TB hatāghaśansāv (VSK. °sā) ābhārṣtām vasu vāryāmi VS VSK TB hemantaśistrāv (VSK MS KS °rā) rtū (TS rtūnām) VS VSK TS MS KS ŠB

hotārāv (VSK MS °rā) indram aśvinā VS VSK MS TB hotārāv (VSK MS KS °rā) indram prathamā suvācā VS VSK MS KS 'TB

§889. The variants of o before other than u-vowels are ubhayebhyah pra cikitsā gavistau (VSK gaistau) RV VS VSK kuvit su no gavistaye (MS KS gaistaye) RV SV TS MS KS AB AŠ ApŠ

ye sāmbare harıvo ye gaviştau (VSK garştau) RV VS VSK AB KB eko bahünām ası manyav īdıtah (AV manya īdıtā) RV AV tam tvá ghrtasnav (VSK °sna) īmahe RV SV VSK ŠB tava vāyav (VSK vāya) rtaspate RV VS VSK ŠB nıyıttan vāyav (VSK vāya) ā gahı RV ArS VS VSK nıyutbān vāyav (VSK MS KS vāya) ıştaye durone RV VS VSK TS

MS KS nıyudbhır (AV vıyugbhır) väyav (AV VSK MS väya) ıha AV VS

VSK MS SB TA AS SS ApS
maitrāvarunasya camasādhvaryav (MS °ya) ādrava (ehi) TS SB KS
ApS MS

vasat te vişnav (KS vişna) āsa ā krnomi RV SV TS KS AŚ vy astabhnā (etc., §137) rodasī vişnav (VSK MS KS vişna) etc RV VS VSK MS KS ŠB TA

sahasah sūnav (MS KS sūna) āhuta RV TS MS KS

§890. In the following o of voc sing is retained without change sa no mayobhūh pito (AS SG PG SMB [Jorgensen] pitav) āvišasva (AS āvišeha) TS TB AS SG PG SMB

(AS āvisena) 15 1B AS tāsv adhvaryo indrāya AB AS tāsv adhvaryo indrāya

brhaspatisutasya ta (MS tā, KS omits) indo (MS KS inda) indri° TS MS. KS brhaspatisutasya deva soma ta inda indri° VSK

INITIAL & AFTER FINAL & AND O

§891. In the great mass of variants under this heading, the initial a is in one form elided as in classical Sanskrit (abhimhita), while in the other form both the a and the final diphthong are left unchanged in writing. A few cases of different and anomalous treatment will be mentioned at the end of the section. Disregarding them for the moment we shall consider the writing or elision of a. On the probable actual pronunciation of e, o when followed by written a, see Wackernagel I p 324, the diphthong was, as he says, no doubt regularly pronounced in some way as a short vowel, but the variants throw no light on this question

§892. On the principles governing writing or elision of initial a after e and o the Prātišākhyas give no help—Boiled down, their statements amount only to this, that the a is sometimes written and sometimes elided—VPr 4 78 specifies that it is generally written in verses (rksu)

§893. Early statements in western grammers add little except that in metrical passages the meter shows that the a was generally pronounced, whether written or not, tho it is generally omitted in writing, whether pronounced or not Whitney, Grammar §135c, says specifically that there is no 'accordance in respect to the combination in question between the written and the spoken form of the text'

§894. Yet as long ago as 1862, in his note to APr 3 54, Whitney himself showed, from a count of AV instances, that

- (a) In prose passages, a is omitted seven times out of eight
- (b) In metrical passages where the meter indicates elision (we shall use this familiar term, altho doubtless 'absorption' would be more accurate, cf Wackernagel, l c, p 324, bottom) of a, it is omitted in writing six times out of seven
- (c) In metrical passages where the meter indicates pronunciation of a, it is written nine times out of ten, except that at the beginning of a pada in the middle of a verse-line, where of course it is always pronounced, it is omitted in writing four times out of five

\$895 If these facts are at all typical of Vedic works in general, and there is reason to believe that they are, they seem to indicate that at some time in the history of our tradition an attempt was made to make the writing conform to certain definite standards, which had some relation to actual pronunciation. The statement quoted above from

Whitney's Grammar is therefore exaggerated, to say the least To be sure, the attempt was either incompletely carried out, or else its results have been somewhat disturbed by later copyists and redactors. Cf. Oldenberg, Proleg. 460 f, Wackernagel I p 325

General practice of Vedic texts

§896. Before summarizing the evidence of the variants, we shall venture a statement of what seems to us to have been the general procedure in the Vedic tradition Apparently this tradition was fixed at a time when the usual custom was to elide the a, as in classical But those who established the norm in the Vedic texts were quite aware of the fact that these texts themselves. by their meter, indicated that the a frequently, if not usually, had to be pronounced. As a concession to this observed fact, or perhaps, more accurately, in order to help in the proper recitation of the Vedic texts, they undertook to write the a in cases where the meter required its pronunciation, leaving it unwritten in the comparatively rare cases where the meter required its omission, and in prose generally. Only when the a came at the beginning of a pada in the middle of a line, the awas elided in writing, in accordance with the general custom of the time when the redaction was carried out, perhaps for the very reason that no confusion or error of pronunciation could well arise in such cases is since the a would have to be pronounced in every such case, its omission in writing, according to the usual rule of the time, was considered allowable.

§897. Thus, except in the last-mentioned case, an attempt was made to conform spelling to original pronunciation of the metrical texts, while in prose texts the a tended to be omitted. Exceptions may often be explained as due to carelessness or ignorance, whether on the part of the original reductors who applied the rules, or on the part of later copyists or reciters

Evidence of the variants

§898. In interpreting the bearing of the variants on these rules, we must remember that they are a specially selected group, and make allowance for the principle of selection. Thus, first, they cannot in the nature of things take note of the cases in which initial a is elided at the beginning of a pada. All such padas are necessarily printed in the Concordance, and in the Variants, with initial a; whereas, as we have seen, according to Whitney the a is elided in four-fifths of such cases

SÁNDHI 421

in the AV; and much more regularly in the RV. In fact, RPr 138 (2.13) requires that a should never be written in this position

§899. Secondly, every one of our variants contains, by definition, at least one instance, in some text or other, of both possible forms: a written and a elided. This means that invariably, except in the few cases in which a pāda can be read metrically either with or without pronunciation of a, at least one of the texts quoted violates the general rule. Consequently, statistics based on our variants cannot possibly be expected to agree precisely with the rules laid down in §896. If, despite this artificial weighting of the scales in favor of the advocatus diaboli, the variants nevertheless show a definite tendency in favor of the rules as stated, this may be considered a valuable confirmation of them. And such, we think, is the case

§900. The extent to which variants may be trusted as representing general usage may be tested by comparing the AV. passages found among them with Whitney's statistics for the entire AV, mentioned in §894. Thus, in metrical passages where a is pronounced, Whitney found it written in mne-tenths of the cases, the variants have it written in more than two-thirds, or nearly five-sevenths of such cases (26 out of 38). In metrical passages where a is not pronounced, Whitney found it omitted in six-sevenths of the cases; the variants show it omitted in all the six cases which occur. The prose variants from AV are very few (only 5); in two of them a is written, in three elided, whereas Whitney reports elision in seven-eighths of the prose cases. These correspondences suggest that when the variants occur in considerable numbers, they may be taken as a fair index of conditions in the texts as a whole.

Metrical passages

§901. The a is pronounced in 59 metrical padas among the variants; it is not pronounced in 10. In 24 it may be read either way, or the readings are changed in other respects so that both forms of the variant are metrical as written

§902. When the a is shown by the meter to be pronounced, it is also written in nearly two-thirds of the cases in all texts together (213 to 117). In general, the proportion is higher in the older texts. Thus RV, written 21 times, omitted 4; AV. 25 to 12; TS. 19 to 7, MS 24 to 9 But it is lower than the general average in VS (10 to 6) and KS (20 to 16). SV. forms a striking exception; among the variants it has a written only once, omitted 4 times. Its school texts show that this is no

accident due to the small numbers; they also write a 3 times and omit it 8 times. The SV, school clearly tended against the writing of a, in accord with classical Sanskrit usage (we shall see below that in prose texts, also, the dropping of a predominates in the SV school much more than in the others). While the SV, and its school texts are the only ones that show a majority for dropping a when it is pronounced, later texts in general show a growing tendency to do so, approaching the classical norm. Thus RV, school texts have it written 14 times, omitted 11 times (against RV, itself 21 to 4).

\$903. When the a is shown by the meter not to be pronounced, it is also omitted in writing in five-sevenths of the cases in all texts together (46 to 19) The cases are too few to make it safe to set up rules for the individual schools.

§904. Thus we see that in all metrical padas the writing is consistent with the pronunciation in nearly two-thirds of the cases (259 to 136), whether the meter requires pronunciation of a or the reverse. In the few cases where it is possible to read the pada metrically either way, we have given the written text the benefit of the doubt, assuming that it was pronounced when written, not pronounced when omitted in writing. They are not numerous enough to affect the result, and our procedure seems justified by the evidence of other cases where there is no ambiguity.

Prose passages

§905. In the prose variants the school texts of SV, show a considerable preponderance of clided over written a (12 to 1), and the same tendency, tho less decisive, is noticeable in the Taittiriya school, which shows clision in two-thirds of the cases (49 to 25) Other texts show no very marked tendency in either direction MS has a majority for a written (21 to 15), but its school texts are nearly even The totals for all prose passages are 105 written, 151 chded Contrast this with 232 written, 163 chded among the metrical variants (213 to 117 where the meter shows that a was pronounced)

Table of final a written or omitted after e and o

§906. The figures in the following table are worth quoting, the perhaps not to be taken too absolutely. As stated above, when the meter permits either pronunciation or elision of a, we assume consistency of writing and pronunciation. Repetitions of the same formula in the same text, with or without modulations in the adjoining words are not counted.

	metrical passages				PROSE PASSAGES	
TEXTS	Writing and pronunciation consistent		Writing and pronunciation inconsistent			
	a written and pronounced	a not written, not pro- nounced	a not written, but pro- nounced	a written, not pronounced	a written	a clided
RV	21	0	4	0	0	0
RVKh	1	0	1	0	0	0
RV school texts	14	2	11	1	9	14
sv	1	0	4	0	0	0
SV school texts	3	0	8	1	1	12
AV	25	6	12	0	2	3
AV school texts	4	1	1	0	1	2
VS	10	2	6	2	13	13
VSK	2	1	0	0	0	2
ŚB	8	0	5	1	8	10
Other Vāj school	5	1	4	0	0	3
TS	19	6	7	2	10	20
TB	17	2	9	0	3	8
ApŚ	10	0	7	4	8	11
Other Tart school	10	3	6	2	4	10

TEVIS	METRICAL PASSAGES				PROSE PASSAGES	
	Writing and pronunciation consistent		Writing and pronunciation inconsistent			
	a written and pronounced	a not written, not pro- nounced	a not written, but pro- nounced	a Writton, not pronounced	a wntten	a elided
MS	24	6	9	3	21	15
Maitr. school	14	5	2	0	9	7
KS	20	8	16	3	15	18
Late and misc	5	3	5	0	1	3
Totals	213	46	117	19	105	151

§907. We now proceed to list the variant passages, beginning with the metrical ones, and first with those in which the meter indicates that the a was pronounced, whether written or not (59 items)

so adhvarān (AV. Kauś. 'dhvarān) sa riūn kalpayāti RV AV TS MS KS SB. Kauś.

anumate 'nu (KapS † anu) manyasva na idam (AV. 'nv idam manyasva) AV KS. KapS. (quoted in note to KS.). anumate 'nu manyasva (prose) GG. KhG. HG. ApG

nır amum bhaja yo 'mıtro asya TB.: niş lain bhaja yo amıtro asya AV. tatra sısrıye 'ja ekapādah AV.† 13 1. 6: tasmıñ chısrıye aja ekapāt TB teşām yo ajyānım (PG. 'jyānim) ajülim āvahāt (SMB Conc ajüjim āvahāh, but Jörgensen as other texts) TS SMB PG. BDh

700 akşare (Nipu. 'kşare) parame vyoman RV. AV. GB. TB. TA SvetU.

NrpU. N.
yasmāj jāto na paro 'nyo (ŚŚ anyo) astı JB. ŚŚ: yasmād anyo na paro astı
jātah PB: yasmān na jātah paro anyo astı (NrpU 'sti) VS TB
ApŚ MahānU. NrpU.

ye agnayah (TS KS TB. ApŚ 'gnayah) samanasah (KS adds sacetasah) VS TS MS. KS. ŚB TB. ApŚ MŚ

tam tvā višve avantu (AV. 'vantu) devāh AV. ApMB. HG. A very poor pāda but intended for tristubh.

yo 'syese dripado yas catuspadah AV.: ya īse asya (MS. KS. * īse yo asya) dripadas catuspadah RV. VS TS MS KS (both)

vaisvānaro angirasām (AV. 'ngi', AS angirobhyah) AV. AS. SS.

śucih śukre ahany ojasīnā (MS ahann ojasīne, KS †śukro ahany ojasye; AŚ 'hany ojasīnām') TS. MS KS AŚ.

sūryo ahobhır (KS. suryo [misprint] 'hobhır) anu tıāvatu KS TB.

so asmān (MŠ asmān) adhipatīn karotu TS. MŠ.. so 'smān adhipatīn kṛnotu ŠŠ

svām tanvam (TS TB. tanuvam) varuno 'suşot (TS. TB. aśrśret) TS. MS. KS. TB. It would be forcing probabilities to compress the MS. KS. reading to an anuşlubh.

agnır ajaro 'bhavat sahobhıḥ MS . agnır amrto abhavad vayobhiḥ (KS. sahobhıh) RV. VS TS KS SB. ApMB

na tā arvā reņukakāļo ašnute (AV. 'šnute) RV. AV. KS. TB AŠ Many AV. mss. read ašnute

adhı bruvantu te 'vantv (TS TB. ApŚ avantv) asmān RV. AV. VS TS. MS KS TB. ApŚ.

anīkair dveşo ardaya (ŠŠ 'rdaya) MS. ŠŠ

annam payo reto asmāsu (SB. 'smāsu) dhatta (MS. ApŚ. dhehi) VS MS. KS SB. TB. SŚ. ApŚ.

anyam te asman (NppU. 'sman) nı vapantu senāh RV. TS. NppU.

anyo-'nyo (Vait.-anyo) bhavatı varno asya TB. Vait

avāsījo apo (TB. 'po) achā samudram RV. MS. KS. TB.

pra vartaya divo asmānam (AV. 'smānam, v. l. as') indra RV. AV.

prothad asvo na yavase 'ınşyan (TS avışyan) RV. SV. VS. TS. MS. KS. SB.

namo astu (MŠ 'stu) parāyaie AV. MŠ

prānco agāma (TA. prānjo 'gāmā) nrtaye hasāya RV. AV. TA.

payo grheşu payo 'stu tan nah MŚ.: payo vatseşu payo astu tan mayi AB TB. AŚ. ApŚ

ye agnayah pāncajanyāh (MŚ purīsinah) VŚ ŚB MŚ: ye 'gnayah purīsyāh (KŚ. 'sinah) TŚ KŚ ApŚ. JUB.

dhātā samudro apa (AG. 'va) hantu pāpam AG. PG.: dho sao abhayam krnotu MG

śiśu kridaniau pari yāto adhvaram (AV. arnavam, and 'rnavam) RV. AV. MS TB.

namo astu (VS. SB. KS PG NīlarU. 'stu) sarpebhyah RVKh. VS. TS. MS KS. SB. KS. ApS. MS PG. ApMB HG. MG. NīlarU

ye'do (MS amī) rocane divah RVKh. TS MS. ApMB

yo asyāh prthivyās tvaci TB ApS.: yo 'syāh (so all mss. but one, and so Conc., but ed.† asyāh) prthivyā adhi tvaci MS.

yo nah svo (AV svo yo) aranah (SV 'ranah) RV SV AV AG SG Oldenberg. Proleg. 40, thinks of inserting yo in RV., tho he fails to note that AV reads so

vaisvānaro adabdhas (AV. no adabdhas, TA. me 'dabdhas, MS Ap\$ 'dabdhas) tanūnāh AV. VS MS SB TA ApS SMB.

ko ambādadate (AŚ 'mbā°) dadat MS AŚ

mayā so annam (AV 'nnam) atti vo vipašvati RV AV

ındra väjeşu no 'va (TB ava, KS vaha) RV AV SV ArS MS KS TB vad vā me anı (LS 'nı, Vait apa) gachati AS Vait LS

ue agnavo divo ne prthivyāh MS ApS MS ue 'anavo divo ne 'ntariksāt KS (wrongly printed as prose in ed)

ye agnıdagdhā ye anagnıdagdhāh (TB Poons ed † 'nagnı'; so v 1 of AV) RV AV. TB AS. ye agnısvällä ye 'nagnısvälläh (VS anagnı') VS. TB ApS

sā tvam asy amo 'ham (SB BrhU PG. amo aham, ApMB amūham, MG apy amo 'ham) KS JUB SB BrhU AG SG PG ApMB MG sa tvam asy amo 'ham AB

kīkasābhyo anūlyāt (ApMB 'nū°) RV AV ApMB

te asmat (TS 'smat) pāśān pra muñcantv enasah (TS anhasah) AV TS divo antebhuas (KS 'nte°) pari RV SV KS.

yo adya (PB 'dya) saumyo (AV senyo) vadhah AV PB AS-Ppp

'dua acc to Roth vyāghro varyāghre adhi (TB 'dhi) KS TB vyāghro adhi varyāghre AV ye annesu (VS KS 'nnesu) wwdhyanti VS TS MS KS

varsisthe adhi (KS 'dhi) näke TS KS TB

rājā me prāno amriam (TB 'mriam) VS † MS KS TB

ıdam (KS ā mā) varco (AS rādho) agnınā (KS 'gnınā) dattam ügāt (AV

āgan, KS etu) AV MS KS TB AS vrsāyamāno 'vrnīla (AV av') somam RV AV TB

satotaye 'bhimātisāhe (PG abhi') TS KS MS SMB PG

krnvāno (KS Lurvāno) anyān (TS KS Ap\$ † anyān, MS anyan, K\$ †

'nyān) adharān sapatnān AV TS MS KS KŠ ApŠ

synvanty (PB °tv) apo adha (PB 'dhah) kşarantih RV PB

so adhvarā (AB 'dhvarā karatı) jātavedāh AB SB Cadenced prose, cf krnotu so .

annapate 'nnasya (MS KS MS MG an°) no deht VS TS MS KS SB TB ApS MS PrānāgU AG SG MG SMB Intended for

ayam yo asya yasya ta ıdam sırah MS ayam yo 'sı yasya ta ıdam sırah KS ApS

[yo asya kauşihya jagatah MŚ yo 'sya kauşihya (KS 'tha) ja' KS TA.

ApŚ. So Conc; but Van Gelder's ed reads 'sya for MŚ without
v 1]

[anamitram no (VSK me) adharāk (AV °rāt) AV. VSK.† KS Conc 'dharāk for VSK]

[brhaspate abhisaster (AV ed 'bhio') amuñcah AV. VS TS MS KS TAA But read abhio in AV, see Whitney's note]

§908. In the next group, a much smaller one, containing 10 items, the a seems not to have been pronounced, whether written or elided: namo 'stu (TS KS astu) nīlagrīvāya (NīlarU. nīlašikhandāya) VS TS KS NīlarU BrhPDh

vıśvasmaı bhūtāya dhruvo (TS ApŚ bhūtāyādhvaro) astu (TS 'sı, Mچ 'stu) devāh (TS omits) TS KS ApŚ MŚ

ye apsu şadānsı (KS 'psu sa') cakrıre MS KS

ye te 'ryaman (KS arya°) bahavo devayānāh TS MS KS † 10 13a vājinām vājo 'vatu bhakşo asmān VSK : vājinām bhakşo avatu vājo asmān ApŠ

yo'gnım (AS agnım) hotāram avrthāh TS AS ŠŠ † jātavedo maruto adbhıs (TB 'dbhıs) tamayıtvā TB ApS

kṣāmad devo 'tı durıtāny (TA MahānU atı durıtāty) agnıḥ AV. TA. MahānU

aghorebhyo 'tha (MS atha) ghorebhyah MS TA MahānU.

yāś ca devyo antān abhito tatantha SMB. yāś ca gnā devyo 'ntān abhito 'tatananta (mss tatantha) MG See §63 The meter is poor in any case

§909. We now come to the third group of metrical variants, 24 in number, in which the surrounding conditions are so flexible metrically that the a may either be pronounced or not (in which case we assume that it was pronounced when written, and not pronounced when not written); or in which there are further changes in the pada which alter the metrical conditions

anv adya no anumatih (AV Kauś 'nu') AV MS ŚŚ MŚ Kauś yān agnayo anvatapyanta (TS 'nva') dhişnyāh AV TS MS ye asmın (KS 'smin) mahaty arnave MS KS MŚ Jyok kṣatre 'dhi jāgarat AV jyog rāṣṭre adhi jāgarat HG jyok śrotre 'dhi (HG adhi) jāgarat AV HG antarikṣe adhy (TS KS 'dhy) āsate TS MS KS MŚ sarvābhyo abhayam (TB 'bhayam) karat RV AV TB N

garbho asy (MS 'sy) oşadhīnām AV VS TS MS KS. SB Vait —Ppp. also 'sy (Barret JAOS 48 38)

- tanvo adya (MS 'dya) dadhātu me AV MS
- vasanto asyāsīd (VS 'syāsīd) ājyam RV AV VS TA The meter of VS (with ājiam) seems easier
- satyam it tan na tvāvān (MS °van) anyo asti (MS. 'sti) RV MS KS TB The meter of MS (tvāvan?) is inferior
- ye 'sman abhyaghayantı AV yo asman abhyaghayatı AV
- ūrubhyām te as(hīvadbhyām (ApMB 'sthī') RV AV ApMB
- te asmā agnayo (MS "ye, v. 1 "yo) dravnam dattvā MS ApS te 'smā agnaye dravnāni dattvā KS. The meter of MS ApS is very poor svisim no abhi (KS 'bhi) vasīyo (AV vasyo) nayantu AV TS KS svisiam no 'bhi vasuo nayantu KS MS
- sūryāyā ūdho 'dītyā (VSK † KŚ † adītyā, KS. adīter) upasthe VSK TS KS. ŚŚ KŚ
- eko vo devo apy (AV 'py) atişihat AV MS. eko devo apy atişihat TS KS Only MS is certainly inconsistent (a written but not pronounced)
- bheşazam gave 'śvāya (MS aśvāya) VS TS MS SB LS bheşazam gave 'śvāya puruṣāya KS In the last the attaching of puruṣāya to this pāda makes the elision of a better metrically
- mā va eno anyakṛtam bhujema RV · mā vayam eno 'nyakṛtam bhujema KS In both forms of this variant the writing and pronunciation are consistent
- tām u dhīrāso anudišya yajante VS. ŠB (a not pronounced) tām dhīrāsah kavayo 'nudišyāyajanta MS (kavayo looks like a secondary intrusion, cf KS in next form; without it a-nu° would have to be pronounced) tām dhīrāso anudršya (VSK °dišya) yajante (KS anudršyāyajanta kavayah) VSK. TS KS TB (a pronounced)
- anyāns te asman (KS anye'sman) nwapantu tāh MS KS Both writings are metrical VS TS have anyam asman nwa° tāh, which is inferior to both MS and KS
- yad vāto apo (MS. MŚ 'po) aganīgan (TS KSA ApŚ agamat) VS TS.

 MS KSA ApŚ MŚ. Writing and pronunciation are consistent
 in all texts except VS, where one of the initial a's must be omitted
 in reading, tho both are written
- yo agnau rudro yo apsv antah AV (intended for tristubh, reading agnau, apsu, and perhaps rud-r-o, but more likely a syllable short) yo 'gnau rudro yo 'psv antah SirasU. (meant for anustubh, 'gnau, 'psu) 'yo rudro agnau yo apsu (MŠ rudro 'psu yo 'gnau) ya oşadhīşu TS ApS MŠ (tristubh; 'gnau, 'psu—inconsistent with the writing of TS ApS) 'yo rudro agnau yo apsu, (then as new pāda, correct Conc) ya oşadhīşu yo vanaspatişu KS (writing and pronunciation consistent).

- so asmān pātu sarvatah AV.: so 'smān pātu (prose) TS \$910. There follow the prose variants, which number 53.
- abhayam vo 'bhayam no astu (AB. AS. me 'stu) AB AS SS.: abhayam me astu (AB.† 'stu) AB. ApS
- işe rāye (ApŚ. rayyaı) ... dyumnāyorje (VS ŚB.† dyumna ūrje) 'patyāya (VS.† ŠB.† apa°, TB.† patyāya, ApŚ. °yorjapatyāya) VS MS. ŚB. TB. AŚ ApŚ
- etāni te aghnije (PB. 'ghnije) nāmāni TS PB: etā te aghnije nāmāni VS. SB. MS. In the last, an attempt has been made to make metrical a passage which was most assuredly prose to begin with. This metrical form is not counted in our table, the a- may or may not have been pronounced (aghnije or 'ghnije).
- vīvarto aṣṭācatvārinsah (MS 'ṣṭā') MS KS · nvarto 'ṣṭā' VS TS ŚB yo 'smān (MS MŚ asmān) dveṣṭ yaṁ (AV adds ca) vayam dvṣmah AV VS TS MS KS ŚB TB. TA MahānU KBU JUB AŚ. ŚŚ LŚ KŚ. Apś. MŚ. Kauś. HG. BDh This extremely common phrase seems always to be written with asmān in texts of the Maitr. school, with 'smān in all others, if the editions are to be trusted For other formulas containing it see the Conc under it, and also: tam abhi śoca yo 'smān etc.; agne yat te tapas (tejas, 'rcis, śocis, haras) etc; tasya nāmnā vṛścāmi etc, ny aham tam mṛdyāsam yo ṭasmān (Apś 'smān) etc MS Apś † 6 18 2; abhy aham tam bhūyāsam etc.; prāham tam atibhūyāsam (Apś †abhi') etc; vy asau yo etc.; durmitrās (or the like) etc.
- devānām tvā patnīr devīr . sadhasthe angurasvad (TS. 'n̄gı') VS TS MS. KS. ŚB. The same with aditiş tvā ('tis tvā), dhişanās tvā, varūtrayo (etc.), gnās tvā
- ākūtyai prayuje 'gnaye (MS. KS agnaye) svāhā VS TS MS KS ŠB ApŠ The same with medhāyai manase, sarasvatyai pūşne, and dīkṣāyai tapase
- agneh (also, indrasya, višveṣām devānām) priyam pātho 'pīhi (TS apīhi) VS 8 50, VSK 8 22 4, TS \$B. 11 5 9. 12
- yo maitasyā diśo abhidāsāt. (five formulas) MS agnim (also, indram, mitrāvarunau, somam) sa (TB sa diśām devatānām) rehatu yo maitasyai (KS °syā) diśo 'bhidāsati KS TB. ApŚ.
- namo agrīvāya (VS KS 'gryāya, MS. 'grīvāya).. VS. TS MS KS namo agrīvadhāya (MS KS. 'gre') ... VS. MS TS. KS.
- namo aparasadbhyah (PB and v 1 of MS. 'para') PB. MS
- namo 'śvebhyo (TS aś°) 'śvapatrbhyaś ca . . VS. TS† MS KS
- namas te astu (PB. JB LS SMB. 'stu) VS TS MS KS AB PB JB

ŚB TB TA. TAA AŚ ŚŚ LŚ ApŚ MŚ AG Kauś SMB. AnMB ApG Occurs frequently, and apparently always with astu except in SV texts which read 'stu

namo vo 'stu (AŠ ŠŠ astu) VS PB AŠ ŠŠ Vait SMB Here, in curious contrast with the preceding, the SMB reads astu according to Jörgensen's edition (not in the Cone), while 'stu is read by VS. and Vart

tebhyo namo astu (PG 'stu) VS MS KS PG SB namo 'anaya (ApS agnaya) upadrastre SS ApS

namo astu (VS SB 'stu) rudrebhyo ye antarikse (VS KS SB 'ntario) VS MS KS SB MS Also namo astu (VS SB. KS 'stu) VS MS KS SB KS MS ru° ye divi (and, pṛthivyām)

namo mahadbhyo arbhakebhyaś (KS 'rbha') ca . VS KS namo brhadbhyo 'rbhakebhyas ca MS MŠ

namo rathibhyo arathebhyas (TS 'rathe') ca VS TS

yo no antı kapatı tam etena 1esam MS yo me 'ntı düre 'rātīyatı tam etena sesam TS

rudro 'gnīt (MS agnīt) MS. TA ŚŚ rudro 'dhipatih (MS adhi") MS TA

tasyāpo apsarasa (KS † 'psa°, MS 'psarasā) ūrjo nāma (TS 'psaraso mudāh) VS TS MS KS SB

dhūrta (KS ote) namas te astu (KS 'stu) KS ApS dhūrte namante (?) astu MS

yazamāno 'grabhīd (ŚŚ agra°) KB SS. pratu etā vāmā

PrānāgU prāno 'anih MU nrano aonth

madhu hutam ındratame agnau (LŠ 'gnau) VS SB LS hutam havır ındratame 'anau MS AB TA AS SS

ye devā dwibhāgā (MS °gāh stha) ye antarıl-şabhāgā (TS KS 'ntarı') TS MS, KS

śwam prajābhyo 'hınsaniam (KS † ahın'') sadhasthe (VS ŠB ' sthād) agnım (TS 'gnım) VS TS MS KS SB—KS punctuates before agnim, so that elision of a is impossible

sajūr abdo ayavobhih (TS ApŚ 'yāvabhih) VS TS SB ApŚ samıdhah-samıdho 'gne-'gna (SŠ odho agna, MS † odho 'gnā) āzyasya vyantu AS SS MS samıdho agna (MS agnā) āzyasya. . MS

KS TB MS

ApS . sūyame me'dya suyame me adva agnır adhı vıyatto asyām KS agnır vıyatto 'syām TS agne yat te 'rcis (MS arcis) tena . . AV MS KS ApS angıraso me asya (KS 'sya) yaznasya prataranuvakan ahauşuh MS KS

- tam (KS † tat) tvendragraha saha yan me 'sti (ApŚ asti) tena KS ApŚ tam tvā pra višāmi saha yan me 'sti tena AV
- diśo abhy alhūd ayam MS KS MS diśo bhy ayam rājābhūt TS TB Semblance of meter, perhaps to be classed with metrical variants antimitras (TS aniyami°) ca dūre-amitras (MS 'mitras) ca gaṇah VS TS MS KS
- andho achetah (TS ApŚ 'chetah) VS TS KS ApŚ Ed of KS 'chetah, but the sole ms aschetah
- apāgne agnīm (TS MS TB MŚ ApŚ 'gnīm) āmādam jahī VS TS MS KS ŠB TB ApŚ MŚ
- apsu dhautasya . yo aśvasanıs (KS 'śva°) MS KS: ..yo bhakşo aśvasanır TS
- aświbhyām tıroahnıyānām (MŚ tırohnyānām) somānām anubrūhi ApŚ MŚ Also tıroahnıyān (MŚ aświbhyām tırohnyān) somān prasthitān preṣya ApŚ MŚ
- ürdhvo adhvaro asthāt (VS SB 'dhvara āsthāt, KS 'dhvare sthāh, ApS adhvare sthāt) VS MS KS SB ApS
- āpo devīr agrepuvo agreguvo . TS TB devīr āpo 'greguvo 'grenīyo MS MŠ devīr āpo agreguvah premam . KS
 - ye devāh purahsado (so also TS, for which Conc† parah^o) 'gninetrā (MS agni^o) TS MS. KS BDh
 - dhūrva iam yo 'smān dhūrvatı VS TS $\dot{S}B$ TB dhvara dhvarantam yo asmān dhvarāt $\dot{M}S$
 - agnıs te 'gram TS · agnış te agram . MŚ
 - somo 'smākam (KS asm°) brāhmanānām rājā VS VSK TS MS KS ŠB TB MŠ ApŠ
 - svadhā prirbhyo 'niarıkşasadbhyah (AV antar
°, GG † 'niarī°) AV ApŚ. MŚ GG HG
 - yo asmı so asmı AV yo 'smı sa san yaze MS KS AB \cdot yo 'ham asmı sa san yaze TB Ap\$
 - tutho vo viśvavedā vibhazatu varşışthe adhı (KS 'dhı) nāke . TS MS. KS
 - nırasto aghasansah (Ap\$ 'gha') KS Ap\$
 - [devo narāšanso 'gnau (ŚŚ † 'gnā) vasuvane vasudheyasya vetu AŚ ŚŚ Conc quotes agnā for ŚŚ]
 - [yena turyena brahmanā brhaspataye 'pavathās JB yena rūpena prazāpataye †'vapathās (Conc ava°). KS]
 - §911. Very sporadically, other forms of sandhi between final e and initial a occur among the variants. For a single case of y as 'Hiatustilger' developed between e and a, see §338. In addition, there are a few

variants which seem to point to a possible resolution of e into ay before a and \bar{a} ; but formal differences are always concerned, so that the variation is never one of sandhi pure and simple.

tve \bar{a} (SV. tvay \bar{a}) bh \bar{u} santi vedhasah RV SV. A loc in RV is replaced by an instr. in SV, with resolution of e to ay, this time however before long \bar{a} .

ubhe id asyobhayasya (AV asyobhe asya) rājatah RV. AV Followed by ubhe yatete ubhayasya (AV. ubhe asya) pusyatah RV. AV The verse is mystic and obscure If the AV. text is right, it seems to have understood the original ubhay- as representing ubhe, perhaps under influence of suggestion from the preceding ubhe; so that we should have just the reverse of the resolution in question. Whitney translates the prior pāda according to the RV reading, but keeps the AV. reading in the second

§912. By a misquotation in the Conc we would seem to have a single similar case of av for o before a:

dyāvāpṛthwī uro antarīkṣa VS VSK MS KS ŠB; the Conc quotes urav for uro in VSK. But the actual text is urv If the text as a printed (with antarīkṣa, not °kṣam) is right, it is an illogical blend of this with the other form of the variant, dyāvā° urv antarīkṣam AV. TS.

SANDHI OF a-VOWELS WITH FOLLOWING T

§913. The variants indicate the following school tendencies Rigvedic and Vājasaneyin texts write a-r for both \bar{a} and a followed by rThis is prescribed by RPr. 136 (2–11) and VPr 4–48 (which gives a-r for \bar{a} -r and makes no reference to a-r, implying no change)

§914. Taittiriya texts and KS write ar for both \bar{a} and a followed by r, as prescribed by TPr. 10 8. So does LS in the single variant noted §915. The rule of APr 3 46 is like that of TPr, ar for both \bar{a} -r and

a-7 But the mss of AV, according to Whitney's note on this passage, follow this rule in general only when the r is not followed by a sibilant, when a sibilant follows they generally write a-r (because of svarabhakti, Whitney on APr 1 101) There are exceptions in the mss, and the Berlin edition, says Whitney, does not always follow either the mss or the Prātiśākhya rule, nor any consistent practice. As to the variants noted, the Berlin edition (and consequently the Cone) agrees through with what Whitney tells us is the general practice of the mss, namely, ar for both ā-r and a-r except when a sibilant follows, in that case a-r. Both Vait and Kaus sometimes write ar even when a sibilant follows, the instances recorded are few

§916. Maitrāyanīya texts regularly write \bar{a} - τ and a- τ without change. Occasionally, however, they seem to shorten \bar{a} to a; so in one variant, see yad $d\bar{a}dayac$ (° $ya\bar{n}$) etc., §918 Two variants occur in which final a is lengthened to \bar{a} before r in MS, these may be regarded as cases of rhythmic lengthening of final a, of §§452 and 458. They are found below in §919. $yatr\bar{a}$ rsayo yagmuh and $yen\bar{a}$ rsayas $tapas\bar{a}$. There is even one variant in which complete sandhi, ar, is apparently found for \bar{a} -r in MS.

savitre tvarbhumate (VS SB tva rbhu°, MS tvarbhū°) VS MS SB
TA This sandhi is unique among the MS variants It is perhaps
worth noting that two mss read svarbhū°, but p p tvā, rbhu° Cf.
§549, and Wackernagel I §267aα, note, which is somewhat misleading or at least incomplete as regards MS.

 $\S 917$. It may be noted that in metrical passages the meter regularly indicates complete fusion (as if ar) in all variants, even for texts which write the r-vowel separately

There are a very few real or apparent exceptions to the above rules, besides those noted for MS, attention will be called to them as they occur

§918. The following are the cases concerning \bar{a} followed by r savitre tvarbhumate (VS SB. tva rbhu°, MS tvarbh \bar{u} °) . VS MS SB TA See §916

yad dīdayac chavasa (MS. °yañ śavasa; TS °sā) rtaprajāta (KS chavasarta°) RV VS TS MS KS AB. This is the only case in which MS shortens ā to a; see §916 The TS reading is due to the fact that the word happens to end a kandikā, which always suspends all sandh; it is no real exception to the Tait practice

dvā yantārā bhavatas tatha rtuh (TS. KSA tathartuh, MS tathā rtuh) RV. VS TS KSA MS

agniyihvebhyas (MS agnihvarebhyas) tvartāyubhya[h] (MS tvā ṛtā°)
..TS MS KS

yatha rnam samnayāması (AV yatharnam samnayantı) RV AV. yatha rtava (AV TA. yathartava) rtubhır yantı sādhu (AV sākam, TA klptāh) RV AV. TA

siāha rşabham (MS svāhā rṣ°, TB svāharṣ°) VS MS TB viśvaharma rṣih (MS °mā rṣih, KS °marsih) VS MS KS ŚB

tapasarṣayah (MahānU. °sarṣayah) suvar (TB svar) anvavından TB TA MahānU The MahānU. rending is exceptional, but is repeated in the comm, which calls special attention to the sandhi, referring to Pāṇ 6 1 128.

yayo rathah satyavarimarjurasmih AV vyo ram ratha rjurasmih satyadharmā TS MS KS Here only AV has this sandhi, the other texts stand for rathas plus rgu° Note, however, that the meter favors the pronunciation ratharjuo, with double crasis, even in the YV texts

lviśvādhiko rudro maharsih (TA Conc maharsih, but Poona ed correctly maharsih) TA MahanU l

§919 The rest are cases of short a followed by r

yatra rsayo (MS yatrā ro, KS yatraro) jagmuh VS MS KS SB On the MS forms of this and the next of \$916

yena rsayas (MS MS yenā ro, TS KS ApS yenaro) tapasā VS TS MS KS SB ADS KS MS Cf prec

yatrarşayah (Kauś yatra rs°) prathamajā ye (Kauś °jāh, om ye) purānāh TS TB Ap\$ Kauŝ

śāradena (also, śaiśirena, vasantena, hemantena) rtunā (KS TB "nar-VS MS KS TB KŚ

rtusthā (MS °āh, KS °ās) stha rtāvrdhah (KS sthartuspršah) VS MS KS SB

riava (KS °vas) stha riāvrāhah (KS† sthartā°) VS KS SB riasthā sthartavrdhah TS

medhām sapta rsayo (ApMB saptar°) daduh ApMB RVKh Scheftelowitz reads saptarsayo also in RVKh

srāhāh rtasya sam u trpnuta rbhavah (TB [so Poona ed] Ap\$ trpnutarbhavah) RV TB ApS

brāhmanam adya ṛdhyāsam (KS adyardh°) MS KS MS tasya įksāmāny (TS KS tasyaik°) VS TS MS KS ŠB

tvām adya īsa ārseya īsīnām (KS † TB adyarsa ārseyarsīnām) VS MS KS TB

avartyaı badhāyopamanihıtāram (TB avartyaı †vadh \bar{a}^a , so Poona ed) VS TB

yathāham bharata rṣabha (ŚŚ bharatarṣ°) AB ŚŚ The only uregular case in SS or any RV text among the variants. No v 1 is recorded

yebhyo na rie (TS KS narie) pavate dhāma kimcana VS, TS MS KS SB tarunasya riasadanam (KS "syaria") ası VS KS SB

varunasya rtasadany (ApŚ °syarta°) ası VS SB KS ApŚ tṛtīyasya satanasya rbhumato (ApŚ °nasyarbhu°) KS ApŚ MŚ TS MS TB AS ApS

tenarsınā (MS AS tena rsınā) śruta esim (TB srutarsim) ugram abhimāticāham RV MS TB

śwo me saptarsīn (KŚ MŚ sapla rsīn) TS Vant KŚ MŚ Note ar in Vait even before a sibilant, of §915

satyaš (VS šukraš) ca rtapāš (TS KS carta°) cātyanhāh VS TS MS KS saptarṣayah (VS MS sapta τ°) sapta dhāma priyānı VS TS MS KS

TB In TS 1 5 3 2b sapta rs° is read without sandhi merely because a kandikā ends here, it is no real exception to the rule

sapta rṣayo (TS KS saptar") 'srjyanta VS. TS MS KS SB'

saptarşīnām (ApŚ Kauś saptar°) sukrtām yatra lokah Vait KŚ MŚ ApŚ Kauś Note ar in Kauś even before a sibilant (one ms ar), cf §915

saptarşīn (ApS saptarşīñ) jinva ApS KS

upahūtā dhenuh (SB gāvah) saharşabhā (SB °bhāh, AS SS † saharşabhā) TS TB SB AS SS Irregular sandhı in SB

upa mā (AŚ ŚŚ mâm) dhenuh saharşabhā (AŚ ŚŚ saharş°) . TB AŚ ŚŚ

ındrartublır brahmanā vāvṛdhānah TB ApŚ · ındra ṛbhubhır brahmanā samvıdānah ŚŚ

undro vidyāt saha rşibhih (KS saharş°) RV AV KS ApMB — In ApMB we must certainly read saharşibhih with four mss , in accord with Tait usage, Winternitz prints saha r° with only one ms

upa rşabhasya (TB LS uparş°) retası (AV nad retah) RV AV TB LS ındrāya rşabhena VS ındrāyarşabhenāsvibnyām sarasvatyaı TB

rnān no narnam erisamānah AV nen na rnān rnava it samānah TA nem na rnān rnavān īpsamānah MS Only AV has this sandhi (na, rnam), the others nas, r-

yatrā sapta ṛṣīn (TS KS yatra saptarṣīn) para ekam āhuh RV VS TS MS KS N

yathaika †şır (KS °karşır) vıjānate KS TA ApŚ Only KS. has this sandhi, the others eka(h) †şır, two words

SANDHI OF FINAL n

§920. On this subject the variants throw little new light School tendencies are seldom discernible, when they do seem to appear, other known facts sometimes throw doubt on the value of this evidence

I Final n before initial vowels

 $\S 921$. All the variant passages concern forms which originally (pre historically) ended in s, except a small group, mainly locative singulars of n-stems, in which the ending n (appearing as nn) varies with ny These, of course, really concern morphology and not phonetics, they hardly belong in this place

Final an before rowels

§222. The Pratisakhyas in general (RPr. 284 [4, 26], VPr. 3 141, APr. 2. 27) make anuscara the rule, but with numerous exceptions. Whitney's note says that AV, more often retains n. TPr. 9, 20-24 gives detailed rules and exceptions, without any generalization; Whitnew's note (p. 225) states that TS, retains n five times out of six.

\$923. Our variants are as confused as would be expected from these statements. It happens that those occurring in TS, show anusrara more often than n; but this is probably accidental in view of Whitney's statement just quoted. Maitr, texts and KS, show about as many cases of one alternative as of the other. But as to Maitr, texts when they change ", to anustara, they generally also shorten the preceding 5 to a: ci. Schroeder, MS., Einleitung, p. XXIX. When this shortening of a is the only difference in the readings of a variant, we have not troubled to record it. The variants fall naturally into three divisions: accusatives plural, reminatives singular, and s-consts (only one of the last). $\S 924$. The cases involving accusatives plural in $\bar{c}n$ are:

ognis jān (MS. jan, KS. jān, TS. TA. ognis tān) ogre pra ... AV. TS MS. KS. TA. The same with $n\bar{n}yu\bar{s}$ (AV. τ $t\bar{c}n$).

agne derārī (MS. deran, SG. derān) irā raha RV. AV. SV VS TS MS KS. TB. AS. SS. ApS. SG. The isolated form of SG. is suspicious (misprint or error?).

นไม ลางล้า (VS SB. ลางลิก์) ออูลิก กลิกงลิก (VS. SB กลิกงลิก์) นอลีดูลิก

VS. TS. MS. KS. SB. MŚ. ApŚ.

cita (VS. SB. adhā) sapainān (KS. twicet nān; TS. twicet nān, once and indra me VS TS. MS. KS. SB. ApS. MS.

ดระสัก (MS. KS ดระสัก) น ประจั . . . RV. SV. TS. VS. MS. KS

ið ernān anu raslöri chilena ApS. MS.: idawāsmān anu vaslām vralena JT.

นากลบุลิกร์ ระลัก (MS. ระลก, AV. ระลิก) aham AV. VS. TS MS. KS SB TA.

dai iran dwa sana . . . derën (TS. KS. Apŝ. derën) upāgāh VS. KS. TS SB. ApS.:...derān upārņiah MS.

k yrāno (KS, kurvāņo) anyān (TS, KS ApS,t anyān, KS 'nyān) adharān SEDERAR AV. TS. MS KS. KS. ApS.

jambhyais (KS. "gabhis) tael arāñ (KS "rān) uta VS. TS KS. jambi I-

bhrān taskaran (p.p. crān) uta MS purolesian (MS. "sen, GB. Vait. "san) alamburu TS GB SB Van. KŠ. Apš. MŠ.

mā so asmān avahāya parā gāt TS . ned eşo asmān avahāya parāyat MS marşo asmān avahāya parāgāt KS

yān (AV TS MS KS Vait yān) āvaha ušato deva devān AV VS TS MS KS SB. KS Vait

yā devīr antān abhīto 'dadanta AV yā's ca devīr (SMB devyo) antān etc. ApMB. SMB. HG yā's ca gnā devyo 'ntān etc MG

rakşohāmitrān (VS °trān) apabādhamānah RV AV SV VS TS MS.

KS

vājo devān (MS KS devān) rhibhih kalpayāti VS TS MS KS sarvān (MS °van) agnīnī apsusado huve vah (MS omits vah) TS MS.

AV . śwān agnīn apsuṣado havāmahe AV.
sarvān apa yajaması Kauś · sarvān ava yajāmahe KS † TB TAA. ApŚ
so asmān (MŚ. asmān) adhipatīn karotu TS MŚ . so 'smān adhipatīn
hrnotu ŚŚ

ye 'smān abhyaghāyanti AV yo asmān abhyaghāyati AV

§925. Nominatives singular in ān are concerned in the following agnih pravidvān (MS °van, KS °vān) iha tat . . MS KS. ApŚ idāvān (MS. °vān) eşo asura prajāvān RV. TS MS KS işto yajāo bhrgubhir . āšīrvān (ApŚ °vān) atharvabhih KS ApŚ cilitvān (MŚ °vān) anu manyatām TS KS MŚ

pumān enam tanuta ut kṛnatti RV pumān enad vayaty udgṛnatti AV visalyo vānavān (TS MS KS bā°, MS. °van, v l °vān, KS NīlarU °vān) uta VS TS MS KS NīlarU

payasvān (TS TB ApMB° vān) agna āgamam AV VS TS MS KS JB SB TB LS ApMB

pra yo jajñe vidvān (AV vidvān) asya bandhum (AV.° dhuh) AV TS KS havişmān (KS °mān) asiu sūryah VS TS MS KS ŠB

[adha tviṣīmān abhy ojasā . . RV SV \dagger (Cone tviṣīmān for SV)]

§926. We have noted only a single case involving an aorist form santā jyotir ud ayān (KS ayān, MS ayan) ajasram RV. VS. TS. MS KS SB

2 Final $\bar{i}n$ and $\bar{u}n$ before vowels

§927. For this sandhi RPr 289 (4 29) requires $\bar{\imath}nr$, $\bar{\imath}nr$. The other Prs allow this also in specific cases, but it is very rare in other texts than RV See APr 2 29 and Whitney's note, TPr 9. 20 and Whitney's note, VPr 3 140 The variants include very few cases, not enough to justify deductions

sarvān (MS °van) agnīnr apsusado huve vah (MS. omits vah) TS MS AB śwān agnīn apsusado havāmahe AV padā panīnr (SV panīn) arādhasah RV SV AV rtūnr (TB rtūn) anyo vidadhaj RV AV MS TB rtūn (AV rtūnr) utsrjate vatī AV SV TB AS SS

[tisro bhūmīr dhārayan (MS 'yans) trīnr uta dyūn RV TS MS KS AS. In this variant the printed text of MS reads tirīnr, with nasa consonant n, instead of trīnr This reading, which the Concurrences is no doubt merely a slip, or a bad writing, for trīnr l

3 Final nn varying with ny before vowels

§928. As remarked above, §921, this is really a morphological matter, not one of phonetics. The few cases are chiefly locatives singular of n-stems

asmın brahmany asmın karmany . AV asmın brahmany asmın kşaire (ŚŚ adds 'smın karmany) KS ŚŚ asmın brahmann asmın karmann (PG karmany) TS ApŚ PG . te nah păniv asmın brahmany asyam purodhāyām asmın karmany . MS

ālmann (IšāU 'ny) evānupasyatı VS IšāU

śucih śukre ahany ojasīnā (MS ahann ojasīne, KS † śukro ahany ojasye, AŚ 'hany ojasīnām) TS MS KS AŚ.

divye dhāmann (once ony acc to Cone) upahūtah (once otā) TB (both)

But Poona ed dhāmann both times]

[trtīye dhāmany abhy (VS dhāmann adhy) arrayanta VS TS MahanU

So Conc, but TA MahānU both have dhāmāny, acc plur] One isolated case concerning verb forms

One isolated case concerning very forms

agany agair holā (ApŚ ajann agaih) KS ApŚ See VV I p 51

II Final n before initial consonants

§929 Before voiceless mutes, as is well known, the usage varies The insertion of a sibilant, before which n becomes anusvāra, is commoner in later texts than in RV

1 Final n before c

§930. RPr 228 (4 4) requires \$\tilde{n}\$, but numerous exceptions are mentioned, of 293f (4 32) VPr 3 133 and APr 2 26 require \$n\tilde{s}\$, and so does TPr 5 20f, with a few exceptions. Whitney's note on APr 1 c says that this rule is universally followed in the mss and text of AV, a statement which is true only if the twentieth book of AV be excluded from consideration (the Pr in fact does not deal with Book 20). In AV 20, and occasionally elsewhere, we find \$n\$ represented by anusvāra without an inserted sibilant. The variants are

acılıtvañ (AV °vānś) cılıtuşaś cıd atra RV AV anadvānś (TS °vāń) ca me VS TS KS dhenuś cānadvānś ca MS MS asmānś (RV KS asmān) calre mānyasya medhā RV MS KS Most

mss of MS asmān (with dental n), v l of KS asmānś ghoşenāmīvānś cātayata (PB °mīvān cătayadhvam) TB PB ApŚ tām airayanś candiamasi svadhābhih MS KS yām airayans (TS ° yañ) etc VS TS ŚB

mahah pıtum papıvāñ (AV 20, °vān) cārv annā RV AV vapıñ (AV 20, SV vaprın) cıtrābhır ütibhih RV AV SV MS asmāñ (SV. asmān) cıtrābhır avatād abhişţibhih RV. SV

2 Final n before t

§931. The usage fluctuates here also RPr 295 (4 33) implies that it is exceptional to insert the sibilant, by quoting a few cases in which this is done So also TPr 6 14. In the few variants found, the RV and TS schools, and KS, generally keep the nasal unchanged. On the other hand APr 2 26 and VPr 3 134 require ns, tho both allow exceptions. The variants from these schools are not inconsistent herewith, and Maitr texts seem also to favor ns. But the number of variants is too small to be conclusive. Besides the writings n and ns, a couple of cases of n alone without the sibilant occur, as before c, above, and before j, below, probably this is to be regarded as a bad writing for n

§932. The following variants occur,

agnır āyusmān sa vanaspatibhir āyuşmān (PG KS °māns) tena (KS tasyā) TS KS PG ApMB (in the last with punctuation after āyuşmān)

asmans (KS asman) te kşut VS TS MS KS SB KS ApS
thawa san tatra sato vo agnayah TB thawa san (MS sans) tatra santam
tvāgne TB AS MS

tasmın (Vant MŠ °mıns) tad eno RV TAA Vant MŠ tısro bhūmīr dhūrayan (MS °yans) trīnr (MS text †trīnr) uta dyūn RV TS MS KS AŠ

paśūns (RV paśūn) tānś calre vāyavyān RV AV VS TA pūsan (ŠB TB pūṣans) tava vrate vayam RV AV VS ŚB TB AŚ ŚŚ śarman (MS śarmans) te syāma MS KS TA tava syāma śarmans

trivarūtha VS tava syām šarman trivarūtha TS
dhāman (AG dhāman) te višvam RV VS KS AŠ ApŠ AG ŠG
brahmans (MS KS brahmā3ns) tvam (MŠ tvam me) brahmāsi VS MS
KS ŠB MŠ brahmā3n (TB °mā3n) tvam rājan brahmāsi TS TB
ApŠ (in the last with punctuation after brahmā3n)

[brahman team as: Mahan U. acc to Cone brahman etc in TA but the Poona ed of TA reads brahman]

3 Final n before 1

§933. The usual statements (e.g. Wackernagel I §280a) make no mention of any other possibility than assimilation of n to \tilde{n} . This is prescribed by the Prätiśākhyas RPr 228 (4 4), APr. 2 11, TPr 5 24, VPr 4 92. For \tilde{n} the spelling n occurs very commonly in mss of many, perhaps most, texts. Thus in the AV. mss, according to Whitney (note to APr 1 c), it is the commonest writing in this case, and has been generalized in the Berlin ed., Whitney, however, feels it as merely another way of writing \tilde{n} before j, and as such it is doubtless always to be taken. A modern editor would no doubt prefer to write \tilde{n} . We find, in fact, n in all the AV variants, and also in SV in the two variants recorded there. (But in ArS. once \tilde{n} .) Compare the like writing before c and t, above

§934. The variants from VS and SB, following Weber's editions, print dental n before j, not \(\tilde{n}\) Why Weber adopted this practice does not appear his note on VPr. 1 c (ISt 4 237) seems to indicate that at least the excellent Chambers mas follow the Pratisakhya Perhaps some of his other mass keep dental n if he gives information on the subject we have not noted the fact. Altho we can hardly attribute any importance to the recorded readings of VS and SB on this point, we report them in accordance with Weber. Note that the comm on VPr 4 92 quotes as an example of the rule ayam vājān jayatu, VS 5 37, which Weber prints vājān

§935. According to Von Schroeder's edution, MS. also reads n, not \tilde{n} , before j in all the variant passages noted. The sole variant noted from another Maitr. school text is MS 1 6 3 15b, where Knauer's edition reads $qrha\tilde{n}$ jugupalam yuvam with a majority of his mss., but against that which he regards as the best, its reading is $grha\tilde{n}$, which is the reading found in the corresponding MS passage according to Von Schroeder—KS usually reads \tilde{n} but once n (yat te asmin etc., below) Most other texts read \tilde{n} , except in so far as they show n (cf. above)

§936. The following are the variants adyā devāñ (VS devān) juṣṭatamo hi gamyāh RV VS TS KSA akīnś ca sarvān (TS KS sarvāň) jambhayan (KS °ya) VS TS MS KS āyuṣmān (PG ApMB °māň, RVKh VS °mān) jaradaṣṭur RVKh AV VS AG. PG ApMB Scheftelowitz reads āyuṣmān for

RVKh. The mss of PG have corruptly ayusyam

kam agañ (AV agan) janayopanah RV. AV N.

garbhah samjāyase punah MS : garbhe sañ (VS ŚB san, KS sam-) j° p° RV VS TS KS ŚB

tam arcışā sphūrjayañ (AV oyan) jātavedah RV AV.

tvam etan (AV etan) janarājno dvīr daša RV AV

te asmın (TS KS asmıñ) javam ādadhuh VS. TS MS. KS ŚB

devān (RV TB. devān) jigāti sumnayuh RV MS SB TB

pasyañ (AV °yan) janmānı sūrya RV. AV ArS N

pntrī (KS pntrī) jinva TS KS PB Vait KS ApS . ojasā pitrbhyah pntrī jinva MS

prajāk kṛnvan janayan virūpāk MS prajā vikṛnvañ (ApŚ vikurvañ) janayan virūpam (ApŚ. °pāk) KS ApŚ

praty ajātān (AV °tān, TS KS. TA °tān) jātavedo nudasva AV. VS. VSK TS MS KS TA

märe asman maghavañ (SV. °van) jyok kah RV SV

yat te asmın ghora āsan juhomı KS · yad adya te ghora āsan juhomı MS : yasyās te ghora āsan ju° VS ŚB yasyās te asyāh kī ūra āsañ ju° TS. ApŚ Exception in KS

yans (TA Poona ed. †yas) te soma pranans tan (Poona ed tan, MahanU tan) juhomi TA MahanU

vibhrājañ (AV SV. °jan) jyotişā svah RV. AV SV.

vytrāni vytrahañ (AV. °han) jahi RV AV.

satyānīte avapašyañ (AV. °yan, MS °yan) janānām RV AV. TS. MS ApMB. This is quoted by APr. 2 11 as an example of ñ before j!

saptarşīñ (KŚ saptarşīn) jinva KŚ ApŚ

[grhān (MŚ grhān, read grhān, see above, §935) nuqupatam yuvam MS MŚ]

4 Final n before &

§937. Before \hat{s} , the regular sandhi of n requires \tilde{n} , which however is often written n, and seems regularly to be printed so in the editions of SV and AV. The \hat{s} changes to ch (representing $t-\hat{s}$). But in the single variant noted from the YV Samhitās, TS alone has this regular \hat{n} -ch, MS and VS keep \hat{s} unchanged, MS writing \hat{n} before it and VS. n, the sole ms of KSA reads like VS, but von Schroeder emended to \hat{n} -ch in his edition. This exceptional treatment is due to the fact that a mute follows \hat{s} , in which case \hat{s} is retained by VPr. 4. 94. We begin with this variant

ādītyān chmaśrubhih (VS and ms of KSA "tyān śma", MS "tyān śma") VS TS MS KSA, asmıñ (AV. asmıñ) chūra savanc mādayasva RV AV.

tam nah püşan chivatamam crayasva IIG ; tam püşan (AV püşan) cho. . RV. AV. ApMB

divi sañ (AV. sañ, SV. san) chukra átatah RV AV SV

maghavañ (AV. SV. PB. TB. Conc ovan, TB Poona ed ovañ) chagdhi ... RV. AV. SV. PB TB. TA ApS. Mahanu.

yűcehresthábhir maghavañ chűra jinva RV . yűvacehresthábhir maghavan AV.

yat te rajañ (AG. rajan) chrtam hawh RV. AG. SG. suro na rurukvāň (SV. °vān) chatātmā RV SV. parārcisā mūradevāň (AV, °vān) chrnīhi RV AV

pratvañcam arkam anayañ (AV.º yañ) chacibhih RV. AV. Salam hemantañ (AV. ºtáñ) chatam u vasantan RV AV. N.

5 Final n before s

§938. Before s, the insertion of t after final n is required by APr 2 9 and TPr 5 33, and authorized by 'some' according to RPr 236 (4 6), of the divergent views recorded in VPr 4 14f. It is quite common in all texts, likewise the analogous insertion of k after final \tilde{n} before s Cf Wackernagel I §282 The Concordance ignores altogether the writing of t in such cases It has not seemed profitable to try to collect and sift its occurrences. We therefore record here only a few stray cases in which final n before s varies with anusvara, most of them concern san sam, in the latter case the preposition sam being felt as involved.

brahman (I.S * brahman) stosyamah prasastah KB GB SB AS SS Vait LS. (bis) ApS MS

sasavān san (MS sam) slūyase . RV VS TS MS KS SB p p. of MS san, all samh mss sam The other texts all actually rend sant, except KS san

pumānsam vardhatām mayı SG. (Conc says that this is an error for puman samvaro, but the text is correct, see \$97). puman samvartatām mayn PG

nhvā paviliam asvināsan (TB °nā sam) saiasvatī VS MS KS TB.

§939. To these may be added a couple of cases—probably not a complete list-in which k is alternatively added after final n before s pratyañ (VS TS. MS † SB * TB pratyañk) somo audrutah (with var)

AV VS VSK MS TS KS SB TB ApS. Poona ed of TB.

mān (VS. TB prānh) somo atidrulah VS VSK SB. TB. ApS Again Poona ed. of TB pran.

6. Final n before p

§940. The only cases noted concern $n\bar{r}n\bar{s}$ or $n\bar{r}nh$ for $n\bar{r}n$, since this variation really concerns final s before k and p, we quote the variants below under that heading, §965

7. Final n before k

§941. Only a single case has been noted, AV writes jayam (jayan) for jayan according to the edition, but Whitney and the Conc would read jayan In any case it is purely a matter of orthography. samjayan (AV. ed jayam) kşetrām. . AV TS MS KS

8. Final n before y

§942. See RPr. 287 (4. 28), VPr 3 135, Wackernagel I §281a, Macdonell 77. 2d.

dadhanvān (MS KS °vān, VS ŚB TB °vā) yo naryo apsv antar ā RV SV. VS MS KS. ŚB TB

9. Final n before l

§943. Two variants

agniş ţān (VS tān, AŠ tāl) lokāt pra nudāty (etc.) asmāt VS ŠB AŠ ŠŠ ApŠ SMB · agniş tān asmāt AV MŠ Inconsistent with RPr 227 (4 4) and Wackernagel I §281b, the VS reading also inconsistent with VPr 4 13, which requires nasalized l. Cf further APr. 2. 35, TPr. 5 26 A nasalized l is required by all authorities and was probably pronounced in all texts

eşa me 'muşmın (GB. 'muşmınl, Gaastra) loke prakāśo 'sat PB GB† 2 5 8

[wṣnus tryaksarena trīnl lokān (VSK trīn ımānl lokān, TS † trīn lokān) VS VSK. TS]

10 Final n before v

§944. One variant

puru tvā dāśvān (SV. dāśvān) voce RV SV N Cf RPr 287 (4 28), APr 2 28, Wackernagel I §281a, Macdonell 77 2d

CHANGE OF DENTAL n TO LINGUAL n

\$945. The variants of course mainly concern the change of n to n under the influence of a lingual sound in a preceding word (in the same word the lingualization occurs almost invariably). In general, the

greater degree of psychological propinquity between the alterent sound and the n. the greater is the likelihood of lingualization That is, both verbal and nominal compounds show a tendency to be treated as single words for the purposes of this change; and enclitics, and other monosvilabic particles, tend to be regarded as parts of the preceding word (For a few cases of variation between n and 'spontaneous' n, not conditioned in the normal way, see §§163, 165, 170)

8946. The school tendencies which appear are capricious and unstable, one sometimes has a feeling as if Taittiriya texts, in particular, took a perverse delight in violating their own general principles

§947. (1) The n is the initial of monosyllabic words, especially enclitics; or in forms of the enclitic pronoun ena- Here we find that Samavedic and Maitrayaniya texts rarely alter to n, while Taittiriya texts generally alter to n, but there are exceptions in both cases Other schools seem to show no definite tendencies among the variants

5948. We have separated the cases in which the alterant sound is a final r of the preceding word from those in which it occurs earlier in that word But so far as the variants indicate, we find no reason to suppose that lingualization was any more apt to occur in the former This is, indeed, what we should expect on the case than in the latter analogy of the classical rule, by which lingualization is not in the least dependent on close proximity of the alterant to the altered sound that after a final r, Taittiriya texts keep dental n in a case or two where all other texts (in one instance even SV and MS, which generally avoid lingualization) show lingual n, and yet, as we have said, Tait texts generally favor lingualization

§949. In the following cases the alterant sound is final r:

svar na (TS. ApŚ suvar na) gharmah (ApŚ * gharma) svāhā VS TS. KS

SB ApS. The same with yyotth, sukrah, sūryah, arkah; all in the same passage, but not all in the same texts (see Conc.) Only

TS has n in the rest (they are not in ApS)

svar na (TS suvar na) zyotih RV SV VS TS MS KS asya sutasya svar na (AŠ ŠŠ na) AV SV AŠ ŠŠ AV MS Vait MS

āśīr na (MS MŚ nā) ūrjam anuttam ā ie maghavan nakır nu (MS nu) RV. VS MS KS The mss

of MS read corruptly nakrnu, p p nakrh, tu MS TB. (two variants in the same passage) vrtratūr no (TB no) §950. In the rest the alterant sound is not final in the preceding word

pra no naya vasyo acha RV . pra no naya prataram vasyo acha RV pra na (SV MS PB na) āyūnsı RV AV SV VS TS VSK MS

KS PB TB. TA AS. SS ApS Kaus N

pra na (SV na) indo. RV SV.

pra nah (SV. nah) pinva RV. SV

pra nu (TA ApMB HG nu, Kauś no, read nu) vocam cikituse janāya RV TA SMB ApMB Kauś PG HG MG. Jorgensen reads nu for SMB, but with v 1 nu, which should undoubtedly be read in accord with the usage of SV texts

pra no (also, no) jāyantām mithunām rūpašah Kauś (both)

pra no (TS† JUB. no) nvatave sura VS TS KS SB MS JUB Conc wrongly no for TS 5 5 7 5 Note JUB no, contrary to SV usage pra no (TB. no) navychus RV MS KS TB

pra no (AV TS no) yachatr aryamā RV. AV VS TS MS KS SB

pra no (AV. TS no) yacha (KS rāsva) viśaspate (AV viśām°, TS bhuvas°, VS SB sahasrajit) RV AV VS TS, MS KS SB

paraınan (AV onan) devah savıta dadatu RV AV

parı nah (SV nah) sarmayantyā RV SV

parı no (SV. no) asvam asvavıt RV SV

parı no (VS MS no) rudrasya. VS TS MS KS TB parı no helī rudrasya .. RV. VSK.. parı no hedo . RV

ataś cid indra na (SV. na) upa RV SV ŚŚ

ındra enam (KS enam) prathamo adhyatışthat RV VS. TS KS ındra enam (AV. enam) parāšarīt AV TB ApS

sam ındra no (AV. MS KS. Kauś no) manasā...RV. AV VS TS MS KS SB TB SS. KS Kauś

sumıtrā (etc.) na (KS na) āpa ..VS TS MS KS ŠB TB TA. MahānU AŠ ŠŠ. LS BDh ApŠ. KŠ MŠ

uruşyā no (MS no) aghāyatah samasmāt RV VS MS KS ŚB ApŚ. N. tebhih (RV also tena) somābhi (TA °bhī) rakşa nah (TA nah) RV. (bis) TA

śikṣā no (TS no!) ... RV AV VS TS KS AB Note that TS perversely avoids lingualization, despite its general tendency

devih (AV dai°, KS trayīs) sad urvīr uru naḥ (only RV nah, AV. ed nah, but read nah, see Whitney's note, KS.† nas) kṛnota RV AV TS. KS ApMB

asthūri nau gārhapatyam. MS KS: tayor (ApS. tayor nāv) asthūri (MŠ °ri nau) gārh° . ŠB KŠ ApS MŠ · asthūri nau gārhapatyāni ... Kauš asthūri nau (VSK no, ŠŠ no) gārhapatyāni VS. VSK. ŠB ŠŠ · asthūri no (TS TB no, KS nau, MŠ [van Gelder] †nau) gārhapatyāni santu RV. TS MS KS TB MŠ. In the first-quoted version, the two best mss of MS read nau, in accord with MS usage, but the MŠ form of it (tayor etc.) has nau according to all Knauer's mss

6951. (2) The n occurs in a longer word, or in the second part of a compound, the alterant being in the preceding word or the prior member of the compound Note that in compounds initial n is nearly always. and medial n often, lingualized in the RV just as in simple words. Wackernagel I \$170

\$952. We begin with cases in which the n is initial Here lingualization is standard and regular in verb forms from roots in n-compounded with pra (and certain other prepositions, Wackernagel I §169) SV shows three times forms of pra-nu with dental n, it is therefore exceptional But otherwise, with independent words, lingualization is Among the variants, TS twice lingualizes the n of only sporadic nāman; and the n of nāsatya is twice lingualized, once in VS and once in MS. (1 despite the tendency of MS to avoid lingualization)

abhi pra nonumo (SV no°). RV SV SV abhı pra nonuvur (SV. nonavur) RV SV tvām abhi pra nonumah (SV no") RV SV KB RV. TS MS KS pra nāmāni (TS nā°). athainam jarimā nayet HG yathainam jarase nayāt AV AV TS MS KS tasmād vār nāma (TS nāma). gomad ū su nāsalyā (VS nā°) RV VS AŚ

nāsatyā (MS nā°) bhrsajāśvinā VS MS TB Preceded in all by bhisan, which may be meant for part of this pada

punar ãadh punarnava (AV "nava, and "navah) RV AV (bis) uşiro ghrnīvān vārdhrīnasas (MS ghrnāvān vārdhrānasas) VS MS ·

grdhrah sitikaksī vārdhrānasas (KS ms vārhīnasas, ed em vārdhrī°)

.. TS KSA

sahasranīthah (SV ° nīthah) padavīh kavīnām RV SV

§953. Of the rest, in which n is not initial, there are only a few sporadic cases

The form omna sādhyebhyaś carmamnam (VS °mnam) VS VSK TB

occurs in RV agne deva panıbhır viyamānah (MS MS °nah; VS SB guhyamānah

KS 1dhyamānah) VS TS MS KS SB MS TB ApMB HG abhūr āpīnām (HG onām, v 1 onām) dyutadyubhir namasyair iyana MS mitajñubhir namasyair iyana RV VS VSK TS MS KS SB devaśrih śrimanāh (VSK TS °nāh) agneh purīsavāhanah (MS purīsya°, VS † SB † °vāhanah) VS TS MS

§954. (3) The alterant is in the same part of the same word as the n, ks šb so that lingualization would be expected The variation is due

(a) to secondary origin of the alterant sound, due to sandhi, in some texts the analogy of the uncompounded word keeps the *n* dental susumnah (TS N. onah) sūryarasmih VS TS MS KS SB In TS

N there is thought of the simple sumnah

(b) to the use of the word as first member of a compound, in one text the n, in the seam of the compound, is felt as final and hence not lingualized, while in the other it is treated as internal and lingualized amrnmayam (ApS amrn°) TB ApS

FINAL S AFTER NON-a VOWELS, BEFORE INITIAL t

§955. On this point the various schools show markedly different tendencies. As to the Prātiśākhya rules RPr 349 requires s regularly before tvā and te (but cf 356), and 350-354 allows it also before other words, mostly pronouns. APr 2 S4, 85 also makes s the rule especially before pronouns, but allows various exceptions, according to Whitney, s is commoner in AV VPr 3.75, 76 (cf. 79ff) likewise makes s the rule particularly before monosyllables (mostly pronouns). TPr 6.5 allows the change to s in only a few specified cases

§956. Wackernagel I §286b says that the change to s occurs, outside of compounds, mainly before pronouns, and 'die andern Samh kennen solches s im Satz ausser in den mit dem RV gemeinsamen Stellen nur vor Pronominalformen'. This statement is copied by Macdonell 78, 2, b. It is, however, not quite correct, as is shown by the following two variants, in which SV shows s for RV s, not before pronouns. These are, incidentally, the only variants where this sandhi occurs before other than pronouns.

dhanuş tanvantı (RV dhanus ta°) paunsyam RV SV. uşā apa svasus tamah (SV †svasus tamah) RV AV SV AŚ

§957. All the other variants concern cases with following pronouns (Cf agnes tvā tejasā sūryasya MG, to which the parallels in other texts show s, because no pronoun follows agnes tejasā sūryasya. MS KS AB TB TA) They show that the schools of RV, AV, VS, and TS follow fairly well the rules of the Prātīšākhyas to their respective Samhitās To be sure, only one case happens to concern RV, and that is exceptional in showing s, but the RV school texts show 12 cases of s to 1 of s AV shows 4 of s to 1 of s, and its school texts 3 to 0 VS has 17 to 2, and other Vāj texts (incl VSK) 22 to 1 TS, on the other hand, is unanimous for s (24 cases), and so are its school texts (28 cases) This is the only school which, on the evidence of the variants, overwhelmingly prefers s but KS also has 14 of s to 8 of s SV itself has

only one instance (of $\mathfrak s$), and its school texts have 2 of each MS is as unanimous for $\mathfrak s$ as TS is for $\mathfrak s$ (20 cases, and 16 from MS and MG) Summarizing the schools of RV, AV, VS, and MS regularly write $\mathfrak s$, that of TS always, and KS usually, $\mathfrak s$, the variants from SV are indecisive

§958. There follows the list of variants, all before pronouns

ansur-ansus te (TS KS ApS °sus te) deva somā pyāyatām VS TS MS

KS AB GB ŚB AŚ ŚŚ Vait LŚ ApŚ MŚ agnis te 'gram (MŚ agnis te agram) TS MŚ

agnış te tanvam . MS agnıs te tanuvam (KS tanvam) TS KS TB

ApŚ agniş te tvacam VS ŚB KŚ
agniş te tejo AŚ MŚ agnis te tejo TS TB JB ApŚ
agniş te (TS agnis te) 'dhipatih VS TS MS KS ŚB
agniş tvābhi (TS agnis tvā) pātu. VS TS MS KS ŚB
agniş tvā (TS KS agnis tvā) śrīnātu VS TS MS KS ŚB
agnis tvā (MS agniş tvā) hvayati TS MS KS TB
agnis tvā (agnis tvā) hvayati TS MS KS TB
agnis tvā (agnis tvā) hvayati TS MS KS TB

agnış ftan agre MS. agnış tān (AV tān, TS TA [but not KS f]
ganıs tān) agre AV TS KS TA

agneş tvā (KS ApS agnes tvā) tejasā sādayāmı VS MS KS SB ApS KS MS.

agne; tvā (TS KS. agnes tvā) mātrayā TS MS KS MŚ agnes tvāsyena (TS ApŚ. agnes tvā°) VS VSK TS GB ŚB KB

SS LS ApS

adding te (TS KS TA ApS "hs te) VS TS MS KS SB TA ApS

KŚ MŚ

adstrz tvā (TS KS ApŚ [but not MŚ †] *tis tvā) VS TS MS KS

SB ApŚ MŚ KŚ

avatatya dhanuş tvam (TS KS NilarU "nus tvam) VS TS MS KS

MŠ NilarU zopāya mā (VāDh mām) ševadhis te (N °dhiş te) VāDh ViDh N kābhiş (vam (KS TA tābhis tvam) ubhayībhih samvidānah MS KS TA ebhiş (vam putram janaya ŠG tais tvam putram (putrān) vindasva

AV ApMB dyauş tvā (ŠŠ dyaus te) prtā prthrvī mātā AV ŠŠ orajāpatrs tvā sādayatu VS ŠB MS MŠ prajāpatrs tvā sā°

TS TB TA ApŠ KS
rajāpates tvā (MŠ °teṣ ṭvā) prānena TB ApŠ MŠ
rabhos te (SV °bhoṣ ṭe) †satah RV SV
bahıs te (AV KS bahış ṭe) astu AV TS KS ApŠ
rhaspateş tvā (TS TB °tes tvā) VS VSK TS ŠB TB

brhaspatīs tvā (TS KS ApŚ °tīs tvā) sumne VS TS MS KS ŚB. ApŚ MŚ

brhaspatış ivā (SMB HG °tıs ivā) nıyunaktu . AG ŚG. SMB HG MG

brhaspatiş tvā (TA °tis tvā) višvair . MS TA. brhaspatiş tvā (TS ApŚ °tis tvā) sādayatu . TS MS ApŚ MŚ brhaspatiş tvopasīdatu (TA ApŚ °tis tvo°) MS TA ApŚ MŚ manoş tvā MS KŚ. MŚ: manos tvā . KS TB ApŚ varūtrīş tvā . VS ŚB varutrīs tvā . KS

vāyuş †tān (MŚ tan, KS ṭān, TS TA vāyus tān) agre . AV TS KS TA MŚ

vāyuş te (TS vāyus te) 'dhipatih VS TS MS
vāyuş te (TS vāyus te) vājin yuñ TS KSA
vāyuş tvābhipātu (TS vāyus tvā'). VS TS MS KS ŚB
śwebhir arcibhiş tvam (TS. °bhis tvam) VS TS MS KS ŚB
savitus tvā (AG ŚG °tuş tvā) prasava. VS ŚB KŚ AG ŚG
svadhitis te (ŚG °tiş te) pitā VS ŚG ApMB

FINAL S BEFORE INITIAL k AND p

§959. Here the rules of the Prātiśākhyas ($_{\sim}$ lPr 260 [4 14] ff, APr. 2 62ff, TPr 8 23-35, VPr 3.10f, 20ff, especially 29, 36) give a mass of detailed prescriptions, which may be summarized thus. in compounds s (or ş after non-q vowels) prevails, otherwise h (or upadhmānīya and phvāmūlīya) But there are numerous exceptions to both parts of the rule

§960 European grammarians have added practically nothing (cf Macdonell 78 2, c) Wackernagel I §286c, β , note, thinks he detects a tendency for the ending of the first part of an amredita compound to be made like that of the second part, so as to make the two exactly alike in form, where that is possible

§961. Among the variant formulas we find only one which concerns an amredita, and very few others concerning compounds. They show no clear tendency to be treated differently from uncompounded words, but in view of the traditional distinction just mentioned, we shall list them separately. The sole amredita noted is the following.

paruṣah-paruṣas (KS paruṣas-paruṣas, TS TA MahānU paruṣahparuṣah) parī VS TS MS KS ŚB TA MahānU Note that in the VS and MS schools the final sound is dissimilar in the two parts of the compound, altho a p follows in both cases, and that the distinction made by these schools is exactly the reverse of that laid down in the Pratisakhyas, namely: we find h in the prior member, s in the last member. VPr. 3.36 mentions this as an exception; likewise TPr. 8.33, which states that h remains in compounds when the following vocable contains s or dh, covers the case; this might be regarded as a kind of dissimilation, but is probably merely an artificial rule made up to cover actual occurrences.

§962. The other compounds noted are the following (in the first the s is preceded by a, in the others by i or u):

sādyaskrīš ... ApMB.: sadyaķkrīš ... \$G.

éociekesam (MS.* éocih") purupriya RV. VS. TS. MS. (both) KS.

upahūto bhūyasi haviskarane (MS. havih°, but p p. havis°) MS. AS. SS.: bhūyasi haviskarana upahūtah (TB.*°tā) TS. TB. SB.

āvukrd āvuhpainī ... Ap\$.: āyuşkrd āyuşpainī ... AV.

§963. In uncompounded words, contrary to the statements of the Prātišākhyas, the variants indicate if anything that s or s is commoner in most texts than h. Perhaps, however, the numbers are not sufficiently large to justify such an inference The Taittiriya school, to be sure, seems definitely to prefer h, especially after a-vowels; but most other schools show a majority for s or s in both groups (curiously, and perhaps by mere accident, the Maitrāyanīya school shows a majority for s after a-vowels, but for h after others). We give the lists for what they are worth, separating the two classes The statistics for all occurrences among the variants—including the few cases of compound words mentioned above—are as follows:

thought about and	After a-vowels		After non-a-vowels		
	ħ	E	ķ	ş	s (dental)
RV.	7	9	3	12	
RV. school	5	12	1	2	
SV.	5	4	3	2	
SV. school	1	3	1	3	
AV.	4	7	1	8	
AV. school	0	4	0	1	
VS.	3	15	5	7	
VS. school	3	16	4	8	
TS.	21	2	2	4	_
TS. school	24	7	16	6	2
	6	15	10	5	1
MS.	2	2	5	1	1
MS. school	9	9	5	7	1
KS.	Õ	2	0	1	
Others	•				

	After a-vowels		After non-a-vowels		els
	h	8	h	ş	s (dental)
Total RV. school	12	21	4	14	
Total SV. school	6	7	4	5	
Total AV. school	4	11	1	9	
Total VS. school	6	31	9	15	
Total TS school	45	9	18	10	2
Total MS school	8	17	15	6	2
Total all texts	90	107	56	67	5
Total all minus TS school	45	98	38	57	3

1. The s is preceded by an a vowel

§964. Here s remains in a majority of variants in all schools except that of the Taittiriyas, the latter is nearly unanimous for h Besides the two cases concerning compounds (§§961f), the following occur. somah (SV somas) patī rayīnām RV. AV SV.

sa no dwā sa rīṣah (VS MS. rīṣas) pātu naktam RV. AV. VS TS MS KS TB

śam nas (RV nah) karato aświnā RV. TB Ap\$

manyāsai šam ca nas (TS nah) kīdhi VS TS. MS. KS AŠ ŠŠ. N.

devīh (davīh) şad...uru nah (nah) kṛṇota RV. AV. TS. ApMB.. trayīş şad...uru †nas kŗ° KS

uru kṣayāya nas (TS. nah) kṛdhi RV AV. VS VSK. TS MS. KS. SB. AS. SS.

varivas (RV. °vah) krnvan .. RV. SV.

ayam no agnır varwas (TS KS AS. ApŚ °vah) krnotu VS. TS MS KS SB AS ApŚ MŚ

urvī rodasī varīvas (TS. KS °vah) kr° TS. MS KS

dıvah (VS dıvas) parjanyad ... VS TS MS KS

dıvah prihıvyāh pary antarıkşāt TS KS TB ApS dıvas etc RV. AV. MS

dwah prihwyāh pary oja udbhriam VS TS KSA. dwas etc RV. AV. Vait Kaus

dwah prziham svar (swar) . TS MS KS : dwas etc AV. VS SB dwas (SV dwah) prziham adhi RV SV

divas (SV divah) prsthany AV SV.

divah (RV divas) prsiham (PB °ihe) ... RV PB TA Ap\$

abhı prıyā dıvas padā (SV. dıvah kavıh) RV. SV.

agne tvam sūktavāg . . . dwas (TS TB dwah) pṛthivyoh TS. (fragment) MS SB. TB. AS SS parameşihî tıā sādayatu dwah (VS. SB. dwas) prsthe...VS TS MS KS SB ApS

śrnihi wśvalah prati RV.: Tśrnāhi viśtalas pari SV. Add to VV I §275 girir na viśvalas (SV. °lah) prihuh. . RV. AV. SV.

yathā nah śreyasas (TS °sah) karat VS TS MS. KS. SB. LS

yathā no vasyasas (TS °sah, LŚ. vasīyasas) karat VS TS MS KS. SB LŚ.

višvābhyo mā nāṣṭrābhyah (VS.† ŚB PG†°bhyas, MS. danṣṭrābhyas) pāhı (TS TB pāta, PG. parɪpāhı...) VS. TS MS ŚB. TB TA PG.

yeşām apsu sadas (TS ApMB sadah) kṛtam VS TS SB. Nīlar U
 ApMB † 2 17.6c

mıtrās (RV mitrah) pānty adruhah RV. SV.

pṛthwyāh sampṛcas (TS TB ApŚ °cah; VS ŚB. samspṛśas) pāhi VS. TS MS ŚB TB. ApŚ AŚ.

nānā hi vām devahitam sadas (TB ApS sadah) kītam VS MS. KS AB. SB. TB ApS AS.

diva oşadhayas (TS. oyah) pari RV. VS TS. MS.

ubhe ca no (etc)...añhasah (MS SB.† AŚ. °sas) pālām (TB Conc syālām, Poona ed. añhasah spālām!; AŚ. text, †añhasa syālām) MS SB. TB. AŚ. ŚŚ

ındrah (ŚŚ ındras) patis ... AV. AA ŚŚ

ıdāyās (ApŚ ıdāyāh) padam...AV. AŚ. ApŚ MŚ SMB. Vait Kauś apah (TS. TB ApŚ apas) pinva VS TS. MS. KS. ŚB TB. KŚ ApŚ.

MS. Note the perverseness of the Tant texts in reading s, contrary to their usual rule, against all other texts!

agne irālar rias (SV. riah) kavih RV. SV.

pūsādhvanah (VS. KS SB °nas) pātu VS TS MS KS SB Ap\$ prāņasya tvā ... tanuvah (MS tanvas) pāhi MS TA praitu brahmaņas (MS °nah) patnī TS Ap\$ M\$. san marvīr anhasas (S\$. °sch) pāntu ... SB A\$ S\$ Ap\$

2. The s is preceded by a non-a vowel

§965. Here the variants are less numerous, and there seems to be a larger element of chance. In general, however, ε prevails The dominance of h in the Tait school is less marked; TS itself has only half a dozen variants, a majority of which happen to contain ε . More curious is the fact (which may be accidental, since the total number of cases is not very large) that the Maitr. school this time favors h, the after a-vowels it shows a majority for ε . Nevertheless, in the three

variants where the preceding vowel is an τ -vowel, MS alone shows s, other texts h These all concern the single form $n\bar{r}n$, acc plur of $n\tau$, the vowel $\bar{\tau}$ alters the s across the intervening nasal which becomes anunāsika (cf. §940 above)

hotā yakşad uşāsānaktā . nīnh (MS nīns) patībhyo . . MS KS TB hotā yakşan narāšansan nīnsastam nīnspranetram (TB. nīnh) MS TB nīnh (MS nīns) pāhi RV SV VS. MS) KS ŠB.

§966. Anomalously, dental s is preserved without change in two variants, both times before a form of root k_T (does the form sk_T exercise an influence here?)

suprppalā osadhīs (ApŚ dhīh) kṛdhi MS KS ApŚ MŚ.

sam agnir agnibhis (RV °bhih) karat RV. TB ApS

§967. Besides these and the cases concerning compounds (above, §962), we find the following variants:

dyauh (RV. dyaus) pitah pṛthivi mātar adhruk RV MS. TB.

dyauh pitā... TB ApS: dyaus pitā . AV.

dyauh prelham prihivī šarīram ŠŠ 10 17 4 (as two separate mantras):
dyaus prelham antariksam . . ŠB KŠ

upahūto dyauş (TB. ApS. dyauh) pitā VS SB TB. ApS

upa mām dyaus (TB ApŚ dyauh) pītā hvayatām VS ŚB. TB. ApŚ. 190tis (MS LŚ 190tih) pasyanta (MS tā) uttaram RV MS KS ChU.

LŠ nyotis (SV. °tih) pašyanti vāsaram RV. SV KS

yas tānı veda sa pıtuş (VS and most mss of AV pıtuh) pıtāsat AV. VS: yas tā vıjānāt sa pıtuş (TA. savıtuh) pıtāsat RV. AV TA N: yas tad veda savıtuh (MahānU sa pıtuh) pıtāsat TA. MahānU

aham id dhi pituş (MG. pituh) pari RV AV SV Vait MG

sa idhāno (KS ms edh°, ed. emends) vasuş (MS vasuh) karıh RV SV. VS TS. MS. KS.

havış (HG MG havıh) krıvanlah parıvalsarınam (HG † SMB.† °nām, MG °yam) AV SMB ApMB HG MG

yasya dvārā manuş (SV manuh) pitā RV SV.

mṛtyoh (VSK. °yoş) pāhi VS. VSK MS KS SB MS

citrah śiśuh (MS śiśus) pari ... RV. VS. TS. MS. KS SB

āyoh paimane svāhā KS.: āyoş paivane svāhā ApŠ

ārīş (MS ārīh) kīnuşva dawyāny agne RV VS TS. MS KS

apālām . trīs (ApMB MG trīh) pū° RV. AV. JB. ApMB MG. parne vo vasatīs (TS MS °tīh) krtā RV. VS TS MS KS SB

nıh kravyādam nudāması (MS nudasva) AV MS · nış kravyādam sedha VS TS. KS SB TB ApS : nış kravyādam anīnasat RV.AV.MG. [szāduş (AV. °duḥ; but most mss., SPP., and Whitney °duş) kilāyam madhumān viāyam RV. AV. AB. Apš.]

ALTERATION OF FINAL " BEFORE & AND D

1968. Among the variants occur only three pādas belonging here, and they all concern the word exarpati. This occurs in that form in RV. (three times), AV. and KS. (once each), while in SV. (three times) and PB. (once) it occurs in the form scalpati. This accords with RPr. 258 (4.12), which requires exar before any voiceless sound in composition (otherwise i). APr. ignores the case, which does not come within its purview since it occurs in Book 20, which the Pr. does not treat. The pādas are:

yuvam hi sthah svarpatī (SV. PB. svahpatī) RV. SV. PB. dātrasyāgne svarpatūh (SV. svahpatīh) RV. SV. KS. svahpatīr yadī vydhe SV.: svarpatīm yad īm vydhe RV. AV.

FINAL & BLIFORE INITIAL SIBILANT (NOT FOLLOWED BY A CONSONANT)

\$969. In this case RPr. 251, 253 allows either h or retention of the sibilant, except in cases where the initial is altered to s by the influence of a non-a vowel preceding the final s, in which case the final s must be assimilated to s. A violation of this rule is permitted in Aufrecht's edition and Müller's edition princeps in the first variant quoted below, nileabaratio...; Müller's editions of 1873 and 1877 read nissah' in accordance with the Pr. rule. VPr. 3. 8 i. quotes opposing views of different authorities and does not decide between them; according to Weber the mss. of both VS. and VSK. generally write h. APr. 2. 40 requires assimilation of the sibilant, but according to Whitney the mss. of AV. generally write h, and the edition usually follows them. TPr. 9. 2 also requires assimilation of the sibilant, but Whitney says that the mss. of TS. generally write h, and this practice Weber seems to have reneralized in his edition.

§970. The few variants recorded in the Concordance indicate that in most texts s in these circumstances appears as h, whether absolutely final or in compounds. In KS however it is always retained or assimilated, according to Von Schroeder's edition (cf. his Einleitung, p. XII): the Concordance rarely takes note of this habit of KS, and it has not seemed worth while to collect such cases here. Among the variants, the RV retains or assimilates the sibilant in about half the cases (five in all); but in several of these Müller prints h instead. According to the Concordance (based on the Bibl. Ind. edition), TB. also

retains the sibilant three times; but in all of these the Poona ed. has h. ApMB. also retains or assimilates the sibilant (see Winternitz, p. xlviii); but again the Concordance usually ignores this. All other texts would seem to write h. [But it is impossible to say how much this is due to editorial systematization on the one hand, and on the other to the failure of the Concordance to record readings with the sibilant, which evidently did not seem to Bloomfield worth recording when he was preparing the Concordance. In this opinion I agree with him; and I consider the following list of variants of extremely slight value. F. E.] \$971. The following variants have been noted:

nuḥṣahamāno (SV. nuṣṣa°) yamate nāyate RV. SV. On the RV. reading see the preceding paragraph

vakşahsu (RV. vakşassu; but Muller °hsu) rukmā upašišrīyānāh RV. MS. TB.

vardhanam purumışşıdhe (SV. onihsidhe) RV. SV.

prisutūrsu śravassu (AV. and Müller's RV. hsu) ca RV AV.

vrṣā na kruddhah patayad rajassv (AV. and Müller's RV. °hsv) ā RV. AV.

havır havışşu vandyah (SV. havıhşu †vandyah) RV. SV.

křivanta (TB. priyā ta) ā barhih (KS.† TB. °his, but TB Poona ed °hih) sīda RV. AV. KS. TB.

wto aranyānih (TB. onis, but Poona ed. onih) sāyam RV. TB.

upa nah (KS.† TB. nas, but TB Poona ed nah) sūnavo giraḥ RV. SV. VS. KS TB.

ıdam devānām ıdam u nah (KS. idam nas) saha TS. MS KS. TB. ApS MS.

salyā eşām (AG etā) āšişah (ApMB. °şas) santu ... VS. VSK. AG. SMB Kaus ApMB. HG.

FINAL S BEFORE SIBILANT PLUS CONSONANT

§972. RPr 255 (4. 12) prescribes the dropping of the s before sibilant plus surd consonant. So also VPr. 3. 12 TPr. 9. 1 quotes a rule of one teacher to the same effect, the comm. and Whitney regard this as intended to be binding, and according to Whitney the mss. of TS. generally follow it APr contains no such prescription, but the AV. mss. observe the practice in a majority of cases, and Whitney says that it has been observed uniformly in the Berlin edition (see his note on APr. 2 40). This appears to be not quite true; cf. the variants hotravidah stomatastaso ... AV. 18 3 47b, and madhvah scotanty ... AV. 20. 88. 3d

§973. None of the Prātiśākhyas authorize the dropping of final s before sibilant plus sonant consonant; but the comm. on TPr. 9 1 says that 'some' prescribe the dropping even then.

1. Final s before sibilant plus surd consonant

§974. The usage varies somewhat arbitrarily in manuscripts and editions, and it is not always clear to what extent editors have been guided by the actual readings of the mss Aufrecht's edition of RV follows the Prātisākhva rule, dropping s before sibilant plus surd; but Müller's edition always prints h, at least in the variant padas, and we believe otherwise Benfey's edition of SV. is apparently not wholly consistent, of the two variant padas noted, one drops the s. theother reads h. On AV see above, \$972 In TS, Weber's edition apparently always drops the s; at least the variants record no contrary case same is true of Weber's edition of VS. Von Schroeder's edition of MS always prints h; but the editor tells us (Einleitung to Vol 1, p XLII) that this was done in defiance of his mss, which generally follow the custom of most texts and drop s. On MS. and MG cf. Knauer, Emleitung to MG, p xxxviii, it appears that the mss. of these texts vary greatly, but that Knauer undertook to print h generally; among the variants we have noted only one case where he failed to do so, yas te drapsa skandah MS 2 4. 3. 29a. The mss. of KS usually, and von Schroeder's edition apparently always, keep the final sibilant, assimilating it to a following palatal or lingual sibilant; in most cases the Concordance ignores this habit of KS, quoting its readings with h like those of MS

§975. Most other texts seem usually to drop the s, at least in the repeated mantras. But evidently the mss of many of them are inconsistent. It will be noted, in our list of variants, that TB especially varies, seemingly at random, and that the Bibl. Ind. and Poona editions are often at variance on the point. SS likewise shows a number of cases of h where other texts drop the sibilant. Instructive is the repetition in the same text of SG. of the mantra mā no hinsīh (hinsī) sthawiram., with and without h; we must assume that so careful an editor as Oldenberg followed his mss. in both cases, and he reports no v l to either

§976. [In recording the variants on this point, I have taken the liberty of applying certain paribhāṣā rules. It would certainly have been futile to record individually all the cases in which Von Schroeder and Knauer insert h in MS, MS, and MG against the evidence of their mss.

Likewise in the case of KS there would be no point in recording every occurrence of the retained or assimilated sibilant, altho in this case the editor appears to have followed the general custom of his mss. The Concordance itself, as stated above, usually ignores this habit of KS When, therefore, in the following list, a variant is stated to be found in MS, MS, MG, or KS, it is to be understood, in default of statement to the contrary, that the printed editions of the three first-named texts read h, and that of KS reads s (or s, s when these sibilants follow). Likewise in quotations from the RV, it is to be understood that the form quoted, without sibilant or h, is found in Aufrecht's edition, while Muller's edition in every case reads h—I would add that in view of the evidently arbitrary way in which this matter is treated both in mss. and by editors generally. I cannot attribute very much significance or importance to the variants recorded -F El

§977. The list of variants concerning final s before sibilant plus surd—to be interpreted in accordance with the paribhāsā just stated is as follows.

pra tad vişnu (TB Poona ed vişnuh; AV † vişnu; SS [pratīka] † pra tad visnur iti] stavate. . RV. AV VS MS KS. SB TB AS. ApS. SS NrpU

ya (ŚŚ yah) strīnām . . . VS TS KSA. ŚŚ

vișno (TB vișnoh) stupo (stūpo) 'si VS TS MS KS SB. TB ApS. MS. visno (TB visnoh) sthānam asi VS TS MS KS SB. TB. ApS. MS

samsrāvabhāgā (or, samsrava°. TB. °bhāgāh) sthesā... VS TS MS KS SB TB MS

hula (TB hulah) stokah TS MS KS TB Ap\$ M\$

hotrāvīda (AV. vīdah, TB vīdha, Poona ed. vīdhah) stomatastāso . . . RV AV. MS TB.

uprca (TB Poona ed 1 3 3 6 °cah) stha VSK KS. SB. TB. (both readings) KS ApS. MS The same with samprea ...

andha sthāndho... VS. SB KS. ambha (ApS ambhah) sthāmbho... TS, MS KS ŠŠ ApŠ MŠ MG

ā na (ŚŚ naḥ) stuta ... RV ŚŚ.

āyu stha ApS: āyuh stha TB

rtava (TB °vah) stha . . . VS KS. SB. TB

ındravanta (AB °tah) stuta (studhvam) AB GB. Vant

diva (TB. divah) skambha° . . . VS VSK KS. TS SB TB ApS.

pra va (KB. ŠŠ. vah) spad . . . RV KB ŠŠ

prohṣitā (TB. Conc °tā and °tāh, Poona ed both times °tāh) stha VS. TS. MS KS TB. SB. KS MS.

balavıjñāya (SV. °yah) sihavırah...RV. AV SV. VS TS MS. KS brhadbhir vāja: (TB. Poona ed vāja:h) sihavırebhir...RV. MS. KS TB brhaspai: (TB. Conc °ti and °tih, Poona ed. both times °tih) slotram VS. MS. KS. TB

madhva (AV. °vah) scotanty . . . RV. AV.

mā no hinsīh (and, hinsī) sthawram . . . \$G (both)

mānta (Apś. māntah) sthur . . . RV AV. AB JB. Apś. Mś.

mā na stena...RV. KS.: mā va (TB. Poona ed. va and vah) stena ...RV. AV. VS. TS MS. KS SB. TB.

yas te drapsa (SS. Vait. drapsaḥ; MS drapsa) skandatı... RV VS TS KS. GB. SB. Vait MS SS.

ye devā devasuva (TB. °vah) stha . . . TS TB.

vāyava (TB. °vah) stha VS TS. MS KS. GB. SB. TB KS. ApS MS upāyava (TB °vah) stha TS. KS. SB. TB KS ApS

prāṇaḥ sthaḥ TB.: prāṇa sthah ApS.

stokā (TB Poons ed. stokāh) ścotantı . . RV. MS. KS. AB. TB.

subhūtakrta stha ApŚ.: suhutakrtah stha AŚ

sŭryatvacasa (TB. Poona ed °sah) stha VS. TS MS KS SB TB MS gura (ApS. gurah) stomāsa īrate RV. AV. SV. MS ApS

cakşu (TB. cakşuh) sthat . . . TB ApS

cıta (TB. cıtah) stha TS. MS. SB TB. ApS MS

cita (ApS. once out of four times, and TA twice out of three times acc to Conc., all three times acc. to Poona ed, citah) stha pari...

VS. TS KS TA. ApS. KS.

prati tvā diva (TB. dwah) skambhanır vettu (TB Poona ed †vetu) TS. TB.

[trınave †maruta (Cone. °tah for VS) stutāh (°tam) VS. MS. KS.]

[dhruwam ası dhruvata (Conc. °tah for ApMB) sthitam ApMB. HG]

2 Final s before sibilant plus sonant consonant

§978. Here the regular usage of nearly all texts, and the prescriptions of all the Prātišākhyas, require h In KS, just as before sibilant plus surd, the final s is retained, or assimilated to an initial palatal or lingual sibilant, again, as in the preceding group, the Concordance usually ignores this, and quotes KS as reading usarga like other texts. The only text noted which regularly drops the final s is ApMB, see Winternitz's Introduction, p xivin—It appears, however, that the mss of some other texts show the same dropping of s not infrequently. Especially is this true of AV; see Whitney's note on APr 2–86, and on his Translation of AV, 6–121–1—The Bibl Ind. editions of TB and TA show the dropping of s a number of times, but the Poona editions of the same

- works print h in most of these cases. There is even one case in MS which seems to have eluded the editorial vigilance of von Schroeder: syonā (for syonāh, so ApŚ) syonena ghrtena mā samukṣata, MS. 4. 2 5. Otherwise the variants which show lack of h are rare and sporadic
- §979. [Again, as in the preceding section, the following list is to be interpreted with two paribhāṣā rules, viz: 1 KS. always retains or assimilates the sibilant, tho this fact is usually not recorded in the Concordance.—2 Variants in which the sibilant is dropped in ApMB alone are excluded from the list, since this dropping takes place universally in that text—F. E].
- §980. The variants of final s before sibilant plus sonant consonant are as follows:
- svapnah svapnādhikarane RVKh.: svapna svapnābhikaranena AV. The latter is to be understood with svápna(h) nom., not voc.; Edgerton, AJP 35 438ff.
- medasah (VSK. °sa) svāhā VS. VSK. MS TB
- yā devy asīstake prānadā ... cakṣurdāś (ApŚ. °dā) śrotradā ... dyaurdās (ApŚ. °dā) svardāh ... KS. ApŚ : yā devy asīstaka āyurdāḥ ... cakṣurdāh śrotradāh MS.
- samjñānam nah (TB. na, but Poona ed naḥ) sve° ... RVKh AV. MS. KS. TB
- ādityebhyaḥ preşya...mahasvasarasya (MŚ mahaḥ sva°)...ŚB. MŚ. ApŚ. See Knauer's note, and pw., Addendum to Vol. 5, s v. mahasvasara.
- avidahantah (TB. °ta) érapayata TB. Ap\$. M\$.
- uşasah śreyasī
h-śreyasīr dadhat ${\rm ApS}$ · uşasa śreyasī-sreyasīr dadhat TB. Con
e , but Poona ed as ${\rm ApS}$
- jyog ajītā (MŚ. jīvā, SMB jītā, but Jörgensen ajītā) ahatāh (SMB. °tā) syāma TS KS MŚ. PG SMB
- śrotrapāh (AŚ °pā) śrotram ... TS MS AB AŚ.
- svar (TS. ApS. suvar) na (TS ApS na) gharmah (ApS.* °ma) svāhā VS. TS KS SB ApS. (both)
- stutah (TB stuta, but Poona ed stutah) éravasyann . . . RV. MS. KS. TB. syonāh (MS. °nā) syonena ghriena mā samuksata MS ApŠ
- supānih (TA °ni, but Poona ed °nih; ŠŠ subāhuh) svangurih VS TS. MS. KS ŠB TA ŠŠ
- citish (TA. °is, but Poona ed °ish) sruk MS. TA SS MS
- paro martaḥ parah (ApŚ all mss , and TB Conc. para, but TB. Poona ed. parah) śvā VS TS MS KSA TB. ApŚ MŚ
- pary āvarte duşvapnyāt (KŚ duhşva°, v 1 duşva°) AV. KŚ See Whitney's note on 6 121 1c for the spelling of this word in the AV. mss.

duşrapnyam durilam nıh (AV. *ni) şvāsmat AV. (both). Whitney, however, would read nih in both places—with the Prātišākhya, but against nearly all the mss

duşvapnahan duruşyaha (Poona ed. duşsvap^o duruşşaha) TA . duhsvapnahan duruşrahā MahānU Cf preceding two

aslonā (AV. comm. asro°) aūgair ahrutāh (TA aslonāūgair ahrtā, Poona ed ahrutāh with v. 1° tā) svarge AV TA.

snuṣā sapainā (TB. comm. and Poons ed. text anāh) śraśuro 'yam astu (AŚ 'ham asmi) TB AŚ sapaināh, nom pl masc (!), seems to be intended in both

INITIAL S VARYING WITH S

§981. Nothing approaching general rules on this subject comes out of the Prätikäkliyas (RPr. 318 (5 1) ff, APr 2 96 ff, TPr 6 1 ff, VPr. 3 58 ff) The variants hardly throw much new light on the excellent treatment in Wackernagel, I §\$204-7 In practically every case the altered s is preceded by an i or u vowel; TS reads rksama for rksama of other texts (§985), and in a few cases s appears after avowels, always owing to the influence of analogy from other words where an i or u vowel occurred (§984) Visarga after i or u does not interfere with the alteration. Wackernagel I p. 237, bottom.

§982. In compound verbs the change was regular in all texts (Wackernagel I §204), and we find no variants except one or two compounds of the copula (§987), and except forms where the augment intervenes between the altering sound and the initial s In these latter cases s is extremely rare in RV, but becomes common in the other Samhitas (Wackernagel I §205a), two of our variants show a under such circumstances for RV. s (§983). The largest group of variants concerns noun compounds Here the conditions are confused, the change is quite common, yet by no means universal, in all periods of the Vedic language (Wackernagel I §206). We find in the variants no evidence of school or other tendencies; earlier s is replaced by later s and vice versa, so far as we can see quite at random. Next comes a somewhat smaller group of cases in which 'light words', monosyllables or forms of the copula, are concerned Lingual s in these is common in the RV, but relatively rare later (Wackernagel I §207), accordingly we find that in most of our variants a later text substitutes s for earlier (generally RV) 8; but the reverse is also found (§987) Finally, there are a very few sporadic cases of longer uncompounded words, in these the change is very rare in post-Rigvedic language, yet our variants show at least one case of s in TB substituted for s of RV. (§988)

§983. The following are the variants concerning augmented forms of compound verbs. As stated above, there are no other variants of compound verbs except a few of the copula, see §987.

vy astabhnā (VS ŠB askabhnā, MS askabhnā, KS asṭabhnā, TS. askabhnād, TA. asṭabhnād) rodasī . RV. VS VSK TS MS. KS. ŠB TA

ād id dhotāram ny asādayanta (TB aṣā°) RV VS TB.

abhy asthām (TS KS ApŚ asthād, MS asthām) névāh prtanā arātīh AV TS MS KS MŚ. ApŚ.

tena dasyūn vy asahanta devāh TS KS : tena devā vy aşahanta satrūn AV yasmād bhīşā nyaşadah (ŚŚ nyasadah) TB. ŚŚ ApŚ

§984. Coming to noun compounds, we mention first the few anomalous cases in which an a vowel precedes, so that the change to \$\(\mathsigm\) is irregular. Four of them contain the Rigvedic words $prtana\tilde{a}ah$ (\(^\sigma^2\tilde{a}h, \(^\sigma^2\tilde{a}h)a^2\)), which are several times changed in later texts to the more regular \(^\sigma^3ah\) etc. Whitney's statement (Grammar, 186a) about this form is not correct, as the variants show. The \$\(\sigma\) is evidently due to the analogy of compounds like \$\(^\sigma^2ah\), bhūrisah, abhīsah etc.—The only other case contains the TS form sastubh, which is obviously analogous to tristubh, anustubh, as noted by Wackernagel I \(^\sigma^{206}b\):

samstup (TS saştup) chandah VS TS MS KS SB.

ā vīram prtanāşaham (SV "saham) RV AV. SV.

tam agne prianāşaham (TS 'saham) RV, TS.

prianāsāhyāya (TB °sāhyāya) ca RV AV. VS TB.

uccarrvāji prtanāşāţ (HG °sāham) RVKh HG

§985. Twice in the same passage of TS occurs the stem rk_sama , for rksama of the others; this is the only case where the alteration is due to a preceding k (cf Wackernagel I p 237, top):

jagatyā rksamam (TS rkṣamam) VS TS MS KS.ŚB rksamāc (TS rkṣamāc) chukrah VS TS MS KS ŚB.

§986. The remaining cases concern a preceding i or u or diphthong In GB 1 5 25d, quoted in Conc as viskandham enam vidhṛtam prajāsu, Gaastra reads viṣkandham visṛtam

abhwīro abhrsatvā (KS 'satvā) sahojāh (AV MS † KS sahojīt) RV. AV SV. VS TS MS KS Many mss of AV, followed by the comm and SPP 's ed., also read abhrsatvā

stotā me gosakhā (SV. gosakhā) syāt RV AV, SV

pṛthwiṣadam (MS pṛthwī°, VS † °sadam) tvāntarikṣasadam (VS † adds, divisadam devasadam). VS TS. MS KS. SB TB deva savitah susāvitram (ApS suṣāv°) . . PB KS ApS.

rayısthano (AV. osihano) rayım asmasu dhehi RV. AV. susamiddho (RV, susa°) na ä vaha RV, SV PB, LS. susamiddho (KS TB. susa°) varenyah VS MS KS. TB. susamiddham (TB. suşa°) varenyam VS TB susadam (\$\hat{S}. susatuam) id gavam . AV. \hat{S}. ye trışaptah (MS. trıs°) parıvantı AV. MS trışaptāso (TB. tris°) marutah . AV TB utkūlanikūlebhyas tristhinam VS: utkūlavikūlābhyām tristhinam TB.

amba nispara (TS. Ap\$ nisvara, KS nisvara, MS nismara) VS. TS. MS. KS SB. AnS In VS SB. divide nis-para; the rest belong

here.

somanetrebhyo . . . uparısadbhyo (VSK °şadbhyo) . . VS. VSK. SB ye devāh somanetrā uparısado (VSK. °sado) . VS VSK SB · ye devā uparisado (KS ° das) . MS KS.

vrazam gacha gosthānam (VS SB TB gosthānam, but TB. Poona ed ostho) VS. TS MS KS SB. TB Ans. MS

krsnagrīvah stitkakso 'ñnsakthas (MS 'sakthas) ta aindrāgnāh VS MS. añnsakthāya (KSA † °sakthāya) svāhā TS KSA

dusvapnahan durusyaha (Poona ed dussvapo durussaha) TA · duhsvapnahan durusvahā MahānU.

5987. Next we come to the group of monosyllables or forms of the copula. In one or two of these s of RV, is replaced by s in a later text: druhah pāśān (TS KS. pāśam) prati sa (KS sū) mucīsta RV. TS. MS KS.

apo su (MS. su) myaksa . . . RV. MS

But in most of them the change is in the opposite direction:

kīdhī sv (TS. sv) asmān .. RV TS MS KS

pratı şma (SV. sma) deva rīşatah (SV n°) RV SV MS KS TB

prati sma (AV. sma) raksaso daha (AV jahi) RV AV.

asti hı şmā (TS MS KS. astu sma) te suşmını avayāh RV. VS TS. MS. KS. SB.

vayam ghā te apı şması (SV. smasi) RV SV. anupūrvam yatamānā yatı sika (AV sika) RV AV. divî şañ (AV şan, SV san) chukra ātatah RV AV SV

dun sad (RV. sad) bhûmy ā dade RV SV VS

ūtī sa (SV. sa) brhato divah RV SV.

parı şya suvāno akṣāh RV . parı sya svāno akṣarat SV. cf parı sya suvāno avyayam RV.

tasmād āpo anu sthana (TS sthana) AV. TS MS. KS.

§988. Finally, we come to the few sporadic cases of longer uncom-

pounded words. Note that in the first a later text introduces s where RV. has s:

trīni šatā trī sahasrāny (TB. şa°) agnım RV. VS. TB.

ye apsu şadānsi (KS. 'psu sadānsi) cakrire MS KS.: teşām apsu sadas kṛtam RVKh.

apsu dhautasya te deva soma (TS. tr soma deva te) nrbhih stutasya (KS. nrbhis stu°, TS. PB. nrbhih sutasya)...TS MS KS. PB. The mss of MS. read nrbhi, which von Schroeder as always (cf. §974) changes to nrbhih; but the presence of final h, as noted above, would have no influence here in any event

pari bhrātuh pari şvasuh HG. ApMB.: pari mātuh pari svasuḥ PG vāyo ve (TS. ApŚ vīhi) stokānām (VSK °nām juṣānah, KS. sṭokānām) VS. VSK. TS. ŚB. ApŚ. KS † 3. 6 (with †ve, not veş).

SECONDARY CRASIS, AND HIATUS

- §989. Secondary crasis or double sandhi occurs rarely among the variants Most of the cases quoted below are capable of different morphological or lexical interpretations without assumption of double sandhi. There are however a few cases where it is clearly found, and we shall begin with one from MG, which according to Knauer (p. xxxviii f.) has it quite frequently:
- dhruvā strī patikule iyam (MG °kuleyam) SMB MG. In SMB, also, the v. l °kuleyam is recorded, as well as °kula iyam, which is the regular form and would seem preferable to the reading adopted by the editor, °kule iyam (with complete hiatus).
- uc chuşmā oşadhīnām (AV. chuşmauş°) RV. AV. VS TS. MS. KS. Whitney would 'probably' read chuşmā (for °māh) oş°; this is supported by Ppp, cf Whitney's note and Barret, JAOS 35. 50 f.
- viśvādītyāh [pratika] MG. This probably refers to the formula viśva (PG text †viśve, with hiatus) ādītyā vasavaś ca devāh (MG. sarve) AG. PG MG. All mss of MG (in the pratika) read viśvād.
- sahasradhāre 'va (AV. °dhāra eva) te sam asvaran RV. AV. KS. ApS. Whitney, note on AV. 5 6.3, suggests that RV. stands for °dhārāh, with double sandhi. The RV pp reads °dhāre, ava Oldenberg, Noten, would read avate as one word, keeping °dhāre of p.p. The whole verse is difficult and obscure

anāmayaidhi etc , see §344.

§990. All the remaining cases permit, if they do not compel, interpretations of both forms of the variant without assuming double sandhi.

They are, however, similar enough to the foregoing to be worth quoting in this context:

- ado ma āgachatu ApŚ . ado māgachatu MS KS MŚ. (not ApŚ which in 4. 13 8 reads †ma āga°)—In ApŚ. me, in the others mā
- māgadhah punšcalī kitaiah klibo 'šūdrā abrāhmanās (VSK....'šūdrābrāhmanās) te prājāpatyāh VS. VSK. Two separate words in VS, a compound in VSK. So also in the following; cf the section on False Divisions, which contains other somewhat similar cases that might perhaps also be mentioned here
- aslonā (AV. comm asro") aūgair ahrutāh (TA aslonāūgair ahritā, Poona ed. ahrutāh, v. 1 "tā) svarge AV. TA 'Unmaimed in limbs', or 'with unmaimed limbs'. Cf preceding
- ākrayāyā ayogūm VS.: ākrayāyāyogūm (so Poona ed text and comm)
 TB. Different genders: fem in VS, masc in TB.
- saha ojah (VS sahaujah; VSK sahojah) VS VSK. AB GB AS Vart In VS. VSK. saha plus ojas (on VSK.'s sandhi see §731); in the others, sahas plus ojas The latter form is probably original
- yathaika 18ir (KS °karşır) vijānate KS TA ApS See §919, end yā (MS. ya) 1şavo yātudhānānām VS TS. MS ŠB. NīlarŪ. ApMB yeşu vā yātudhānāh KS Serpents are referred to 'who are missiles of sorcerers' is certainly original, yet KS makes reasonable sense: 'either in whom are sorcerers'... (correlative with the following, which see). But it is clearly based on yā (or ya) 1şavo, mispronounced with secondary crasis
- §991. From a purely external standpoint, the variants concerning hiatus are indistinguishable from those concerning double sandhi or they may be called the converse of them—In the cases of double sandhi, the form with hiatus is regular, in those we are about to give, it is irregular. A fitting bridge between the two is formed by a group of variants in which a secondary text resolves a long vowel or diphthong incorrectly, leaving a secondary hiatus, or at least one whose historicity is questionable:
- uta śravasā (MS. śravasa ā) pṛthwīm VS TS MS TA. The p p of MS reads śravasah, ā; but both meter and sense show that the MS has a stupid blunder.
- yad ındra cıtra mehanā (SV. PB ma ıha na) RV. SV PB AS SS N
- vasneva (KS tasna iva) nkrīnāvahai VS TS MS SB AS. Since the uncombined form was a neuter nom -acc plur of an a-stem (vasna), it seems that we are to understand it as vasnā (so MS pp), rather

We have, then, in KS, perhaps a case of what may be called partial sandhi, that is shortening of a long vowel before a following vowel, as in \bar{a} -r = RV etc. a-r: cf. Wackernagel I §267b for such shortenings before other vowels than r. Otherwise KS. would be a mere blunder, like MS in the preceding Cf. the next.

sapatnā vācam manasā (AS. esa) upāsatām TB AS 'His (or. mv) rivals shall obey his (or, my) word with their minds'. Both texts must intend manasa: TB. has complete hiatus, while AS. (if the text is correct; we have not much faith in the edition) shows 'partial sandhi': see under the preceding variant. The meter is against fusion.

See also the variant praty eta vama (sunvan) etc. §357.

\$992. The rest concern cases of complete hiatus, except in so far as they may be capable of different formal or lexical explanations will be noticed that the meter sometimes favors the hiatus, as in the variant last quoted:

bhūyo vā atah somo rāzārhati (MŚ. rājā arhatī) SB KŚ ApŚ, MŚ. All Knauer's mss read thus for MS.: Knauer suggests pluti. The passage seems to be prose, but with hiatus as in MS it could pass for a fair jagatī pāda

pavasva deva āyuşak (RV. devāyuşak) RV. SV. PB. The accent in SV. (devá) indicates a nom. form; but Benfey translates a voc. In any case SV. is secondary, and metri gr.

pāpmānam uta vāgham (SMB. vā agham) SMB. ApMB HG. Another case of hiatus for metrical reasons

ā pūşā etv ā vasu TS: ā puşţam etv ā vasu AV. Hiatus for metrical reasons in TS.; in AV the meter is improved without fusion.

tatra ındro brhaspatıh VS.: tatrā (SV. tatra) no brahmanaspatıh RV. SV Hiatus metri gratia in VS

tan ma (Vast mā) āpyāyatām punah GB. Vait. Not only the hiatus, but the meaning of the verb is strange in Vait. Garbe and Caland take it with active meaning, which it has according to BR. only in one epic passage (Mbh 5. 508) In GB. (with me) there is no hiatus and the verb is intransitive, both improvements But if $m\bar{a}$ be read, hatus is necessary to give good meter.

sam tvā rınantı (Vait manti) LS KS Vait The hatus in Vait may be connected with pronunciation of r as r, see §676

punantu rşayah TA MahānU. Hıatus in both forms

darvyā hotārāgna (MS. °gnā, ŠŠ hotārā agna) ājyasya vītām MS. KS. AŠ SS Probably SS stands for hotārā, not °rāu, and therefore has hatus, see §885d. For hotārāu we should expect ${}^{\circ}r\bar{a}v$ in §§

achidrā usijah padānu takşuh TS: achidrosijah kavayah padānutakşişuh (see §627) KS. Keith, 'flawless abodes', as if achidrā went with padā as in KS; but TS pp achidrāh, with usijah, and so comm

abhīm (SV. abhī) riasya dohanā anūşata RV. SV. Cf abhīm riasya (SV. abhy rīstasya) sudughā ghriascutah RV. SV. On m as "Hiatustilger" see §309

pıtrbhyah svadhāstu (MahānU svadhā astu) TA MahānU

§993. With the last variant belongs the next group, all in like contexts; in them we might indeed think of nominatives of the radical \bar{a} declension (in $\bar{a}s$) varying with nominatives of the derivative \bar{a} declension in \bar{a} . But the uncombined forms occur only in Tait texts, and-according to TS pp. and TPr 5 2, 10 13, are to be regarded as uncombined forms of $-m\bar{a}$, without s.

māsi MS MS. mā ası TA ApS Likewise (in MS TA) pramā, unmā, vimā, sammā, pratimā.

sahasrasya pramāsı (TS °mā asi) VS TS MS KS. ŠB The same with pratimā, and sahasrasyonmā.

§994. The next is different in character:

manās (KS manā asi) VS TS MS KS SB ApS MS N. All texts have a curious feminine stem (the gender doubtless due to attraction to parallel feminines in the context) which is supposed, no doubt correctly, to mean the same as the normal neuter manas In KS it has the form of a feminine s-stem (nom manā's) In the others it becomes an ā stem

§995. The next group contains textually dubious cases:

pitaras ca upāsate (VS copā) RVKh VS The histus improves the meter, but Scheftelowitz reads copāsate, with all his authorities except the late Prayogaratna, which reads copa āsate, with histus in a different place


yā medhā apsarāsu (MG. medhāpsarahsu) RVKh MG The meter is better, tho still poor, with hiatus However, most of Knauer's mss read medhā apso in MG, and on the other hand Scheftelowitz reads medhāpso in RVKh without report of variant; he also reads opsarassu

devā brahmāna āgachata āgachata GB, Conc de bra āgachatāgachata tāgachata LS But Gaastra reads for GB āgachatāgachata, he notes a v 1 āgachatā āga.

withur withāvā suṣakhā (AV. sakha ā) sakhīyate RV AV. So the mss of AV, leaving sakha unaccented; SPP. follows them; the vulgate ed reads sākhā ā' It seems at least possible that the AV. mss correctly

present the Atharvan tradition; the verse is addressed to Kāma, so that a vocative sakhe is conceivable. If we were to accept the vulgate text, we should have a case of hiatus. Whitney in his Transl. assumes $s\hat{a}kh\hat{a}'$ (fusion of $s\hat{a}kh\hat{a}$ and \bar{a}').

- §996. The variants concerning the pronoun sa followed by a vowel constitute a special case. Here crasis was originally the rule, but (especially in late texts) there is a tendency to approach the Classical Sanskrit rule which requires hiatus. The variants are not numerous; in some of them the meter favors hiatus, notably in the first where the RV. itself (the it writes a combined form) seems by its meter to call for hiatus:
- semām (AV. sa imām) no havyadātim juṣānah RV. AV. VS TS. MS. KSA. Oldenberg, Noten, thinks that RV. should probably be read sa imām.
- agnir vidvān sa yajāt sed u hotā (AV. Kauś. sa id dhotā) RV. AV. TS MS KS ŚB. Kauś. Here both forms are metrically correct, since AV. omits the particle u.
- sa imām (ŚG. semām) devaḥ pūṣā (also aryamā, and varunah) ŚG AG SMB.
- soma āyuşmān sa oşadhībhir (PG. sauşa°) āyuşmān TS. KS PG ApMB This passage is prose. PG is hyper-archaizing





INDEX OF SOUNDS, SOUND GROUPS, AND LETTERS

Note -Here are indexed all sounds, combinations, and letters which are treated as varying from a phonetic or graphic standpoint. In so far as they have semantic significance, they are to be sought rather in the following Sanskrit Index For example, ā as a sound, and ya as a phonetic combination (which varies with z. I, and e), are treated here; but ā the preposition or privative prefix, and va the suffix, are listed in the Sanskrit Index All references in all the Indexes are to sections

```
c, epenthetic, 755, 763, elided before
                                              546-569, r, 641-3, J, 645; o, 713-9; au.
  e. o. 709, 731; sandhi of initial (after
                                              724, ra, vã, 739-742; ri, vī, 743
  e, c) S91-911, sandhi of final, with r.
                                            ur. and ar, 605, 615; r. 654
  913-7, 919 -and ā, 422-512; i, 570-
                                            uv and av, 601-4; v, 766-798
                                            ũ. and a, 621, ava, 750, ā, 619; ₹, 628,
  596; ī, 600, u, 601-618; ū, 621; r,
  631-4; a plus nasal, and ā, 300-2
                                              u, 546-569; r, 644; f, 644, o, 720-3.
aya: and e, 741-6
                                              au, 725-7; ra, 739; vī, 743
cyi: and ci. 747
                                            ūr and 7, 655
ar: and ir, 573, 575, ur, 605, 615, r,
                                            r, sandhi of, with preceding a, ā,
  647-651; rā, 806
                                              913-9 -and a, 631-4; ā, 632, 2,
cr: and uv. 601-4
                                              635-640, \bar{\imath}, 638; u, 641-3, \bar{u}, 644, o,
ara: and ū, 750, o, 748-9
                                              646; ar, 647-651; ar, 652; ir, 653; ur,
ari, are: and e, 747
                                              654, ür, 655, ra, 656-8, 660, 662-5,
a, sandhi of final, with r, 913-8 -and
                                              rā, 657-9, 661; ra, 666-676; rī, 677, ru,
  c, 422-512, i, 599, ī, 597-8, u, 620;
                                              678-684
  ū, 619, r, 632; prā, 873; a plus nasal,
                                            r and u, 644
  300-2
                                           ! and u, 645
\bar{a}y\bar{a} and \epsilon, 747
                                            e. and aya, 744-6, avi. ave. ava. 747; 2.
ār: and r. 652
                                              686-694; iya, 1ye, 747, ī, 695-8, a1, 703-
i, epenthetic, 751-764.—and a, 570-596;
                                              712; ya, yā, 803
  ā, 599, iya, 734; ī, 513-545; u, 622-7;
                                           ar and ayr, 747; i, 699-700; ī, 701-2,
  r, 635-640, e, 686-694, ai, 699-700,
                                              e, 703-712
  du, 878; ya, yā, 733-8; yu, 736, 738; 1
                                           o, sandhi of final, 885, 887, 889 f .-- and
  plus nasal, and 7, 300-2
                                              ara, 748-9, u, 713-9, v, 720-3; r, 646;
1y and y, 766-798
                                              au, 728-732; ta, vā, 804
13a: and i, 734; e, 747
                                           au, sandhi of final, 885-6, 888 -and
iye: and e, 747
                                              u, 724; ū, 725-7; o, 728-732
ir: and ar, 573, 575, 7, 653
                                           h, present or absent, 378-384
ī: and a, 600; ā, 597-8; i, 513-545, u, ū,
                                           n(m), present or absent, 300-310, as
  628; r, 638; e, 695-8, ai, 701-2, ya,
                                             hiatus-bridger, 308-9
  734-5; yā, 737; yu, 738; 1 plus nasal,
                                           k, optional between final \bar{n} and initial
  300-2
                                             s, 939 -and kh, 81; g, 45-9, gh, 83; c,
iy. and y, 786
                                              126-7; ch, 128a; d, 135; t, 137-142; p,
u, epenthetic, 759, 761, 765 -and a,
                                              148-153a; bh, 152
  601-618; ā, 620, i, 622-7; ī, 628; ū,
```

ks. and ks, khy, 190-1

ks, followed by evanescent y, 332. 335:-and ks khy, 190-1; ch, 184; ts, 140; ps, 1534; bj, 196; £, 297 kh: and k, 81; g. 82; gh, 70, ch, 129, t, 143; dh, 147; b, 151; f, 296; s, 295; h, 124 lhy: and ks, ks, 190-1 g: and k, 45-9; kh, 82; gh, 83; c, 128; j, 130-4; d, 144-5; p, 153; b, 151-2 gdh: and dhv, or ddh, 875 gh and k, 83; kh, 70, g, 83; th, 147; dy. 868; dh, 147; pv, 875; h, 123 \bar{n} , sandhi of final, 939.—and n, 146 c and k, 126-7; g, 128; ch, 84; j, 50-7; t, 155-6; d, 158; p, 162; bh, 878; v, 866; s, 195; s, 194 ch: and k, 128a; ks, 140, 183-4; kh, 129, c, 84; ts, ps, 140, 183, 185-6; \$, 195 j: and g, 130-4; c, 50-7; jh, 85; t, 156-7; d, 159; dh, 160, y, 192-3; v, 876; £, 195, h, 196 3h and 3.85 i and ih, 86-8; d, 58; i, 164-5, 167-8, 170; th, 170 th and i, 86-8; v, 876 d and L, 135; t, 58; t, 169-170; th, 165; d, 165-170; dh, 169; r, 272; l, 270-1 dh and dh, 168, 170 n: and n, 163, 165, 170, 945-54; l, 273 t, optional between final n and initial s, 938.—and k, 137-142, kh, 143; c, 155-6; j, 156-7; i, 164-5, 167-8, 170, d. 169-170; th. 89-96; d. 59-68; dh. 97-8; n, 871; p, 180; bh, 177; l, 878; s, 874 ir. and r, 876 is, followed by evanescent y, 333and Ls. 140; ch. 183, 185; ps. 180, end th: and gh, 147; t, 170; d, 165; t, 89-96, dh, 71-8; y, 877 d: and g, 144-5, c, 158; j, 159; d, 165-170, 1, 59-68; dh, 99-110; b, 179, bh, 177-8; y, 161; r, 272a, l, 273; r, 569 du and i, 878 ddh- and gdh, dbhy, dr, 875 dbhy and ddh, 875 dy: and gh, 868 dr and ddh, 875

dh and kh, 147; gh, 147, J, 160, d, 169; dh, 168, 170, t, 97-8; th, 71-8, d, 99-110; p, 177; bh, 172-6; h, 122 dhv. and gdh, 875 n, sandhi of final, 920-944; present or absent, 300-311; as histus-bridger, 309 -and n, 146, n, 163, 165, 170, 945-954; t, 871; m, 181; r, 860-5, l, 878 p, rhythmic lengthening of a before, 433, 460, 464-6 -and k, 148-153a; g, 153; c, 162; t, 180, dh, 177; ph, 111, b, 69; bh, 112-4; m, 203-5, y, 867; r, 198, 200-2; \$, 872, \$, 874 pi and s, 874 ply and pr. 878 pr: and ply, 878; \$n(y), 878, s, 874 prā: and ā, 873 pv. and gh, 875 ps and ks, 153a; ch, 183, 186, is, 180, ph and p, 111, bh, 79, v, 199 b: and Lh, 151; g, 151-2, d, 179, p, 69, p. 206-219; m. 241 bj and ks, 196 bh and k, 152; c, 878; t, 177, d, 177-8; dh, 172-6; p, 112-4; ph, 79; m, 242, v, 220-2; s, 874; h, 116-121 m, present or absent, 300-312, lengthening of a and u before, 464-5, 468, 549, as histus-bridger, 309 -and n, 181; p, 203-5; b, 241; bh, 242; v, 223-240; a, 870 y, present or absent, 36, 313-347; as histus-bridger, 36, 338-344, after two consonants, 314-5, 321-2, 332-7; after palatals, &s, etc , 332-7; assimilation to adjoining consonant, 408 -and 1y, 766–798, fy, 786; j, 192–3; th, 877, d, 161; p, 867; r, 244, l, 245, v, 246-255, s, 877, h, 256 yc, yā and i, ī, 733-8; c, 803 yu and 1, 736, 738; ī, 738, ri, 805 vu- and vi. 805 r, final, before L, p, 968; present or absent, 349-357; as histus-bridger, 353; after two consonants, 357, assimilated to adjoining consonant,

407; rhythmic lengthening of a and z

before, 515-6, 550 -and d, 272; d, 272a; n, 860-5, y, 244; l, 257-265; v. 266-8: h. 269 ra: and r, 656-8, 660, 662-5, ri, 573 rā and ar, 806, r, 657-9, 661 ri: and r, 666-676, ra, 573 rī and r. 677 ru and r, 678-684 I. assimilated to adjoining consonant, 409 —and d, 270-1; n, 273; t, 878; d, 273, n, 878; y, 245, r, 257-265 v, present or absent, 358-371; as histusbridger, 358-362; after two consonants, 367, 370, assimilated to adjoining consonant, 408, 410, rhythmic lengthening of short vowels before, 464-8, 515-6, 520, 547, 550-1; variation of a and u before, 601-4 and uv, 766-798, c, 866, j, 876; th, 876; tr, 876, d, 869, p, 198, 200-2, ph, 199, b, 206-219, bh, 220-2; m, 223-240, y, 246-255, r, 266-8; ş, 876; h, 269 va and u, 739, 741-2, u, 739, o, 804

vā and u, 739-740, 742, o, 804

v1 and u, 743; yu, 805 v1 and u, u or yu, 743, 805 s and ks, 297, kh, 296; c, ch, j, 195, s, 288-292, s, 275-287 sc and sy, 188 sn(y) and pr, 878 s, rhythmic lengthening of 1 and u

- s, rhythmic lengthening of i and u before, 515-6, 547; for s final after non-a vowel before t, 955-8, for initial s, 981-8—and kh, 295; c, 194, p, 872; y, 877; v, 876; \(\xi\), 288-292; s, 293-4; h, 299
- s, present or absent, 372-7; final after non-a vowels before t, varies with \$\(\epsilon\), 955-8; final before k, p, 959-967, final before initial sibilant, 969-971; ditto, before sibilant plus surd, 972-7, and plus sonant, 972-3, 978-980, initial s varies with \$\(\epsilon\), 981-8 —and t, p, pt, pr, bh, 874; m, 870, \$\(\epsilon\), 275-287; \$\(\epsilon\), 293-4; h, 298-9
- sy. and sc or s plus consonant, 187-9 h, present or absent, 385-7.—and kh, 124; gh, 123; j, 196; dh, 122, bh, 116-121; y, 256, r, v, 269, s, s, 298-9

SANSKRIT INDEX

Note—Here are indexed the most important words, roots, stems, and formative elements which are treated in this book as having semantic value (cf. Note at the head of the Index of Sounds etc.) with this exception, that (to save space) words which occur first in their respective mantras are, as a general rule, not listed here, since they can be located in the Index of Mantras. The Index of Mantras is therefore to some extent supplementary to this Index, and should be consulted if a word sought is not found here. Of course, not all variant words could be listed here, even with this deduction. It has been the intention to include (a) those of greatest interest and importance, and (b) those which could least easily be found by other means. Nor are the references in this Index completely given to all occurrences of the variant word; only those references are given which deal with the matters most apt to be sought in connexion with the words listed. The Index of Mantras will supply complete references to all occurrences—In this Index the colon () is used in the sense of 'varying with' or 'as a substitute for' References are to sections

a-privative, lengthened, 470-1 ansadhrī °drī, 99 akūpāra, 198 agni agra,863-4 agneyānī, 357, 692 agra agni, 863-4 aghrni āgh°, 473 afighrni agh°, 300, 473 acha achā, 461 atatantha, adadanta, 63 adham. sadam, 110 adhı abhı, 172 anapatyatām anapado, 59 anavaprgna, 55 anasyato, "svato, "ssato, 255, 408 anasrū anassū, 407 anūkya anūpya, 151 antarīksa, 517 apas apas, 498 apıkakşa apıpakşa, 151 aptu(bhih), 152 abbhuva abhva, 392, 790 abhi adhi, 172 abhısastıpüvä °pü u, 740 abhīspāt. 142 abhva abbhuva, 392, 790

arsat arşat, 288 av (root), 253 avața °ta, 164 avākā, 496 avithura avidhura, 77 avišvaminyām avišvavinnām, 236 asita as°, 277 asn(y)usni. 337 agrīvī asrīvī, 277 ast(h)Iva, 86 -as -as (in s stems), 502 asamheya, 121, 124 askra āskra, 473 asyate asy°, 278 ū, preposition, present or absent, 508-9, 652, 694, 698, 711, 718, 722, 730 ū- a-, privative, 470-1 -a. stem final, shortened, 493 ākkhidate, 401, 405 üghrnı aüghrnı aghrnı, 300, 473 anrhuh anrdhuh, 122 apas apas, 498 üyabhüva, 215 avrt ravat ravat, 168, 632 -ns -as (in s stems), 502 fiskra askra, 473

SANSKRIT INDEX

āsyan, 32S ikşva iyakşva, 734 indh: Id, 169 īd: indh, 169; -: vīd etc., 169, 360 ugra· ūgra, 567 uttara: °rā, 476 ud-ac ud-aj, 53 uramdha. °dhra, 353 uruvā. 743, 791 urv -: urm-, 228 urviyā: urvyā, 767, 791 ulumbara: "la, 265 ulbar ulva, 219 usnan (=musnan?), 401 ügra: ugra, 567 ūrm-: ūrv-, urv-, 228 rnanti: rinanti, 676 rşabha: vṛṣ°, 359 etagya: edagya, 59 kakutha: kakkata, 88, 401, 607 kakud, kakubh, 178 kakubha: kakuha, 120 kakkata kakutha, 88, 401, 607 : katkata, 139 kanānakā: kanī°, kanīnikā, 595, 597 kayāda: kravyāda, 355 karīşa, 152 kavysvāhana: kravya°, 353 kahya: gahya, 49 kāsthā gā°, 48 kirika: girika, 49 kılbişa: kilv°, 216 kīrṣā: kīrśā, 290 kulanga: kulunga, 607 kulikaya kulikā kulipaya, 149, 802 kulmah = kurmah, 263 kuvala: kvala, 767, 782 kusthā kustā, 86: —: gusthā, 49 kuha: guha, 49 kūvāra, kūvara, 198 krnattı: gr°. 48 krtadvasu, 95 kṛtta. kṛta, 401 kṛtsnāmi: grathnāmi, 47 krmi kruni, 668 krvi: krivi, 673 kṛṣṭi gr°, 46

ketu, ketas. cetu, cetas, 126

kevarta kai°, 708 krayī· kravi, krīvi, girī-, 47 kravyavāhana kavya°, 353 kravvāda, kavāda, 355 krımi krmi, 668 krivi krvi, 673;-see krayī kruñca krauñca, 724 kliba, kliva, 219 kvala kuvala, 767, 782 kšā ksā, khyā, 190 kşayana kşena, 744 ksā, kšā, khyā, 190 ksivant, ksyant, 767, 795 ksu, 183 ksudra(ka): kşullaka, 262 ksena, ksayana, 744 ksyant kşiyant, 767, 795 khagalya khrg°, 199, 631 kharva khalva, 265 khid: chid, 129 khilya-khilla, 408 khrgalya: khag°, 199, 631 khyā: kšā, ksā, 190 gabhasti, 151 gambh- gsh-, 120 galgā galdā, 144 gahya kahya, 49 gāsthā: kā°, 48 giri-, see krayî girika, kir°, 49 guggulu. gulgulu, 409 gulph: gusp, 111 gulbadhānah. 260 gusthā·ku°, 49 guha: kuha, 49 güh for guh, 558 gr. pr. 153 grnatti: kr°, 48 grsti krsti, 46 gotrabhid. °bhrd, 636 grathnāmi krtsnāmi, 47 grabh· grah, 115-6 ghosad, 83 canīkhudad, 126 car tar. 155 carışnu jar°, 57 cākupāna cākļp°, 645 cıkitnu. 45

citra ávitra, 195, 369 cıdākoh, 47 cubuka, 84 cetu, cetas ketu, ketas, 126 cyu(t) · scut etc . 336 chid khid, 129 chubuka, 84 jaksuh· ca°. 55 jagybhnā, 116 janman manman, 856 jarişnu· car°, 57 jasa jhasa, 85 jāgryāma jāgriyāma, 674 pgatnu, 45 jiny, piny, 852 ımann. dyam, 159 ıyam. dyam, 159 jyut dyut, 159 jhaşar jaşa, 85 ta tya, 345; -- tva-, 365 tanakmi tanacmi, 127 tap tam, 204 tar. car, 155 tarutra tarudra, 69 tādīknā· otnā, 141 tityagdhi titigdhi, 733 tisthato (for "tu), 715 tevi (devi), 21, 66 tya ta, 345, tyam tvam, 252 -tra -trā (adr suffix), 451-2 tva- ta-, 365 tvam· tyam, 252 tviş dviş, 60 -tha -thā (adv suffix), 453-5 da dha, 100-6 dips dhips (dabh), 107 diś viś, 869 duruşyaha, °şvaha, °şşaha, 255, 408 durbhutam °dam, 59 durhanāyatah durhrn°, 4, 631 dūraka dūragā, 46 dībā dīvā drubā, 219, 679 devayat deva-yat (-yaj), 170 devakāmā devīk°, 633 dyām jmann, 159, - jyāu, 159 dyut jyut, 159 drāghuyā, 240, 764 drubā drvā drbā, 219, 679

dvis tvis. 60 -dha -dhā (adv. suffix), 453-4 dhavani dhamani, 144, 225 -dhā -dha (adv suffix), 453-4 dhā dā, 100-6, - dhr, 350 dhāman nāman, 855 -dhi -dhi, impv. ending, 518 dhita bhrta, 175, 639 dhips dips (dabh), 107 dhur dhur, 557 dhūr(u)sadam, dhūr(u)sāh-, 759 dhr dha, 350 dhrsat, dhrsad, 60, 110 dhenukā °zā. 48 -na -nā (instrum ending), 458 naptī naptrī, 357 navakrt navagat, 46 nahrsa nahusa, 642 näth nädh, 76 nāman dhāman, 855 nicankuna nicunk° nicumpuna, 150. nişangadhi °thi °ti, 77, 93 nyemur (nı yemur), 767, 770 nyantar (niyantar), 767, 770 padbīša "viša [·"vinša], 217, 302 padbhih pad 166 pad pad, 499 parasvī °spī, 193 parīta parītta, 404 palaksa, 69 pasthavāh prs°, 631 pansura. Ja, 261 pld pad, 499 pitar pităr-, 500 pitrya pitrya, 674 piny jiny, 852 pivas cic pibo, 211 punijista. *stha, 86 purikaya, see pulio puritată, puri°, puli°, puli°, 263, 532 purisa, 152 purutama °dama, 60 puruşa pū°, 566 pulikaya, puri", pulikā, puliraya, 149, 802 pulitată, sce purle pūrusa pu°, 566

pr gr. 153, - bhr. 112 priicanti vriijanti, 57, 200 prnacmi prnajmi, 55 prthivi °vi, 524 prsthavah pas°, 631 prava prusva, 680 prakkhidate, 401, 405 prakhān praghān, 70 pratadyasu, 95 pratuagrāham. 803 pratīta pratītta, 404 prapharvi vi. 524 prayakşu: prayatsu, 140 pravišivānsam, 808 prasutah prasupah, 180 prā, for pra, 429, 439, 465, 512 pru. plu, 261 prusvā· prsvā. 680 prorn(u)vāthām, 767, 797 plu pru, 261 phaliga, 46 badabā, 219 badh vadh, 209 bandhura vano. 213 bala· vala, 210 bal(1)h valh, 214, 762 başkiha: vaşº: bāska, 219 bahistha vah 214 bākura· vā°, 216 bāna vāņa, 218 bāla vāla, 214-5 bāşka, see başkiha bija· vija, 216 brh: vrh, 212, 215 brhat mahat, 241, 634 bhū hu, hū, 119 bhūyāma· bhūyāsma, 377 bhr pr, 112; -. hr, 117 bhrta hita dhita, 118, 175, 639 -ma -mā (endings of nouns), 459-460 mangiradasakau, °gau(h), etc. 49 mathavva. 78 man van (roois), 227; (suffixes), 240 mant, lengthening of u before, 549 mant. vant, vin, varī (suffixes), 238-9 manthilava, 77, 597 mand: vand, 229 manman, janman, 856

mayas vayas, 232 marūka, 81 masmasā, masmasā, 294, 632 mahat brhat, 241, 634 mahānaghnī (°nagnī), 83 -mā -ma (noun endings), 459-460 mätrk (mädrk), 21, 66 mānthāla, "lava, māndhāla, mānthīlava, 77, 597 māremi mārimi. 131 mrddha mrdhra, 407 mṛsmṛsā, 294, 632 medin vedin, 231 medh-: vedh-(ved-), 109, 230 -ya. noun suffix, 313-326, - iva. 784-7 -ya -yā, gerund suffix, 456-7 yati yatti, 401 -yin -vin, 246-7 yunagmi: yunami, 131 yup. lubh, 113, 245 yuva-: vuvā- (pronoun), 504 raghusvadah. °tah. 64 ratha-krtsa °krtsna, °grtsa, 46 rabh labh, 262 rayyās, rayyai: rāyas, rāye, 396 rarāta: lalāta, 265 rāyas, rāye: rayyās, rayyai, 396 rāvat·rāvat·āvrt. 168. 632 ripanti rnanti, 676 ris lis, 261 rışak rışat, 142 rohita· lohita, 262 labh rabh, 262 lalāța, rarāța, 265 lış: ris, 261 lubh yup, 113, 245 loka. loga, 46 lohita rohita, 262 vadabā, vadavā, 219 vadh badh, 209 van man (roots), 227, (suffixes), 240 vanasad, vanarşad vanışad, 650 vanistu. osthu. 86 vant mant (suffixes), 238-9; lengthening of a, i, before, 467, 520 vand mand, 229 vandhura ban°, 213 vayas mayas, 232

varivan variyah, 249, 541a varī. vatī, matī (suffixes), 239 vala-bala, 210 valh. bal(i)h, 214, 762 vaşkıha. baş°, bāşka, 219 vas: viś, 281, 576 vastya pastya, 198 vahiştha· bah°, 214 vākura: bā°, 216 vācam: vājam, 51-2 vāna bāna, 218 vāvosāvitra, 716 vāra· vāla, 261 vārdhrānasa vārdhrī°, vārhī°, 122, 597 vāla: bāla, 214-5; - vāra, 261 vicarturam, 156 vicṛt: vivṛt, 866 vicṛta: vicṛtta, 401 vitudasya, 65 vid: vrdh, 108, 640 -vin, lengthening of a before, 467, --mant, 239, --: -yin, 246-7 viprcah· vibhrjah, vimrjah, vivrtah, 57 viyantu: vyantu, 796 vivit vicit, 866 viś· diś, 869, — vas, 281, 576 viśvahā, viśvāha, °hā, 477, 511 vīja bīja, 216 vid. vid. id, 169, 360 vrkka vrkya, 408 vrňjanti · prňcanti, 57, 200 vrdh vrt, 97; - vid, 108, 640 vršcyantām, vršcantām, 334 vrsabha rs°, 359 vrh: brh, 212, 215 ved- vedh-. medh-, 109, 230 vedin medin, 231 vyantu viyantu, 796 šak · šik, 571 samtācī °tātı, 156 šabali- šavo, 219 sam (root) sum, 572 sam (particle) sam, 276, 278, 280 samopyāt, 277 sava sapha, 199 śavali śab°, 219 favas elc · fravas elc , 349 śaspińjara sasp°, 278, 294

śākī sākī. 278 śābalya: śābulya: śāmulya, 241, 607 śińśumāra · śiśu °, śiśū °, 305, 551 šık šak, 571 śitimga śvi, 369 śim śam, 572 śırā śılā, 263 śiśumāra, śiśū°: śinśu°, 305, 551 sukra sukla, 262 sudh subh, 173 śuśulūkā, 279, 624 śūra· sūra, 278, 284 śoka śoca, 126 scut scyut cyu(t), 336 śn(y)aptre. 337 śranś: srans, 277 śrama syma, 277 śravas etc. śavas etc., 349 áris álış, 261, 265 śru· sru, 274-5, 278, 283 śrona ślona, 261 ális áris, 261, 265 ślona śrona, 261 śvitimga śi°, 369 śvitra citra, 195, 369 şadvinsa, 217, 302 sa sam, 306; -: su, 612, - sva, samskrti samkrti, 374 samkışya. °kasya, °kuşya, 4, 631 sacate smate, 3, 57, 634 samugaīre, 387 sat(a) sada(s), 60 sad sad, 278 sada(s) sat(a), 60 sadhrışu, 353 sanısan sanışyan, 334 sam sa, 306, -- śam, 276, 278, 28 samıddham samrddham, 39, 635 samude (sammude?), 401 sarıra salıla, 264 saru saru, 278 salıla: sarira, 264 sasrgmahe sasrj°, 131 saspiñjara śasp°, 278, 294 sākī šākī, 278 sūvisak gat, 142 sımāh (śi°), 278 su sa, 612, - sva, 741

SANSKRIT INDEX

suka (suka), 278 suci: śuci, 278 suta stuta, 419 subhutam °dam, 59 sumatitsaru, 180 suvāna svāna, 768, 794 auşılīkā, 279, 624 sūra śūra, 278, 284 sr sru, 682 srkāyin °vin, srgāyin, 48, 247 srjate. sacate, 3, 57, 634 sidh sridh, 672 srma śrama, 277 senānī °ni, 523, 527 soma stoma, 419 somapitsaru somasatsaru, 180 skabh stabh, 137

stuta suta, 419 stoma, soma, 419 sthūra. sthūla, 261 srans śranś, 277 sravatī srotyā, 749 srı śri, 278 sridh. srdh, 672 sru sr, 682; -: śru, 274-5, 278, 283 srotyā· sravatī, 749 sva sa, 364, -: su, 741 svasūr· svasīr. 644 svāna suvāna, 768, 794 hariśaya hari", harā", 521, 597 hita bhṛta, 118, 639 hu, hū bhū, 119 hr. bhr. 117 hrda hrada, 658

SUBJECT INDEX

References are to sections

Ablaut see Guna, Vriddhi, Samprasāraņa, and under the various vowels and diphthongs in the Index of Sounds etc

Attareya Brāhmana: prefers r to l, 259 Āpastamba Mantra Brāhmana. drops finals before sibilant plus sonant, 978 Aspirates and non-aspirates, 80-114,

and h, 23, 115-124

Assimilation and dissimilation of consonants, 38, 139, 406-416, of vowels, 416a, 601-5, 607, 609, 622-4, 678-680

Atharva Veda and its school prefers such to such, 173, variyah for varivah, 249; sandhi of final o, au, 885a; sandhi of a, a, with r, 915, final s after non-a vowels before t, 957, final s before sibilant plus sonant, 978, Book 20 has l for d, 270

Consonants double and single (in conjunction with other consonants) 389-392, (between vowels) 393-405, simplification of groups, 417-421 (see also 314-5, 321-2, 332-7, 357, 367, 370), optional dropping of mute between nasal and other consonant, 417-8; see also Assimilation

Denominative stems in aya, āya, 478; in iya, īya, 534; in (ī)ya, 786

Dentals and gutturals, 136-147, labials, 171-181, linguals, 25, 163-170; palatals, 24, 154-161

Diphthongs 41-2, 685-750 Dissimilation, see Assimilation

Dittology, 810-3 Epenthesis of vowels, 43, 751-798

False divisions 814-840

Gerunds in *ya*, *yā*, 456–7 Graphic variants, 858–878

Guna (normal Ablaut grade), 570-3,

582-3, 601-5, 615, 647-651, 686-8, 696, 713-5, 720

Gutturals and dentals, 136-147; labials, 148-153, linguals, 135; palatals, 125-134

Haplology, 807-9, 812-3

Hiatus, 991-6; hiatus-bridger (Hiatustilger), nasals as, 308-9, y as, 36, 338-344, r as, 353, v as, 358-362

Hieratic language prefers adha to alha, 72ff, grabh to grah, 115; r to l, 258, 261-2, 284

Instrumentals in na, nā, 458

Käthaka Samhitā writes kśā for khyā, 190; triyam for tryam, 768, 776, sandhi of final o, au, 885b; sandhi of a, ā, with r, 914; final s s after-non-a vowels before t, 957, final s before sibilants, 970, 974; āgrāyana for āgra°, 492

Lahials, 29, 197-242; lengthening of short vowels before, 433, 460, 464-8, 515-6, 520, 547, 549-51; shortening of long vowels before, 475;—and dentals, 171-181, gutturals, 148-153, palatals, 162

Linguals and dentals, 25, 163-170, gutturals, 135

Maitrāyaui Samhita and its school writes kāā for khyā, 190; [i for r?, 259,] sanda sanda, 289, a before vant and vin, 467, prefers u to a before v (?), 601-4; sandhi of final o, au, 885b, sandhi of a, ā, with r, 916, change of n to n, 947, 952; final s for s after non-a vowels before t, 957, final s before k, p, 963; final s before sibilants, 974, āgrāyana for āgra°, 492

Metathesis, 799-806

Meter, relation to rhythmic lengthening and shortening, 425, 428-431, 438-448, 457-460, 515-6, concerned in hiatus, 991ff, in patch-words, 843ff

Nasals, present or absent, 35, 300-312; as histus-bridgers. 308-9; assimilation of consonants to adjoining-, 411-5, nasal after short vowel, varies with long vowel, 300-2

Nirukta has l for d. 270-1

Palatals, 26-8, 182-196; followed by evanescent y. 334, 336-7,-and dentals, 24, 154-161 gutturals, 125-134, labials, 162

-Patch words, 822-833, 841-850

Popular language prefers atha to adha, 72ff : grah to grabh, 115, l to r, 258, 261 - 2

Prakritisms, 20-43 (summary, which see for further references)

Reduplicating svllable rhythmic lengthening of vowels in, 468, 519, 548, a and 1 m, 581

Rhythmic lengthening and shortening, see Vowels

Rigveds and its school r for l in, 261-2; l, lh, for d, dh, 270, suvāna for si āna. 768, 794; h for dh, bh, 23, sandhi of final o, au, 885d; sandhi of a, a, with τ , 913, change of n to n, 951, final s s after non-a vowels before t. 957. final r before k, p, 968

Rime words, 851-7

Sama Veda and its school has atha etc for adha etc , 72, g for g before m. 131, prefers u to a before v. 601-4. sandhi of final o, au, 885d, tends to drop initial a after e, o, 902, change of n to n, 947, 952, final r before l, p. 968

Samprasārana, 656-665, 733-743

Sandhı, 879–996 See 881-2 for general principles, 883-4 (or Table of Contents) for analysis of contents of the chapter, 879 for references to sandhi in other parts of the book -Secondary crasis or double sandhi, 939-990 See Huatus

Sānkhāvana Srauta Sūtra has I for d. 270; h for final s before sibilant plus surd, 975

Sibilants, 30-4, 274-299, lengthening of 1 and u before, 515-6, 547

Surds and sonants, 21-2, 44-79 Taittirīya Samhitā and its school prefers u to ι , 8, 622, prefers v to y, 8. 247-8: guttural for final labial. 148, 151, ā for a before vant and vin. 467; prsiā for prustā, 680, favors w, w, for y, v, after consonant, 767ff (exceptions, 767); sandhi of final o, au, 885c, sandhı of a, ā, with r. 914: change of n to n, 947-8, 952: retains final s after non-a vowels before t, 957; final s before k, p. 963 Vājasanevi Samhitā and its school has badh for radh (?), 209, but often r for original b. 215-8, sandhi of final o, au, 885d; sandhi of a, a, with r, 913, final s s after non-a vowels before t, 957

Vājasaneya Samhatā, Kānva has k and g for c and 7 before m, 125, 127, 131: badh for vadh (?), 209, l for d, 270, sandhi of final o, au, 885b; final s s after non-a vowels before t. 957

Voiceless and Voiced, see Surd and Sonant

Vowels, short and long, with and without following nasal, 35, 300-2; before double and single consonants, 393ff; rhythmic lengthening, (of a) 422-468, (of z) 514-521, (of u) 546-552, rhythmic shortening, (of ā) 424, 473-7. (of ī) 522-4, (of ū) 553 See Assimilation, Epenthesis

Vriddhi (Dehnstufe) in primary noun formations, 485-9 in secondary noun formations, 314-326, 490-1, 699, 702, 707, 724-5, 728, in verb stems, 480-1 700, 702, 712, 729

INDEX OF MANTRAS

References are to sections

ansum gabhasti (babhasti) haritebhir āsabhih, 151 ansur-ansus te (-ansus te) deva somā pvlivatām, 958 ansun babhasti haritebhir asabhih. 151 anso rājā vibhajatīmāv ("mām) agnī. 237 anhasaspataye (anhaspatyāya) tvā, 325, 810 anhārır ası bambhārih, 123 anhomuce pra bharemā (bhare) manīsām, 808 akah su (sa) lokam sukṛtam pṛthivyāh (°vy ām), 612 aktam rihānā viyantu (vyantu) vayah, 96, 152, 796, 857 akrān samudrah prathame vidharman, aksakrtyās tripaticāšīh, 185, 192, 353 aksatam aristam ilandam, 411, 576 akşatam asy ariştam ilānnam gopāyanam, 411, 576 aksānām vagnum (vagmum, gatnum, ganam) avajighram apah (upajighnamānah, upalīpsamānāh), 181, 832, akşitam asi mā pıtrnām (pitāmahānām, prapitāmahānām) kṣeṣṭhā , 576, 586 aksıtam asi mā me kşeşthāh, 576, 586 aksitam asv aksitam me bhūyāh, 576, 5S6 akşitir ası mü me kşeşthā , 576, 586 akşıtis ca me küyavās ca me, 552, 587 akşyos (akşos) tanvo rapah, 335 akhıdrah praja abhivipasya, 129 agan prānah svargam lokam aganma yatra pratiranta äyuh (prataram na āyuh), 411, 575, 824

aganma viśvavedasam, 508 aganma vrtrahantamam, 508 agrbhīt, agrbhīsata, 657 agotām anapatyatām (anapadyatām), 59 agor arir ā ciketa, 244, 837 agdhād eko 'hutād ekah samasanād ekah, 181, 511, 875 agna āyuhkārāyusmāns tvam tejasvān devesy edhi, 598 agnaya upāhvayadhvam, 509 agnaye gayatraya trivrte rathamtarāyāşţākapālah (etc.), 495 agnaye tvā mahvam avur (mavo) dātra...mayo mahyam pratigrahitre (pratigrhnate), 511, 657, 719 agnaye dhūnkṣnā (dhūnkṣā), 255, 311, 335, 568 agnaye samidham āhārsam (ahārsam), 508 agnāv (agnā) agniš carati pravistah, SSS agnāvişnū mā vām ava kramışam, 723 agnıh pareşu (pratneşu) dhāmasu, 579 agnih pratnena manmanā (janmanā), agnih pravidyān (°vān) iha tat krnotu (karotu, dadhātu), 925 agnıh priyeşu dhāmasu, 579 agnım yunajmi (yunagmı) ghrtena, 131 agnım éreşthasocışam, 747, 843 agnım sa rchatu yo maitasyaı (°syā) diso 'bhidasatı, 910 agnım sa dıśām devam devatānām , 910 rchatu yo agnım sruco adhvareşu prayatsu, 140 agnım sve yonāv (Jonā) abhār ukhā,

agnım hotāram antarā vivrttāh, 866 agnım ca viśvaśambhuvam (°sambhuvam), 278 agniihvebhvas tvartāvubhva (°bhvo) .,918 upa te huve agninendrena somena savāham ('sā aham), 362 agnim naras trisadhasthe sam idhire (indhate), 301 agnım atırugbhyam (ati°), 516 agnım adva hotāram avrnītāyam yajamanah pacan paktīh (panktih) pacan , 310 agnım ındram vṛtrahanā huve 'ham ("hanam huvema), 850 agnım ındhīta martyah, 169, 302 agnim indhe vivasvabhih, 301 agnım idita martyah, 169, 302 agnım īdhe vivasvabhıh, 301 agnım u śreşthaśocışam, 747, 843 agnir aiaro 'bhayat sahobhih. 907 agnır adhı vıvatto asvam. 910 agnır adhyakşah (°āh), 494 agnır annādo 'nnapatır dadhātu (dadātu) svāhā, 104 agnir amrto abhavad vayobhih (sahobhih), 907 agnir āyuşmān sa vanaspatībbir āyuşmān (°māńs) tena (tasyā) agnır ukthena vāhasā (ukthesv anhasu), 310 agnır garhapatyanam (grhapatinam), 652, 737 agnır dād (dā) dravinam vīrapešāh, 392 agnır diksitah prthivi . diksavatu , 745 (dīkseta) agnır devebhyah suvidatriyebhyah (°trebhyah), 315, 747 agnir devesu pra voca, 379 agnır dvärä vy rnvatı (urnvatı), 654 agnir no vanate (vanute, vansate) rayim, 377, 606 agnir me hotā sa mopahvayatām, 509 agnır vidvan sa yajat sed u hota (sa id dhotā), 848, 996 agnir viyatto 'syām, 910 agnır havıh (havyam) şamitā sūdavātı (svadayatu), 737, 739

agnır havyānı sışvadat, 739 agnir havyānumanyatām (havyā no ma°), 719 agnır havyl suşüdati, 739 agnır hotā prthivy antarıksam, 821 agnir hotā vetv (vettv) agnil (agner) hotram vetu (vettu) . . 392, 691 agnir hotrenedam (hotrena) havir . , 354, 833 agnis ca dahatam prati. 512 agnis tān (tān, tan) agre pramumoktu devah, 924, 958 agnis tăn (tân, tâl) lokāt (asmāt) , 943 ora agnis te agram . , 910, 958 agnış te tanvam mā vinait, 958 agnış te tejo mā hārşīt (°īh, vinait), 958 agniş te tvacam mā hinsīt, 958 agnıs te 'dhipatıh. 958 agnis te hastam agrabhīt (agrahīt), 116 agnıs tvābhı pātu . . ., 958 agnıs tvā śrinātu. 958 agnış tvā hvayatı, 958 agnis tan agre . , 924, 958 agnis te 'gram nayatu, 910, 958 agnıs te tanuvam mäti dhāk (tanvam mā hinsīt), 958 agnis te tejo mā vi nait (mā prati dhākṣīt), 958 agnis te 'dhipatih. 958 , 958 agnıs tyābhi pātu agnıs tvä šrīnātu, 958 agnıs tvü hvayati devayajyayai, 958 agnıh sudakşah sutanur ha bhütvü, 554, 578, 612 agnih sruco adhvareşu prayaksu, 140 agnihotram prthivīm antariksam, 821 agnihotrenedam havir ajusatāvīvrdhata (°dhanta) , 354, 833 agnihvarebhvas tvā rtā°. 918 agnī ındrā vṛtrahanā huve vām, 850 agnid rajanarāuhinau (rāja°) . , 490 agnindtayor aham devayajyayā viryayan ındriyayan bhuyasam, 467 agnīşomā imam su me, 888 agnīşomībhyām justam ni yunajmi (vunagmi), 131 agnīsomāv imam šu me. 888

agne akşīm nır daha svāhā. 338 agneh purisam ası, 325, 381 agneh purişavāhanah (purişya°, °vāhanah), 319, 953 agneh priyam pātho 'pīhi (apīhi), 910 agne kahya (gahya), 49 agne grhapata upa mā hvavasva, 509 agne ghrtenāhuta (°tah), 380 agne tan vettha yadı te jatavedah. 60 agne tejasvin tejasvī agne trātar rtas (rtah) kavih, 964 ague tvam yonım āsīda sādhuyā, 505, 874 agne tvam süktaväg asy upaśruti (°tī, °śrito) divas (divah) prthivych, 525, 626, 964 agne tvam purişyah, 325, 381 agne tvāmkāmayā (tvām kāmaye) girã. 820 agne dakşaıh punihi nah (mā, punimahe), 802 agne 'dabdhāyo 'sītatano ('sīrtatano, , 353, 808 'sītama) pāhı agne deva panibhir viyamānah (onah. guhvamānah, idhvamānah), 953 agne devăn (devăn) ıhā vaha, 924 agne devānām ava heda ıyakşva (1ksva), 325, 696, 734 agne deveşu pra vocah, 379 agne purisyādhipā bhava (bhavā) tvam nah, 434, 446 agne prthivipate varuna dharmanām pate , 494 prthivyā adhipate agne varuna , 494 dharmānām adhipate agne prehi prathamo devayatām (devā°, devatānām), 478 agne brhann uşasam , 864 agne brahma grbbnīşva (grhnīşva, grhīsva), 116 agne 'bhyāvartını abhı mā nı vartasva (māvartasva, na ā vartasva, no nivartasva, na il vavrtsva), 516, 648 agneyakşīm nir daha svāhā, 338 agne yajasva rodasi urūci, 57, 363 agne yajñasya cetatah, 864 yo'smān (asmān) agne vat te tapas dvesti , 910

agne yat te tejas tena tam atejasam kuru (tam prati tityagdhi, titigdhi) yo 'smān (asmān) , 733, 910 agne yat te 'rcis (arcis) vo 'smān (asmān) , 910 (bis) agne yat te haras yo'smān (asmān) , 910 agne yan me tanvā (tanuvā) ūnam (yan ma unam tanyas) tan ma a prna. 503 agne yan devan ayad tām sasanu-, 870 şīm (samanaısīr) agne yāhi dūtyam mā rişanyah (dūtyam värişenyah), 225, 829 agne vähi sušastibhih, 509 agner akınvann usijo amıtyave, 152, 643, 650 agner aksnah kanīnakam (°kām, °nıkām). 595 agner agneyāny (agnivāny) asi, 357. 692, 818 agner apunann uśijo amrtyayah, 152, 643, 650 agner avena marutam na bhoiva, 837 agner jihvān, abhi (jihvābhi, jihvayābhi) grnītam (grnata), 309 agner jihvāsi suhūr (subhūr, supūr) , 114, 119 agner yany asi, 357, 692, 818 agne varcasvin (°van) varcasvābs varcasvān (°vy) aham (°vī) 596 . 360 agne vājajid vājam tvā agne vikşu pratidayat, 64, 864 agne vitatam antar ā (antaram), 826 agne vittād dhavişo yad ynjāma (°mah), 379 agne virājam upasedha šakram, 138 569, 616 agne vyacasva rodasi urūci, 57, 363 agne vratapate vratam acārışam (acārsam), 754 agnes tvā tejasā sādayāmi, 958 agnes tvā tejasā sūryasya agneş tvü mütraya jügatyü 958 agnes įvūsyena prūšnūmi, 958 agne samstjmahe girah, 306

agne sakhve mä risämä vayam tava, 224 agne sadaksah satanur ('nūr) hi bhūtvā, 554, 578, 612 agne samıdham āhārsam, 864 agne samrād işe rāye (rayyai) ram-, 37, 396, 705 agne sasrimahe girah. 306 agnes tejasā sūryasya..., 957 agnes tvā tejasā sādavāmi, 958 agnes tvā mātrayā jagatyai (°tyā) , 491, 958 , 958 agnes tväsyena präśnāmi agne svam (svām) vonim ā sīda sādhyā (sādhuyā), 505, 874 agnau läjän ävapanti, 151 agnau samrādhanīm yaje, 617, 806 agrabhīt, agrabhīsata, 657 agre brhann usasām ūrdhvo asthāt, agre vaiñasva socatah (cetatah), 156. 195, 864 agre vājasya bhajate mahādhanam (bhajase mahad dhanam), 395a agre vikşu pradīdayat, 64, 864 agre samidham , 864 aghadvıştā devajātā, 147, 381, 619 aghāya bhūma hariyah parādai (°daih), 384 aghorah prajā abhivipašya, 129 aghoraghoratarebhyaś ca, 816 aghorena cakşuşā mitrīyena (maitreņa, cakşuşāham sivena), 314, 699 aghorebhyo 'tha (atha) ghorebhyah, aghnyāv asunam āratām, 569 aghnyau sūnam āratām, 569 añkāńkam (añkāv-añkam, añkañkam) chandah, 362, 511 angād-angāt sambhavasi ("śravası), 853 angani ca me 'sthanı ('sthini) ca me, 598 angani ta ukthyah patu. 322 angiraso me asya ('sya) yajuasya . , angırobhır a gahi yajnıyebhih, 849 angirobhir yajniyair a gahiha. 849 angoșinam avavasanta vănih, 490, 599. 720

angosinam payamanam sakhayah, 490, 720 anghārir ası bambhārıh, 123 anghrina vișno (vișnu) ma tvava (vām ava) kramisam, 723 andhi kham vartava panim (pavim). 857 acikitvān (ovāns) cikitusas cid atra. 930 acıkradat svapā iha bhuvat (bhavat). 602, 838 acıttapājā agnīt, 399, 738 acıttamana upavakta, 399, 738 acışyama vriane visva ūtī, 242, 878 acety agnis cikituh (°tih), 623 acyutapājā agnīt, 399, 738 acyutamanā upavaktā, 399, 738 acha vāhy ā vahā daivvam janam. 460 achalābhih (°rābhih) kapifijalān, 26, 184, 265, 631 achā devān ūcise dhisnyā (oniyā) ye, 784 achā no yāhy ā vaha, 460 achā ma indram matavah svarvidah. achāvam vantī šavasā ghrtācīh, 824 achāvam eti savasā ghrtena (ghrtā cit). achā va indram matayah svaryuvah, 234, 805 achā vīram narvam panktirādhasam (panti°), 418 achidrā uśijah padāņu taksuh, 627, 992 achıdram parayişnum ("yişnvim), 743 achidrośniah kayayah padāni (onu) taksis(v)at (°suh), 627, 992 achinnam tantum anu sam tarema (carema), 155 achinnapatrāh ("rah) prajā anuvīksasva, 129 achinno divyas (daivyas) tantur mā mānusas (manusyas) chedī, 316, 490, ajagan rātri sumanā iha syāh, 508 ajanti vahnim sadanany acha, 634 ajany agnir hotā (ajann agnih). . 928 ajasya nābhāy (nābhā) adhy ekam arpitam, 888

ajasram tvām (tvā) sabhāpālāh, 304 ajāšvah pašupā vājapastyah (vājavastyah), 198 ajitāh syāma šaradah šatam, 537 ajijapata (*jipata) vanaspatavah, 584 ajījapatendram vājam. 52 azītāh ("tā) syāma šaradah šatam, 537 ajaişmādyāsanāma ca (°sanāmādya), 158 ajo dhumro na godhumaih kuvalair (kvalair) bhesaiam, 782 ajosā vrsabham patim, 376 anjanti suprayasam panca janah, 192, 339, 617 anjısakthaya ("gakthaya) svaha, 580, atnärasya parah putrah, 511 ata ü şu madhu madhunābhi yodhi, 68, 379, 533 atandraso vuvatavo vibhrtram (vibhartram, bi°), 207, 650 atas caksāthe adıtım dıtım ca. 853 atas cid indra na (na) upa, 950 atas tvam deva vanaspate satavalso (tvam barhih satavalsam) viroha, 817 atıkırıtam (°rītam) atıdanturam, 545 atıkulvam ("külvam) catılomasam ca, 568 atı niho atı sıdhah (sridhah), 672 atıratram varşan pürtir avrt (vavarsvān pūrta rāvat, vavrsvān pūta ravat) svaha, 351, 586, 632, 649 atı vă yo maruto manyate nah, 477, 545 atividdhā vithurenā cid astrā (astāh), 357, 381 atı setum durāvyam (durāvyam), 253 atīva yo maruto manyate nah, 477. 545 ato annenaiva jivanti, 94 ato ıyayans ca püruşah (pur°), 566 ato devi prathamānā prthag yat, 68, 525 ato dharmānı dhārayan, 578 ato no 'nyat pitaro mā yoşta (yūdhvam), 302 ato no rudră uta vā nv asya, 719, 778 aty anyān (anyān) agām nānyān (nānyān) upāgām, 924 atra jahīmo 'šīvā ye asan, 452, 686

yathābhāgam , pitaro vathā° mandadhvam), 301 atră jahama (jahita, jahimo) ve asana aseväh (asıvāh, asan durevāh, 'sıvā ye asan), 452, 686 atră te bhadrā raśanā apašvam (bhadrā vrsanā agrbhnām), 292, 865 atră yamah sădană (°nāt) te minotu. 405, 452, 512 atrāha tad urugāyasya visnah (vrsnah), 640 atrınă tvä krime hanmı, 668 atrivad vah krimavo hanni, 668 atsarābhih kapinialān. 26. 184, 265, atha jivrir (jirvir) vidatham ā vadāsi, 73, 454, 529, 544, 801 atha devānām vašanīr bhavātı, 454 atha bhaya yajamānāya sam yoh, 454 atha māsı punar āyāta no grhân, 75, 454 atharva pitum me pāhi. 248 atharva pitum me gopāya (pāhi), 248 atharvyustā devajūtāh, 147, 381, 619 atha višve arapā edhate grhah, 75, 454 athā jīvah pitum addhi pramuktah, 75, 569. 870 athā jīvrī vidatham ā vadāsi, 73, 454, 529, 544, 801 athā te sakhye andhaso vī vo made, 73 athā te sumnam īmahe, 73 athā te syāma varuna priyāsah, 73 athādītya vrate vayam tava, 74 athā devānām vašanīr bhavātı, 454 athā devānām apy etu pāthah, 74 athā devaih sadhamādam madema, 341 athā na mdra id višah. 341 athū nah sam yor arapo dadhāta (°tana), 74 athā no vardhayā girah (rayım), 74 athā no višvacarşane, 73 athā pitīn suvidatrān upehi (apihi, apīta), 74 athā poşasya poşena, 75 athā bhava yajamānāya sam yoh, 454 athā mano vasudeyāya kṛṣva, 74 athamrtena jaritāram andhi (angdhi), 418

atra pitaro madayadhyam fodhyam

athā yayam ādītya vrate tava, 74 athā satakratvo vūvam, 73 athā sapatnān indrāgnī me, 75 athā sapatnān ("nīn) indro me, 75, 924 athā sapatnī yā mama, 74, 382 athā somasya prayatī yuvabhyām, 74, athāsmabhyam sam vor arapo dadhāta, sahavīrām ("ram) athäsmabhyam rayım däh, 505 athāsya madhyam ejatu, 75, 160 athā svāta surabhayo grheşu, 75, 454, 618, 840 athāsyai (°syā) madhyam edhatām (°tu, ejatu, ejati), 75, 160 athāham anukāmınī ("gāmınī), 45 athemam asyā vara ā pṛthivyāh, 236, 477, 840 athemam enam .. , 810 athem ava sya vara ā pṛthivyāh, 236, 477, 840 athem enam pari dattāt pitrbhyah, 810 athem enam pra hinutat pitrbhyah (pitīnr upa), 810 athaitam pitum addhi prasūtah, 75, 569, athamam jarima navet, 341, 952 atho adhivikartanam (°cartanam), 126 atho annenaiva jīvanti, 94 atho amīvacātanah, 386 atho jīva šaradah šatam, 75 atho ta indrah kevalih. 341 atho pitā mahatām gargarānām, 94 atho mātātho pitā, 96, 386 atho yamasya padbīśāt ("vīśāt), 217, 302, 872 atho ye kşullakā 1va, 96, 262, 386 atho rājann uttamam mānavānām. 94 athorama ulumbarah, 78, 265 atho vayam bhagavantah syama, 74 atho varunyād uta, 325 atho sthūrā atho ksudrāh, 96, 262, 386 adabdham cakşur arıştam manah . . . 179, 802 adabdham mana isiram caksuh , 179, adabdho gopāh (gopah) pari , 493

adayo yirah (adaya ugrah) satamanyur indrah, 471, 489 adah su madhu madhunābhi yodhīh, 68, 379, 533 adëvo virah satamanyur indrah, 471, 489 adārasrd bhavata ("tu) deva soma, 611 adāsyann agna uta samgrnāmi, 45 aditis te (aditis te) bilam grbhnātu (grhnātu) , 116, 958 adītis tvā (aditis tvā) devī višvadevyāvatī (°yavatī) sadhasthe angırasvat ('ngi') , 467, 910, 958 adıtsan vā samıagara janebhyah, 45, 107, 180, 446, 480 adidyutat sv apāko vibhāvā, 838 adīkşiştāyam brāhmano 'sāv amuşya , 888 adīvyann rnam vad aham cakāra, 702 adrohathäh śarkarābhis trivistapi (tribhrstibhih), 222, 384, 640 adrárann (adráann) udahāryah, 356 adevā devavattaram, 401, 840 ado devî (devi) prathamānā pṛthag yat, 68, 525 ado ma agachatu, 990 adomadam annam addhi prasūtah, 110, 569, 870 ado magachatu, 990 ado yad devi prathamānā purastāt, 68, adbhir viśvasya bhartribhih, 677 adbhih sarvasya bhartrbhih, 677 adbhyah sambhūtah (°bhṛtah) pṛthivyaı (°vyā) . 644 adya no deva savitah, 436, 440 adyā krnuhi vītaye (°hy ūtaye), 743, adyā tvā vanvan (vardhan) sureknāh, adyā devāñ (devān) juştatamo hı gamyāh, 936 adyā no deva savītah, 436, 440 adyā mamāra sa hyah sam āna (sahyah samānah), 383, 829 adroghavācam matibhih šavistham (yavı^o), 857 adroghāvitā vācam acha, 52

adveşe (°şye) dyäväprthıvî huvema (huve), 319 adha tvisīmān abhy ojasā krivim (kṛvim) yudhābhavat, 673, 925 adharāncam parā suva (suvā), 431 adharo mad asau vadāt svāhā, 235 adharo vad asau vadā svāhī. 235 adha vāyum niyutah sascata svāh. 454 adha sma (sml) te vrajanam kṛṣṇam astı (astu, °nam astu kışnam), 436, 441 adha syāma surabhayo (syām asur ubhayor) grhesu, 75, 454, 618, 840 adhah sapatni va mama, 74, 382 adhā jivrī vidatham ā vadāthah, 73, 454, 529, 544, 801 adhā jīvema šaradām šatāni, 75 adhā te vişno viduşā cid ardhyah (rdhyah), 649 adhā te sakhye andhaso vi vo made. 73 adhū te sumnam īmahe, 73 adhā te syāma varuna priyāsah, 73 adhā devānām apv etu pāthah, 74 adhā nah sam yor arapo dadhāta, 74 adhā no vardhayā rayım, 74 adhā no viśvacarsane. 73 adhā pitēn suvidatrān apīhi. 74 adhā posasya posena, 75 adhā mano vasudeyāya krnusva, 74 adhāma sakthyor aya gudam dhehi, 641 adhā māsı punar ā yāta no grhān, 75, 454 adhā vayam ādītva vrate tava, 74 adhā vayam bhagavantah syāma, 74 adhā vāyum niyutah sascata svāh, 454 adhā visvāh īrapa edhate grhe, 75, 454 adhā vişitah pitum addhi pramuktah, 75, 110, 569, 870 adhā šatakratvo yūyam, 73 adhā sapatnān indrāgnī me, 75 adhā sapatnën indro me, 75, 924 adhā sapatnīn māmakān, 74, 382 adhā somasya prayatī juvābhyām (yuva°), 74, 504 adhāsyā madhyam edhatām, 75, 160 adhi kranda virayasva, 260 adhi kṣamı prataram didhyanah, 107, 508

adhı kşamı vışurüpam (kşamü vısva°) yad astı (asya, asta), 291, 599 adhı dätre (dhätre) vocah. 104 adhi na indraisām (indresām), 709 adhi bruvantu te 'vantv (avantv) asmān. 907 adhıvāsam(adhi°) yā hıranyāny asmaı. adhi skanda virayasva, 172, 260, 272, 853 adhīvāsam ., see adhio dhṛṣnvojasam adhrstam (dbrsnum ojasā), 237, 818 adhorāma ulumbalah, 78, 265 adho vadādharo vada, 235 adhyaksävänuksattäram, 321, 491 adhvanām adhvapate śresthah svastyasyādhvanah (śresthasyadhvanah, áraisthyasya svastasvādhvanah) pāram ašīya, 321, 707 adhvád eko 'ddhád eko hutád eko 'hutad ekah . sanasanad ekah, 181, 511, 875 adhvä rajääsindrivam, 421 anakşıkaya (°şakaya) svaha, 591 anadvāns (°vān) ca me , 930 anadvāns tapyate vahan (talpate vahān), 503, 867 anandho 'slono 'pisacadhirah, 857 anamitram no adharāt (me adharāk, no adharāk), 142, 907 anamīmūsā Idayā (anamīvāsa nivyā) madantah, 224, 544 anarsarātim vasudām upa stuhi, 292, 579, 878 anasthikāya (°thakāya) svīhā, 591 anagaso adham it samkşayema, 110, 376, 582 anāgaso yathā sadam it samkşivemi, 110, 376, 582 anügü devüh sakuno grheşu (grham nah), 849 anādhṛṣṭam sahasyam (sahasrıyam) sahasvat. 353 anādhrstā apasyo vasānāh, 176, 599, dadhatih (dadaanādhrstāh sīdata tth), 104

anābho mrda dhūrte (°ta), 353, 749, anāmavaidhi ("yedhi) mā risāma indo, 78, 338, 344, 709, 989 anāmi ksatram ajaram suvīryam (suvīram), 323 anārbhava mrda, 353, 749, 862 anāhanasvam vasanam carisnu (jarişnuh, jarisnu), 57, 381 anitır ası, 371 anibhrstā apasyuvo vasānah, 176, 599, anîkair dveso ardaya ('rdaya), 907 anukāšena bāhyam, 371, 550 anukšātre (°khvātre) namah, 190 anugrāsas (°grābhas) ca vṛtrahan, 874 anuttam ā te maghavan nakir nu (nu, nakrnu), 653, 949 anu tvā harino vrsā (mrgah), 235 anu daha sahamuran kravyadah (kayadah), 355, 371 anu no mārstu tanvo yad virustam (vılı°), 261, 813 anu nau śūra mansate (°tai), 710 anupūrvam yatamānā yatı stha (stha, yatışta), 86, 826, 987 anupauhvad (anu po 'hvad) anupahvayet (anuhvayah), 200, 732, 833 anumate 'nu (anu) manyasva na idam ('nv idam manyasva, 'nu manyasva), 847, 907 anu manyasva suyajā yajāma (yaje hi, yajeha), 578, 849 anu mārştu tanvo (tanuvo) yad viliştam, 261, 813 anuyā rātryā rātrīm jinva, 255 anuroham jinya, 550 anurohāya tvā, 550 aruroho 'sī, 550 anuvāya (anuvāsı) rātriyai (°tryaı) rātrīm ("trım, tvā rā") jinva, 255, 770 anuvrtam jinva, 550 anuvrte tvā, anuvrd asi, 550 anuştup (°tuk) paŭktvā saha. 148 anuştup (°tuk) panktyaı (°taye), 148 anuştub (°tum) mıtrasya, 241, 412 anu sapta rājāno ya utābhisiktāh, 63

anu stomam mudimahı (mademahi), 617, 697 anūkāšena bāhvyam, 371, 550 anūdhā yadı jījanad (yad ajījanad) adhā ca nu (adhā cid ā). 578. 840 anūrohenānūrohāvānūroham jinva, 550 anūroho 'sı, 550 anūvrtānūvrte 'nūvrj jinva, 550 anüvrte tvā, anüvrd ası, 550 aneśann asva vā isavah (asvesavah). antarā dyāvāpṛthivī apah ("thivyor apasyuh), 833 antarıkşa uta vā prthivyām pārthīvā yāh), 321 antarıkşam samam tasya väyur upadrastā , 833 antarıkşam puritatā (puri°, puli°, buli°), 263, 532 antarıksam prthivim adrihit, 509 antarıkşasamantasya te väyur upa\$rotā, 833 antarikse adhy ('dhy) āsate, 909 antarikse pathibhir Iyamanah (hīyo. hrīyamānah), 353, 386 antarenānūkāšam, 371, 550 antah **<u><u>subhrāvatā</u>**</u> (Sundhyāvatā) pathā, 173, 244, 305 antas tışthatu (°to) me mano 'mrtasya ketuh, 715 antımıtras (antyami°) ca düre-amıtras ('mitras) ca ganah, 737, 910 andha sthāndho vo bhaksīya, 176, 977 andhāhin (°he, °heh) sthulagudayā (sthūra°, °gudā), 261 andho achetah ('chetah), 910 annapate 'nnasya (annasya) no dehi, 907 annam payo reto asmāsu ('smāsu) dhatta (dhehi), 907 annam me (no) budhya (budhnya) pāhi , 311 annam me (no) budhyājugupas (budh-, 311 nyā°) annam me dehi (dhehi), 103 anyam te asman ('sman, asmat te) ni vapantu senāh (senyam), 319, 907

(anyadyra°) sascima anyavratasya (sascire, sascimah), 379, 420, 818 anyāns te asman nivapantu tāh, 909 anyām icha pitrşadam vyaktām (vittam), 139, 738 anye 'sman nivapantu tah, 909 anyo-'nyo (-anyo) bhavatı asya, 90. anv agnir uşasām agram akhyat (aksat), 190 any adya no anumatih ('nu°), 909 anvādīdhyāthām iha nah sakhāyā. 236, 832 anvāsi, 770 anvitır asi ..., 371 apah pinya, 964 apah prāgāt . ., see apa . apa kşudham nudatām arātım, 201 apa tasya balam tira, 201 apa durhārddiśo (°dviśo) jahi, 410, 869 apanuttau ("tā) śandāmarkau (sa") saha . ., 289 apa (apah) prāgāt tama ā jyotir eti, apa bādhatām duritāni visvā, 201 apamityam apratittam yad asmi, 404, aparihvṛtāh (°hṛtāḥ) sanuyāma vājam, 371 apasmvate tvā, 616 apatcidaghvannasya (apascaddaghvānnam) bhūvāsam. 403 apascāddaghvane (apaścădaghvane) nare (narah), 403 apa sveta padā jahi (apah svetapad ägahı), 134, 201, 384, 817 apasedhan (odham) duritā soms mrdaya (no mrda), 849 apa snehitīr (snīhītim) nīmanā adhatta (adhad rāh, nemanām adadhrām), 77, 110, 356, 616, 696, 802, 824 apas pinya, 964 apah sisasan svar (suvar) apratitah (°tittah), 404 apām rasam udvayasam (udayansam, udayansan), 310, 371 apāgne agnim ('gnım) āmūdam jahi, 910

apām gambhan sīda, 120 apām gambhīram gacha, 120 apānudo janam amitrayantam (amitrā°), 478 apām tvā gahman sādavāmi . 120 apām tvā sadhışı (sadhrışu) sādayāmı, apām napātam ašvinā huve dhiyā ("nā bayantam), 847 apām napād āśuheman ya ürmih kakudman (ürmih pratürtih kakudmān *or* kakubhyān) ., 178, 239 apām naptre jasah (jhasah), 85 apām na yanty ūrmayah, 829 apapaco (°vaco) abhibhute nudasya. apāma edhi mā mrthā na mdra. 78. 98, 205, 344 apāmityam (apām ittham) īva sambhara, 832, 877 apām ojmānam pari gobhir āvītam (ābhṛtam), 221 apām oşadhīnām garbham dhāh (garbham me dāh). 104 apām payaso yat payah, 735 apām payasvad it (yat) payah, 735 apālām ındra (ındras) triş (trih) pūtvī (pūtvē, pūrtvī, pūrtī), 351, 367, 598a, 967 арачасо ., see apapaco apāvrnod duro asmavrajānām (asmadrathänäm), 287, 363 apā vīdhi parivītam (°tim, parivītum) na rādhah, 401, 586 apäśnusnim (apäśnyusnim) apā raksah (ragham), 337 api pūṣā ni ṣīdatu (°tı), 720 apīparo mā rātriyā (rātryā) ahno mā pābi, 791 apīparo māhno rātrīyai (rūtryai) mā pähi, 791 apūtapā ādhūyamānah, 355, 628 apūpakrd astake (apūpaghrtīhute), 83 apo adyūny acīrişam, 244, 498, 754 apo anv acūrisam (acūrsam), 244, 498, 754 apo dattodadhim bhinta, 418 apo divy a acayışam, 244, 498, 754

ano devă madhumatir agrbhnan, 116 apo devīr upasria ("jā) madhumatīh, 446 apo devir madhumatir agrhnan (agrbhrām), 116 apo navanta ürmayah, 829 apo mahi vyayati cakşase tamah, 529, spo mahī vrņute caksusā tamah, 529, apo vrnānah pavate kavīyan ("yān. ksvysn), 786 ano su (su) myaksa yaruna bhiyasam mst. 987 sptubhī rihāņā vyantu vayah, 96, 152, 796, 857 sprajsstām (°185yam) pautramytyum ("martyam), aprajāstvam mārtavatsam, 368, 494, 650, 652 sprivah prati muncatam, 849 aprive prati muños tat. 849 spriye prati muñcatam, 849 sprive sam nayāmasi, 511, 878 spssrssām anudsttānrnāni. 237, 823 apsarasāv anu dattām mah (rpāni), 237, 823 apsarassu vo gandhah, 395 apsarāsu ca yā medhā, 395 apsarāsu ca yo gandhah, 395 apsu dhūtasya deva ... nrbhi stutastotrasya (urbhih sutasya stuta°) ...yo 'svasanir ..., 419, 726, 910 apsu dhūto (dhautam) nrbhih sutah (sutam), 726 apsu dhautasya te ... nrbhih stutasya . . . yo asvesanis . . ., 419, 726, 910, 988 apeu dhautasya te . . nibhih sutasya ..., 419, 726, 988 apeu dhautasya te . . nrbhis stutasya ...yo 'śvasanis . .. 419, 726, 910. 282 apsu dhantasya soma . . . nrbhih suta" ... yo bhakşo asvasanir . 419, 726, 910, 988 sbaddham mano . . . 179, 802

abadhişma rakşo . . ., 209

abhayam vo 'bhayam no astu (me 'stu), abhayam me astu ('stu), 910 abhi kranda vilayasya, 172, 260, 272, abhikhvā bhāsā brhatā susukvanıh, 240, 283, 624 abhi tyam devam savitāram onyoh (ünyoh) kavikratum, 720 abhi dyumnam devabhaktam yavistha (devahitam yavisthya), 121, 315, 579, 857 abhi no vājasātamam, 516 abhinne khilye (khille) ni dadhāti devayum, 38, 408 abhî pra nonumo (no°) vrşan, 952 abhi pra nonuvur (nonavur) girah, 603, 952 abhi priyā dīvas padā (dīvaḥ kavih), 964 abhibhuve ("bhve, "bhave) svāhā, 604, 789 abhi yo na irasyati (no durasyati), 878 abhi yo visvā bhuvanāni caşte, 220 abhiratāh smah (sma ha). 379 abhiramyatām ("thām), 92 abhi rāstrāva vartaya (vardhaya), 97 abhivartah savinsah, 516 abhi vānīr rṣīṇām sapta (saptā) nūṣata, 436, 447 abhi visvāni bhuvanāni caşte, 220 abhivīro abhisatvā ("satvā) sahojāh (sahojit), 986 abhiśaster avasparat (°svarat), 198 abhisikşa rājābhuvam ("bhūvam), 288, 559, 736 sbhišrīr yā ca no grhe. 292 abhişāhe svāhā. 516 sbhi ştana duritā bādhamānah, 582 abhiştir (°tir) yā ca me dhruvā (ca no grhe), 292, 529 abhi syāma vriane sarvavīrāh, 242, 878 abhi sumnam devabhaktam yaviştha, 121, 315, 579, 857 abhi soman mṛśāmasi, 383, 830 abhi somo avīvītat (°vīdhat), 97 abhi sprdha usro vedim tatarda, 618

abbī rtasya dohanā anūşata, 309, 992

abhī na ā vavrtsva, 516, 648 abhī no vājasātamam, 516 abhīmam ("mām, "mān) mahinā ("mā) divam (divah), 181, 505 abhīm rtasya dohanā anūşata. 309. 992 abhīm rtasya sudughā ghrtaścutah, 309, 992 abhīvartah savınšah, 516 abhīsāc cābhīsavī ca, 516 abhīsāt cābhīsāhī cābhimātihas 516 abhīsās (°sāt) cābhīsāhyas ca, 516 abhīsāhe svāhā, 516 abhūn mama (nu nah) sumatau viśvavedāh. 849 abhūr grstīnām (vasānām, v āpīnām, āpīnām, "nām) abhisastīpāvā ("pā u), 46, 360, 740, 824, 953 abhy arcata (arsata) sustutim gavyam āum, 194 abhyaşıkşı rājābhūt ("bbūm, "bhūvam), 288, 559, 736 abhy astham (astham, asthad) viśvah prtana aratih, 983 abhy aham tam bhūyāsam yo asmān , 910 ('smān) dvesti , 309, 992 abhy rtasya sudughā abhyaiti (abhyeti) na ojasā spardhamānā, 711 (°hīt tad amanmahid anāśavah #favah), 828 amā ma edhī mā mṛdhā na (ma) indra, 78, 205, 344 amāyān māyavattarah, 475 amāvāsye samvasanto (samvišanto) mahitvä, 281 amāsi sarvān (sarvān) asi pravistah, amīmadaņta pitaro yathābhāgam āvīsāvisata (°yīsata, avīvīsata), 533 amukthā yaksmād durītād avadyāt, 60, 355, 715 amutrabhūyād adha (adhı) yad yamasya, 578 amum ma iṣūna (amum manıṣūna), 829 amüham asmi sā tvam, 723 amṛnmayam (amṛn°) devapūtram, 954 amṛtenāvṛtām puram (purīm), 600

amestam ası svāhā, 339 amori yaksmād duritād avartvai, 60. 355, 715 amo 'sı sarvān ası pravıştah, 146 amo 'ham asmı sā (sa) tvam, 723 amba nispara (nisvara, nisvara, nismara), 200, 205, 234, 986 ambā ca bulā ca nītatnī (ambā dulā nitatnir) . 179, 529 ambāyai svāhā dulāyai svāhā, 179 ambhah (ambha) sthāmbho vo bhaksīya, 176, 977 ayam yah puro vibhinatty ("naty) ojasā, 392 ayam yo asya yasya ta idam sirah, 738, ayam yo 'sı yasya ta ıdam sırah, 738, 907 ayam satrun jayatu jarhışanah (jarhisānah), 635 ayam sa vām ašvinā bhāga ā gatam, 612 ayam sa śińkte (śińte) yena gaur abhīvṛtā, 418 ayam sahasram anavo dršah V1dharma (°mā), 460, 833 avam sahasram ā no dṛśe vidbarmanı, 833 ayam su vām ašvinā bhāga ā gatam, 612 ayanam mā vīvadhīr (viba°) vīkramasva, 209 ayann arthuni krnavann apänsi, 482 ayam no agnir varivas (°vah) krnotu, avavānām ādhīpatyam, 485 ayasā manasā dhrtah, 401, 402, 502 ayasā havyam ühişe, 502, 739 ayasthunam (ayah", ayas", ayasthunāv) uditā ("tau) sūryasya, 92, 188, 237, 824 ayasmayam vicrtā (viśrtā) bandham etam, 195 ayasmayan vı erta bandhapasan, 195 ayad ındrägnyoś (agnir ındrägniyoś) , 792 ayā no yajūam vahūsi, 739 ayāvānām ūdhipatyam, 485 ayııs cugue 'sy anabhısastıs ('tis) ca,

ayā (ayāh, ayās) san (ayāsā) manasā hitah (krtah, krttah), 401, 402, 502 ayā (ayāh, ayās) san (ayāsyam) havvam ühise, 502 avāsā manasā (vayasā) kṛtah, 401, 402, 502 ayā somah (soma) sukrtyayā, 380 ayuktāso abrahmatā vidasāma (yad asan), 255 ayupitā yonih, 113 ayebhyah kitavam, 253 avoddheva (avodhveva) durmada ä hi juhve, 347 sramgamāva jagmave (jagmave). 248 aranyāva srmarah, 316, 490 arāddhyā edidhişuhpatım (arādhyai didhisūpatim), 381, 474, 554 arāyo asmān abhiduchunāyate, 248 arālāg udabhartsata, 90 arāvā vo no abhi duchunāvate, 248 arıstvä avyathyai . abhibhūtyai svähä. 644 arejetām (arejayatām) rodasī pājasā grā. 745 aredatā manasā devān gacha (gamyāt, manasā tac chakeyam), 269 arepasah manyumattamāś (°mantas) cite goh (cita goh, cidakoh), 47. 61. 826 arghah, arghyam, arghyam bhoh, 123, 321 arcışātrıno nudatam praticah, 156 arcışā satrûn dahatam pratītya, 156 artham rihānā vyantu vayah, 96, 152, 796, 857 arthas ca ma emas (ca mā ema, ca me yāmas) ca me. 803 ardhamāsyam prasūtāt pitryāvatah, aryamā te hastam agrabhīt, 116 aryamāyātı vṛṣabhas tuvişmān, 509 aryamā hastam agrablīt (agrabīt), 116 aryo nasanta (nah santu) sanisanta (°tu) no dhiyah, 287, 828 arvān ehi somakāmam tvāhuh, 512 arhanīj ā āpah, 123, 321 arhann idam dayase viśvam abhyam (abbhuvam), 392, 790

alarsırātım vasudām upa stuhı, 292, 579. 878 alıvandaya svaha, 579, 627, 862 alubhitā vonih. 113 avartvai badhāvopamanthitāram, 209, avakraksınam vışabham yathüjuram (yathā juvam), 267, 835 avakro 'vithuro ('vidhuro, 'vithuro 'ham) bhūvāsam, 77 avanhya muhyika, avanhyaka muhvaka, 595 ava jyām iva dhanvanah, 24, 159, 594 azatasva visariane, 25, 164 avatatya dhanus tvam (dhanus tvam). 958 ava tara nadisv ä. 401, 833 ava tasya balam tira, 201 avatasya visarjane, 25, 164 avattaram nadīsv ā. 401. 833 avattaro nadīnām, 401, 833 ava dikşüm asrkşata (adastha) svahu, 201 ava devānām yaja hedo agne (yaje hīdyāni, yaje hedyāni), 325, 696 ava devān yaje hedyān, 325, 696 ava dyām ıva dhanvınah, 24, 159, 594 ava dronām ghrtavānti sīda ("vanti roha), 501a avadhışma rakşah, 209 avanty asya pavitäram (pavi°) āśavah, 531 ava bādhatām . 201 avabhrtha nicumpuna (nicankuna, nicuñkuna), 150, 605 avabhṛthaś ca svagākāraś (sugā°) ca,741 avamais ta ürvais te , 750 ava rudram adimahı, 535 avartyaı vadhüyopamanthıtāram, 209, avavyayann asıtam deva vasma (vasvah), 240 ava šveta padā jahı, 134, 201, 384, 817 ava sedum trşnām kşudham jahı, 201 ava somam nayāması, 383, 830

avasphūrjan didyud (vidyud) varşan

varşans tveva rāvat) svīhā, 869

bhūtar āvrt (varşans tvesa rāvat.

ava sma durhanāyatah (durhṛn°), 4, 39, avasyur ası duvasyan, 554 avasyuvātā brhatī ("tīr) na (nu, tu) šakvarī (°rīh), 381, 614 avasyūr ası duvasyān, 554 avād dhavyānı surabhīni kṛtvā (kṛtvī), avātīratam bīsayasya (prathayasya) seşah, 69, 658 avā no devyā dhiyā (kṛpā), 421, 824 avānyāns tantūn kirato dhatto anyān, avāmpa rudram adimahi (adī°), 535 avāra iksavah pāryebhyah (pārīyebhyah) . ., 325, 786 avārāya kevartam, 41, 325, 708 avāryāni paksmāni pārvā iksavah. 325 avāryāya mārgāram, 325 avāsrjo apo ('po) achā samudram, 907 avıkşobhäya (°kşodhāya) paridhin dadhāmı, 176 avidahanta (°tah) srapayata, 980 avinastūn avihrutān (°hrtān), 683 avımuktacakra (°rā) ūsīran. 139. 235. 643, 861 aviraghnir ud ajantv (acantv) āpah, 53 aviraghno (°ni) viratarah (°tamah, vīravatah) suvīrān (suševān), 123 avivarata vo hi kam (hikam), 817 avebhyah kitavam, 253 avocāma kavaye medhyāya, 109, 230 avo devasya sānasi, 421 avyo (avyā) vāre (vāraih) pari prīyah (prayam), 381, 706 avradanta vilitä, 271 asisliksum sisliksate (aslılıpu slılışate), 195 asimahı tvü, 617 asīrsānā ahaya (°no 'baya) iva (°na avāhavah), 512 asūšubhanta yajūiyā rtena, 174, 286, 292 aśmańs (aśman) te kșut, 932 asrathnan drdhävradanta viditä, 271 aśrīram (aślīlam) cit krnuthā ("thāt) supratikam, 261

aśrīrā (aślīlā) tanūr bhavati, 261 aśrubhih prsvām (prusvām), 40, 680 aśronā, see aslonā. . aślilipu . , see asisliksum aslīlam, and aslīlā, see asrīr°. aślesā naksatram, 265, 473 aślonā (aśro°) añgair ahrutāh (aślonāngair ahrtā, ahrutāh) svarge, 261. 683, 819, 980, 990 aslono 'piśäcadhītah, 857 aśvam jejñānam samrasya (salilasya) madhye, 264 aśvavat soma viravat, 467 aśvasya vāje (krande, krandye) puruşasya māyau, 315 aśvān anaśśato (anaśyato, anahsato, anašvato) dānam, 255, 408 aśvā bhavata (°tha) vājinah, 90 aśvāvat soma viravat, 467 aśvinā gharmam pātam hārdvānam (hārddivānam, pātam aharvyānam, pıbatam härdrānum), 267, 764 aśvinā bhisajāvatah (°tam, °ta), 379 ašvinendram na jägrvi (°vi), 525 aśvinau dvyaksarena (*ksaravä) prūnāpānāv (°nā) ud ajayatām, 886 asvibhyam tiroahniyanam (tirohnyānām) somānām anubrūhi, 787, 910 asyıbhyam tırohnyan soman prasthıtān presva. 787. 910 ašvibhyām pradhāpaya (pradāpaya), 104 asādham (asālham) yutsu . . ., 474 aşādham ugram sahamānam ābhih, 474 asādhāya sahamānāya vedhase (mīdhuse), 170, 235, 696 astabhyah ("yah satebhyah) svāhā, 495 aştasthûno dasapakşah, 495 nştāpakşām dašapakşām, 495 aştābhyah (°yah satebhyah) svāhā, 495 astrām tūdam pratīnāhā (tālam pratīnāham), 271 asamheyam parābhavan, 23, 121, 124 asadan mātaram purah, 853, 861 asanan mataram punah, 853, 861 asapatnah kilābhuvam, 602 asapatnā kilābhuvam (°bhavam), 602

asapatnā sapatnaghnī (°nıganī), 588 asambādham badhyato (ma°) mānavānām (°vesu), 241

asambādhā yā madhyato mānavebhyah, 241

asambhavyam parābhavan, 23, 121, 124 asammṛṣṭo jāyase mātroh (mātṛvoh) śucih. 368

asāv (asā) anu mā ., 888 asā (asāv-asāv) upahvayasva, 886 asīkny (°kniy) asv osadhe, 777

asiknyā (°knıyā) marudvīdhe vitastayā, 791

asum gharmam dıvam (svar) ātişthānu, 360

asunītāya ("thāya) vodhave, 93 asūrtā ("te) sūrtā ("te) rajaso ("sı) vimāne (nıṣatte, "tā, na sattā), 293, 578. 828

asüşudanta yajñiyā rtena, 174, 286, 292 asrūmukho rudhirenābhyaktah (°āvyaktah), 220

astabhnād dyām vṛṣabho (dyām ṛṣa°) antarikṣam, 359

asti hı şmā (astu sma) te suşminn avayāh, 436, 442, 987

astrto nāmāham ni dadhe (pari dade), 104

asthabhyah (asthi°) svāhā, 591

asthūri nau (nau, no, no) gārhapatyam (°tyān) . , 732, 950

aspārṣam (°śam) enam śataśāradāya, 292

asmadrātā (asmaddātrā, °rātā madhumatī, °tīr) devatrā gachata (gacha), 357, 800

asmadryak (°driyak) sam mimīhi šravānsi, 784

asmadryag (°driyag) vävrdhe viryāya, 784

asmabhyam dattām (dhattām) varunaš ca manyuh, 105

asmabhyam indra varivah (variyah) sugam kṛdhi, 249, 541a

asmabhyam mahi varivah sugam kah, 249, 541a

asmān u devā avatā haveşu, 742, 924 asmānš cakre mānyasya medhā, 930 asmākam yonā (yonāv) udare suševāh, 886

asmākam ańśum (anśam) maghavan puruspṛham, 618

asmākam abhūr haryasva medī, 231, 263

asmān cakre mānyasya medhā, 930 asmān (asmān) citrābhir avatād abhistibhih. 930

asmān u devā avatā bhareşv ā, 121, 267, 742, 924

asmān devāso 'vatā haveşu, 121, 267, 512, 742

asmān sīte payasābhyāvavītsva, 849 asmāsu nīmnam dhāh, 509

asmin kşaye pratarām dīdyānah, 107, 506

asmin goşthe karīşınīh (°nah, purīşinīh), 152, 617

asmıŭ (asmın) chūra savane mādayasva, 937

asmin nara indriyam dhattam ojah, 105 asmin brahmany (°mann) asmin karmany (karmann) . , 928

asmin rāstram adhi sraya, 704 asmin vayam samkasuke (°kusuke), 605

asme indrābrhaspatī, 704 asme karmane jātah. 704

asme kşatrāni dhārayer anu dyūn, 704 asme devāso vapuşe cıkıtsata, 704

asme dehi . , see asme dhehi

asme dyāvāpṛthivī bhūri vāmam, 704 asme dhatta vasavo vasūni, 704

asme dhārayatam ("tām) rayım, 704 asme dhehi (dehi) jātavedo mahi śravah, 105

asme prayandhı maghavanı rılşin, 704 asme raştranı dharaya (raştranı adhıs-raya), 704

asme rāstrāya mahi sarma yachatam,

asmai indrābrhaspatī, 704 asmai karmane jātah, 704

asmaı kşatranı dharayantam agne, 704 asmaı dyavapṛthıvi bhūrı vämam, 704 asmai dhatta vasavo vasūnı, 704

asmai dharayatam rayım, 704

asmai prayandhi maghayann rijsin. 704 asmai rästräva mahi sarma vachatam. 704 asya kurmo (kulmo, krnvo, krnmo) harivo medmam tvā, 231, 263 asya te sakhye vayam, 340 asya pītā (pītvā) svarvidah, 367 asya sutasya svar na (na), 949 asya snuşā ávašurasya prašistim, 857 asya hotuh pradišy (prašisy) rtasya vāci. 292 asyā avata vīryam, 449 asyām devā abhī samvišantah, 340 asyai nūryā upastare (°stire), 573 asredhanta itana vājam acha, 52 aham satrün jayamı jarhışanah, 635 aham hv ugras (ūgras) tavisas tuvisman, 567 aham hy ugro (ugro) maruto vidanah, 567 aham dandenāgatam, 580 aham id dhi pitus (pituh) pari, 967 aham pratnena manmanā (janmanā), ahar-ahar aprayāvam bharantah, 117 ahar-ahar balım ıt te harantah, 117 ahar divābhir ūtibhih, 165, 272, 272a, 324, 360 ahalag (ahalam) iti vaficati, 511 ahaścarebhyah, 488, 690 ahā anadatā hate. 888 ahā arātım avidah (avartım avidat) syonam, 806 ahā neta sann (ned asann, netar asann, ahād eta sann) avicetanāni (apurogavāni), 62 ahā yad dyāvo (devā) asunītim ayan (āyan), 482, 803 ahāv anadatā hate, 888 ahāh śarīram (ahāc char°) payasā sametı (sametya), 737 ahım dandenagatam, 580 ahım budhnyam ('nıyam) anu riyamānāh (samcarantīh, anv īyamānāh) 353, 784 ahir asi budhnyah (°niyah), 787

ahır jaghāna kım (kam) cana, 578

ahir dadarsa kam cana, 578

ahir na jūrnām (ahir ha jīrnām) ati sarpatı tvacam. 628 ahirbudhnya mantram me 'iugupah ('1ū°) , 548 ahirbudhuva mantram me pāhi, 787 ahır budhnyo ("nıyo) devatā, 787 ahīti ca sarvān (sarvān) jambhayan (°ya), 936 abedatā manasā devān gacha, 269 ahedatā ("latā) manasedam juşasva, ahe budhniya mantram me gopāya, 787 ahorātrayor vṛṣtyā , 803, 840 ahorātrābhyām purusah samena (ksanena) - 420 ahorātre ūrvastīve (°sthīve) , 86, 803, 840 ahnānsi rātryai , 255 ahnā yad enah kṛtam astı pāpam (kımcit, enaš cakrmeha kimcit), 849 ākaršye karšyo yathā, 290 ākūtım (°tam) agnım prayujam svāhā, ākūtım (°tīm) devīm manasah (°sā, subhagām) puro dadhe (prapadve) 'gnaye (agnaye) īkūtyai prayuje svābā, 910 ākramanam kuşthābhyām. 49 ākrayāyā ayogūm (ākrayāyāyogūm, ākram°), 990 , 508 ākrān samudrah ākhuh kašo mānthālas ("lavas, māndhālas) te pitrnām, 77, 489, 597 ākhum tvā ye dadhire devayantah, 193, 296, 835 ākhuh srjayā šayandakas te maitrāh (šayāndakās te maitryāh), 315, 489 , 508 āgann apäna āganma mitrāvarunā varenyā (varena, varenyam), 326 āganma višvavedasam, 508 äganma vṛtrahantamam, 508 ā garbho yonım etu te, 711 ā galgā dhavanīnām (galdā dhamanīnām), 144, 225 āgniš ca dahatam pratī, 512 āgne yāhi sušastibhih, 509

āgrayanas (āgrā°) , and °yanas, °yanāt, °yano , 492

ā gharmo agnim rtayann asūdi (°dīt), 533, 840

ā gharmo agnir amṛto na sādi, 533, 840 āngūṣānām avāvasanta vānīh, 490, 599, 720

āngūşyam pavamānam sakhāyah, 490 720

āchettā te (vo) mā rīşam (rīşat, mārşam), 753

ājagan rātrī sumanā īha syām, 508 ājīm tvāgne. , 360

ājim na girvavāho jigyur asvāh, 810 ājim na jagmur girvāho asvāh, 810 ā juhotā (°ta) duvasvata. 442

ājyasya kūlyā upa tān kṣarantu, 565 ānjanena sarpiṣā sam višantu (spṛśantām, mṛśantām), 200, 205, 235, 375, 640

ātapatī varsan virād āvīt svāhā, 168 ā tasthāv (tasthā) amītam dīvi, 888 ātīr vāhaso darvīdā te vāyave, 325, 529 ā tistha mitravardhana (°nah), 380 ātī vāhaso darvīdā te vāyavyāh, 325,

ā te garbho yonim etu (aitu), 711

ā te yonım garbha etu, 711

ā te suparnā ammanta (°tan) evaih, 308 ātmann (°many) evānupašyati, 928 ātmam indrāya pyāyasva, 224, 831 ātmānam ta āgrāyanah (āgra°) pātu, 492

ātmāsy ātmann ātmānam (ātmanatmānam) me mā hinsīh, 401, 836

ā tvam (svam) indrāya pyāyasva, 224,

ā tvā parišritah (°srtah, °srutah) kumbhah (°āh), 275, 626, 682, 831

ā tvā prāpann aghāyavah (adyā°), 832,

ā tvā vahantu harayah sucetasal. (sace°), 612

ā tvā subhava (suhava) sūryāya, 119 ā dadhnah kalaśair (*śīr, *śam) aguh (ayan, gaman, upa, ayann ıva, aırayam), 701 ā daršati (darşate) kavasā bhūryojāh (sapta dānūn), 292

ādāyo virah satamanyur indrah, 471, 489

ādītyam garbham payasā sam atīgdhi (atīdhi, atījan), 418

ādītya nāvam ārukṣah (ārokṣam), 715 ādītyasya vratam upakṣiyantah (kṣyantah). 795

ādītyān chmasrubhih ("yān sma", "yān sma"), 937

ādityānām patvānv (patmānv) ihi (ehi), 240, 694

ādītyānām prasitir (°srtir) hetir ugrā, 637

ādītyā rudrā vasavas tvedate (tvel°, tenute), 271

ādityāsah sumahasah (sa°) kmotana, 612

ādītyās te citim (citam) āpūrayantu, 587

ādityās tvā prabrhantu (pravr°) jāgatena chandasā, 212

ādityebhyah preşya (ādityebhyah) priyebhyah ..mahasvasarasya (mahah sva°).., 980

ādītyebhyas tvā pravībāmi..., 212 ād id antā adadībants pūrve, 341, 835 ād id drāvānībis anaklets.

ād id dyāvāpṛthivī aprathetām, 341 ād id dhotāram ny asādayanta (aṣā°), 983

ā devo yāti bhuvanāni pašyan (bhuvanā vipašyan), 840

ādhyaksyāyānuksattāram, 325, 491

ā na indo mahīm isam, 353 ā na indo satagvinam (šā°), 512

ā na indra mahīm isam, 353

ānandā modāh pramudah, 713

ānando modah pramodah, 713 ā nah śṛnvann ūtibhih sīda sādanam,

376

ā na (nah) stuta upa vājebhir ūtī, 977 ā nu tac (tyac) chardho divyam vmīmahe, 345

ā no agne sucetunā (suketunā), 126

ā no gosu višatv ausadbīsu (osc, ā tanusu), 730

ā no jāhi taprsī janesu (janisva. janeşv ā). 693, 742, 826 ā no višva Iskrā (višve askrā) gamantu ("in) deval, 473. antarıkşanı pethicim adenhit, 509 Intrimukhah . , 386, 511 anyavakşid (anya vaksad) vasu varvăpı, 481 Spataye tv3 grbn3ms, 867 apataye tvi. tanūnaptre šākvarāva šakvana (°tre šakmane šīkvarīva šakmann) ojisthūya, 240 ăpaprivăn (apaprvan) rodast antankşam, 671 apah sundhantu mainasah, 173 āpas tad ghnantu sarvadā (te sadā), āpas tvā sam arinan (arınyan, āpah sam arinan), 366 ā pitaram vaišvānaram avase kah (kuh), 611 āpura stā... 90, 319, 568 a pustam etv a vasu, 309, 992 āpūryā sthā . . ., 90, 319, 56S ā pūşī etv ā vasu, 309, 568, 992 āprno 'si samprnah (aprnosi samprna) . .. 293, 380, 827 āpo agre višvam āvan, 253 āpo adyāny acārişam, 244, 495, 754 āpo asmān (mā) mātarah sundhayantu (sūdayantu śundhantu), 109, 286, 302 apo grhesu jūgrata, apo jūgrta, 662 āpo devīķ pratigrbhņīta ("grhņīta) bhasmaitat, 116 apo devir agrepuvo agreguvo , 910 āpo devīh svadantu (sadantu) . , 371 āpo deveşu jāgratha, 662 āpo malam iva prānaiksīt (prānijan), 700 āpo mā . . ., sec āpo asmān . . āpo me hotrāšansinah ("nyah), 328 āpo ha yad brhatīr (yan mahatīr) višvam (garbham) āyan, 253 Jpo havihşu jägçta, 662 āptam manah, 874 aptye sam nay amasi, 511, 878 āpiājadhvam aghnivā (aghnyā) ..., 757

āprā (āprād) dy āvāprthu i antariksam. äbbiş trăham sūtavai ("ve), 705 ābhur anyo pr ('va) padyatām, 201 (ābhūr) asvs nisangadhih (°thib), 77, 93, 98, 554 ā mā gantīm ("tam) pitarā mātarā ca (yuvam), 452 ā mā goşu višaty ā tanūsu. 730 ā mā varco 'gninā dattam etu, 907 ā mīšiso (ām āšiso) dohakāmāh. 836. ā mā stutasya stutam gamyūt (gamet), 357, 713, 803 ā mā stotrasya stotram gamyāt, 357, 713, 803 äyataye tvü grhnimi, 867 ā yat tṛpan maruto vāvašānāh (°nah), ä yam (äyan) narah sudānavo dadāśuse, 413, 831 āyann arthāni kṛnavann apānsı, 482 ā yāta pitarah somyāsah (somyāh), 747 ā yā dyām (divam) bhāsy ā pṛthivīm orv (urv) antarıkşam, 718 ā yābi tapasī janeşu (janişva, janeşv 3), 693, 742, 826 ā yāhi sūra haribhyām (hariha, barī iha), 545 ā yāhy arvān upa vandhureşthāh (ban°), 213 āyuhpati rathamtaram (āyuh pratirathamtaram) . , 354, 840 āyukrd āyuhpatnī svadbā vah, 962 āvuksi sarvā osadhīh, 140, 255, 805 äyur dadhad yajñapatāv (°tā) avihrutsm, 888 āyur dadhānāh prataram naviyah, 575 āyurdā agne jarasam vīnānah, 196, 267, 64C, 854 āyurdā agae 'si, 100 āyurdā agne havişo juşānah (havışš vrdhānah), 196, 267, 643, 854 āvurdā asi 100 āyurdā deva jarasam vīnīnah (gīn°), 196, 267, 643, 854 āyur dehi, 103 ãy urdhā agne 'si, 100

āvurdhā ası, 100 ayur dhehi, 103 ayur no dehi jivase, 105, 106 āyur no viśvato dadhat, 105 āyur brhat tad asīya tan māvatu (mām avatu), 812 äyur mayı dhehı, 100, 102 āyur me dehi (dhehi, dāh, dhattam), 100, 102, 103 āyur vasāna upa vetu (yātu) šeşah (sesam), 803 āyus ca prāyus ca cakṣas ca vicakṣas (caksuś ca vicaksuś) ca prān cāpān (cāvān) ca. 202, 608 āyuşkrte svāhā, 716 āyuskrd āyuspatnī svadhāvantau, 962 āyuş te visvato dadhat, 105 āyuşmān (°mān, °mān, āyuşyam) jaradaştır yathasat (°sam, °sanı), 936 āyusmān agne havişā vrdhānah, 196, 267, 643, 854 ayu (ayuh) stha, 977 āyoh patmane svāhā, 240, 967 a yonim garbha etu te, 711 āyobhavyāya catuşpadī, 319, 421 ā vo višvāni šavasā (šravasā) tatāna, 349 avoskrte svaha, 716 āvos patvane svāhā, 240, 967 āranāya sṛmaraḥ, 316, 490 ā raśmīn (raśmim) deva yamase (yuvase) svasvān (°vah), 235, 617 ārādhvai didhisūpatim, 381, 474, 554 āruroha tve sacā (tvayy apı), 747 āre asman (asmin) ni dhehi tam, 578 āre śatrun (āreśatrum) krnuhi sarvavīrah (°ram), 820 ā rohantu janayo yonum agre, 863 ārtavā adhipataya āsan, 652 ārtavā asrivanta, 652 ārtavo 'dhipatir āsīt, 652 ārtyai janavādinam, 652 ärdrah prathasnur (pṛthusnur) bhuvanasya gopāh, 609, 658 āryamā yāti vṛṣabhas turāṣāṭ, 509 ārvān ehi somakāmam tvāhuh, 512 hantrimukhah ālıkhann anımişah , 386, 511

ālebhānād retibbir yātudhānāt, 262 ā va indram krīvīm (krvīm) yathā, 673 āvat tam indrah sacyā dhamantam. 407, 826, 873 ā vatso jagatā (jāyatām, jagadaih) saha, 60 āvartam indrah śacyā dhamantam, 407, 826, 873 ā vah somam nayāması, 383, 830 avitte dvavaprthivi rtavrdhau, 97, 466, 665, 871 āvittau mitrāvarunau dhṛtavratau, 466, 665, 871 āvītsī sarvā oṣadhīh, 140, 255, 805 āvinne dyāvāprthivī dhṛtavrate, 97, 466, 665, 871 avinnau mitravarunav rtavidhau, 466, 665. 871 āviş (āvih) kŗnuşva darvyāny agne, 967 ā vīram prtanāsaham ("saham), 984 ā vṛścyantām (vṛścantām) aditaye durevāh, 334 avo yudhyantam vrsabham dasadyum, āvyuşam jāgṛtād (jāgṛyām, °yāmy) aham, 674 āšātīkāh kṛmaya (kri°) īva, 668 āsise rādhase mahe, 627 āšīr na (nā, ma) ūrjam uta saupraıästvam (supra°), 724, 949 ā šīrsnah šamopyāt (sam°), 277 āśuh kāsthām (gā°) ivāsaran (°ram), 48 āšum jayantam anu yāsu vardhase, 287, 339, 618, 840 āšum tvājau dadhire devavantah, 193, 296, 835 ã suse rādhase mahe, 627 āśūn ıva suyamān ahva ūtaye, 843 āśūn huve suyamān ūtaye, 843 āśresā naksatram, 265, 473 , āṣādham ugram āşādbam yutsu . 474 āşţa (āşţhāh) pratışţhām avidad dhi (avido hi, avide Jodan) nu) gādham, 86 āsannā udabhir yathā, 90 āsann ā (āsan nah) pātram janayanta ("tu) devāh, 383, 837

Isannışûn hrtsvaso mayobhûn, 180, 298, 386, 634, 693, 820 āsann esām apsuvāho mavobhūn. 180. 298, 386, 634, 693, 820 ā samudrā acucyavuh, 144, 600, 829 asam manah, 874 ü sīm ugrā acucyavuh, 144, 600, 829 ā sutrāvne sumatim āvrnānah. 60. 287. 294, 355, 854 ā soma suvāno (svāno) adribhih, 794 āstām jālma (jalma) udaram śranšayitvā (sradsayitvā), 277, 489 āsmā ašrnvann ūšūh, 873 āsmāsu nrmnam dhāt. 509 āsminn ugrā acucyavuh, 144, 600, 829 ā svam ındrāva . see ā tvam āhalag (°lam) iti vancati (sarpati), 511 āhnārasya parasyādah, 511 ımkārāya (°krtāya) svāhā, 386, 544 ichanto 'paridākrtān, 159, 186 ıda (ıdā) ehr. 272 idaprajaso (idā°) mānavīh, 475 ıdā manusvad ("yad) ıha cetayantī, 248 idāvās (°yāh) padam , 964 ıdāvatī dhenumatī hı bhūtam, 272 ıdāvān (°vān) eso asura prajāvān, 925 ıdāsmān anu vastām ghṛtena, 271, 665, idito devair harivan (°van) abhiştih, ıdaıvāsmān (ıdaıva vām) anu vastām vratena (ghṛtena), 271, 665, 924 ıtı cıd dhı tvä dhanā jayantam, 68, 735 ıtıdam vısvam bhuvanam sam eti (vi yātı), 803 ıto dharmanı dharayan, 578 ıdam rādhah pratı grbhnihy (grhnihy) afigirah, 116 ıdam rādho agnınā dattam āgāt, 907 ıdam vatsyāmo bhoh (vatsyāvah), 237 ıdam varco agnınā dattam āgāt (āgan), 907 ıdam ta ekam para ü ta (uta) ekam,

547, 831

dhyät, 614

ıdam tam adhitışthāmı (abhı°). 172

ıdam te tad vı şyāmy āyuşo na ma-

664

ıdam devänäm ıdam u nah (ıdam nas) saha, 971 idam aham rakso 'bhi (raksobhih) sam dahāmi (sam ühāmi), 383. 826 ıdam aham sarpānām grathnāmı (krnatmı, krtsnāmı), 47.665 ıdam aham amusyāmusyāyanasya pāpmānam ava (apa) gūhāmi, 201 ıdam brahma pıprhı (pipîhi) saubhagāya, 640 ıdam me prāvatā vacah, 449 ıdāhna ıd āharam asīya, 709 ıdhmasyeva prakşāyatah (prakhyāyatah), 27, 191 ınatamam āptyam (āptam) āptyānām, ino višvasya bhuvanasya gopāh, 693 ındur ındum avagāt (°gan, upagāt, apā°), 201 ındra ıyarışto akşatah (akşıtah), 576 ındra ukthebhir mandişthah (bhand°), 242 indra rbhukşā marutah parı khyan (ksan), 190 ındra rbhubhır brahmanā samvidānah, 108, 640, 919 ındra enam (enam) prathamo adhy atisthat, 950 ındra enam (enam) parāšarīt, 702, 950 ındrah karmasu no 'yatu, 380 ındrah krtvā maruto yad vašāma, 380, 664 ındrah patis tuviştamo (tavastamo) janeşv ä, 596, 604, 742, 964 ındrah püśena sıktvä vah (vah sıktvä), 367, 383, 819 ındram yajne prayaty ahvetam (āh°), ındram vājam vi mucyadhvam, 52 indram sa rchatu yo martasyai (°syā) diśo 'bhidāsatı, 910 ındram sa dıśām devam devatānām rchatu yo maitasyai diśo 'bhidāsati, 910 ındra karmasu no 'vata, 380 ındra kratvā maruto yad vašāma, 380,

indragniyor (ognyor) aham devayajyındra dartā purām ası, 107 ındra dhartā purām ası, 107 ındrapäsena sitvä, 367, 383, 819 ındram agnım ca vodhave, 694 brhaspatiındram ädıtyavantam , 239 mantam (°vantam) ındrartublır brahmana vävrdhanah, 108, 640, 919 indravanta (°tah) stuta (studhyam), 977 ındravanto maruto vışnur agnıh, 467 ındra väjeşu no 'va (ava, vaha), 907 indravān brhad bhās svāhū, 467 ındravan svavan brhad bhah, 467 ındravāhāv ("hā) rbhavo vājaratnāh, 888 ındras ca mrdayāti (mṛl°) nah, 271 ındra (ındrah) śrutasya mahato mahānı, 380 ındra sayugbhır indra sutesu someşu, 380 indra somam ımam pıba (somam pıbā mam), 432, 444 ındra somasya pītaye, 380 ındra stomena pañcadasena . 380 indras patis tavastamo janeşu, 596, 964 ındrasya tvā bhāgam somenā tanacmı (tanakmı), 127 indrasya nu viryāni pra vocam (nu prā vocam vīr°), 437, 449 ındrasya priyam pātha upehi (pātho apīhi, 'pīhi), 910 , 699 ındrasya vaımırdhasyāham ındrasya suşmam irayann apasyubhıh, ındrasyāham vimrdhasya , 699 ındrasyāham devayajyayendriyavî (°vān, °yavān) bhūyāsam, 467, 598 indra svadhām anu hi no babhūtha, indra svayugbhir . . , 364 indrah suteşu someşu, 380 ındrah sürah prathamo vısvakarmā, 820 ındrah somasya pitaye, 380 indrah stomena pancadasena ındrah svadhām anu hı no babhūtha, 380

avendriyāvy annādo ("driyavān vīryayan) bhuyasam, 467, 792 ındragnyor (ogniyor aham) ujjıtım antijiesam, 792 bhägadheyi indragnyor (°gniyor) (°vih. °vis) stha, 792 ındrānyai kīršā (kīrsā), 290 ındrādhipatıh ("patyaıh) pıprtād ato nah, 700 , indrāpāsya phaligam, 46, 545, 811, 867 indrāva rsabhena. 919 indrāva tvā bhāgam somenātanacmi, 127 ındrava tva susuttamam, 397 ındraya tva srmo 'dadat (śramo dadat). 277, 664 ındrāyayāsya sepham alikam ..., 46, 545, 811, 867 ındräyarşabhenüsvıbhyam sarssvatvai. 919 ındraya vacam vi mucyadhvam, 52 ındraya suşütamam (susuttamam), 397 indrāvatam karmanā (kāvyair) dansanābhi^L, 77 indravathuh (°dhuh) kayvair dansanābhih, 77 indrāvanto maruto visnur agnih. 467 indrāvarunā algābhyām, 888 indrāvān svāhā, 467 indrāsūrū janayan višvakarmā, 820 ındrena devir (devair) virudhah samvidānāh, 701 indrena ma ındrıyam dattam ojah, indrena yujā (sayujā) pramṛnīta (pra-[mr]nītha) šatrūn. 90 ındremam prataranı (oram) krdhı (naya), 506 ındre suvānāsa (svānāsa) ındavah, 794 ındro ıyeşthanam (ıyaısthvānām, °thyāya), 321, 707 indro nāma śruto grne (gane), 633 ındropānasyakehamanaso indro balam rakşıtāram dughānām, 210 indro marudbhir rtuthā ('dhā) krnotu. 75

ındro me sarma yachatu, 234 indro yajvane prnate ca siksati (grnate ca siksate), 153 indro yad abhinad valam (balam), 210 ındro valam rakşıtaram dughanam, 210 ındro vah sarma yachatu, 234 ındro vidyüt saha rsıblılı (saharsibhih), 919 ındro vo 'dya parüśarait, 702 indhana enam jarate (jarite, janate) avadhth, 861 ınvakă (°gā) nakşatram, 48 ima udvāsīkārina ime durbhūtam akran, 59, 126, 520a, 875 ımam yaıfıam syadhaya ye yajante (dadante), 159, 741 ımam yajñam juşamana ("nav) upetam, imem yajñam avantu (avatu) no (vā' ghrtūcīh (°cī), 281 ımanı logam (lokam) nıdadhan mo aham risam, 46 ımam ça yaınam sudhaya dadante, 159, 741 ımam tam abhıtişthāmı, 172 imam tam punar Edade 'yam ('ham), 256, 845 ımaın agne camasaın mä vı jıhvarah (11°), 519 ımam ındra vardhaya kşatriyam me (kentriyünüm), 826 ımam ü (u) şu tvam asmākam (tyam asmabhyam), 252, 547 ımanı me agadam krta (krdhı), 849 ımam me varuna srudhī (°dhı), 518 ımı uddhasıcarina ımo durbhūdam nkran, 59, 126, 520a, 875 ımüm su nüvam üruham, 817 ımanı khanamy oşadlum (°dhim), 529 ımün narâlı (naralı) krouta vedim etya (etn, etnt), 328, 401, 404 ımü brahma pipihi saubhagüya, 640 ımā brahma brahmayāhah (°ha), 381 ımā yā devih pradišas catasrah, 707 ıme ilvü vi mrtair üvavrtran (üvavarttin), 648 me 'rātsur me subhūtam (sūdam) akran, 59

ime väsantikä rtu abhikalpamäpäh. ıme saisirü rtü abhıkalpamünüh, 888 ıman te pakeäv (pakeä) ajaran patatrınau (°nah), 670, 732, 888 imau bhadrau dhuryāv (°yā) adhı. 888 imau stūm anupaksitau (anapeksitau), ıyan vah sa satya sandhabhud (samvāg abhūd) vām indrena samadhaddhvam (°dadhvam), 104, 391 ıyan vai pitre raştry ety agre, 321, 803 ıyarh te yajnıya tanüh (tanuh), 554 ıyam apa (ava) dikşām ayaşta, 201 ıyam eva sü ya prathamü vyauchat (vyuchat), 724 ıyam oşadlıc (°dhī) trāyamānā, 695 1yam pitrya (pitre) rastry cty (ctv) agre, 321, 803 ıyanah kreno dasabbıh sahasraılı, 538 ira chi, 272 ıram u ha (ıram alıa) prasansatı, 613. ıravatı dhenumatı bı bhütam, 272 ıryatāyā akıtavam, 544 ıla ehı, 272 ıluvardüya svähü, 579, 627, 862 ılaıva väm anu vastām vratena, 271 ısam ürjam yajamänäya dhehi (duhrām, dattvā), 105 isas corjas ca sūradāv (°dā) rtū. 888 isum na viro astā. 840 işur navirastaram, 840 150 pipihi (pipihi), 545 160 raye (rayya1) ramasya sahase dyumnāyorie ("yoria-, dyumna ūrie) 'patyāya (patyāya, apa"), 37, 396, 705, 910 iskartā vihrutam punah, 650, 683 iskrtāhāvam avatam, 164 ıştam vitam abhıgürtam vaşatkıtam, 153 ıştain ca vitam (vittam) ca (cabliat), ıştam pürtam abhıpürtam vaşatkıtam, iştena pakvam upa te huve savaham

('sa aham), 362

upa śravat (śruvat) subhagā yajűe asmin, 603 upaśrito (upaśruti, *śrito) divah prthivyoh, see agne tvam sūktavāg upa śrestha na aśisah (aśirah), 857 upastutyam (°stutam) januma tat (mahi iätam) te arvan, 327 upa stuhi (snuhi) tam nṛmnām (nrmanām) athadrām, 77, 110, 356, 616, 696, 802, 824, 871 upasthāvarābhyo dāśam, 597 upasthāvarībhyo bai(n)dam, 597 upasthe mātuh surabhū ("bhāv) u loke. upasthe soma ähitah (ädhitah), 122 upa snuhi, see upa stuhi upahūtā gāvah saharsabhāh, 919 upahūtā dhenuh saharsabhā (saharş°), upahūtā saptahotrā ("tāh saptahotrāh), 381 upahūto dvaus (dyauh) pitā, 967 upahūto bhūyasi havışkarane (havihk°), 962 upahūto 'yam yajamāna uttarasyām devayajyāyām ("yājyāyām), 487 upākrtam sasamānam yad asthāt (sadhasthat, sad asthat), 110, 829 upānasah saparyan, 383, 614, 832 upāyava (°vas, °vah) stha, 977 upāvīr asi. 465 upo nu sa saparyan, 383, 614, 832 upo ha vad vidatham vājino guh (gūh), 558 ubhayebhyah pra cikitsā gaviştau (gaistau), 889 ubhayor artnyor (artniyor, ubhayo rājāor) jyām, 791, 837 ubhā(ubhāv) upānšu prathamā pibāva, ubhā dātārāv (°rā) ışām rayīnām, ubhāv indrā (indro) udīthah sūrvas ca. 92, 188, 824 , see ubhā ubhāv upānáu ubhe id asyobhayasya (asyobhe asya)

rājatah, 832, 911

ubhe ca no (camam) dyāvāprthivī anhasah (°sas) pātām (syātām, etc.), 867, 964 ubhe prnaksi rodasī, 718 ubhe yatete ubhayasya (ubhe asya) pusyatah, 832, 911 ubhau lokau sanem (sanomy) aham, 331 uruka urukasya ..., 49 uru kşayāya nas (nah) kṛdhi, 964 uruga urugasya . , 49 urunasāv., see urū° urudrapso višvarūpa induh, 291, 421, 742 uru prathasvornamradam sväsastham devebhvah, 475, 493 urusya rāya eşo (rāyo 'veşo, rāvah sam işo) yajasva, 361 uruşya no (no) aghayatah samasmat, urūnasīv (uru°) asutrpā (°pāv) udumbalau (ulu°), 273, 551, 886 uror ā no deva rīṣas pāhi, 371a, 716, 821 uro va padbhir (padbhir) anate (°ta). urva ıva paprathe kāmo asme, 564 urv antariksam vihi. 564 urvī gabhīrā (gambhīrā) sumatis te astu, 305 urvim gavyām parīsadam no akran, 46, 564, 824 urvī rodasī varīvas ("vah) krnotam (krnutam), 964 urvy antanksam vihi, 564 ulūkhalā grāvāno ghosam akrata (akurvata), 724 ulena parisito 'si, 568 ulokam u dve upa jāmim īyatuh, 392, ulo halıkşno vışadansas te dhātre (dhātuh), 532, 568 ušimahi tvā, 617 usasa śreyasi-śreyasir (uşasah śreyasīh-śreyasīr) dadhat, 980 uşā apa svasus tamah (svasus tamah), uşo dadrkşe na punar yatīva, 568 ustārayoh pilvayoh (pil°), 544

utarebhanan retibbir yatudhanan, 262 utālabdham (utārabdhān) sprnuhi jātavedah, 262 utula parimidho 'si. 563 utem anamnamuh (uteva namnamuh), 236, 840 utem arbhe havāmahe, 569, 693, 831 utem (uto) āśu mānam piparti (bibbarti), 112 utainam gopā adréran (adréan), 356 uto aranyānih ("nis) sāyam, 971 uto padyābhir javisthah (yavo), 192 utkūlanikūlebhyas tristhinam (utkūlavikulābhyām tristhinam), 986 uttamam nākam (uttame nāke) adhi rohayemam (rohayainam, rohemam), 712, 745 uttarasyām devayajyāyām upahūtah (°tā), 437 ut tişthata ("tā) pra taratā sakhāyah, 433, 442 ut tistha purusa harita pingala lohi-(puruşāharitapıñgala tākṣa).., 591 ut te stabhnāmi (tabhnomi) prthivim tvat parı, 374 ut tvā (u tvā) mandantu somāh. 392 ut parjanyasya dhāmabhih (suşmena, dhāmnā, vṛṣṭyā, dṛṣṭyā), 869 ut sakthyā (°yor) ava gudam (°yor grdam) dhehi, 641 utsam jusasva madhumantam ürva (ūrmim, arvan, juşasva šatadhāram arvan), 228, 621 ut satvanām māmakānām manānsi (mahānsi), 857 udādāya pṛthivīm jīvadānum (jīradānuh, onum), 266 ud it te vasuvittamāh, 345, 627 udicyām tvā diśi viśve . abhişincantv .. , 512 ud īrayathā (°tā, °ta) marutah samudratah, 90, 443 ud u tye (ud-ut te) madhumattamāh, 345, 408, 627 ud usriyāh stjate (sacate) sūryah sacā, 3, 57, 634 ud enam uttaram (°rām) naya, 506

udgātar devayajanam me dehi (dhehi). udgrābhenod agrabhīt (aligrabhat, ajigrabham, ajigrbham), 519, 657 udno cattodadhun bhintta (dehy udadhim bhindhi), 418 udno divyasya no dehi (dhātah), 106. ud balasyābhinas tvacam, 210 udbhinnam rājñah, 724 udyatām īva sūryah, 743 udyan nakşatram arcıvat (°mat), 239 ud vanšam iva yemire, 110, 296, 354, 569, 840 ud valasyābhinat ("nas) tvacam, 210 un nayāmi svān (svān) aham. 924 unnetar un non (no) nayonnetar vasvo abhy un nayā nah, 243 unnetar vasīyo na (nā) un nayābhi (vasyo 'bhy un nayā nah), 248, 786 unmāsı (unmā ası), 993 upa rşabhasya (uparşac) retasi (yad retah), 919 upa imann upa vetase, 159 upa tvā kāma Imabe sasīgmahe, 131 upa tvā kāmān mahah sasrımabe, 131 upa dyām upa vetasam, 159 upa drava payasā godhug oşam (oşum; payasā goşam), 618 upa nah (nas) sūnavo girah, 971 upa no mitrāvarunāv ihāvatam, 180, 437, 440, 888 upa prakșe (upaprakșe) madhumati kşiyantah, 817 upapravada (upapla") mandūki, 263 upa preta jayatā narah, 441 upa mā jakşur (ca°) upa mā manīşā, 55 upa mā (mām) dhenuh saharşabhā (saharşa°) hvayatām, 919 upa mām dyaus (dyauh) pitā hvayatām, 967 upa yajñam asthita (astṛta, astu no) vaisvadevi, 96, 627, 640, 643, 849 upayāmam adharenausthena (onosthens, adharosthens), 731 uparsabhasya . . , see upa 13° upavir ası, 465 upasrnvate tva, 616

upa śravat (śruvat) subhagā yajūe asmin, 603 upaśrito (upaśruti, "śrito) divah prthivyoh, see agne tvam süktaväg upa śresthā na āśişah (āśirah), 857 upastutyam (°stutam) janima tat (mahi jātam) te arvan, 327 upa stuhi (snuhi) tam nṛmnām (nṛmaṇām) athadrām, 77, 110, 356, 616, 696, 802, 824, 871 upasthāvarābhyo dāśam, 597 upasthāvarībhyo bai(n)dam, 597 upasthe mātuh surabhā (°bhāv) u loke, upasthe soma āhitah (ādhītah), 122 upa snuhi, see upa stuhi upahūtā gāvah saharsabhāh, 919 upahūtā dhenuh saharsabhā (saharsa). upahūtā saptahotrā (°tāh saptahotrāh), upahūto dyauş (dyauh) pitā, 967 upahūto bhūyası havişkarane (havibk°), 962 upahūto 'yam yajamāna uttarasyām devayajyāyām ("yājyāyām), 487 upākrtam sasamānam vad asthūt (sadhasthat, sad asthat), 110, 829 upanasah saparyan, 383, 614, 832 upāyava (°vas, °vah) stha, 977 upāvīr asi, 465 upo nu sa saparyan, 383, 614, 832 upo ha yad vidatham vājino guh (gūḥ), 558 ubhayebhyah pra cıkitsā gavıştau (gaīşţau), 889 ubhayor artnyor (artniyor, ubhayo rājnor) jyam, 791, 837 ubhā(ubhāv) upānšu prathamā pibāva, ubhā dātārāv (°rā) işām rayīnām, ubhāv indrā (indro) udīthah sūryas ca, 92, 188, 824 ubhāv upāńśu , see ubhā ubhe id asyobhayasya (asyobhe asya) rājatah, 832, 911.

ubhe ca no (cainam) dyavaprthivi anhasah (°sas) pätäm (syätäm, etc), 867, 964 ubhe prnakşı rodasi, 718 ubhe yatete ubhayasya (ubhe asya) puşyatah, 832, 911 ubhau lokau sanem (sanomy) aham, 331 uruka urukasya . . , 49 uru kşayāya nas (nah) kṛdhi, 964 uruga urugasya . . 49 urunasāv . , see urū° urudrapso viśvarūpa induh, 291, 421, uru prathasvornamradam sväsastham devebhyah, 475, 493 uruşya rāya eşo (rāyo 'veşo, rāyah sam iso) yajasva, 361 uruşya no (no) aghayatah samasmat, urunasāv (uru°) asutrpā (°pāv) udumbalau (ulu°), 273, 551, 886 uror ā no deva rīsas pāhī, 371a, 716, 821 uro vā padbhir (padbhir) ānate ("ta), urva ıva paprathe kāmo asme, 564 urv antarıkşam vihi, 564 urvī gabhīrā (gambhīrā) sumatis te astu. 305 urvim gavyām parışadam no akran, 46, 564. 824 urvī rodasī varīvas ("vah) krnotam (kṛnutam), 964 urvy antarıkşam vihi. 564 ulūkhalā grāvāno ghoşam akrata (akurvata), 724 ulena parı«Ito 'sı, 568 ulokam u dve upa jāmim īyatuh, 392, 627 ulo halıkşno vışadansas te dhatre (dhätuh), 532, 568 ušimahı tvā, 617 uşasa śreyasi-śreyasir (usasah śreyasih-śreyasir) dadhat, 980 uşī apa svasus tamah (svasuş tamah), uso dadrkse na punar yatīva. 568 ustārayoh pīlvayoh (pil°), 544

ustro ghrnīvān vārdhrīnasas (ghrnāvan vardhranasas) te matvai, 597. 952 uşnena väya udakenehi ("kenaidhi, väyav udakenehi, väyur udakenet), 122, 712, 887 usrā etam dhūrbādhā avIrabanā anassū ("Srū) brahmacodanau, 122, 207, 407, 888 usrā (usrāv) etam dbūrşāhau (dbūrvāhau) [yujyethām] anasrū avīrahanau brahmacodanau, 122, 207, 407, 876. 888 ūtim arbhe havāmahe, 569, 693, 831 ūtī sa (sa) brhato dīvah, 987 üdhno divyasya no dhatah, 106, 569 ūmaih pitrbbir , 750 urubhyam te asthivadbhyam ('sthio), 909 ūruvor ojah, 792 ūrjam samsūdena (°sīdena), 628 ūrjam ca tatra sumatim ca pinvata (°tha), 90 ūrjam bibhrad vasuvanih (vah sumanüh, vah suvanih, vasumanäh) sumedhāh, 227, 383 828 urjam may i dhehi, 103 ūrjam me dhehi (dehi), 103 ürjasvatī rījasvaš (rūjasūyūya, rūjasūyās) citānāli, 326 ürjasvatīr oşadhir ā rišantām (viša). 267 Orjasvatih svadhävinih (svadhävinih), ūrjā prthivīm gachata (vache), 853 ürje pipihi (pipihi), 545 umamradasam (urnas) tva strnum prath issu) (Grnamr with [°dam] ev Csastham ("atham) devebby ah, 475, 493 Grnamradā yuvatir ("mradih prthivi) dal smisate ("sati), 695 Ordhy in 1 h im iva menire, 110, 296, 351, 569, 510 urdhaneit in fragadhanm (fnay"), 195,

ürdhyadhans i pratihitäbhir asti, 569

355 865

ürdhvam manah svargyam (suvargam). Grdhvasritah srayadhyam, 195, 355, 867 ürdhvä yasyamatır bha adıdyutat (niidyutat), 63 ūrdhvo adhvaro asthāt ('dhvar i āsthat, 'dhvare sthih, adhvare sthit), 508, 910 ürdhvo virajann apa sedha satrun, 138, 569, 616 ūrva īva paprathe lūmo asme. 564 ūrvam gavyam paris idanto agman 40, 564, 824 ūrvaih, 725 ürvor ojah 792 ürvy antarıkşam vihi, 564 ülena parımidho 'sı, 568 ulo halikeno yrsadausae te dh'ituh, 532. 56S ūsā dadīše na punar yatīva, 569 rksalābhih kapinjalān, 26, 184, 265, 631 rkso jatūh susilīkā (susulūkā) tr itarajanānām, 279, 290, 624, 628 rksamūc (°samāc) chukrah, 985 rco akşare ('ksare) parame və oman, 907 ritte pari vrādhi nah, 360 rnān no narnam ertsamānah, 180, 694, 693, 919 rtaprajūt i bhaga id vah s, ama, 611, 918 rtava ("vas) etha rtivrdhah («tharta"), rtavah stha , 919, 977 rtaxa 'dhipataya Kean, 652 riano 'arijanta, 652 rtautha sthart is rdhah, 919 riasja goptri tapasah parasvi (paraspi, tarutri), 198 rtasya tantum vitatam vivrtya (vicrtya, drie kam), 866 rtasya tv enam Amutah, 353, 627, 838 rtasva dhümno amrtasya yoneh, 121 mänuq mes (idda) idba siddi'n esett (°tı), 172 ringa brahma prathamota jajae, 460 rtasya yonita mahisasya dharim, 421 rtasyarteus mām uta (ita), 353, 627, rtin mi muhenticharah, 421

rtur janitri tasyl apas (apasas) pari, rtusthā (°sthāh, °sthās) stha rtāvrdhah (sthartuspráah), 919 rtūnr (rtūn) anyo vidadhaj jūyate punah (jāyase navah), 927 rtun (rtunr) utsrjate vašī, 927 rtun prstibhih (prsti°), 539 rtena (rte 'va) sthūnām (°nāv °nā) adhi roha vansa (vansah), 237, 380, 824. SSS rtyai janavādinam, 652 rdhag aya (ayad) rdhag utasamişthah (°mista), 86, 234, 835 rdhyāsam adya makhasya sirah, 659 rsabham narvapasam, 359 rşabhāya gavayî ("ya rājūe gavayah), rşabhena gah (tvaşta), 359 rşabho gaur vayo dadhuh, 359 rsabho 'si svargo lokah, 359 rşır ha (hî) dirghasruttamah, 578 rşīnīm ca stutīr ("nīm sustutīr) upa, 293, 850 rşīnīm putro adhırāja esah (avirāja eşah, abhisastıpī u, abhisastıpīvā, abhiśastipā ayam), 172, 254, 740, 824 rşī bodhapratībodhau, 516 rsvāh satīh kavasah (kavavah) sumbhamanah, 877 ekayā ca dašabhiš ca svabhūte (cā suhūte), 119, 434, 446, 741 eko devo apy atişthat, 909 eko bahunim asi manyay iditah (manya īditā), 889 eko vo devo apy ('py) atişthat, 909 eko ha devah pradišo 'nu sarvih 578 etam jānātha (jānītāt, jānīta) parame vyoman, 90 etat tin pratimanvano asmin, 227, 365 etat te agne rādha aiti (eti) somacyutam, 711 etat tvam deva soma (tvam soma) . . . devān (devān) upāgāh (upāvrtah). 924 etat tvātra pratimanvāno ("vanvāno) asmi (asmin), 227, 365

etad brahmann upavalhīmasi (apa°, upabalıhamahe) tva, 214, 762 eta pitarah somyāsah, 747 etām samkrsya ("kasya, "kusya) juhudhi 4, 605, 631, 641 etā te aghnye nāmānī, 787, 910 etāni te aghnive (ghnye) nāmāni, 787. etena tvam šīrsanyām ("yān) edhi (tvam atra śirsanvan edhi), 243 edam barhir ni şīdata (şīda nah), 849 ed u madhvo (madhor) madintaram, enam parisrutah kumbhyz, 275, 682, 831 enas cakryan mahi baddha eşam, 592 enī višvasya bhuvanasya gopīh, 693 enāhnedam ahar ašīva svāhā, 709 eno mahac cakṛvīn baddha eşa 592 endram vagnunī vahata 256, 346, 800 endram agnim ca vodhave, 694 endram acucvavuh . . . 712 emī agmann īšišo donakāmāḥ, 836 emām anu sarpata, 379 emām parisrutah kumbhah, 275, 682, S31 em enad adva vasavo rudrā Editvāh svadantu (sad°), 371 erum tundīnā patyeva jāyā, 159, 421 evam vapīmi hārmyam, 491 evā vapāmi harmvam, 491 esa işāya māmahe, 640 eşa u sya vrsā rathah 325, 491 esa rsaye mamahe, 640 eşa te yajno vajnapate . . . suvîrah (suvīryah, sarvavīras . .), 323 esa me 'musmin ('musminl) loke prakāśo 'sat, 943 eşa sya rīthyo vṛṣī, 325, 491 eşa hi devah pradiso 'nu sarvāḥ, 578 esā te agne samit tayā (tayā tvam) vardhasva cī ca pyūvasva, 808 esī vas sā satvī samvīg abhūd vām indrena samadadhyam, 104, 391 eşu dyumnam svar yamat, 711 eşo ha devah pradišo 'nu sarvāh, 578 eha gatir vāmasva, 694 aidamrd3 yavvudhah, 165, 241, 271, 828

aindrah prano ange-ange nididhyat (ni dedhyat, nidhītah), 696 aındram acucyayuh , 712 aındrah suşmo visvarūpo na agan, 699 aındrasūrāh ("saurāh) šyetalalāmās (£) āmala°) tūparāh, 725, 818 amdropanas yakehamanaso aılabıda (aılamıda) avuryudhah (yavvudhah, vo vudhah), 165, 241, 271, 828 aışu dyumnam svar yamat, 711 okhām dadhātu (dadātu) hastayoh, ojasa pitrbhyah pitřa jinva, 936 ojasyā nāmāsi, ojasvinī nāmāsi, 248 ojo dehi (dhatta), 103 olo mayi dhehi (me dah), 103 ottarād adharād (°rāg) a purastāt, 145 obhe aprā rodasī vi (vī) şa āvah, 515, obhe prnāsi rodasī, 718 osadhayah prati grbhnita, 116 oşadhayah pratı grhnitägnım (grbhni°) etam, 116 osadhayah prāvata vācam me, 449 osadhibhyah (°dhibhyah), 529 osadhibhyah pasave no (pasubhyo me) janāya (dhanāya), 160 osisthadāvne sumatim graānāh, 60, 294, 355, 854 śinginikośyābbyām osisthahanam (°kośābhyām), 293, 347, 618, 804, 816 o şu (sū) vartta (varta) maruto vıpram acha, 389, 547 audbhidyam rājāah, 724 survaih, 725 aulaba it tam upā hvayatha (aulava hvayata), 90, 219 aulūkhalā grāvāno ghoşam akrata, 724 aulūkhalāh sampravadantı grāvānah, kakup (kakuc) chanda ihendriyam, 178 kakup (kakuc) chandah, 178 kakubham (kakuham) rūpam vṛṣabhasya (rūpam ṛṣa°) rocate brhat (brhan), 23, 120, 359 katı kıtvah pranatı capanatı ca (praniti căpa căniti), 582

kati dhāmāni katı ve vivāsāh. 739 kad va rtam kad anrtam (amrtam). 181 kanātkābhām na ābhara, 79, 151 kanikhunad iya sapayan, 126 Lapota (°tā) ulūkah šašas te nīrrtyai (nairrtäh), 699 kam agañ (agan) janayopanah, 936 kara ad (id) arthayasa it, 599 karanam asi, karunam asi, 606 karnābhyām chubukād (cubukād) adhı, 84 karma krnyantu (°to) mānuşāh, 719 kalpantüm te dısah sarvüh (me dısah sagmāh), 235, 285 Lalpayatam mānuşīh, 316; 490 kavasyo kośadhävanih (kosa°, 'kosa°), kavir gīrbhih kāvyenā (°na) kavih san, 458 kavır yah putrah sa im ā (ımā, sā imāh) cıketa, 383, 545, 831 kavīn chavyā, 128a kavīn pṛchāmi vidmane (vidvano) na vidvān, 240 kasotkāva svāhā, 33, 81, 295 kas te gätränı samyatı (sım°), 572 kaholam kauşītakım (°kam), 590 kā ūrū pādā ucyete, 886 kāny antah puruşe arpıtānı (°şa arpitāni), 509 kā pratnā va āhutih, 365 kāmam duhātām iha šakvarībhih, 91 kāmayamāno vanā tvam, 312 kāmāyai svāhā, 319 kāmena kṛtah (kṛta) śrava ıchamānah, kāmyāyai svāhā, 319 kāyamāno vanā tvam, 312 kāv ūrū pādāv ucyete, 886 kāşthā ajmeşv (yajūeşv) atnata, 339 kım it te vişno paricakşyam bhût (°cakşı nāma), 737 kım ürü pādā ucyete, 886 Lıyāmby atra rohatu, 782 kīkasābhyo anūkyāt ('nūkyāt), 907 kukūnanānām tvā patmann ādhūnomi, 151, 720, 810

kumbhinasah (kaum°) puskarasādo krte yonau (krto yonir) vapateha lohitāhis te tvāstrāh, 724 bijam (vijam), 216 kuyavam (kū°) ca me 'kṣītiś ('ksītam) krtyaisā padvatī bhūtvā (bhūtvī), 598a ca me, 552, 587 krtvī (krtvā) devair nikilbisam, 598a. krtvī (krtvā) savarnām adadur (adakurkurah sukurkurah, 568 kurkuro nilabandhanah, 568 dbur) vivasvate, 105, 598a kurvāno anvān adharān sapatnān, 907. krdhī şv (sv) asmāń adıter anāgān 924 (°gāh), 987 kulikā devajāmibhyah, 149 kṛṣnagrīva āgneyo rarāte (lalāte) purkulpāny āvapantikā, 151, 568, 800, 867 astāt, 265 kulvābhvah svāhā, 565 śitikakso krsnagrivah 'finsakthas kuvayah (°yıh) kutarur , 596, 782 ('ñjışakthas) ta aındrügnäh, 986 krsno 'sy ākharesthah (°sthāh), 493 kuvit su no gaviştaye (gaīştaye), 889 krsyaı tvā susasyāyaı (sumanasyāyaı), kuvin no asva sumatir navivasi (bhavi°), 857 867, 870 kuśmāndāh, °dānı, °dyah, 290, 568 kevalāgho (°lādyo) bhavatı kevalādī, kuştaya te krinanı, 86 868 ku sthah ko vām asvinā, 553, 831 ko ambādadate dadat, 907 kusthavā te krīnāni. 86 ko asyā dhāma katidhā vyuştīh, 739 kusmāndāh, °dāni, °dyah, 290, 568 kotanāsu, 151, 720, 810 kuhum aham (kuhum devim) suvrtam ko nu vām mitrāvarunāv (°nā)rtāvan. (sukṛtam, subhagām) vidmanāpasam, 857 ko 'mbādadate dadat, 907 kuhvai (°ve) trayo 'runaitāh, 705 kauberakā višvavāsah, 235, 267 kūtanānām tvā patmann ā dhūnomi, kaumbhīnasah, see kumbhī° 151, 720, 810 kyāmbūr atra rohatu (jāyatām), 782 kūyavam, see ku° kratūdaksābhyām me varcodā varcase kürkurah (°ras) sukürkurah, 568 pavasva, 556 kūrkuro bālabandhanah (vāla°), 214, kratvā varıştham vara āmurim uta. 215, 568 293, 529, 691, 840 kūlyābhyah svāhā, 565 kratve vare sthemany āmurīm uta, kūśmāň (kūș°) chakapındaıh (śaka°, 293, 529, 691, 840 chakabhih), 290 krānā šišur mahīnām, 152 kūśmāndāh, °dānı, °dyah, and kūş°, 290. krānā sindhūnām kalašān avīvašat, 152 568 krıyanta ā barhih sīda, 152, 825, 971 kūstho devāv asvīņā, 553, 831 krīdantau (krīl°) putrair naptrbhih, 271 kūş-, see kūskrīdī (krīlī) ca šākī cojjeşī (sākī corkrkalāsah , krkılāsah , 596 11șī, °jīșī, ca), 278, 407, 693 kṛnutam nah sviṣṭim (°ṭam), 45, 587 krūram ānanša (ānāša) martyah (markṛnutām tāv adhvarā jātavedasau, tah), 301, 315 kva pratnā va āhutīh, 365 kṛnotu so adhvarāñ (°rā) jātavedāh, kvayıh kutarur . 596, 782 kşatrasyolbam (°vam) ası, 219 kṛnvāno anyān (anyān,'nyān) adharān kşayasyāsı vidhatah (vidhartā), 350 sapatnān, 907, 924 kṣāmad devo 'tı durıtāny (devo atikrtam cid enah pra mumugdhy (muduritäty) agnih. 908 muktam) asmat (asmāt), 510 kşıpreşave deväya svadhāvne (°dhāmkṛtūn nah pāhy anhasah (enasah), 421

ne), 240

ksumūsı (ksupāsi), 205 kşuro bhrajas (bhrjvān, bhrjas, bhrājas) chandah, 486, 658 khakholkäya svähä, 33, 81, 295 khajāpo 'jopakāsinīh, 21, 69, 151, 381 khanvakhāzi khaimakhāzi madh) e tadurı, 124 khanyābhyah (khalyā°) svāhī, 878 gandharvāya janavide (jani°) svāhā, 588 gandharvo dhāma paramam guhā yat (dhāma vibhrtam guhā sat) 118, 639, 855 gandharvo nāma nihitam guhāsu, 118. 639, 855 gabhiram (gambh°) ımam adhvaram krdhi, 305 gambhīrebhih pathibhih pūrvebhih (pūrvinebhih), 315 gambhīraih pathibhih pūrvyaih (pūryāneth), 315, 368 gargī vācaknavī. 490 garbha iva (ivet) subhrto garbhinibhih (sudhito garbhinīsu), 175, 639 garbham sravantīm agadīm akarma, 46 garbhas ca athātām garbhas carathām (°tām?), 93 garbhah samıäyase punah, 829, 936 garbhe sañ (san, sam-) jāyase punah, 829, 936 garbho asy ('sy) oşadhinām, 909 garbho jarāyuh pratidhuk pīyūşah, 381 gavayam te sug rchatu (te kşut), 145 gātum vittvā gātum ihi, 360 (°trı) chandasām gāvatrī (mātah), 525 gāyatriyai (°tryaı, °tryā) gāyatram, gārgī vācaknavī, 490 gārhapatyah (°tyāt) prajāyā (prajāvān) vasuvittamah, 250 gāva upāvatāvatam (upa vadāvate), 60, 164, 511, 835 gāvo gulgulugandhayah (guggulu°), gāvo bhago gāva indro me achān (achāt, ma ichāt), 580 gira stomān pavamāno manīṣāh, 419

gıra (girah) stomāsa Irate, 977 girah somah pavamāno manīşāh, 419 girā-girā ca daksase (cakşase), 158 gırā ca śruştıh sabharā asan nah, 57, 383, 865 girir na visvatas (°tah) prthuh patir dıvalı, 964 gīh kośvosy aur yadā girah, 290 guhā satīm gahane gahvareşu, 299 guhāhitām nihitām gahvareşu (gubāhitim gaho), 299, 808 grnata nah syistave, 45 grnānāh śravase (śa°) mahe, 349 grdhrah šitikaksī vārdhrānasas te divyāh (vārhīnasas, vārdhrio, te 'dıtyāh), 23, 122, 597, 952 grbhnāmı te saubhagatvāya (suprajūstväya) hastam, 116 grbāfi jugupatam yuvam, 548, 935, 936 grhānāngāny apve (aghe) parehi, 875 grhān ajūgupatam vuvam. 548 grhā nah santu sarvadā (sarvatah), 68 grhān aimi (emi) manasā grhān jugupatam yuvam, 548, 935, 936 grhā mā bibhīta mā vepadhvam (vep-1dhvam), 168, 584 grho hiranyayo mitah (mithah; grho mito hiranyayah), 96 grhnāmi te saubhagatvāya (suprajästväya) hastam, 116 grhyopagrhyo . 646 godānāc chubukād adhi, 84 godhāyasam vi dhanasair adardah (atardat), 63 godhūmās ca me masūrās (masurās) ca me, 568 gopāya mā (mām) ševadhis te (°dhıs te), 958 gomad ū su nāsatyā (pā°), 952 gomān id (yad) indra te sakhā, 735 gošaphe šakulāv (°lā) iva, 888 goşad ası, 83 goşv aśveşu śubhrışu (°uşu), 622 gohya upagohyo maruko (mayukho) manohāh, 81, 244, 646 gauram te sug rchatu (te kşut), 145 gaurir (gauri, gaur in) mımaya salılanı taksati, 357, 545, 824, 862

gaur dhenubhavyā (dhenur bhavyā). 357, 818 gnās tvā devīr višvadevyāvatīh (°vyavatīh) pṛthivyāh sadhasthe añ-('figirasyac), 467, gırasvat . 910 graha višvajanīna niyantar viprāyāma te (nyantar vipra ā satī), 342, 695. 770, 838, 870 grāmam sajānayo gachantı (grāmin sajātavo yanti), 871 grāme vidhuram (vikhuram) ichantī svābā, 147 grāmyamankīradāšakau (grāmy am mañgīradāsakau), 49, 279, 824 grāvāvādīd (grāvā vaded) abhī somasyānsum ("sunā), 481, 697, 836 grīvāyām (grīvāsu) baddho apıkakşa āsani (apīpaksa āsan), 151 gharmam socantah ("ta, "tam) pravanesu (pranavesu) bibhratah, 384, 802 gharmam pāta vasavo yajata (°tā, °trā) vāt (vet, vat), 357, 448, 511 gharmas trišug vi rājatı (rocate), 57 ghasinā (ghasīnā) me mā samprkthāh. ghrtam yavā madhu yavāh, 803 ghrtam ghrtayone (ghrtayane) piba. ghrtam duhata (duhrata) āśıram, 356 ghṛtam duhānā viśvatah prapītāh (prapīnāh, pravīnāh), 170, 198, 871 ghrtapratīkam va (ca) rtasya dhūrşadam (dhüruşadam), 759, 866 ghrtaprusas tvā sarito vahanti (harito vahantu), 299 ghrtapruşo haritas tvāvahantu, 299 ghṛtam eva madhu yavāh, 803 ghṛtam mimikṣe (°kṣire) ghṛtam asva yonih, 356 ghrtavatī savitar ("tur) ādhipatve (°tyaih), 381, 610, 706 ghrtascuto madhuscutah ("scyuto, "scyutah, "cyuto, "cyutah), 336 ghṛtasya dhārām amṛtasya panthām, ghrtasya dhārām mahişasya yonım, 421

ghrtāhutah somaprethah (stoma°) suvīrah, 419 ghrtena dyavaprthivī prornuvāthām (prornva°, prornuvātām), 91, 797 ghrtena no (mā) ghrtanvah (°puvah) punantu, 789 ghrte śrito ghrtam v (uv) asya dhama, 774 ghora ghoratarebhyah, 816 ghorā rsayo namo astv ebhyah (astv adya yebhyah), 340 ghosenāmīvāns cātayata (°mīvān cātayadhvam), 930 cakratundāya dhīmahi, 866 caksasī sāmavedasya, 608 caksurdā (°dhā) ası, 100 caksurdā varcodā varīvodāh, 104 cakşur dehi (dhehi), 103 caksur ma urvyā (uruyā, urviyā) vi bhāhı, 743, 791 caksur mayı dhehi, 100, 103 caksur me dah (dehi, dhehi), 100, 103 cakşur yad eşām manasas ca satyam, cakşur yesam (hy esam) tapa uccabhimam, 340, 396 cakşusa esām manasas ca samdhau. 340 caksuşī sāmavedasya, 608 cakşuh (cakşu) sthas . , 977 catuşpadām uta yo (ca) dvipadām, 499 catuspāda uta ye dvipādah, 499 catvāri māyobhavāya, 319, 421 canisthad agne angurah, 54 canīkhudad vathāsapam, 126 candrena 1yotir amrtam dadhānāh (°nā), 381 capyam (cappam) na pāyur bhişag asya vālah (vāraḥ, bālah), 214, 261, 408 cami mā hińsīr amuyā śayānā, 57, 181, 512, 824 carmevāvādhus (°bādhus) tamo apsv antah, 207 cikitvān (°vān) anu manyatām, 925 cita (citah, citas) stha . , 977 cittim (citim) juhomi . ., 399 cittim acittım (cıtim acıtim) cinavad (°vo) vi vidvān, 399

cittih (citti) sruk, 980 cıtra ādıtyānām, 195, 369 citrah sisuh (sisus) pari tamansy aktūn (aktah). 967 citră etagya (eda°) anumădyasah, 21. citrebhir abhrair upa tisthato (°tho) ravam, 91 citro rakşitā, 195, 369 cec-cec chunaka sria . 84 corasyannam (caur°) navaśraddham. 728 chad apehi , 84 chandonāmānām (chandomananam, chandomānām) sāmrājyam gacheti (gachatād iti, gached iti) , 802, 808 chavim chavyā, 128a chlilipu chlilisate, 195 jakşıvānsah papıvānsas (°pānsas) ca viéve, 200 divy astabhāyat ısgatā sındhum (aska°), 137 jagatyū įksamam (įksa°), 985 jagatyamam ("tyenam) vikşv ā veśayamah (°yamı, °yani), 709 1agad ası. 491 jagāma sūro adhvano vimadhyam (vi madhyam), 816 jagrhmä (jagrbhmä, jagrbhnä) te daksinam indra hastam, 116 , 156, 634 jagdhā viceştir (vitṛṣṭir) jagdho jagdhā vicastir masako (vitrstir) , 634 jagdho vyadhvaro jagdhā vicastir . jagdhā vitrsti svāhā) . , 634 jajāā neta sann apurogavāsah, 62, 192 jananta usaso bhagam 366 janayas tvāchinnapatrā devīr visvadevyāvatīh (°vyavatīh) . 467 janıyanti nav agravah, 534 janista hi jenyo agre ahnām, 441 innisthad agne afigirah, 54 janışı a ("şva) hı jenyo agre ahnam, 441 janiyanto nv agravah, 534 jambhābhyām (jambhyais, jambhyebhis) taskarān ("ran, "ran) uta, 315, 924

jayam (jayan) ksetrāni sahasāvam ındra, 941 jarām gachīsi (gacha, su gacha) pari dhatsva vūsah, 850 jarı cetid abhısışah, 193, 353, 676, 802 jāgatam ası (jāgatīsı), jāgato 'si, 491 jāgarītāya (jāgrtāva) svāhā, 649 jägrtsyas tripaūcāših, 28 47, 185, 192 jätavedo nayā hy (nayāsy) enam sukrtām yatra lokah, 298, 825 jātavedo maruto adbhis ('dbhis) tamayıtva, 908 ıātavedo vahemam (vahasvainam) sukrtām yatra lokah (lokāh), 298, 825 jätänäm janajäš ca yän (janayänsi [°yāsı] ca), 303a jātena jātam ati sa pra sarsīte (ati art pra arnaate), 633 jänita smainam (jänitäd enam) parame vyoman, 90 jāmim icha pitrşadam nyaktam ("tām), 139, 738 jāmim itvā mā vivitsi lokān, 198, 579, 637, 840, 871 jāmim rtvā māva patsi lokāt, 198, 579, 637, 840, 871 jāmim mā hidsīr amuvā (anu vā) śayānā, 57, 181, 512, 824 jinva gā jinvārvatah, 852 unyanta usaso bhagam, 366 jihvä pavitram asvināsan (°nā sam) sarasvatī, 835, 938 ıımutan hrdayaupasabhyam ("sena, °sena), 278 jivam rudanti vi mayante (nayanty) adhvare ("ram), 181 jivann eva pratidatte (prati tat te) dadāmı (°nı, dadhāmı), 61, 106 jīvasūr devakāmā (vīrasūh) syonā, 633 jīvām rudanti vi mayante adhvare, 181 jīvātave na mṛtyave (martave), 327, jīvātave pratarām (°ram) sādbayā dhiyah, 506 parintya-(mrt°) jivām tebhyah mānām, 311, 402 Jivebhyas tvā samude (sammude)

vāyur indrah, 401

juşantām somyam (sau°) madhu, 728 usetam (otham) yajnam istaye, 91 nustam devebbyo havyam ghrtāvat (ghrtavat svaha), 467 juhota (°tā) pra ca tişthata, 433, 441 jaitrāvā (jaitryāyā) višatād u mām (°tan mam, ° tam mam), 315 ıyeşthasya dharmam dyukşor anike, ıvesthasya vä dharmanı kşor anike, 840 ıvok ksatre 'dhı ıägarat, 909 1yok śrotre 'dhi (adhi) jāgarat, 909 jyog ajītā (jītā, jīvā) ahatāh (°tā) svāma, 980 jyog jivema sarvavirā vayam tama, 224 jyog rästre adhi jägarat, 909 ıyotıh paşyantā (°ta) uttaram, 967 jyotih pasyanti vāsaram, 967 jyotişam na prakāšate, 278 ıvotıs paşyanta uttaram, 967 ıvotıs paśvantı vāsaram, 967 tekas ca sasaramatankas ca. 135. 165 nāsatyā , see nāsatyā ta ā vahanti kavayah purastāt, 342 tam vai manyet pitaram mataram ca. 849 tam vo grhnämy uttamam, 116 tam sakhāyah purorucam (purū°), 721 tam sadhrīcīr ūtayo vṛṣnyāni (vṛṣniyānı), 784 tam sma jānīta (otha) parame vyoman, tam hed agnır vidhāvati, 123, 637 tam gopāya (°vasva), 365 tam ghed agnır vıdhāvatı, 123, 637 tatah pāvakā āśişo no juşantām, 811 tatam me apas (ma āpas) tad u tāyate punah, 488 tataś cakṣāthām (cakrāthe) adıtım ditum ca, 853 tato jyāyāńś ca pūrusah, 566 tato dharmūni dhārayan, 578 tato na vicikitsati (vijugupsate), 45, 56, 68, 180 tato no dehi jiyase, 105 tato no mitrāvarunāv avistam, 533, 888 tato no rudrā uta vā nuv ('nv) asya, 719, 778

tato no vardhayā rayım, 74 tato yajnas tāyate visvadānim, 157 tato vaiño iavate visvadanih, 157 tato vākā āšiso no jusantām, 811 tato visvañ vyakrāmat, 94 tato ha jajñe ('ham yajñe) bhuvanasya gopāh (goptā), 192, 307 , see tam tve° tat tvendragraha tatra indro brhaspatih, 452, 992 tatra cakrāthe adıtim dıtim ca. 853 tatra no brahmanas patih, 452, 992 tatra pūsābhavat (°bhuvat) sacā, 602 tatra yamah sadana te krnotu, 405, 452, 512 tatra vonım krnavase, 452 tatra rayıştham anu sambharaıtam (°retām, sambhavatām), 267, 712 tatra siśriye 'ja ekapādah, 907 tatra havyāni gāmaya (gam°), 479 tatrā no brahmanas patih, 452, 992 tatrā sadah krnavase, 452 tat satvam vad vīram bibhrthah (°tah), 91 tathā visvan vvakrāmat (tathā vvakrāmad visvan), 94 tad agnir devo devebhyo vanate (vanutam), 606 tad asya priyam abhi pātho asyām (asthām), 287, 877 tad aham nihnave (nihnave) tubhyam, 603 tad ävuh. 360 tad āharanti kavayah purastāt, 342 tad ındragnī jinvatam (pinvatām) sünrtävat. 852 tad vävuh. 360 tad viprāso vipanyavah (°vuyah), 604 tad vipro abravid udak (u tat), 65, 142, 830 tad vo astu sucetanam ("tunam, sajosanam), 607, 612 tanuvam . , see tanvam tanūnapāc ca sarasvatī, 195, 810 tanūnaptre šakmane šākvarāya šakmanā ojişthāya, 240 tanūnaptre šākvarāya šakmann (šakvana) ojisthāya, 240 tanūpāc ca sarasvatī, 195, 810

tanūpā bhişajā sute, 867 tanūpā ye nas (tanūpāvānas) tanvas tanujāh (tapojāh), 254, 723, 833 tanūpāš ca sarasvatī, 195, 810 tanūyā bhisajā sute, 867 tanûr me tanvā saha, 793 tanur varsisthä gahanesthä, 368, 861 tanūs tanvā (tanuvā) me saha, 793 tam te grbhnamy uttamam. 116 tam te duścaksā māva khyat, 190 tam te vı şyāmy āyuşo na madhyāt (nu madhve), 614 tam tvam višvebhyo devebhyah kratün (°bhya rtun) kalpaya, 420, 665 tam tvā grnāmi tavasam atavyān (atavīyān), 786 tam tvā ghrtasnav (°sna) imahe, 889 tam tvā pra višāmi saha yan me 'sti tena, 910 tam tvā bhrātarah suvrdhā ("dho, suhrdo) vardhamānam, 109, 269 tam tva vavam sudhvo (sudhiyo) navyam agne, 789 am tvā višve 'vantu (avantu) devāh, 907 tam (tat) tvendragraha saha yan me 'stı (astı) tena, 910 tan nah parşad (parişad) atı dvışah, 43, 758 tan nas trāyatām tanvah sarvato (tan no viávato) mahat, 410 tan no dantī (°tih) pracodayāt, 529a tan no durgih (durgā) pracodayāt, 599 tan no brahmā (°ma) pracodayāt, 460 tan nau samvananam krtam, 593 tan ma (mā) āpyāyatām punaḥ, 992 tan mā jinva, 354, 829, 871 tan mā devā avantu šobhāyı, 414. 700 tan mā puńsi kartary erayadhvam, 414 tan mārjitvā, 354, 829, 871 tan māvatu (mām avatu), 812 tan māvīt (mām āvīt), 812 tan me tanvam trāyatām sarvato brhat, 410 tan me rādhyatām, 659 tan me samrdhyatām (samrddham), tanvam (tanuvam) me pāhi, 793

tanvo adya ('dya) dadhātu me. 909 tapatı varşan virād rāvat (rāvat) svāhā, 168 tapate svāhā, 329 tapatyai syaha, 248, 329 tapaś ca tapasyaś ca śaiśirāy (°rā) rtū, 888 tapasarşayah ("sarşayah) suvar (svar) anvavindan, 781, 918 tapasas tan mahmājāyataikam, 204 tapur yayastu carur agniyan (°mān) IVB. 239 tapūrīsy agne juhvā patamgān, 723 tapojām vācam asme niyacha devāyuvam, 51 tapobhir agne juhvā patamgān, 723 tapyate svaha, 329 tapyatvai ("tyai) svāhā, 248, 329 tam agne prtanāşaham (°saham), 984 tam ajarebhir vṛṣabhis tava (tapa) svaih, 200 tam ahhi soca yo 'sman (asman) dveşır..., 910 tam arcışă sphūrjayañ (°yań) jātavedah, 936 tam ardhamāsam prasutān pitryāvatah, 559 tamasas tan mahinājāyataikam, 204 tam aham punar ādade, 256, 845 tam ahve vājasātaye, 613, 798, 828 tam ā prna (prnā) vasupate vasūnām, 442 tam ähutam nasimahı (°tam asimahı), tam id arbhe havişy ā samānam it, 365, 826 tam ın mahe vrnate nanyam tvat, 365 tam u tvam māyayāvadhīh, 252 tam u nir vāpayā punah, 365 tam u me agadam kṛdhi, 849 tam u sucum sucavo didivansam, 547 tam u huve vājasātaye, 613, 798, 828 tam ū šucum šucayo dīdīvānsam, 547 tam piprhi dasamāsyo 'ntar udare, 112 tam priyāsam (bhri°) bahu rocamānah, tam manyeta pitaram mātaram ca, 849 tam mātā daša māso bibhartu, 112

tam mā devā avantu sobhāyai, 414. tam mā punsi kartary erayadhvam, 414 tam mā mṛdhah, 98, 225 tayā grnantah sadhamādeşu, 325 tavānantam kāmam (lokam) aham 1avāni, 365 tavā nas tanvā (tanuvā) šamtamayā, 793 tayā prattam svadhayā madantu, 365 tayā madantah sadhamādyeşu (°mādesu. ° mādhvesu), 110, 325 tayāvahante kavayah purastāt, 342 tavāham šāntvā tayā hatena pāpena, 365 tayor anu bhakşam bhakşayamı, 315 tavor (tavor nav) asthūri (°ri nau) , 950 gārhapatyam tayor aham anu bhaksam (°syam) bhakşayāmı, 315 tayor aham bhakşam anubhakşayāmi, 315 tayor devā adhısamyasantah, 172, 281 tayor nāv, see tayor asthūri tarakşuh (°kşah) krşnah svā caturakşo (°kşyā) , 335, 609 tarī mandrāsu prayaksu, 374, 381, 830, 839, 861 tava-tava rāyah, 42, 748 tava tvan māvavāvadhīh. 252 tava prasastayo mahih ("taye mahe). 695 tava vāyav (vāya) rtaspate, 889 tava śravānsy upamāny ukthyā (°ya). tava syām sarman trivarūtha udbhit, tava syāma śarmańs trivarūtha udbhau, 932 tavāham nāma bibharāny agne (agre), tavāham agne bibharāni nāma, 864

tasthau nākasya sānavi (śarmani), 287 tasmā u adya samanā (savane) sutam

tasmā u rādhah kṛnuta prasastam

(krnuhi supraśastam), 845

bhara, 233

tasmād āpo anu sthana (sthana). 987 tasmād vār nāma (nāma) vo hitam (vah priyam), 952 tasmins tad, see tasmin tad . . tasmıñ chiśriye aja ekapat, 907 tasmin (tasmins) tad eno vasavo ni dhetana (dhattana), 932 tasmını a tasthur bhuyananı visva, 386 tasmını arpıta bhuvanani visva, 386 ca, 491 106, 844 yamı, 594 594 dvesti tasthur grnantah sadhamādyāsah, 325

tasmın ma ındro rucim ä dadhātu, 596 tasmin vavam upahūtās tava smah (sma), 379 tasmın sidamıte pratitıştha (sidamite pratitisthan), 638 tasmın somo rucam ā dadhātu, 596 tasmın ha tasthur bhuvanānı viśvā, 386 tasmai devā adhī bravan (bruvan). tasmaı no devāh parıdatteha ("dhatta, °dhatteha) sarve (višve), 106, 844 tasmai brahma ca brāhmāš (brahmā) tasmaı mā devāh pari dhatteha sarve. tasmaı somo adhi bravat (bruvat), 602 tasya rksāmāny ., 919 tasya tārkşyas cārışţanemis ca senānīgrāmanyau (senāni°), 523 tasya te bhaktıvansah syama (°vano bhūyāsma), 377 tasya te vājipītasyopahūtasyopahūto (vājapītasyopahūta ["hatal upahūtasva) bhaksavāmi. 594 tasya te vājipītasyopahūto bhakşatasya te vājibhír väjipitasya tasya doham asimahı (asiya, asiya te). tasya nāmnā . yo 'smān (asmān) , 910 tasya no dhehi jivase, 105 tasya no rāsva tasya no dhehi (dāh), tasya prajā apsaraso bhiruvah (bhiravonama), 604 tasya yad āhuh pippalam svādv agre, 746

tasya rathagītsas (°krtsnas, °krtsas) ca rathaujās ca senānīgrāmanyau (senānī°), 46, 311, 523

tasya rathaprotas (rathe°) cāsamarathas ca senānīgrāmanyau (senāni°), 523

tasya rathasvanaś .. sen inigrāmanyau (senimo), 523

tasyarksämäny . , 919

tasya senajic . senānīgrāmanyau (senāni°), 523

tasyām devah savītā dharmam sāvisat, 142, 307

tasyām devā adhi samvasantah, 172, 281, 340

tasyām devaih samvasanto mahitvā, 281

tasyām no devah savītā dharmam (°ma) sāvīsat (°sak), 142, 307

tasyāpo apsarasa ('psarasa, °sā) ūrjo nāma ('psaraso mudāh), 910

tasyās te bhakşıvānıh syāma (bhaktivāno bhūyāsma, bhāgam asīmahı), 377

tasyās te sahasrapoşam puşyantyāš caramena pašunā krīņāmi, 162

tasyed āhuh pippalam svādv agre, 746 tā ubhau caturah . . prasārayāvahai ("yāva), 379

tā ekamūrdhnīr abhı lokam ekam, 172 tā eva vıvahāvahai, 269, 578, 694, 888 tī ehı sam rabhāvahai, 269, 694, 888

tīh prācya ('yah, prācīr) ujigāhire ('hīre, samjigāīre), 387, 540, 581, 737 tām vidyām brahmayonim svarūpām (brahmayonisva'), 818

tām šašvantā upayanti vājāh, 365 tām ba jaritar na (nah) pratyagrbhņan, 384

tā te dhāmāny ušmasi gamadhyai, 705 tādītnā (*knā) šatrum (*ūn) na kilā vivitse (vivatse), 141, 580

tānī brahmā tū (brahmota) šundhati (šumbhatī, šansatī), 173, 616

tām dhīrāsah kavayo 'nudišyāyajanta, 637, 909

tām dhīrāso anudršya ("dišya) yajante ("dīšyāyajanta kavayah), 637, 909 tām nah pūşan chivatamām erayasva, 937

tāny antah puruse arpītānī (°sa ārp°), 509

tābhir yāsi dūtyām (°yam) sūryasya, 494

tābhih śāntibhih sarvaśāntibhih śamayāmy aham, 365

tābhiş (vam (tābhis tvam) ubhayibhih samvidānah, 958

tābhyām ("yām vayam) pritema sukrtām u lokam (pathyāsma sukrtasya lokam), 96

tī mandasānā manuşo duroņa ā, 609 tām u dhīrāso anudišya yajante, 637, 909

tām nirayańs candraması svedhābhih, 930

tīm pūşan (pūşan) chıvatamam eravasva, 937

tām pūṣānu yachatu (pūṣābhi rakṣatu), 184. 244

tā yā devā ... sāsva (šāssva) ..., 391 tā vām vāstūny usmasi gamadhya, 705

tā vām gīrbhir vipanyavah (°yuvah), 604

tīv imā upa sarpatah, 379

tāv iha sam bhavāva, 269, 578, 694, 888 tāv ehi vivahāvahai (eha samvahāvahai), 269, 578, 694, 888

tav ehi samrabhāvahai, 269, 694, 888 tav ehi sambhavāva, 269, 694, 888

tāsīm visišnīnām ('šnyānām), 315, 878 tāsīm svasīr (svar, svasūr) ajanayat (ajanan) paūca-paūca, 644

tāsām išāno bhagavah (maghavan), 83, 242

tāsām ekī harikņikā (*klikā), 273 tīs tvā višantu manasā šivena (mahasī svena), 287, 857

tāsv adhvaryav ādhāvendrāya. brhaspatimate... 239, 890

t'sv adhvaryo indraya brhaspairvate.., 239, 890

tigmam Jyudham viditam (°dham Iditam, anikam viditam) sahasvat, 169, 360, 545 tıgmāyudhāya bharatā srnotu nah (srnotana), 383, 827

tirašcirājī (tirašcīnarājī) rakķitā, 542 tiroahniyān somān prasthitān presya, 787, 910

tiro rajānsy aspṛtah (°tam, astṛtaḥ), 180

tilvilāstām irāvatīm, tilvilā sthājirāvatī, tilvalā sthirāvatī, tilvilā syād irāvatī, 596, 828

tışthā ratham (rathe) adhi tam (yam, yad) vajrahasta (°tah), 380

tısrah kşapas (°pās) trır ahātıvrajadbhih, 494

tisras ca rajabandhavih (°vaih), 490, 701

tisro jihvasya samidhah parijmanah, 192, 579

tısro dadhur (dadur) devatāh samrarānāh. 105

tısro bhūmīr dhārayan ('yans) trīnr uta dyūn, 927, 932

tisro yahvasya samidhah parijmanah, 192, 579

tisro ha prajā atyāyam āyan (Iyuh), 598 tuce tanāya (tunāya) tat su nah, 605 tuje janā (jane) vanam svah, 207, 387 tujo yujo vanam (balam) sahah, 207, 387

tutho vo . varşışthe adhi ('dhi)
näke, 910

tutho 'sı janadhāyāh ("yah), 54, 93, 375 tubhyam sutāsah somāh, 846

tubhyam somāh sutā me, 846

tubhyam agne (agre) pary avahan, 864 turas cid visvam arnavat tapasvān, 64, 578, 826

turīyādītya (turyā") savanam (ha") ta indriyam, 299, 786

turo na yāmann etašasya nū rane, 561 tuvidyumnam vibhvāsaham (vibhā°), 371

tuvişvanasam (°şmanasam) suyajam ghrtasriyam, 236

tūrnim devāsa iha suśriyam dadhuh, 177

tūrvan na yāmann etašasya nū rane, 561

tṛṇam vasānā ("nāh) sumanā asas (asi) tvam, 381

trta enam (enan) manuşyeşu mamrıe, 414, 468, 670

trtīyasya savanasya rbhumato (°syaı hu°) brhaspatimato (°vato) , 239, 919

trtīye dhāmāny abhy (dhāmann adhy) arrayanta, 172, 928

trte devā amrjataitad enah, 670 trsucyavaso juhvo nāgneh, 40, 667 trsu yad annā vevisad vitisthase, 667 trstam pišitam asyate (aš°), 278 te arsantu te varsantu te krivantu, 360 te asmat pāšān pra muñcantv enasah, 907

te asmā agnaye (°yo) dravinam dattvā, 909

te asmın (asmıñ) javam īdadhuh, 936tekas ca sasaramatandas ca, 135, 165 tegān danstrābhyām, 374

tejo mayı dhehi; tejo me dah (dehi, dhah), 103

tejo yaśasvi sthaviram samiddham (samrddham), 39, 635

te te dhāmāny usmasi gamadhye, 705 te dakṣinām duhate (te duhrate dakṣinām) saptamātaram, 356

te na ātmasu jāgratı (jāgṛta), 662 tena ṛṣinā , 919

te nah pāntv asmin brahmany asmin karmany asyām . . . 928

tena krīdantīš carata (°tha) priyena (vašān anu), 90

tena tvam agna iha vardhayemam, 835 tena dasyūn vy asahanta devāh, 983, tena devā vy asahanta šatrūn, 983 tena no mitrāvarunāv (°nā) avistam, 533, 888

tena mām abhişincatam, 293, 835 tena mā saha sundhata (sumbhantu, °atu), 173

tena yo 'smat samrchātai (samrtsātām), 183, 811

tena rādhyāsam (tenardhyāsam), 806 tenarşinā., 919

tena vayam sahasravalšena, 458 tena vayam bhagavantah syama, 458 tena vardhasva cā ca pyāyasva (vardhasva cāpyāyasva), 808 tena samvaninau svake, 593 tena samhanu krnması, 47, 386, 840 tena sann anugrhnāsı, 47, 386, 840 tena sahasrakāndena, 458 tena somābhi raksa nah, 516, 950 tenägne tvam uta vardhayemam (vardhayā mām), 835 tenānyo 'smat samīchātai, 811 tenārātsyam (°tsam), 333 tenā vayam bhagavantah syāma, 458 tenā sahasrakāndena, 458 tenemam agna (agra) iha varcasā samangdhi, 864 tenemām upa sincatam, 293, 835 te no 'gnayah paprayah parayantu (pāla°), 260 te pāyavah sadhryanco (sadhrıyanco) nisadya, 784 te brahmalokesu (°loke tu) parāntakāle, 824 tebhis tvam putram janaya, 958 tebhih somābhi (bhī) raksa nah (nah), 516, 950 tebhyo ghrtasya kulyaitu (dhārayitum), 747 tebhyo namo astu ('stu), 910 te mat prātah prajanisyethe (°te), 91 te mā prajāte prajanayişyathah ("tah .), 91 te varşantı te varşayantı, 360 teşām yo ajyānim ('jyānim) ajītim), 588, 907 avahāt (ajījim , 878 teşām visipriyānām teşām sam hanmo akşānı (sam dadhmo aksīni), 598 teşām ajyānım (°nam) yatamo vahātı (na āvahāt), 588 tesām apsu sadas kṛtam, 988 teşv aham sumanāh sam višāmi (°ti, °nı, vasāma), 281 te 'smat pāšān pra muñcantv anhasah, 907 te 'smā agnaye dravinām dattvā, 909 te ha jajne bhuvanasya gopāh, 192, 307 tais tvam putram ("ān) vindasva, 958

to-to (to te) rayah, 42, 748

vvasasarıa) bhūmvām, 736 tau te krodham navāması. 98 tau te bhaksam (bhaksyam) cakratur agra etam, 315 tau saha caturah prasāravāvahai (°vāvah), 379 tyam hy agne agnina, 252 trayis sad urvīr uru nas krnota, 817, 950, 964 trātāram indram akrnor avadhyam (ayudhyam), 255 trınşad asyā jaghanam yojanānı, 340 trınsad dhāma (trınsaddhāmā) vi rājati, 460 trınsad yasyā jaghanam yojanāni, 340 trikakuc(°kup) chandah, 178 trikadrukebhih patati (pavate), 853 trinave marutah (°ta) stutāh (stutam), trita etan manuşyeşu māmrje, 414, trite devā amrjataitad enah, 670 tridhā baddho vrsabho roravīti, 687 tripadā yā ca şatpadā (yāś ca şatpadāh), 381 tribandhurena trivitā rathena, 213 tribandhuro manasā yātu yuktah, 213 triyavı-, see tryavıtrir asmai sapta dhenavo duduhre ("hrire), 810 trivandhurena trivrtā rathena, 213 trıvandhuro manasā yātu yuktah, 213 trivid bhuvanam yad rathavrt (°vrk, trivid yad bhuvanasya rathavit), 142 trıśug gharmo vibhātu me (gharmas sadam ın me vıbhātı), 145, 355 triśrud gharmo vibhūtu me, 145, 355 trişaptāso marutah svādusammudah, 986 trisucyavaso juhvo nagneh, 40, 667 trışu yad anna vevışad vıtışthase, 667 trıştub (trıştug) graışmī, 148 trısaptāso marutah svādusammudah, 988 trīnī padāni (padā) nihitā guhūsya (guhāsu), 803, 826

toyena jīvān vi sasarja (vya ca sarja,

trīni padāni rūpo anv arohat, 569 trīni šatā trī sahasrāny (şa°) agnum, tredhā baddho vrsabho roravīti, 687 . and tryavis (tritrvavir (triyavir) vaviš) ., 776 tva eşah samdadhur bhürivarpasah, 292, 360, 694 tvam rājāsi pradivah (pratipat) sutānām, 64, 200 tvam rāva ubhavāso janānām, 507 tvam rauhmam (roh°) vyāsyah, 728 tvam valasya gomatah, 210 tvam vettha yatı te jätavedah, 60 tvam hi rādhaspata (°syata) eka Iáise, 867 tvam hy agne agninā, 252 tvam gopāva, 365 tvam no devatătaye (deva dătave), 61, 248, 832 tvam u nirvāpayā punah, 365 tvam etāň (etān) janarājňo dvir daša. 936 tvam balasya gomatah, 210 tvavāgne kāmam aham jayāmi, 365 tvayā įvasena sam ašīmahi tvā, 421, 835 tvayā prattam svadhayā madantı (°tu), 365 tvayā bhūşanti vedhasah, 831, 911 tvayāyam vrtram vadhyāt (badhet, badhyāt), 209, 803 tvayāvasena sam asīmahı tvā, 421, 835 tvayāham sāntyā tvayā hatena pāpena, 365 tvastar devebbis sahasāma indra, 380, tvastā turīpo ("yo) adbhutah, 867 tvaştā devaih sahamāna indrah, 380, 870 tvaştā no atra varivah (varīyah) krnotu, 249, 541a tvaştā no atra vi dadhātu rāyah, 849 tvaştā rūpāni dadhatī (dadatī) sarasvatī, 105 tvaştā sudatro vi dadhātu rāyah, 849 tvastīmatī te sapeya, 357, 641 tvaştur varutrim varunasya nābhım. 528, 562

tvastrmantas (tvastri°, tvastu°) tvā sapema, 39, 357, 641, 667 tvastrīmatī te sapeya, 357, 641 tvām rāva ubhayāso janānām, 507 tvām šašvanta upa vantī vājāh, 365 agne samidhānam vavistha (°thya), 315 tvām adya rşa (adyarşa) ārşeya rşīnām (ārseyarsī°) 919 tvām abhi pra nonumah (no°), 952 tvām arbhasya havişah samānam it, 365, 826 tvām maho vrnate ("te naro) nānyam tvat, 365 tvışımındre na (indrena) bheşajam. tvişir apsu goşu yā puruşeşu, 849 tvisir aśvesu purusesu gosu. 849 tve ā bhūsantı vedhasah. 831. 911 tve ısah (viśve) sam dadhur bhūrivarpasah (bhūriretasah), 292, 360, 694 tve kratum apı vrājantı višve (prācanti hturi), 57, 200 tveşam cakşur dadhıre codayanvatı (°mati), 239 tvesas te dhūma rnvatı (ūrnotu), 655 dakşakratubhyām . . 556 dakşam ta ugram ābhārışam (te bhadram ābhārşam), 758 daksam dadhāsi (dadāsı) jīvase, 105 datto asmabhyam (dattvāvāsma°. dattāyāsma°, dattāsma°) dravineha bhadram, 90, 342, 367 dadhatha no dravinam yac ca bhadram, 90, 342, 367 dadhad yo dhayi sute vayansı, 272a, 592, 612 dadhad ratnam ("nā) dakşam pitrbhya (dakşapıt°) ayunı (ayūnşı), 555, 819 dadhad ratnā dāšuşe vāryānı (ratnānı dāšuķe, ratnā vi dā°), 849 dadhad vidhakşyan paryankhayatai, 145, 332, 634, 710 dadhanvān ("vā, "vān) yo naryo apsv antar ā, 942 dadhı mantham parışrutam (mantham parisrutam), 275

dadhir vo dhāyi sa te vayānsi, 272a, 592, 612 dadhısa ehi. 635 dadhrg vidhaksyan paryankhayate (vidheksan parlūkhayātai), 145, 332, 634, 710 dadhrey chi, 635 dame-dame sustutir ("tya, "tir, "ti) vām ivānā (vāvrdhānā, onau), 236, 544, 640, 828 daridea (°dran) nilalohita. 401 darbhaih strnita haritaih suparnaih (suvarnath), 200 dasasyantāmṛtāya (°tvāmṛtāya) kam, 367 dahram (daharam) vipāpmavaravesmabhūtam (vipāpmam varam veśmabhūtam, vipāpam), 763, 819 dātum cec chiksān sa (chaknuvānsah, °yān sa) svarga eva (eṣām), 381, 571, datrasyagne svarpatih (svah°). 968 dūma grīvāsv avimokyam yat (grīvāsv avicartyam), 649 dāmno-dāmno rājan, 107 dāsyann adāsyann uta sam grnāmi (uta vā karışyan), 45 digbhyas cakravākah (cakr°), 658 digbhyo vadabe (°ve), 219 diteh putrāņām adıter akārşam (°rısam), 758 diva oşadhayas (°yah) parı, 964 dıyah parıanyad antarıksat prthivyah, dıvah prthivyāh pary antarikşāt, 964 divah prthivyäh pary oja udbhrtam, 964 dıyah pıştham svar (suvar) gatyā, dıvah preth-, see divas ek dıvam skabhāna, 137 dıvam agrenāspiksah (°şat, agrenāprāt), 375 divas eid antād upamām (upa mām; antān upamān) ud ānat, 824 dıvaş chadması, 324 diva (divas, divah) skambhanir (°nir, . 529, 977

ony)

divas parjanyād antarīksāt prthivyāh. 964 dıvas prthivyāh pary antarikşāt, 964 dıyas prthivyäh nary ola udbhrtam, dıvas pretham svar gatva, 964 dıyas (dıyah) pretham adhi tışthantı (rohanti) cetasă (tejasă), 57, 802, Ω64 divas (divah) pretham ("the) bhandamanah (mand°) sumanmabhih, 242, divas (dıvah) prethany aruhan (chat), dıyah samspråas (sampreas) pāhı, 195, divacarebbyo (°caribbyo) bhūtebbyah, divi jyotir ajaram (uttamam) ārabhetam ("tham), 91 dıvı mürdhünam dadhışe svarşam (suvarsām), 780 dıvi şafi (şan, san) chukra atatah. 937. 987 dıvı sad (şad) bhümy ā dade, 987 dive lyotir uttamam ārabhethām, 91 divo antebhyas ('nte°) pari, 907 divo jyote (jyotir) vivasva āditya te no , 337, 686, 720 818 devā . dıvo dhärām bhindhi, 324 divo väbhışthām anu yo vicaşte, 156, 170, 220 diyo vā vışnav (vışņa, dıvo vışna) uta vä prthivyäh, 887 divo viśvasmät sim aghāyata uruşyah, divo vistim varsayatā purīsinah, 90 divyah kosah samuksitah, 196, 686, 699, 707 divyam suparnam väyasam (payasam, vayasam, 'sā) brhantam, 200, 490 dıyyam chadmäsı , 324 , 413, dıvyā āpo nannamyadhvam 686 dıvye dhāmanı (°many) upahūtah (°tā), 928 divyo gandharvah ketapüh (°pāh) , 619

dıştāya rajjusarjam ("sargam), 132 dikşayedam (dikşiye) havır agachatam nah. 507 dīkṣāyai tapase 'gnaye (agnave) svāhā. 910 diksito 'yam asa amuşyayanah, 888 dirgham āyuh pratirad bhesajāni, 575 dīrghām anu prasitim (prasṛtim, samṛtim) āyuşe dhām (tvā; samspṛśethām), 78, 292, 637 duras ca visvā avīnod apa svāh, 64, 578, 826 durītāni yānī kāni ca cakrma, 808 durītā yāni cakīma, 808 durmitrās ("triyās, "tryās) tasmai santu (bhūyāsur) yo 'smān (asmān) dvesti ..., 315, 787, 910 luvasyave (duvasvate) tvā vātāya svāhā, 248 duścaksās te māvakšat (°kṣat, °khyat). duścyavanah prtanasad (°sal) ayudhyah (ayo"), 713 duşvapnahan (duşşva°, duhsva°) duruşyaha (duruşşaha, duruşvahā), 255, 408, 980, 986 duşvapnyam duritam nih (nı) şvāsmat. 980 düredráam grhapatim atharyum (athavyum), 267 dūrepašyā ca rāstrabhre ca tāni, 820 dürehetir ındrıyavan (°yavan) patatri (°trih), dürehetih patatrī vājinīvān, 467, 529a dūrvā rohatu puspinī (rohantu puspinîh), 381 düşikābhır hrādunim (hra"), 488, 528, dınhantam daıvir visah kalpantam manuşyāh, 316, 490

diśam devy (tevy) avatu no ghrtaci,

dısam patır abhayad yanınıyan, 869

diśo abhy abhūd ayam, 910

diśo 'bhy ayam rājābhūt, 910

diśo yajńasya daksinah, 161, 579

diśo viśvā anu prabhuh, 381, 869

21, 66

drahasya vidayasya (vira*) su. 272 drdhā cid yamavişnavah, 857 drvāsi (drbāsi), 219, 679 dršā ca bhāsā brhatā sušikmanā. 240. 283, 624 dršāno rukma urvyā (urviyā, uruyā) vy adyaut (vi bhāti), 743, 791 drše ca bhāsā brhatā sušukvabhih (°vanih), 240, 283, 624 devakośah samubjitah, 196, 686, 699, deva gharma rucitas tvam devesv ā. 713 devajūte vivasvann āditya..., 337, 686, 720, 818 devatrā havyam ühişe (ohc, ohire), 722 deva tvastar vasu rama (ranva, rana, rane), 225, 366 deva purascara saghyāsam (devapuras carasa rdhyāsam) tvā, 147, 634, 817, 838, 861 devabarhıh (deva barhis) satavalsam vı roha, 817 devam manah kuto (krto) adhi prajātam, 642 devayuvam (devã°) višvevīrām (°vāre), 478 devayor dharme ("mā, dhāmann) asthiran, 350 deva vișna (vișnav) urv . . ., 887 devasrīh śrīmanāh ("maṇāh) satapayāḥ (°pāt), 953 deva samsphāna sahasraposasyešise (sahasrā°), 466 deva savitah susāvītram (suṣā°) adyāsmın.., 986 devas te savitā hastam grhnātu, 116 devas tvā savitā punātu vasoh... supvā (supuvā), 789 devas tvā savitotpunātu...supvotpunāmi, 789 devasya (°syāham) savituh . . . ruheyam (roheyam), 715 devā akrnvann ušijo amartysve, 152, 643, 650 devā etasyām avadanta pūrve, 810 devāh pāntu yajamānam nyarthāt (nirrthat), 650

devanso yasmai tvede tat satyam upariprutā (apariplutā) bhangena (bhangyena), 261, 315, 616 devā gātuvido ("vido gātum vittyā, gātum itvā) gātum yajnāva vindata (gātum ita), 360 devāñ jīgāti sumnayuh, 936 devā devebhyo adhvaryanto (adhvarīyanto) asthuh, 786 devānām visthām anu yo vitasthe. 156, 170, 220 devānām tvā patnīr devir viśvadevyāvatīh (°devya°) prthivyāh dhasthe angurasyad ('ngı') , 467, 910 devānām devatamā šavisthā (šacisthā), devānām nisthām anu vo vitasthe. 156. 170, 220 devānām agneyāny ası, 357, 692, 818 devānām patnībhyah pulīkāh, 149 devānām patnīr (patnyo, patnayo) disah (visah), 869 devānām bhāgadā asat, 105 devā no yajnam rtuthā (rjudhā) nayantu, 75, 157 devān jigāti sumnayuh, 936 devān devayate (devā°) yaja (yajamānāva svāhā), 478 devān mā bhayād 1t1, 707 devān yajnījān iha yān yajāmahai (havāmahe), 710 devān sendrān upa te huve savāham ('sā aham), 362 devā brahmāna āgachata āgachata (āgachatāgachatāgachata), 995 devā bhavata vājinah, 90 , see deva° devāvuvam devā vā etasyām avadanta pūrve. 810 devī usāsāv (°sā) a\$vīnā, 888 devī dvārau mā mā sam tāptam, 357, 732 devīm nāvam svarītrām anāgasam, devim aham nir;tım vandamānah (bādhamānah), 207 devîr āpo agreguvah (agreguvo devayuvam [devā°]), 478, 910

devīr āpo apām napād dhatta (datta, dāta), 104 devir apo 'greguvo , 910 devīr āpo (āpo apām napād) yo va ürmih pratürtih kakunmän väiasäs tenāyam vājam set, 178, 239 devîr devîr (devair) abhi mā nivartadhvam, 701 devīr devaih samāhrtāh ("bhṛtāh), 118, 639 devīr dvāro mā mā samtāptam, 357, 732 devih şad urvir (sadurvir) uru nah (nah) krnota, 707, 817, 950, 964 devebbir aktam (vuktam) adıtıh saioşāh, 339, 617 devebhyas tanübhyas svāhā. 695, 707 devebhyas tvā devāvuvam (devāvvam) prnacmi (prnaimi) , 55, 805 devebhyas tvā devāvyam (devāyuvam) grhnāmi , 805 devebbyo bhayata ("tha) suprāyanāh. devebhyo bhāgadhā (°dā) asat. 105 devebhyo havyam vahatu prajanan, 849 devebbyo havyam vaha (vaha nah) prajānan, 849 devebhyo havyavāhana ("nah), 380 devebhyo havyā vahatu prajānan, 849 devesu havvayāhanah, 380 devair uktā (nyuptā, nuttā) vyasarpo mahitvam (°tvā), 139, 152, 180 devair devih samāhitāh (°hṛtāh), 118, devair nuttā (nyuptā) . see devair devo narāšanso 'gnau ('gnā) vasuvane , 910 devo vah savitā hiranyapānih pratigrbhnātv (savitā pratigrhnātu .) devo vah savitā hiranyapānih prati (° pānīr upa) granātu, 116 devya āpo nannamyadhvam (nam-), 413, 686 namyadhyam devyo vamryo (vamriyo) bhūtasya daıyam manuşa yuja, 132, 317

dyauh pitah prthivi mätar adbruk, 967 daıvan ma bhayat pahı, 707 dvauh pitā prthivī mātā prajāpatir daivā hotāra ürdhvam adhvaram nah. bandhuh, 967 317 daıvā hotārah sanısan na etat. 317. 411, 623, 825 daıyim nayam svaritram anagasam (°sah), 707 daivibhvas tanübhyah svähä, 695, 707 daivih sad urvir uru nah krnota. 707. 817, 950, 964 daivo yo manuso gandhah, 317 daivyah kośah samubjitah, 196, 686. 699, 707 daivyam mānusā yugā, 132, 317 . , 724, 833 daivyā adhvaryū ā gatam, 888 daıvyā mimānā manusah (manasā) purutrā, 293, 609 daivyāya dhartre jostre (dhātre deşram) tre), 159, 350 daivyāv adhvaryū ā gatam. 888 daivyā hotārāgnā ("gna, hotārā agna) drubāsi, 219, 679 ājyasya vītām, 888, 992 daıvyā hotārā (°rāv) ürdhyam (hotārordhyam) , 317, 886 987 daıvyā hotārā (°ro) vanuşanta (vanişanta, vanışan na) pürve (etat), 317, 411, 623, 825 daivyo yo manuso gandhah, 317 dyām varşayatho (°to) asurasva māyayā, 91 dyam stabhana, 137 ...), 466 dyāvāpīthīvī uro (urv) antanksa ("ksam), 912 arjuni, 499 dyutadyubhır namasyaır ıyana, 953 dyutāno vālibhir yatah (hitah), 256, asmākam, 499 579 dyumattamā supratikasya sūnoh (°tīkah sasūnuh), 189, 716, 840 dyumad vibhāti bharatebhyah sucih (pāpam), 857 (suci), 381 dyumantam suşmam ā bharā (bhara) svarvidam, 446 dyumnam sudatra (dyumnā suksatra) 272a, 651, 838 manhaya, 857 dyumnī ślokī (śuklī) sa somyah (sau°), 714, 728 dyusamantasya ta ādıtyo 'nukhyātā, 682 724, 833

dyauh pretham . . ., 967 dyaur nah pitā pitryāc (pitryāc) cham bhavāti (°si), 674 dyaur yatas cyutad agnāv eva tat, 336 dyaus tvā pitā prthivī mātā. 958 dyaus pitah prthivi matar adhruk, 967 dyaus pitā prthivī mātā, 967 dvaus pratham . , 967 dyaus te pitā prthivī mātā. 958 dvauh samā tasyāditya upadrastā drapsas caskanda prthivim anu dyām (prathamāň anu dyūn), 235, 619, 665 drāghīya āyuh prataram ("rām, prati-506, 575 drunā sadhastham aśnuse, 713 drunā sadhastham āsadat, 713 druhah pāśān (pāśam) prati sa (şū) mucīsta (prati muūcatām sah), 621. drone sadhastham asnuse, 713 drone sadhastham āsadat, 713 dvā yantārā bhavatas tatha rtuh (tathartuh, tathā rtuh), 918 dvārapāya ..., dvārapopa ..., dvārapy . , dvārapyai (dvārā° dvipae catuspad (dvipāc catuspād) dvipac catuspad (dvipac catuspad) dvisate samnayāmasi, 878 dvisato badho (vadho) 'si, 209 dvışadbhyah prati muncami pasam dvışantam apa bādhasva, 201 dvışantam me vabādhasva, 201 dvisas tad adhy arnaveneyase, 244, dvişas taradhyā (°yai) mayā na īyase (frase), 244, 272a, 651, 838 dve srutī (sṛtī) asmavam pitrnām, dvyuşam jāgriyād aham, 674

dhattam ratnāni dāšuse. 849

dhanamjayam dharunam dharayishu. 177, 268, 381, 857 dhanam me sansyājugupah. 548 dhanasātāv ("tā) ihāvatu, 888 dhanasprtam süsuvänsam sudaksam. 609 dhanānı śakro dhanyah (dhanih) surādhāh, 734 dhanus tanvanti (dhanus ta°) paunsvam. 956 dhanusprtam šūšuvānsam sudaksam, dhamantı bākuram (vā°) dṛtım, 216 dhartāras te (te subhage) mekhale mā risāma, 176 dhartā vidhartā paramota samdrk, 350, 835, 869, 871 dhātar āyantu sarvadā (sarvatah svāhā), 68 dhātā dadātu (dadhātu) dāšuşe, 106 dhātā dadātu dāšuse vasūni, 106 dhātā dadātu (dadhātu) no rayım, 105 dhātā dadhātu (dadātu) sumanasyamänah, 105 dhātā vidhātā paramota samdīk (paramo na samvrk), 350, 835, 869, 871 dhātā višvā vāryā dadhātu, 106 dhātā samudro apa ('va) hantu pāpam, 201, 907 dhätä samudro abhayam krnotu, 907 dhātuh katkatah (kakkatah), 139 dhānāsomān manthina indra (indrah) áukrāt, 380 dhāman (°man) te visvam bhuvanam adhiśritam, 932 dhāmno-dhāmna iha muficatu, 107 dhāmno-dhāmno rājan, 107 dhṛṣnvojasah dhārāvarā maruto (dhṛṣnuvojasah), 777 dhik tva jaram (jalmi punscali, "li) , 260 dhipsyam va samcakara janebhyah, 45, 56, 107, 180, 446, 480 dhiya invāno dhiya in no avyāt, 386 dhiyā na (no) vājān upa māsi (māhi) sasvatah, 298

thamā manīsā), 598 dhıya martah sasamate (martasva śamatah), 189, 840 dhiyo hinyano dhiya in no ayyah (avvät), 386 dhisanā tvā devī višvadevvavatī angırasyad abhinddham (abhindhatām) ukhe, 467 dhışanāsı parvatī (pāro, parvatyā), 316, 490 dhısanas tva devir vısvadevyavatih sadhasthe angirasvad abhindhatām ukhe, 467, 910 dhisane Idite-Idetham, 169, 360 dhışane vidü (vidvi, vite) vidavetham (vil°), 169, 360, 743 dhinam antah sabardughah, 696 dhīrā devesu sumnayā (sū°, sumnayau), 563 dhuksimahı prajām ışam, 176, 618 dhuñkṣāgneyī (dhuñkṣyā°, dhuñkṣvā°), 255, 311, 335, 370, 568 dhūmrā babhrunikāšāh pitīnām somavatām, 628, 742 dhurta ("te) namas te astu ('stu), 910 dhürte namante astu, 910 dhūrva tam yo 'smān dhūrvatı, 910 dhenām antah sabardughām, 696 dhenus canadvāns ca, 930 dhruvam yonım ä sida sādhuyā (sādhyā), 505 dhruvam ayā (ayo) dhruvam utāšamışthäh (utā śavistha), 86, 234, 835 dhruvam ası dhruvata ("tah) sthitam, 977 dhruvas tışthāvicācalıh (°lat), 592 dhruvām yonım āsīda sādhyā, 505 dhruvāya bhūmāya (bhaumāya) svāhā, dhruvāsah (dhruvā ha) parvatā ime, dhruvā strī patikule iyam (°kuleyam), dhvańsaso vi vrhāmi te, 176, 222 dhvara dhvarautam yo asman dhvarat,

910

dhıya manota prathamo manişi (pra-

dhvāntam vātāgram anusamcarantau (abhīsam°), 864

dhvāntā vātā agnim abhi ye sam caranti, 864

na kir (ki) devā minīmasi (inī°), 311, 357

nakih sa dabhyate janah, 126, 621

naktamcarebhyah (°cārībhyo bhūtebhyah), 488, 690

nakşatrānām sakāšān mā yauşam, 306 nakşatrānām mā samkāšaš , 306

nagnahur dhīras (vīras) tasarām na vema, 857

na ced avedī (°dı, °dır, °dīn) mahatī vinastih, 525, 530

na jyotinşi cakāsati, 278

na tato vijugupsate, 45, 56, 68, 180

na tadā vicikitsati (vijugupsate), 45, 56, 63, 180

na tad rakṣānsı na pıśācāś caranti (°cās taranti), 155

na tā arvā renukakāto ašnute ('šnute), 907

nadayor vivratayoh sūra indrah, 665, 828

nadībhyah pauñjistham (*stam), 86 na devo vṛtah śūra indrah, 665, 828

na dhvasmānas tanvī (tanuvī) repa ā dhuh, 793

na pāpatvāya rāsīya (ransīsam), 301 nabhas ca nabhasyas ca vārsīkāv (°kā) rtū. 888

nama äkşınakebhyah, 540

nama ākhidate ca prakhidate (ākkhidate ca prakkhidate) ca, 401, 405

nama adıtyaya dıvıkşite lokasprte (°smrte), 205

nama ānurhatebhyah (ānṛha°), 653 na ma idam upadambhiṣag (udam bhiṣag) ṛṣir brahmā yad dade, 272a, 831, 832

nama işumadbhyo dhanvāyıbhyas ("vibhyas) ca vo namah, 247

nama idhriyāya cātapyāya ca, 360, 787 nama ūrvyāya ca sūrvyāya (ūrmyāya ca sūrmyāya) ca, 228

namah kātyāya ca gahvareşṭhāya (°sṭhyāya) ca. 321 namah kinsilāya ca kşayanāya (kṣenāya) ca, 42, 744

namah kṛchrebhyah kṛchrapatibhyaś ca vo namah, 45, 185

namah kṛtsnāyatayā ("yatāya, kṛtsamvītāya, kṛtsnavītāya), 311, 507

namah pathyāya ca srutyāya ca, 682 namah parnāya (parnyāya) ca parnašīdāya (°šadāya, °šadyāya) ca, 325,

486 namah puñjiştebhyo (°şthebhyo) nişādebhyas ca vo namah, 86

namah śamgave (śamgāya) ca paśupataye ca, 250, 808

namah saspinjarāya (sis°) tvisīmate 278, 294, 580

namah sighryāya (sighriyāya) ca sibhyāya ca. 315. 787

namah sibhāya ca sighrāya ca, 315, 787 namah suskyāya (susyāya) ca harityāya ca, 420

namah śvanibhyo (śvani°) mṛgayubhyaś ca vo namah, 528

namas te astu, 910

namas te astu rudrarūpebbyah, 817 namas te rathamtarāya (rātham') . , 491

namas te rudra rūpebhyo namah, 817 namas te 'stu, 910

namah samudrasya cakşase (cakşuşe), 608

namah saspinjarāya tvişīmate, 278, 294, 580

namah sūtāyāhantyai ("hantyāya, "hantvāya), 248

namas sūrmyāya cormyāya ca, 228 namah sūryāya divikṣite lokaspṛte, 205

namah sṛkāyibhyo (°vibhyo, sṛgāyibhyo) jighānsadbhyah, 48, 247 namaḥ sṛtyāya ca pathyāya ca, 682

namah senibhyah seninibhyas (°nibhyas) ca vo namah, 527

namah sobhyāya ca pratisaryāya (°sarāya) ca, 325

namah srutyāya ca pathyāya ca, 682 na mānsam ası nodalam (no dalam). 835

na mänseşu na snāvasu, 826 namucav (°ca) asure saca, 888 na me tad upadambhisar dhrsir brahmü vad dadau, 142, 272a, 831, 832 namo agnaya upadrastre, 910 namo agrīyāya ('gryāya, 'grīyāya) ca prathamāya ca, 541, 787, 910 namo agrevadhāva ('gre') ca dūrevadhāya ca, 910 namo aparasadbhyah, 910 namo aśvebhyo ('śve') 'śvapatibhyaś ca vo namah, 910 namo astu nilagrīvāya, 908 namo astu parāyate, 907 namo astu ('stu) rúdrebhyo ye antarıkşe ('ntar') . . , 910 namo astu ('stu) rudrebhyo ye divi . , 910 namo astu ('stu) rudrebhyo ye prthi-, 910 vyām namo astu ('stu) sarpebhyah, 907 namo girikebbyo devānām hṛdayebhyah, 49 namo girišayāya (girišāya) . 810 namo grtsebhyo grtsapatibhyaś ca vo namah, 45, 185 namo 'gnaya upadrastre, 910 namo 'gnaye prtbivikşite lokasprte (prthivikate lokakate, "vikate lokasmrte), 205, 524 , 'grevadhāya namo 'grīyāya 'gryāya., see namo ago namo jaghanyāya ca budhnyāya (°niyāya) ca, 787 cāhananyāya dundubhyāya (dundubhaye cāhananīyāya) ca, 325, 786 punjisthebhyas nısädebhyah namo (°stebhyaš) ca vo namah, 86 namo nīveşyāya (mº) ca hīdyāya ca, 248, 315, 516, 658 namo 'parasadbhyah, 910 namo babhluśāya vyādhine (vivyūdhine), 810 namo budhnyāya ca jaghanyāya ca, 787 namo mahadbhyo (brhadbhyo) arbhakebhyas ('rbha') ca vo namah, 910

namo mrgayubhyah syanibhyas ca vo namah, 528 namo maunjyäyormyäya (°yaurmyāya) . . 728 namo yuvabhya āśīnebhyaś (āśi°) ca 70 542 namo yuvabhyo nama āsmebhyah, 542 namo rathibhyo arathebhyaś ('rath') namo rudrāyātatāyme (°vme). 247 namo lopyāya colapyāya (colapāya) namo vah kirikebhyo namo vah pitarah susmaya (sosaya, śūşāya), 569, 713, 720 namo vātyāya ca reşmyāya (reş-, 787 miyāya) namo väyave 'ntarıkşakşıte lokasprte (°smrte, lokaksite), 205 namo viksinatkebhyah (viksinakebhysh), 540 namo vidhryāya (vidhrıyāya) cātaруауа св. 360, 787 namo vrddhäya ca savrdhe (samvidhvane, savidhvane, suvidhvane) ca, 306, 612 namo vo astu ('stu), 910 , see namo aso namo 'śvebhyo namo 'stu nila", 908 namo 'stu parāyate, 907 namo 'stu , see namo astu namo hrdayyāya ca nīveşyāya ca, 248, 315, 516, 658 namo hradayyāya (hradavyāya) ca nivesyyāya (°şyāya) ca, 248, 315, 516, 658 na yac chudresv alapsata (alipsata), na yajñasya manvate martyāsah (martasah), 315 nayantam girbhir vanā dhıyam dhāh, nayanto garbham vanām dhıyam dhuh, na yonā (yonāv) uşāsānaktā, 886 narāšansa staviņyate, 490 narāšanse somapītham ya ūšuh (ānnáuh), 490

na vā u (uv) etan mrīyase na rīşyasī, 774 na vai gāvo mangīrasya (mandīrasya), 144 na vai švetasvādhyācāre (švetaš cābhyāgāre, śvetasyābhyācārena, śvetasvābhyācāre), 128, 172, 188, 824 na sīm adeva āpat (āpa tat), 810 na sīsarīdatah (°rīdata), 384, 525 nahı te nāma jagrāha, 116 nahy anyam badākaram (balā°), 271 nahy asyā (asyaı) nāma grbhnāmı, 116 nākam grbhnānāh (grh°) sukrtasya loke, 116 nākro makarah kulīpayas (kulīkayas, pulīkavas, pulīravas) te 'kūpārasya (kūvarasya), 149, 198, 489, 802 nāgo rayır ā ciketa, 244, 837 nātārīd (°rīr) asya samṛtım vadhīnām (ba°), 209, 272a nādya satrum nanu (na nu) purā vivitse (yuyutse), 255, 627, 805 nādhṛṣa ā dadhṛṣate (dadharṣa, dadharşayā), 648 nānā hi vām devahitam sadas (sadah) krtam, 964 nāpa vrnjāte na gamāto antam, 198, 201 nābhā samdāyi navyasī (samdāya navyase), 584, 695 nābhimṛśe (nābhidhṛṣe) tanvā (tanuvā) jarbhurānah (jarhṛṣānah), 121, 292, 654 nārāšansa stavişyate, 490 nārāšansena stomena (somena), 419 nārāšanse somapītham ya āšuh, 490 nāvaprīyāte na gamāte antam, 198, 201 nāvas caranti svasica iyanāh, 170, 254, nāvo viyanti susico na vānīh, 170, 254, 741 nāsatyā (nā°) bhisajāsvinā, 952 nāsām āmitro vyathir ā dadharşati, 491 nāsīkavate (°kāvate) svāhā, 475 nıh kravyādam nudāmasi (nudasva), 967 nıkirya tubhyam abhya asam (tubhyam madhye), 47, 76, 255 ni galgalītı dhārakā, 133, 595, 617, 861

nıgirya sarvā ādhih (tubhyam madhváh), 47, 176, 255 nicerur ası nicumpunah (nicaūkuna. nicuñkunah), 150, 380, 605 nı jalgulîtı (jalgal°) dhānikā, 133, 595, 617. 861 nı düraşrayase yaha (yahah, mahah), 224, 379 nidhanavata āgravanah (āgrā°), 492 nidhedhāsi purusaspārham (pur-uspārham) . , 811 nı nıvartana vartayendra nardabuda (nandabala), 273, 605, 862 ni no rayim subhojasam yuvasva (vuveha), 842 nindād vo asmān dipsāc (dhipsāc) ca, 107 nımrdo (nımrado) 'si, 658 ni van nivanty uparasya niskrtim, 587. 778, 330 nıvutvan vayav (vaya) a gahı, 889 nıyudbhir väyav (väya) ıştaye durone, nıyudbhır väyav (väya) iha tā vı muñca (muñcah), 145, 379, 889 nir amum bhaja yo'mitro asya, 907 nır aranım savıtā sāvişat ("şak) padoh. nır aştavışam (aştha°) asmrtam, 86 nırastah sandah (sandah), 289 nirasto aghaśansah ('ghao'), 910 nırrtım nırjarjalpena (nırjālmakena. nırjalpena) šīrşnā (nirjālmākašīrşnā) 496, 810 nirrto yaś ca nisvanah, 93, 861 nırrtyai svāhā, 699 nırrtho yas ca nisvarah (nisvanah), 93, 861 niroho 'sı, 516 nırdevam nırvīram ("vīryam) krtvā nırbādhyena havısā, 699 nır mä muücamı sapathat, 325 nır mā yamasya padbićāt (sadvinsāt). 217, 302, 872 nır mā varunād uta (adhı), 325 nivarto yo ny avividhah (avivitat), 97

ni viram (viravad) gavyam asvyam (astriyam) ca rādhah 784 nivrtsh (nivrttsh) purusad drtih, 201 niskartā vihrutsm (vihrtsm) punsh. 650 633 niskrtā vihrtem punah, 650 683 nişkriāhāvam avajam, 164 nię krayvadom sedha ("dam aninasat), 957 ni stanihi durita badhamanah, 582 niş jam bhaja yo amitro asya, 907 nihşahamano (nişşa") yamate navate. 971 nihāram in ni me hara (harā[h]), 431. 445 nîroho 'si, 516 nīlagalamālah . . ., 512 870 nīlamgoh ("gave) kimih (krimih), 668 nilāgalasālā, 512, 870 nu cit sa dabhyate janah, 126, 621 nycakşasan tvā . . . khyeşam (kšeşam) 100 nicaksah soma uta susrug (susrug) astu, 145, 283, 612 nibhir dhūtsh (dhau") suto atraih. 726 nibhir dhuto (dhauto) vicakşanah. 726 nibbir yad yukto vive rapādsi (viver ap*), 837 myst krauhi vitaye ('hy ūtaye), 743. 805 nyvadobyo 'ksa paprathanebhir evaih. 684, 840, 861, 875 nīşadmā sīdad apām vivarte ("vā sīdad apām upasthe), 240 nīth (nīts) pāhi smudhī ("hī) girah, 122, 965 nediya it sınyah pakvam a yavan (ruvan), 633 ned eso esman avahava paravat 924 ren na ppēn mava it samēnah, 180, 181, 545 694, 919 nemim tasteva sudrvam (sudruvam), 793 nemis pakram iyābhayat ("bhuyat), 602 nem na jnän jnavän Ipsamänah 180, 151, 545, 694, 919 neva mäase na pibasi. 211, 709, 826

nainam rakṣānsi na pišācāh sahante, 155 nainad devā āpnuvan pūrvam arfat (areat), 31, 233 nsinā smitro vyathir ā dadharsati. 491 nairītyai svāhē, 699 nairbādhyena havişā, 699 naiva mansena pivari, 211, 709, 826 nyag vāto 'va vāti (vāto vāti), 803 nyañ ni yanty uparasya niskrtam, 587, 775, 830 ny eśvinā hrten kāmā (kāmāń) ayansata (arańsata), 244 ny aham tam mrdyāsam yo 'smān (asmān) dvesti . . ., 910 paktā sasyam, 93, 857 pakenāni godhūmaih kuvalair (kvalair) utāni. 782 paūcadašāt prasūtāt pitryāvatah, 559 pañca padāni rupo anv aroham, 569 pancabhir dhātā vi dadhāv (dadhā) idam 888 padbhis caturbhir akramit, 165 patēti didyun naryasya bähvoh (bahuroh), 792 patha ānakti madhvā ghrtena, 509 pathā madhumatā bharan (madhumad ābharan), 61, 840 patho anaktu (ct) madhva ghriena, padă panior (panin) arādhasah, 927 padbhis caturbhir akramīt, 166 panasyuvah samvasanesv (samvaranesy) akramuh, 857 pantham anuvyzbhyam (anno), 550 panthā sasvam, 93, 857 payasvatih kṛṇuthāpa ("tāpa) oṣadhih ... 90 payasvad vīrudhām payah, 200 payasvan māmakam vacah (payah), 200 pavasvān ("vān) agna āgamam, 925 payo giheşu payo aghnyāyām (aghniyāsu, 'stu tan nah), 784, 907 navo me dah (mayi dhehi), 102 payo vatseşu payo astu tan mayi, 907 paramachado vara (paramachad avarāń) ā viveša. 840

parivrādhi (°vrāgdhi)

paramaivā reisamah ("ma), 380 paramam padam ava bhātı (bhārı) bhūri ("reh), 853 paramām tam (tvā) parāvatam, 365 paramena pasunā krivase (krivasva), parameşthî tvä sädayatu divas (dıvah) prsthe .. raśmivatim (raśmio), 520, parasur vedih parasur nah svasti, 381, 755 parah syapna mukhā kṛdhi, 382, 820 para dusvapnyam ("niyam) suva, 784 parā dehi šāmulyam (šābalyam), 240, 607 parapuro nipuro ye bharanti (baranti), parārcisā mūradevāň ("vāh) chrnīhi, para syappamukhāh sucah, 382, 820 pari krošatu sarvadā (°tah). 68 parı ghransam omanā vām (parıghransa vām manā vām) vayo gāt (gām), 804, 821, 828 parijmā cit kramate (cid ramate) asva dharmanı, 420 parı nah sarmayantya, 950 parı no aśvam aśvavit, 950 parı no rudrasya hetir vrnaktu, 950 parı no heti rudrasya vriyāh (°vāt). 170, 950 parı doşād udarpıthah, 63, 96, 384, 516. 821 paridhāsyai vasodhāsyai ("dhāsye vaso dhasye), 705 pari nah sarmayantya, 950 parı no aşvam aşvavıt, 950 parı no rudrasya hetir vrnaktu, 950 parı no hedo varunasya vriyāh, 170, 950 parı püşā parastāt (pur°), 615 pari bhrātuh parı syasuh. 988 parı mātuh pari svasuh, 988 parımidhah kva gamışyası, 67 parimidho 'sy ulena, 568 parı lokān parı dışah pari svah (suvah), parivādam parīksavam ("chavam), 183. 200, 516

parışītalı kveşyasi, 67, 829 parisito 'sy ulena, 568 parısıdah kleşyası, 67, 829 parı sva suvano aksah, 794, 987 parı svajate (°tai) libujeva vikşam, 710 parı satyasya dharmanā (sakbyasya dharmanah), 143 pari suvānas (svānas) cakşase devamādanah, 794 parı suvānāsa (svānāsa) ındavah, 794 parı suvāno (svāno) gırışthāh, 794 parı sya suvāno avyayam (svāno aksarat), 794, 987 pari svā", see pari suvā" paritosat tad arpitha, 63, 96, 384, 516, paridam vājy ajinam (°dam vājinam) paridam väso adhithäh (adhidhäh, adhi dhā) svastaye, 77, 705 parime 'gnim arsata, 387, 648 parīvādam parīksapam, 200, 516 paruşah paruşas (°şah, paruşas-paruşas) parı, 961 pareyıvansam (pareyu") pravato mahir anu (1t1), 622 paramān (onān) devah savītā dadātu, paro martah parah (para) śvā, 980 parnasadah ("sado jaritah, "sado jarıtah), 278 parne vo vasatış (°tıh) kṛtā, 967 pary agnım abrşata (arşata, aharşata), 387, 648 pary agaram (akaram) punah-punah. pary avarte duşvapnyat (duhşva°), 980 pary û şu pra dhanya (°vā) vājasātave. 436, 445 parvata ıvāvıcācalih (°lat), 592 parsur vedih parasur nah svastih, 381. pavamāna (onā) vidharmani. 512 pavamānah ("na) samtanım eşi krnvan, 380 pavamānah svarjanah (suvaro, so ad) a nah), 159

pavamāno dašasyatı (diś°), 577 pavasva devāyusak (deva āyuşak), 992 pavitravantah pari vācam (vājam) āsate, 51 paśūnām tvā himkārenā° (humkārenã°). . 625 paśun (paśuńs) tanś cakre vayavyan. paśūn nah śańsyājūgupah, 548 pasūn me sansyājugupah ("jūg"), 548 paścādosāva (paścāddo°) glāvmam (glävam), 403 paśyań ("yah) janmāni sūrya, 936 paşthavāt (°vāc) ca . 167 paşthavad gaur vayo dadhuh, 631 paşthavād (°vād) vayah, 167 pānktrah (pānktah, pāmtra-) kaśo mānthīlavas (man°) te pitrnām (pitr°), 77, 418, 489, 597 pātam mā dyāvāpṛthivi adyāhnah (aghān nah), 840, 868 pāti priyam ripo (rupo) agram padam veh, 267, 627 pāty agnir vipo agram padam veh, 267, 627 pāpāt svapnyād (pāpah svapnād) abhūtyāh (°yaı), 315 pāpmānam. uta vāgham (vā agham), pāra iksavo 'vāryebhyah ('vārīyebhyah) pakşmabhyah svāhā, 325. 786 pārāva mārgāram, 325 pārāvataghnīm (pārāvadaghnīm) avase suvrktibhih, 59 pāryāni pakşmāny avāryā ikṣavah, 325 pāryāya kaivartam, 41, 325, 708 pāvaka ā citayantyā kṛpā, 343 pāvakayā yas citayantyā kṛpā, 343 pāvamānāh, onyāh, onyah, 319 pāśam grīvāsv avicītyam (°cartyam), pāhi gāyāndhaso (gā an°) made, 343 pāhi no agna enase (edhase) svāhā, pāhi mām yajñanyam (°niyam), 789 pāhı mā didyoh (mādya divah), 738 , 21, 48 pıkah (pıgah) kşvıñkä pitaras ca upasate (copasate), 995

devānām janītā vibhūvasuh (vibhāv°), 619 pitā no bodhi (bodha), 584 pitāmahebhyah avadhāyibhyah ("vibhyah) svadhā namah, 247 pitā virājām rṣabho rayīnām, 236, 359 pitur iva nāmāgrabhişam (°bhaişam), pıtrbhyah svadhāyıbhyah (°vıbhyah) svadhā namah, 247 pitrbhyah svadhāstu (°dhā astu), 992 pitrbhyo barhışadbhyo dhūmrān babhrvanūkāšān, 628, 742 pitřň (pitřn) jinya, 936 piteva putram jarase ma emam (navemam), 181, 343, 835 pitevaidhi sūnava ā (°ve yah) suševah. pitvo (pidvo) nyaňkuh kakkatas (kakuthas, kaśas) te 'numatyaı, 67, 69, 88, 401, 607 pinva ("vam) gā jinvārvatah, pinvatam ga jinvatam arvato nah, 852 pibantu madantu (°tām) vyantu (viyantu somam). 796 pıbāt somam mamadad (somam amadann) enam iste (istayah), 381, 746 pītā bhāsvaty anupamā (pītābhā syāt tanūpamā), 170, 254, 408, 838 pitvi (pitvā) šipre avepayah, 598a pībarīm (pīv°) ca prapharvyam, 211 pībasphākam udārathım (pīvo vṛkka udārathih), 211 punsavanam punsavanam (punsuvanam ası), 604 punse putrāya vettavai (vittaye, kartavai, °ve), 248, 686, 705 punjikasthala (punjiga°) krtasthala (kratu°) cāpsarasau, 48, 609, 664 putrah pitarāv (°ram) avrnīta pūşā, 237 putrah pitre (pitrye) lokakrı jātavedah, 321 putram ıva pıtarāv (°rā) aśvinobhā, 888 putriyantah (putriyantı) sudānavah, 534 punantu rsayah, 992 punantu višvā bhūtāni (bhūtā mā),

849

puru reto dadhire suryasvitah ("śritah). punar agah punarnava ("nava, "navah) 267 380, 952 purodāšān ("šān) alamkuru, 924 punar ūrjā ni vartasva (ūrjā vavrtsva). puro raksānsi nijūrvan, 717, 809 648 purovāta (°to) jinva ravat (ravat) punar dattāv (dātām) asum adveha svāhā, 168, 837 bhadram, 225 purovāto varşañ jinvar āvīt svāhā. punar brahmāno (brahmā) vasunītha ('nītir, 'dhītam, 'dhītım, 'dhīte) 168, 837 pustapate (pustion-pustipataye). vajnaih (agne), 93, 134, 339, 587, 706, punar dehy asmaı (dehi or dhehi 857 svāhā), 104, 587 punar mām aitv (maitv) indriyam, 812 puspavatih (puspā°) prasūvarīh numin enam tanuta ut krnatti, 48, 925 (°sūmatīh, °sūvatīh), 239, 467 pumānsam vardhatām mayı, 97, 840, puşpavatih (puşpā°) supippalāh, 467 pūtanānām tyā patmann ādhūnomi, pumānsam u (ā) dadhad (dadhād) ihe. 151, 720, 810 pūrnān parisrutah kumbhān, 682 pumān enad vayaty udgrnatti, 48, 925 pumān garbhas tavodare, 97, 840 pūrvo ha (hı) jātah (jajñe) sa u garbhe antah, 578 pumān samvartatām mayi, 97, 840, 938 pūlyāny āvapantikā, 151, 568, 800. puramdaro gotrabhid ("bhrd) vajrabāhuh, 39, 636 pūsan (pūsans) tava vrate vayam. 932 puramdaro maghavān vajrabāhuh, 39. pūşā jātıvın (jñātı°, jñātımān). purastāt (puras tvā) sarve kurmahe, pūşādhvanas (°nah) pātu. 964 365, 826 pūsā vispandamāne, 725 purā grdhrād ararusah pibāthah ("tah). pūşna āghrnaye svāhā, 35, 300 pūşne 'nghrnaye svaha, 35, 300, 473 purā cakrbhyā ātrda, 57, 138, 353, 384, pūşne śarase (°sı) svāhā, 691 prksasya vrsno arusasya nū sahah, purā jatrubhya (jartrbhya) ātrdah, 57, 658, 870 138, 353, 384, 681 prnakşı rodasī ubhe, 718 purukşu tvaştā (°tah) suvīryam (suvīprtanāsāhyāva (°sāhvāva) ca. 984 ram), 323 prtsutūrsu śravassu (śravahsu) ca. 971 purutră te manutăm (vanvatăm, vanupṛthivi bhūvarı (vibhūvarı) sınīvāly tām) vişthitam jagat, 227, 742 urandhra (uramdha) ācitte ... 353, puru tvā dāšvān (dāšīvān) voce. 764. 944 pṛthiviṣadam (pṛthivī°, °sadam) tvānpurudasmo ("smavad) vişurūpa (viš-, 524, 986 tarıkşasadam varūpam) induh, 291, 421, 742 pŗthivispŗā (pŗthivī°) mā , 524 purumedhaś (°dhāś) cit takave naram prthivi darvir aksitāparimitānupaddit (dhat), 105 astā (aksatā). . 576 pururāvno deva risas pāhi, 371a, 716, pṛthivīṣadam, see pṛthivi° 821 pṛthivīsamantasya te 'gnır upadraşţā, pururupam suretasam maghonam (°nm), 588

puru višvāni jūrvan, 717, 809 puruştutasya dhāmabhih (nāma°), 855 pṛthivī samā tasyāgnir upadrastā

, see prthvi

prthivī suvarcā

prthivisprä, see prthivi° prthivyām avacuścotaitat. 336 prthivyā (°vyāh) sambhava, 381 prthivyāh sampreas ("cah, samspréas) pāhi, 195, 375, 964 prthyl (prthiyl) suvarca vuvatih sajosäh, 764 pratim divah pari srava. 200 prstibhyah (prsti°) svähä, 529 prsthavad gaur vayo dadhuh, 631 prsvábbyah sváhá, 680 perum tuñjānā patyeva jāyā, 159, 421 peśasvati tantuna samvayanti (°vyayanti), 346 peśo na śuklam (śukram) asitam (aś°) vasāte, 262, 277 poträgnidhro (potā°) nihitam pādam ekam, 353 pauruseyād darvyāt ("yān na darvāt), 317 pausno vispandamāne, 725 pra ketunā brhatā yāty (bhāty) agnih, prakşasya vişno aruşasva nû mahah, 658, 870 (pragāyāmy agratah pragāyāmasy asyāgratah), 134, 840 pra candramās tīrate (tīrati. emas tırase) dirgham āyuh, 507 pracyutim jaghanacyutim, 874 prajananam vai pratisthā loke sādhu prajāyās (sādhuprajāvāns) prajāh kṛnvan janayan virūpāh, 936 prajām suvīrām ("ryām) kṛtvā, 323 prajām no naryājūgupah, 548 dīkşayatu (dīkprajāpatir diksito , 745 seta) prajāpatis tvā ("tis tvā) sādayatu prajāpate višvastj (°stg) jīvadhanyah, prajāpates tvā ("teş tvā) prānen" prajām me naryājugupah (°jūg°), 548 prajāyāmasy agratah, 134, 840 prajāyai kam (kim) amṛtam nāvṛnīta, 578 prajāyai mṛtyave tvat (tat), 365

prajāvatī vīrasūr devrkāmā, 633 prajavatih suyavasam (°se) rušantih (r15°) 627 prajā vikţnvañ (vikurvañ) janayan virupam (°pāh), 936 prajāh sarvās ca rājabāndhavaih (°vyah), 490, 701 pra (prā) na āvur līvase soma tārīh, 439 pra na āyūņsi tārisah (tārisat, tārsat), 753, 950 pra na indo mahe tane, 616, 830, 950 pra nah pinya vidyud abhreya rodasi, pra nāmāni prayajyavas tiradhvam, 952 pra nu vocam cikituşe janāya, 719, 950 pra no jāyantām mithunāni rūpašah, pra no jivātave suva, 950 pra no naya vasyo acha, 950 pra no navyebhis tiratam desnaih, 950 pra no brūtād bhāgadhān (°dhām) devatāsu. 105 pra no yachaty aryamā, 950 pra no yacha bhuvas (višām) pate, 950 pra no vocam cikituşe janāya, 719, 950 pra tad visnu ("nuh, "nus) stavate vīryena (°ryānı, °ryāya), 977 pra tad voced amrtasya (amrtam nu, voce amrtam nu) vidvān, 849 pratikramanam kuşthābhyām (gu°), 49 pratiksiyantam ("ksyantam) bhuvanām višvā, 795 prati grhnāmi (grbhnāmi) mahate vīryāya (mahata ındrıyāya), 116 prati te te ajarāsas tapisthāh, 345 prati tye te ajarāsas tapisthāh 345 pratı tvādītyās tvag vettu (vetu), 392 pratı tvā dıva (dıvah) skambhanır vettu (vetu), 392, 977 pratı två parvati ("tir, parvati) vettu, 490, 528 prati na im surabhim vyantu (viyantu), 796 prati bhagam na didhima ("man), 379 pratimā asi (°māsi), 993 praturavebhyah (praturebhyah) sviiha,

747

prathamam artim yuyotu nah. 383.

prathamāya januse bhūma nesthāh

pradaksının (onam) marutam stomam

pra dhārā yantu madhunah (dhāra-

pra na indo mahe tu nah, 616, 830, 950

pra nah pinya vidyud abhreya rodasi,

yantu madhuno ghrtasya), 833

pra na āvūnsi tārisat, 753, 950

rdhyām (asyām), 596

(bhūmanesthāh, bhuvanesthāh), 240,

650, 825, 840

568, 832

pratilămiti (°niti) te pită, 181, 853 prati vastor aha (ahar) dyubhih, 353 pratisrutkāyā artanam (rtulam), 618, 651, 878 prati sma deva rīşatah, 535, 987 prati sma raksaso daha, 159, 987 prati sma deva risatah, 535, 987 prati sma raksaso jahi, 159, 987 pratikam me vicaksanam, 857 pratitam devebbyo justam ha vyavasthāt (havyam asthāt), 225 pratīpam prātisutvanam ("satvanam), 618 pratnāso agna rtam āśuşānāh (āśaśānāh), 292, 617 pratno hi (pratnosi) kam idyo adhvaresu, 299, 827 pratyak somo atisrutah, 275 pratvag enam šapathā vantu trşţāh (srstāh), 854 pratyank somo, see pratyan pratyañ janan samcukośantakale, 195 pratyañ janās tisthati samcukocāntakāle, 195 pratvañ (°yañk) somo ("hrutah, "srutah, "śrutah), 275, 298, praty ajātān ("tān, "tān) jātavedo nudasva, 936

pranākāphā na ābhara, 79, 151 pra nāmāni pravajyavas tiradhyam, 952 pra nu vocam vidathā jātavedasah, 719 pra nu vocam cikituse janāva, 719, 950 pra nünam pürnayandhura (°bandhura), 213 pra no jāyantām mithunāni rūpašah, 950 pra no jįvatave suva, 950 pra no naya prataram vasyo acha, 950 pra no navyebhis tiratam deşnaih, atidrutah pra no yachaty aryama, 950 pra no vacha (rāsva) višas pate (sahasrajit), 950 pra no vaco vidathā iātavedase. 719 pratyancam arkam anayan ("yan) prapitāmahebhyah svadhāvibhvah chacibhih, 937 (°vibhyah) svadhā namah, 247 praty asya vaha dyubhih, 353 prapinam ("tam) agne sarırasya (salılpratyādāyāpara 19vā, 105 asya) madhye, 264, 734, 871 praty u (uv) adarsy (adrsy) ayati. 648. prapunvanta upaspršata prapunvadbhya svīhā, 867 praty ühatām aśvinā mṛtyum asmāt. prapyātam agne sarīrasya madhye, 510, 727 264, 734, 871 praty etā vāmā . yajamāno 'grabhid pra-pra yajūapatim tira (tirah), 379 (agrabhid) uta pratisthotopavaktar prapharvyam ca pivarim, 211 (°kta) uta , 357, 910, 991 pra budhnyā va īrate (budhniyā īrate praty etā sunvan uta pratisthotovo) mahāńsi, 784 pavaktar uta . , 357, 991 pra bravāma (bruvāma) šaradah šatam, praty eva grbhāyata, 254, 836 praty auhatām asvinā mṛtyum asmāt pra bhānavah sisrate (sas°) nākam (asmat), 510, 727 acha, 581 pra tveva grbhāyata, 254, 836 prabhāyā agnyedham (ágnendham), prathamachad avarāń ā viveša, 840 314, 491

prabhos te (prabhos te) satah pari yantı ketavah, 958 pramade kumārīputram, 617 pramā ası, 993 pra mā brūtād bhāgadām (dhavirdā) devatāsu (°tābhyah), 105 pramāsı, 993 pramude kumārīputram, 617 prayatis ca me prasitis (°srtis) ca me, prayapsyann iva sakthyau (sakthau), 347 794 pra yah satrācā (sa vācā) manasā yajāte (°tai), 710, 828, 876 prayāsāya svāhā, 465 prayugbhya ("yudbhya) unmattam. mrsāsā 888 prayunvanta upaspráata prayunvadbhyah svāhā, 867 939 pra yo jajne vidvān (vidvān) asva bandhum (°dhuh), 925 pravanena sajosasah, 465, 491 pravayāhnāhar jinva. 493 pra vartava divo asmānam ('smānam) ındra, 907 pra vah (va) spad akran suvitāya davane (pra vah sphal akran), 977 pra vā etindur indrasva niskrtim, 587 pra vācam (vājam) indur işyati, 1, 51 pra vām adhvaryuś caratı prayasvān (caratu payasvān), 352 pravāyāhne 'har jinva, 493 pra vistīminam avisuh, 876 pra vedhase kavaye vedyāya (medhyāya), 109, 230 pra vo mahe mahividhe (mahevidhe) 152 bharadhvam, 691 prašāstah pra suhi (sūhi, suva, suva pra suhi), 559 pra śmaśru (°śrubhir) dodhuvad ūrdhvathā bhūt (ūrdhvadhā bhuvat), 74 pra samhrstinam ājisuh, 876 pra sa mrtyum yuyotana, 383, 612, 650, asyen°) 817, 825, 840 pra samrājo (°jam) asurasya prašastim (°tam), 586 pra sumartyam (su mrtyum) yuyotana, 383, 612, 650, 817, 825, 840

pra sulāmīti te pitā, 181, 853 pra suvānāso brhaddivesu harayah. 686, 794 prastotar vārsāharam sāma gāya, 512 pra stoma yanty (yantv) agnaye, 251 prasthāyendrāgnibhyām somam vocato yo (vocatopo) asmān , 835, 867 prasthitā vo madhuścutah (°ścyutah, °cyutah), 336 pra smā mināty ajarah, 439, 512 pra svānāso brhaddeveşu harayah, 686, pra hansāsas trpalam manyum (°lā vagnum) acha. 235 praharşınam ("no) madırasva made astv (mṛṣāsāv prāk (prāň, prāňk) somo atidrutah, prācīm jīvātum aksitām ("tim), 599 prācīś cojjagāhire, 387, 540, 581 pranco agama (pranjo 'gama) nrtave hasāya, 2, 55, 443, 907 prā na āyur, see pra prānam dehi (dhehi), 103 prānasya tvā paraspāyai (°pāya) caksusas tanuvah (tanvas) pāhi. 964 pranasya vidvan samare na dhirah, 244 prānah sindhūnām kalasān acikradat, prānah (prāna) sthah, 977 pranan samkrośaih, 46, 292 prānāpānābhyām balam āharantī (ābharanti, etc), 117 prānā šišur mahīnām, 152 prānā sindhūnām kalašān acikradat, , 910 prāno agnih ('gnih) prāno dātra edhi vayo (mayo) mahyam pratigrahītre (°grhnate), 232, 657 prātahsavasya (*sāvasya) , 486 śukravato prātah prātahsavasyendrāya (°sāv-, 486 prāntar īsaya sthāvirīr (prūntariksāt sthaviris te) asrksata, 640, 833 pranya tantuns tırate dhatte anya, 138 prāvāsāya svāhā, 465

prāvanebhih sajosasah. 465. 491 prāvartam indrah śacvā dhamantam. 826, 873 prāvo yudhyantam vrsabham daśadvum, 873 prāsmā āšā ašrnvan, 873 prāsmān ava prtanāsu pra vikşu (yutsu), 140, 805 prāsmā minoty ajarah, 439, 512 prāham tam atībhūyāsam (abhībhū°) yo asmān ('smān) dveșți priyany angani svadhita parunşi (anga sukrtā purūni), 618, 741 priyā ta ā barhis (°hih) sīda, 162, 825, priyena dhāmnā (nāmnā, nāma) privam sada āsīda (etc.). 855 priyo me hrdo (hito, huto) 'si (bhava), 63, 627, 640, 643 prustābhyas svāhā, 680 prusvā ašrubhih, 40, 680 pruşvābhyah svāhā, 680 pretā jayatā narah, 441 pred u harivah śrutasya (sutasya), 278, 355 premam vājam vājasāte avantu, 51 premām vācam višvām avantu višve, 51 prehi-prehi pathibhih oürvvebhih (pūryānaih), 368 praitu brahmanas (°nah) patnī, 964 praisan samidhenir agharav (°ra) ājyabhāgāv (°gā) āsrutam pro ayasıd ındur indrasya nişkrtam, 587 pro ārata maruto durmadā iva, 361 prokşitä (*tāh) stha, 977 prothad asvo na yavase 'vişyan (avio), pro 'vārata maruto durmadā iva, 361 plāšır (°šīr) vyaktah . , 529 phalāya, 79, 401 phalgunībhyām vy ühyate, 560 phalgunişu vy uhyate, 560 phalgur ("gur) lohitornī balakşī ("kṣīs. palakşī) tāh sīrasvatyah, 69, 554 phallaya, 79, 401 bajābojopakāśini, 21, 69, 151, 381 balam dehi (dhatta), 103 balam mayı dhehi (me dāh svāhā), 103

balavijnāya ("yas, "yah) sthavirah prayirah, 977 balim ichanto vitudasya (vi tu tasya, vidurasya) presyāh (presthāh), 65, 272s, 832 balivardāya (°vandāya) svāhā, 862 basto vayah, 216 bahis te. see bahis te . . . bahişthebhir viharan yasi tantum, 214 bahis te (bahıs te) astu bāl iti. 958 bahu bāhvor balam, 792 bahu ha vā ayam avarşīd iti śruta rāvat svāhā, 598, 648 bahu hāyam avrşād (°şad) iti śrutar āvrt (śruta rāvat) svābā. 598. 648 bāhuvor (bāhvor) balam, 792 bāhuvos (bāhvos) tava hetayah, 792 bidvo nyaňkuh kašas te 'numatyāh, 67, 69, 88, 607 bibheda valam (balam) bhrgur na sasāhe (sasahe), 210, 480 brhatā tvā rathamtarena traistubhvā (tristubhā) vartanyā . , 325, 699 brhaty uşnıhā kakup (kakut), 178 brhat sama kşatrabbrd vrddhavrşnyam (°vrsnam, °nim, °nivam), 315, 784 brhat sūro (sūryo) arocata, 318 brhat somo vävrdhe suväna induh (svāno adrih), 794 bihad işabham güm vayo dadhat, 359 brhadbhir vājai (vājaih, vājais) sthavirebhir asme, 977 brhadrathamtarayos tvī stomena trīstubho vartanyā . . ., 325, 699 brhad vrşabham güm vayo dadhat, 359 brhanto daivāh (divyāh), 316, 699 brhann ası brhadravā (brhadgrāvā, brhadrāyāh, °rāyah), 255, 420 brhaspataye mahişa (mahi şad) dyuman namah, 392, 826 brhaspataye sitputah (simyutah), 867 brhaspatīnā rāyā svagākrtah, 466 brhaspatır devānām (daivo) brahmīham manuşyanam (manuşah), 316, brhaspatir brahmāham mānusah. 316 brhaspatis tvā ("tis tvā) nivunsktu mahyam, 958

brhaspatış tvā ("tis tvā) vısvair devsir upariştād . , 958 brhaspatış tvā ("tis tvā) sādayatu prthivvãh , 958 brhaspatis tvā ("tis tvā) sumne ramnātu (ranvatu), 225, 958 brhaspatış tvopasidatu ("tis tvopa"). brhaspatisutasya (. .) ta indor (ındo, ında) ındrıyavatah , 357, 890 brhaspati ("tih) stotram. 977 brhaspate abhisaster amuñcah. 907 brhaspate pari diya (diya) rathena, brhaspate 'bhisaster amuñcah, 907 brhaspate mahisa dyuman namah, 826 brhaspate yāmyām (°yā) yungdhi (vufidhi) vācam, 418 brhaspates tvā ("tes tvā) sāmrājyenābbi.., 958 bodhanmanā id astu nah, 594 bodha pratibodhāsvapnānavadrāna . , 516 bodhaś ca tvā (mā) pratibodhaś (prati°) ca ., 516 bodhinmanā id astu nah, 594 bradhnas cid atra (yasya) vato na 10tah (10tim), 586 brahmań stosyāmah praśastah, 938 brahmans (brahmāsus) tvam brahmanaspate suyamasya (sû°) viśvahā, 552 brahma tvam ası vıśvasıt (°sık), 142 brahma devakrtam upahütam, 460 brahma devānām prathamajā rtasya, brahman ("man) tvam asi viśvas;t (°srk), 142, 932 brahman stosyāmah prafāstah, 938 brahmavarcasāya pīpihi (pipīhi), 545 brahmāzn(s) tvam, see brahmans ... hrahmāsn . hrahmā devakrtopahūtā, 460 brahmā devānām prathamajā rtasya, brahmādhiguptah (brahmābhi") svārā

kşaranı (surakşıtah sjam) svaha,

172, 569, 742, 802, 840

brahmāzn (°māzň) tvam rājan brahmāsi. 932 brahmābhigūrtam svarāksānah (svarārakş°), 172, 569, 742, 802, 840 brahmāham antaram krnve (karave), brahmattad upāsvaitat (upāsyaitat) tapah, 251 brähmanam adya rdhyäsam (adyardh°) . . 919 brāhmanān rtvijo devān yajnasya tapasā te savāham ('sā aham) ā buve, 362 'bhyanujñātā brāhmanebhyo anu°), 121, 828 bhansaso vi vrhāmı te. 176, 222 bhakşimahı prajām isam, 176, 618 bhakso bhaksyamanah (bhaksa*), 332 bhaga eva bhagayān astu devāh (devah), 507 bhagas te hastam agrabhit (°hīt), 116 bhagemām dhiyam ud avā (ava) dadan nah. 446 bhadrād abhi (adhi) śreyah prehi, 172 bhayam sitimabhyam ("madbhyam), bharatam uddharem anusifica (uddharema vanuşantı), 236, 813 bhartam agnim purlsyam, 648 bhartāras te mekhale mā risāma. 176 bhalāya (bhallāya) svāhā, 79, 401 bhavā kṛṣṭinām (gr°) abhisastipāvā (°DE u), 46, 740, 824 bhava no dūto ajarah suvīrah, 826 bhindhidam (bhindhy ado) divyam nabhah, 324 bhisajam na (nah) sarasvatīm, 384 bhīma ā vāvīdhe (vāvīte) šavah, 97 bhuli (bhulyuh) suparno yaino gandharvah, 738 bhuvad višyam abhy ādevam ojasā, 470 bhuyanam asi sahasrapoşapuşı (°poşam pusa), 491, 820 bhuvanam asi sahasram (sahasrapoşam, sähasram), 491 bhuvas te dadāmi (tvazi dadhāmi), bhuvo višvam abhy adevam ojasā, 470

(prasutah)

rtävrtah

bhūtānām brahmā prathamo ha ("mota) matsarābhih , see atsa° 1ajñe, 460 matsarāsah prasupah bhūmidrhham acyutam pārayişnu, 177, sākam irate. 180 268, 381, 857 matsvā susipra (oprin) hariyas tad bhūmidrnho 'cyutas cyāvayışnuh, 177, (tam) Imahe, 594 268, 381, 857 mathavyān stokān apa yān rarādha, 78 bhumir iti tväbhipramanyate janäh. madanti devir amrtā (°vrdhah), 97 bhūyasi haviskarana upahūtah ("tā). madughānām tvā patmann adhūnomi. bhūvisthadāvne sumatim āvrņānah, madenendram yajamänüh svarküh, 181 60. 355, 854 made-made hi no dadih (daduh, dadrk). bhūyo vā atah somo rājārhati (rājā 622, 640, 642 arhati), 992 mademendram yajamānāh svarkāh. 181 bhūrı sastam (sastram) pṛthuh svaruh, made susipram (madesu sipram) andhasah, 293, 839 bhūrnim devāsa iha suśrivam dadhuh. madyam indrāya jabhrire, 868 madhavyau stokāv (°kā) apa tau bhūr bhuvah svas te dadāmi, 104 rarādha, 78, 888 bhūr bhuvah svah sarvam tvayı madhuntamanam (madhvant°) tya patdadhāmi, 104 mann ādhūnomi, 739 bhūs te dadāmı (tvayı dadhāmi), 104 madhu reto (madhur ato) mādhavah bhrjas chandah, 658 pātv asmān, 716, 837 bhrtam agnim purīşyam, 648 madhu vańsistya (vańs°), 277 bhrmim (bhrumim) dhamanto apa gā madhu śaspair (madhuśa°) na teja avrnata, 40, 679 ındrıyam, 817 bhesajam gave 'śvāya (aśvāya, 'śvāya madhus ca mādhavas ca vāsantikāv purusāya), 909 (°kā) rtū, 888 bhrajas (bhrājas) chandah, 486, 658 madhu havir (madhuhavir) ası, 817 bhrātāntarıkşam abhisastyā madhu hutam ındratame (°sasta enah), 840 ('gnau), 910 bhrumim dhamanto , see bhrmim madhoh payanta urmayah (payasya dhārayā), 804a makhasya te 'dya sıro rādhyāsam madhoh pibatam asvinā, 804a madhoh pibanti gauryah, 804a magham ındrāya jabhrəre, 868 madhor ato mādhavah pātv asmān, maghavañ (°vañ) chagdhi tava tan na 716, 837 ūtıbhih (ūtaye), 937 madho rasam sadhamāde, 368 maghavan mandışimahı (vand°), 229 madhoś cakānaś cārur madāya, 804a mandākako ha vah pitā, 165 madhye divo (divyo) nihitah prénir mandūkāŭ jambhyebhih (jambhaih). aśmā, 324 madhye poşasya tçmpatām (puşyatām, mandūko mūşikā tittiris (°ras) te poşasva tışthantim), 251 sarpīnīm, 589 madhvah pavasva dhārayā (pavanta manduky apsu sam bhuvah, 280, 839 ūrmayah), 804a mandukyā su sam gamah (gamaya), madhvah pibatam asvinä, 804a 280, 839 madhvah pibanti gauryah, 804a matyaı śrutāya cakşase, 357, 713 madhvas cakānas cārur madāva. 804a

mama padyāya vī rāja, 820

madhya ("vah) ścotanty abhito virapsam, 972, 977 madhvā yaıñam nakşatı (naksase) prinānah (prai°), 702 madhvā rajānsīndrīyam, 421 madhy ity ākarşaih kuśair yathā. 290 madhyo rasam sadhamāde, 368 manasaspata ımam deva yajūam (devayajāam svāhā vāci) svāhā manas tanūsu bibhratah (pipratah), manāsi (manā ası), 994 manuşvad deva dhimahı pracetasam. manaı nu babhrūnām aham, 366, 710 mano gāyatryai (°trīyai), 791 mano jagāma dūrakam (dūragāh), 46 mano jinya, 852 mano lyotır (jütir) juşatām ājyasya (ājyam, ājyam me), 337, 720 mano nv ā huvāmahe (°hı, hvāmahe), mano me jinya (pinya), 852 mano yad asya guspitam (gulphitam), 111 manos tvā (manos tvā) grāmanyo mantram vadaty ukthyam (uktham), manthākako ha vah pitā, 165 mandadvīrāyendave, 229 mandāna id vṛṣāyase (ud vṛṣāyate), 627 mandrābhibhūtih ketur yajāānām 220, 321 mandrā vibhūtih ketur yajñiyā 220, 321 manmā dīdhyānā utā nah sakhāyā, 236, 832 manyāsai sam ca nas (nah) kṛdhi, 964 manye vām dyāvāpṛthivī subhojasau, manyoh krodhasya nāśanī, 407, 593 manyor mrdhrasya (mrddhasya) nāśınī, 407, 593 manye nu babhrūnām aham, 366, 710 manye vām dyāvāpṛthivī, 251 mama ca nāma tava ca (tava) jāta-

vedah, 809

mama snusā svašurasya pravistau, 857 mayamdam (mayamtam) chandah, 67 mavā so annam ('nnam) attı vo vipasyatı, 907 mayı tad ındrıyam viryam, 345 mayı tyad ındrıyam brhat (mahat), 345 mayı dakşakratü (dakşo mayi kratuh), 272a mayı dohah padyayaı vırajah (°jah kalpatām), 820 mavı padvāvai virājo dohah, 820 mayı puştım (°tam) puştıpatır (puşta°) dadhātu (dadātu), 101, 587 mavı räyo mayı rakşah (dakşah), 272a mayı rucam dhāh (dhehi), 101 mayum te sug rchatu (te kşut), 145, 297 mayobhūh śamtamā yad dhrudo (dhrdo) 'sı, 684 marutām pitar uta tad grnīmah, 849 marutām pitas tad aham gṛnāmi (grne te), 849 marutvantam sakhyāya havāmahe (huvemahı), 602 marutvān astu ganavān sajātavān (sujātaih), 612 marudbhir ugrā ahrnīyamānāh, 144 marudbhī rudrāh samajānatābhi, 144 marudbhyo grhamedhibhyo (°medhebhyo) 'nubrūhı, 690 marudbhyo grhamedhibhyo (°medhebhyo) başkıhān (vaş°, bāşkān), 219, 387, 489, 690 marteşv (martyeşv) agnır amrto nı dhāy1, 315 malmalābhavantīm tvā (°bhavantītyā) sādayāmı, 255 mahah pitum papiyāñ (°vān) cārv annā, 930 mahas cid yasya mīḍhuṣo (mīlh°) yavyā, 386 mahas te sato mahımā panasyate (panistama), 870 mahān ındrah paras ca nu (puras ca nah), 614 mahāns te mahato mahimā, 870 mahākausītakam (°kım), 590

mahādevam antahpāršvena (°paršavyena), 326
mahāntam gahvaresthām, 368, 861
mahāntāv (°tā) indrāvarunā mahāvasū, 888
mahān mahī astabhāyad (aska°) vi jātah, 137
mahi vareah kṣatriyāya dadhatīh (dadatīh), 106
mahisam nah subhvam (subhuvas, subhavas) tasthivānsam, 119, 384, 604, 789
mahī cid yasya mīdhuşo yavyā, 386
mahīnām (mahi°) payo 'si, 528
mahī no vātā iha vāntu bhūmau, 360,

579,831 mahīva dyaur adha (vadha) tmanā, 360

mahī višpatnī sadane (°nī) rtasya, 695 mahī hy asya mīdhuşo yavyā, 386 mahe śrotrāya cakṣase, 357, 713

maho vā viṣna (maho viṣna) uror antarikṣāt (viṣnav uta vāntarikṣāt), 887

mahnā jinoşi (hi°) mahini 196 mahyam vātah pavatām (°te) kāme asmin (kāmāyāsmai), 342

mahyam dattvā vrajata (prajātum) brahmalokam, 200

mā ası, 993

māgadhah punscalī kitavah klibo 'śūdrā abrāhmanās (punscalī klivah kitavo 'śūdrābrāhmanās) 219, 819, 990

mā chetthā , 853

mā jāmim mosīr amuyā sayānām, 57, 181, 512, 824

mā tad bhūmyām ā śriṣan (śliṣan) mā tṛneṣu, 261

mā tamo (tapo) mā yajāas tamat (tapat), 204

mātā yad vīram dadhanad dhanişthā (vīram jajanaj janiştham), 160

mātur anyo 'va padyata, 201 mātrk kva cana vidyate, 66

mā te mano vişvadryag (°driyag) vi cārīt, 784

mā te yuyoma samdršah, 805

mäteva putram bibhṛtāpsv enat (bibhṛtā sv enat, °cnam), 420, 826 mā te vyoma samdṛsi (°sah, °se), 805 mā tvam hārṣīh srutam mayı, 353

mā tvat kņetrāni aranāni (aranyāni) ganma, 325

mā tvā ke cin ni (cid vi) yaman vim (cin ni yemur in, cin nyemur in) na pāšinah, 360, 770

mū tvāgnir dhvanayīd (dhana°; "yid,
"yed) dhūmagandhih, 370, 533, 697
mā tvā ni kran pūrvacito ("cittā,
"cittau) nikārinah, 399, 732

mā tvā prāpana aghāyavah, 832, 868 mā tvā samudra ud vadhīn (ba°) mā

suparnah, 209 mä tvä süryo 'bhi (süryah parı, parı)

tāpsīn māgnir (mo agnir). , 516 mādrk kva cana vidyate, 66

mā devānām tantus chedī mā manusyānām, 707

mā daivyas tantuš chedī mā manuşyah, 707

mā dyāvāpṛthivī abhisocīh (°sūsucah, °sucah), 715

mā dhenur atyāsārinī (atisā°), 736 mādhyamdīnasya savanasya ..man-

madnyamdinasya savanasya ..manthivato (manthivato) .. , 520

mā na āyuh param ayaram mānadonaih, 159, 836, 861

mā nah kaścit praghān (prakhān) mā prameşmahi, 22, 70

mā nah param adharam mā rajo 'naih (param adhanam mā rajo naih), 159, 836, 861

mā na (nas) stena īšata māghašansah 977

mānasya patnī šaranā syonā, 189, 596, 840

mā nah sapatnah šaranah syonā, 189, 596, 840

mānusād daivyam (daivam) upaimi,

mā no agnim nirrtir mā no āşţān (āṣṭhām), 87, 170

mā no agne 'va (v1) sījo aghāya, 578 mā no andhe tamasy antar ādhāt (ādāt), 105

mā rudriyāso abhı gulbadhānah (gur mā no 'to 'nyat pitaro yungdhvam, 302 mā no nu gād aparo ardham etam, 77 mā no rudrāso adhīgur vadhe nu (nuh), 172, 209, 260, 321, 821, 824 mā no rudro nirrtir mā no astā, 87, 170 mā no vadhih pitaram mota mātaram, mā no vidad (vadhīd) abhibhā mo nšastih, 579 mā no vidad (vrdhad) vrjinā (vrjanā) dveşyā yā, 108, 593, 640 , see mā no vadhīh mä no vidhih mā no vīrān rudra bhāmmo vadhīh, műsi, 993 209, 871 mā no hārdı tvışā vadhih, 60 mā no hińsih (hińsi) sthaviram mā kumāram, 975, 977 manta (mantah) sthur no aratayah, 977 mā brāhmanasya rājanya, 870 mű bheh, 712 , 853 mā bhetthū mā bher mā roā (mo roā, māro) mo ca nah (mo eşām) kım canamamat, 712, 715, 729 mā bhaih, 712 mā bhair mā run mo ca (mā rauñ mā) nah kim canamamat, 712, 715, 729 mām agne bhāgınam kuru, 486 mā mā yūnarvā hāsīt (yono vām hārasih), 307, 354, 723, 823 735 mā mā (mām) hinsiştam svam (yat svam) yonım üvisantau (üvisüthah), 505 mā mā binsīh svām (svam) yonim āvišantī (āvišan), 505 mām ındra bhagınam krnu, 486 mūmīṣām kam canoc chişah, 578, 688 mā me dīkṣūm mā tapo nir vadhista 802 (ba°), 209 mū me hārdı tvışā (hārdım dvışā) vadhih, 60 (yajamānas yajñapatis tapat

tamat), 204

māyādevā avataran, 401, 840

mīyām māyāvattarah, 475

māyobbavyāya catuşpadī, 319, 421

mā rāyasposena viyauşma, 729

mā rīṣāmā vayam tava, 224

vrdhūnah), 172, 209, 260, 321, 821, 824 märe asman maghavañ (°vat) ivok kah, 936 mā va eno anyakītam bhujema, 909 mā vayam rāyaspoşena vi yauşma, 729 mā vayam eno 'nyakṛtam bhujema, 909 mű va (vah) stena isata mäghasansah. mā vo 'to 'nyat pitaro yoyuvata, 302 māsā āchvantu šamyantah, 572 mūsūś chyantu simyantah, 572 mī so asmān avahāya parā gāt, 924 mā sv asmāńs tamasy antarādhāh, 105 māham rāyasposena vi yoşam, 729 māham pautram (putryam) agham rudam (niyām, nigām, rişam), 314, mā hidsişur vahatum uhyamānam (ühvamänäm), 560 mitajūavo (°imavo) varimann (°vann) ā prthivyāh, 240 mıtajüublır namasyair ıyana, 953 mitajmavo, see mitajnavo miteva sadma pašumānti ("manti) hota, 501a mitrah panty adruhah, 964 mitram na im šimyā gosu gavyavat, 735 mitram na yam simyā goşu gavyavah, mitra satyūnām pate ("nām adhipate), mitrasyāsi kanīnikā, 235-595, 640 mitrah samsriya (°yā) pṛthivīm, 457 mıtrah satyānām (satyah), 380 mitrāya kulīpayān (pulikayān), 149, uttarāsadmitrāvarunanetrebhyo , 476 bhyah (uttara") mitrāvarunayos tvā prasāstroh prasisā yunajmi (yunagmi), 131 mitrāvarunābhyām ānustubhābhyām , 319 (°stubhyābhyām) mıtrāvarunāv (°ņā) algābhyām, 888 mitrāvarunā saradāhnām (°hnā) cikıtnü (cıkıttam, jıgatnü, cıkıtvam), 45, 56, 371, 410, 579

mitrāvarunau prašāstārau prašāstrāt (prā°), 490 mitrāvarunau śronibhyām (śronic), 529 diśo 'bhidāsatı. mitrāvarunau sa 910 mitras panty adruhah, 964 mitrāh suvānā (svānā) arepasah, 794 mitro na ehi sumitradhah (°dhāh), 493 mitro no atra varuno vulvamanah. 341. 617 mitro babhūva saprathāh, 180, 235 mitro vatra varuno ajyamānah, 341, 617 mithucarantam (mithuo, mithuya cao, mithus ca°) upavāti (abhiyāti) dūsayan, 551, 818 mışravāsasah kauberakāh, 235, 267 miham na vāto vi ha vāti bhūma, 360, 579, 831 mukham sad asya sira it satena (sadena), 60 muncantu ma sapathyat, 325 mudah pramuda asate, 713 mudgāś ca me khalvāś (kharvāś) ca me. musāvas cakram avīve rapādsī ("ver apānsi), 837 muskāv id (°kā id, °kau yad) asyā e1stah, 735, 888 mrgasya srtam (śrtam, śrutam) aksnayā, 278. 682 mīgā na bhīmās tavişībhir arcinah (tavişebhır ürmıbhıh), 695 mrianti vahnim sadanesy acha, 634 mriyase pavase mati, 195, 337 mriyase soma sataye, 195 mrtāya jīvām parınīyamānām, 402 mrttike hana (hara) me pāpam, 861 mrtyoh padam (padānı) yopayanto yad aita (aima, yopayanta eta, lopayante yad eta), 245, 711 mrtych (°yoş) pāhi, 967 mršase pavase matī, 195, 337 mekşyāmy ūrdhvas tışthan, 332 meghyā vidyuto vācah, 316, 707 medasah kulyā (kūlyā) upa tān (upainan, abhi tan) sravantu (ksarantu). medasah (°sa) svābā, 980

medaso ghrtasya kulyā abbinihsravantu. 565 medhām sapta rsayo (saptarsayo) daduh, 919 medhām ta ındro dadātu. 106 medhām dhātā dadātu (dadhātu) me. medhām agnir dadātu me (dadhātu te), 106 medhām āśāsata śrīve, 230, 508 medhāyai manase 'gnaye (agnaye) svāhā, 910 meşam te sug rchatu (te kşut), 145 maighir vidyuto vācah, 316, 707 maitrāvarunasya camasādhvarvav (°va) ādrava (ehi), 889 mainam hinsistam svām vonim āviśantau. 505 maına arva renukakatah prnak (pranak), 664 maışam kam canoc chışah, 578, 688 maişam nu gad aparo artham (ardham) etam. 77 maisam uc cheși kim cana, 578, 688 maiso asmān avahāya parāgāt, 924 modah pramoda anandah, 713 mo svatvam asmäntarädhät, 105 mo sv asmāns tamasy antarādhāh, 105 ya ājagma ("muh) savanemā ("nedam, °nam idam, ya ajagmedam savanam) juşānāh, 835 ya ātrnatty (ātrnoty) avitathena (avidathena) karnau, 60, 392 ya antarıkşah, 314, 490 ya ābabhūva bhuvanāni visvā, 215, 381 ya āvabhūva bhuvanānı viśvāh, 215, ya āvīvešoṣadhīr (°śauṣadhīr) yo vanaspatin, 731 va āvrnotv avitathena karnau. 60 ya äste yaś ca caratı (yaś caratı) 808 ya imam yajūam svadhayā dadante (bhajante), 159, 741 ya ıme dyāvāpṛthivī tastabhāne, 137 ya isavo yātudhānānām, 505, 990 ya im vahanta āśubhih 307 ya ise asya dvipadas catuspadah, 907

ya usriyā apyā (api yā) antar asmanah yajūam pranaya (pra suva) devāvvam (°n1), 785, 824 ya rte cid abhiśrisah, 193, 353, 676, 802 ya etasmin loke stha . bhūvāsta, 90 ya esa syapnanansanah ("nāsanah), 300 yah pauruşeyena kravışl samankte (samaūte), 418 vah pranato nimisato (nime°) mahitva (°șatas ca rājā), 688 yah prāniti (prānati) ya im śrnoty uktam, 582 yansad višvam ny atrinam, 302 yam sam id anya ındhate, 169, 302 vam sim id anva idate. 169, 302 vaksate cid abhisrisah, 193, 353, 676. yakşmam śronibhyām (śroni°) bhāsadāt, 319, 490, 529 śronibhyűm yakşmam bhasadyam bhāsadam, 319, 490, 529 caskabhāne yam krandasī avatas (avasā tastabhāne), 137 yac ca padbīšam (°vīšam) arvatah, 217 vac ca pranati (praniti) yac ca na, 582 336 yac chikşası stuvate mävate vasu, 140 yachā nah ,yachāsmai) sarma saprathah (°thah), 502 yajamānāya jāgṛta, 90, 662 yajamānāya vāryam ā suvas kar asmai, 833 yajā no (yajāno) devo (devān) ajarah suvīrah, 826 yajur yuktam (yajuryuktam) sāmabhir āktakham tvā (rktakham tā), 365, 632, 817 yaje samrādhanīm (samardham īm) aham, 617, 806 yajnah pratyaşthat (praty u sthat sumatau matīnām), 380, 613, 736, 832 yajñam-yajñam prati devayadbhyah (°yadbhyah), 170, 321 yaıñam devebhir ınvıtam (anvıtam), 577 yajñapataye vasu väryam āsamskarase

(°pataye vāryam ā svas kah), 833

380, 736, 832

yajna pratitistha sumatau suševāh,

(deväyuvam), 805 yajūasya ghosad ası, 83 yaıñasya pakşāv (°şā) rşayo bhavantī. yajūasya yuktau dhuryā (°yāy) abhūtham (°tam), 91, 888 yajñasya vidyān samaye na dhīrah. 244 yajňasya hi stha rtvija (rtviyau), 192 yaıñasyayur anu sam carantı (tarantu), yajñād eta sann (yajñā ned asann, netar asann) apurogavāsah, 62, 192 vajňavate va pašuso na (nu) vajan, 614 vajnävur anu Bamcaran, 155 yajñiya yajñam prati devayadbhyah, 170, 321 vaiño bhūtvā svām (svam) yonum saksava (svak°) ehi, 364, 505 vam tīvam ašnavāmahat (°he). 710 yata āttas (ārttas) tad agan punah, vatah prajā akhidrā vata ścutad agnāv eva tat, 336 yata ścutad dhutam agnau tad astu, vataś codeti sūryah, 843 vatah sūrya udeti. 843 yato bhayam abhayam tan (abhayatvam) no astu, 826 yat kım canrtam odıma (üd°), 722 yat kusidam apratittam (°titam, apradattam) mayı (mayeha), 404 yat kşurena marcayatā (vartayatā) sutejasā (supešasā), 156, 180, 195, 234 yat ta āsthītam šam u tat te astu, 280 vat tatraino apa tat suvāmi, 201 yat te asmin ghora asan juhomi, 935, yat te ditsu (dikşu) praradhyam, 140 vat te 'nādhrstam nāma yajnīyam dhāmānādhṛṣ-(nāmānādhṛṣyam, yam) tena tvādadhe, 855 yat te mahe, see yat tvemahe ... yat te rājañ (rājaň) chṛtam havih, 937 vat te viristam sam u tat ta etat, 280 yat tvemahe (te mahe) prati tan no (prati nas taj) jusasva, 365, 835

yatra gavām nihitā sapta nāma (nāmā), 460 yatra cābhimṛśāması, 866 vatra cuscutad (scutad) agnav evaitat. 336, 885b vatra devā itı bravan, 452, 602 vatra devaih sadhamādam madantı (madema), 341 yatra nah pürve pitarah paretah, 452 yatra bānāh sampatanti, 29, 218 yatra-yatra jätavedah sambabhütha (°bhūva), 207 yatra-yatra vibhrto (bibhrato, etc.) jātavedāh, 207, 662 yatra yanti srotyās (sravatyas) taj 11tam te, 749 yatrarşayah, "yo, see yatra rs" yatra vānāh sampatanti. 29. 218 yatra väbhimršāmasi, 866 yatra saptarsin para ekam āhuh. 452. 919 yatra suhārdah sukrto madante, 452 yatrā rsayo, see yatra . . . yatrā devā iti bruvan, 452, 602 yatrādhi sūra udito vibhātı (udıtau vyet1), 63, 732, 743 yatrā nah pūrve pitarah paretāh (pareyuh), 452 yatrā naś cakrā (cakra) jarasam tanūnām, 443 yatrāmītāsa āsate (āsata), 282 yatrā vrksas tanvai yatra vāsah, 198. 375, 831, 835 yatrāsate sukrto yatra te yayuh (ta īyuh), 734 yatrā sapta rein para ekam āhuh, 452, yatrā suhārdah sukṛto madantı, 452 yatrāspīksat tanvo yac ca vāsasah (tanuvam yatra vāsah), 198, 375, 831, 835

vat pašur māyum akrta, 198, 662

rikse, 888

, 919

. . . 916, 919

yat prthivyām yad urāv (urā) anta-

vatra rsavah (yatrars°) prathamajā

yatra (yatrā) reayo (yatrare°) jagmuh

vatrainan (vatraitan) vettha mhitan parāke (parācah), 126 yat sāsahat (sāsāhā, sāsāhat) sadane kam cid atrinam, 480 yat some-soma äbhayah (äbhuyah), 602 yat somyasyāndhaso (sau°) bubodhati, 728 yatha rnam samnayāmasi. 918 yatha rtava rtubhir yanti sadhu, 918 yatharnam samnayanti, 918 vathartava rtubhir vanti sākam (klptāh), 918 yathākşitim akşıtayah pibanti (°vo madantı), 586 yathāgnir akşıto . . 576 yathā devaih sadhamādam madema. yathadhuram (°dhūran) dhuro (dhūro) dhūrbhih kalpantām, 557 yathā na indrah kevalīh (ındra id višah), 341 vathā nah śreyasas (°sah) karat, 964 yathā no vasyasas (°sah, vasīyasas) karat. 786, 964 yathāpah pravatā yantı, 60, 200 yathayatham dhuro dhurbhih kalpantām, 557 yathāyatham nau tanvau (tanvā, tan nau) jätavedah, 410 yathā yanti prapadah, 60, 200 yathā yamāya harmyam (hār°), 491 yathā ha tyad (tad) vasavo gauryam cit, 345 yathaham bharata rsabha (bharatarso). yathedam strīpautram aganma rudriyāya, 83, 719, 801, 816, 827 yatheyam stri pautram agham na rodāt, 83, 719, 801, 816, 827 yathaika rsir ("karsır) yıjānate. 919. 990 yathainam jarase nayāt, 341, 952 yad agne kavyavāhana, 353, 380 yad agne pürvam prabhṛtam (prahitam, nihitam) padam hi te, 118, 639 yad aghriyata ("yathās) tad ghrtam. yad atramo ava tat suvāmi. 201

vad adivvann rnam aham babhūva (krnomi), 702 vad adva te chora āsan juhomi, 936 yad adva dugdham prthivim asrpta (asakta, abhakta), 152, 634, 874 vad adva hotrvarye (°vürye), 621 vad advārādhyam vadantah, 59, 70, 272a, 836 yad adhriyata tad ghrtam abhavat, 147 yad anena havışāsāste tad asyāt (asyām), 287 yad annam agnır (admı) bahudhā virāddham (virājam, viruddham, virūpam), 144, 569, 619 vad annenätirohati, 408 yad anyenābhavat saha, 408 vad apāmrksac chakumh, 201 yad apsaradrūr uparasya (apsararūparasya) khādatı, 188, 808, 826 vad avāmrksac chakunih, 201 vad asya guspitam (gulphitam) hrdi, yad asyā anhubhedyāh (anuhodbhyāh), yad asravan pasava udyamānam. 278 yadā carışnū mithunāv ("nā) abhūtām, 888 vad apo aghnya (oniya) iti, 784 vad āmayati niş kṛtha (kṛta), 90 yadā rāghatī varadah (yadā rākhātyau vadatah), 59, 70, 272a, 836 yad āhur aghnyā iti, 784 yadı cın nu tvā dhanā jayantam, 68, 735 yadı tvam atra (tvam tatra) manasā jagantha, 735 yad id dyāvāpṛthivī aprathetām, 341 yad ındra cıtra mehanā (ma ıha na), 477, 832, 991 , yadı vāruny ası yadı varunasyāsı yadı somasyāsı (saumy ası) , 728 yadin rnam samgaro devatüsu, 309 yadī vahanty āšavah, 307 yad uttaradrāv uparas ca khādatah, 188, 826 yad u devi sarasvati, 740 yad ürdhvas tışthā (tışthād) dravıneha dhattāt, 392

yad ejati jagati namno (nanvo. mānyo) bhāgo yan ('yam) nāmne (bhago yatnan me) svaha, 411, 801, 871 vaded antā adadrhanta (adadrhh°) pürve, 341, 835 vad eva kim ca pratijagrahāham (°iagrāham), 808 yad oşadhişv apsv ä (apsu vā) yajatra. yad gharmah paryavartayat (paryā°), 508 yad ditsasi stuvate māvate vasu, 140 vad didayac chavasa (°sā) rtaprajāta (chavasarta°), 916, 918 yad düre sann ihābhavah (°bhuvah). 602 yad devā devahedanam ("lanam), 271 yad daivyam rnam aham babhūva, 702 yad dha sā te panīyasī, 345 yad dhastābhyām cakrma (cakara) kılbışanı (kilv°), 216 vad dha syā te panīyasī, 345 natividhe (°de) banhistham yad sudānu, 107 yad bhūtam yac ca (yad vā) bhavyam (bhā°), 487 yad-yat tvam atra manasanu vettha, 735 , 491 yady ası vărunî , 728 yady ası saumi yad yāmam (yady āmam) cakrur nikhananto agre, 837 yady rnam samgaro devatāsu, 309 vad rātrīyāt kurute pāpam, 791 yad rátrıya (rátrya) papam akarşan (akārīsam), 758, 791 yad vašā māyum akrata, 198, 662 yad vā ghā satyam uta yan na vidma, yad vācānrtam odima (ūd°), 722 yad vāto apo ('po) aganīgan (agamat), yad vādāsyan samjagārā janebhyah, 45, 446, 480 yad vā devī sarasvatī, 740

yad rte cid abhisrisah, 193, 353, 676, 802

471, 485

yad vādya satyam uta yan na vidma, vad vā me apı ('pı, apa) gachati, 578, vad vidāv (vilāv) ındra yat sthure, vad vo devā atīpādavāni (°pātayāni). vam te svadāvan svadanti gūrtayah, yam te svadhävan svadayantı dhenavah. 107 yan me mātā pralulubhe (pramamāda, pralulobha), 715 yam akşıtam (°tim) akşıtayah pıbanti. yam aksıtam aksıtā bhaksayanti, 586 vamam gāva bhangvasravah (bhanga°). yamam bhañgyaśrayo (bhañga°) gāya, yamasya dūtas ca vag vidhāvati (dūtah śvapād vidhāvasi), 145, 198, 830 yamasya pätürah (pätorah), 720 yamasya loke adhırajjur ayat (aya, loke nidhir ajarāya), 401, 618, 840 yam ichāmi manasā so 'yam āgāt. 700 yamîr yamasya bibhryād (vivīhād) ajāmi, 222, 256 yam eva vidyāh śucim (sucim) apramattam, 278

yam aichāma manasā so 'yam āgāt, 700 yamo rājābhitisthati (rā·ādhi'). 172

yamyai pāţūrah, yamyāh pāţorah, 720

yayā krnoti muhu kā (muhukā) cid

yayo rathah satyavartmarjurasmih.

yayor vām devau deveşv anısıtam

yayā gā ākarāmahe (°haı), 710

(°sıtam) ojah, 292

yavaya dveşo asmat, 479

yavayārātīh (°tım), 479

yavayāsmad dveşah, 479

yavayāsmad aghā dveşāhsı, 479

yameştam ası, 339

rsvah, 824

yavānām bhāgo 'sı, 485 vavās cāvavās cādhipatava āsan, 485 yasasendrābrhaspatī, 840, 870 vašo bhagaš ca mā vidat (risat, rīsak). 142, 189, 840 yaso bhagasya vindatu, 189, 840 yaśo mendrabrhaspati, 840, 870 vašo vainasva daksinām, 161, 579 yas tad veda savituh (sa pituh) pitāsat, 198, 829, 967 yas tānı veda sa pıtuş (pıtuh) pitāsat, 198, 829, 967 yas tā vijānāt sa pituş (savītuh) pitāsat, 198, 829, 967 yas te agne sumatum marto aksat (akhyat), 191 yas te drapsa (°sah) skandati yas te ansuh, 974, 977 yas te soma prajāvat so 'bhi so aham. yas te stanah śaśayo (°yur) yo mayobhūh, 719 ya strinām jīvabhojanah, 977 yasmāj jātā na parā naiva kim canāsa (jātam na purā kim canaiva), 615 yasmāj jāto na paro 'nyo (anyo) asti. 615, 907 yasmāt param nāparam asti kimcit. 615 yasmād anyan na param kim canāstī, yasmād anyo na paro astī jātah, 615, yasmād bhīṣā nyaṣadah (°sadah), 983 yasmād yoner udārīthā ("tha) yaje (yajā) tam, 446 yasmān na jātah paro anyo asti ('stı), 615, 907 yasmını adlı vitatalı süra eti, 63, 743 yasmını ätastbur bhuvanānı visvā, 386 yasmın süryä ärpitäh (arp°) sapta sākam. 509 yasya te viśvamānusah (viśvam ānusak), 832 yasya te sakhye yayam, 340 yasya dvārā manuş (manuh) pitā, 967

yavā ayavā ūmā abdah (āyavā ūmā

evā abdas) sagarah sumekah, 376,

yasya yonım patireto grbhāya (prati reto grhāna), 116, 341, 354, 363, 819 vasvā udvatah pravatah samam bahu (mahat), 241 vasyam devā abhi samvišantah, 172, 281, 340 vasvā bahvyas tanvo vitaprsthāh, 793 yasyām idam višvam bhuvanam āviveša, 341, 386 yasyāsau sūro vitato mahitvā, 63, 743 yasyās te asyāh krūra āsañ juhomi, 936 vasvās te ghora āsan juhomi, 936 yasyedam ā rajo yujah (°dam û rajah, odam oja ārujah), 244, 800, 808 vasyai bahvīs tanuvo vītapṛṣṭhāh, 793 yah strīnām jīvabhojanah, 977 vā akrntann avayan yā atanvata (väš ca tatnire, akrntan yā atanvan), yā antarīksa uta pārthivīr yāh, 321, 850 yā antarıkşyā uta pārthivāsah (pārthivir yah), 321, 850 yā ātmanvad bibbrto ("tho) yau ca raksatah (°thah), 91, 207, 634, 888 yā ārdroghnih parı tasthuşih, 854 yā 18avo yātudhānānām, 505, 990 yāh krtyās (krechrās) tripancāsih, 28, 185, 192, 353 yān āvaha usato deva devān, 924 yāns (yās) te soma prānāns tān (tān, tāfi) juhomi, 936 yā grtayas tripaficāšīh, 28, 185, 192, 353 yā codītā yā ca nodītā (yā cānudītā) tasya1 . . , 719 chura maghavañ vācchresthābhir 11DVa, 937 yā tām rātrīm upāsmahe, 365 yātudhānebhyah kaņţakīkārīm (kanţakakāram), 600 yā te agne 'yahsayā ('yāsayā) tanūr , 395 yā te agne 'yāsayā rajāsayā harāsayā , 395 tanür yā te agne rajahšayā (rajāšayā) tandr yā te agne harīsayā (harī°, harā°) 521, 597 vā te dhāmāny ušması gamadhyai, 705

yā dabhrāh parisasrusth, 854 yādase sābalyām (sābulyām), 607 yā devīr antān abhito 'dadanta, 63, 92, 924 yā devy asīstaka āyurdāh caksurdāh śrotradāh 980 caksurdāš (°dā) vā devv asīstake **Arotradā** dvaurdās (°dā) svardāh prapharvīdāh (°vidāh) 524. ባደበ vä daiviš catasrah pradišah, 707 yā na ūrū ušatī višrayāte (°ti, visravātai), 278, 710 yan agnayo anvatapyanta ('nv°) dhişnvāh. 909 yan avaha usato deva devan, 924 yāni kāni ca cakṛma, 808 yām tvā jano bhūmīrīti pramandate, 869 vām tvū rātry upāsmahe (upāsate, rātrı yajāmahe), 365 yāny apāmityāny apratīttāny (apratītāny) asmı, 404, 465 yā prathamā samskṛtir yajūe asmin, väbhir indro vävidhe viryāya (virvāvān), 250 yābbir yāsi dūtyām sūryasya, 494 yābhyām svar (suvar) ajanann (ajayann, yābhyām ajayan svar) agra eva, 853 yām apītā upatīsthanta āpah, 472, 871 yām āpīnām upasīdanty āpah, 472, 871 yām ındrena samdhām samadhatthāh (ındrena samadadhvam, °dhadhvam) yā medhāpsarāsu (medhā ap°, °rahsu, °rassu), 395, 995 yām airayans (°yan) candraması svadhābhih, 930 yā rājanye dundhubhāv (°bhā) äyatāvām, 888 yā rājūnam (°nā) saratham yūtha (yāta) ugrā, 91 yāvacchreşthābhir maghavan chūra jinya, 937 yavayaratım, 479 yāvayāsmad dveşam, 479

yāvā ayāvā evā ūmāh sabdah sagarah sumekah, 376, 471, 485 yāv ātmanvad visatho (bibbṛto) yau ca rakṣathah (°tah), 91, 207, 634, 888 yāvānām cāyāvānām cādhipatyam āsīt 485 yāvānām bhāgo 'si, 485 yāš ca gnā devyo 'ntān abhito 'tatananta (tatantha), 63, 908, 924 yāš ca devīr antān abhito 'dadanta,

63, 92, 924 yāś ca devīs tantūn (devyo antān) abhito tatantha ('ta'), 63, 92, 908, 924

yā samjayantam adhi yāsu vardhase, 287, 339, 618, 840

yāsad višvam ny atrınam, 302

yā sarasvatī višobhagīnā (veša°, vešabhagīnī) . , 542, 686

yā sarasvatī vaišambhalyā (°balyā, °phalyā) , 79, 114

yāsām agnīr iştyā (niştyā) nāmāni veda, 421

yās te soma prajā vatso 'bhi so aham, 840

yās te soma prānāns , see yāns elc yāsyā aputryā (°triyā) tanūs , 787 yīyapsyata (yī°) rva te manah (mukham), 519

yuktās tisro vimījah (vibhr°) sūryasya, 57, 156, 189, 205, 234, 242

yuktā (yuktvā) harī vīsanā yāny arvān (arvāk), 367

yuje samardham im aham, 617, 806 yuñjanti suprajasam pañca janāh, 192, 339, 617

yunajmı tısro vıpıcah süryasya te (vıvıtah süryah save, or savah), 57, 156, 189, 198, 205, 234, 242, 840

yuyuyātām ito rapo apa sridhah, 808 yuvam hi sthah svarpatī (svahpatī), 968

yuvalam chandah, 805

yuvā kavih purunistha ("sthā) ītāvā, 493

yūpāyocchriyamānāyānubrūhi (°chriya°), 536

yūj am vṛṣṭim varṣayathā purlṣmah, 90

yüyätäm asmad rapo apa sridhah, 808 ye agnayah päűcajanyāh (purişinah), 907

ye agnayah ('gnayah) samanasah (°sah sacetasah), 907

ye agnayo divo ye pṛthivyāh, 907 ye agnidagdhā ye anagnidagdhāh ('nagni'), 907

ye agnışvāttā ye 'nagnışvāttāh (anagnı'), 907

ye anneşu vıvıdhyanti, 907

ye apsu şadānsı ('psu sadānsi) cakrıre, 908, 988

ye amî rocane divah, 907

ye asmın ('smın) mahaty arnave, 909 ye ke cobhayādatah (caubha°), 732

ye 'gnayah purişyah (purişmah), 737, 907

ye 'gnayah samanasah, see ye agnayah

ye 'gnayo divo ye 'ntarikşāt, 907

ye ca ke cobhayādatah, 732 ye ca bhūteşu jāgrati (jāgrtha), 662

ye cit pūrva ŗtasāpaḥ (°sātāh), 180 ye cid dhı pūrva ŗtasāpa āsan, 180

ye tütrşur (tütrpur) devatrü jehamānāh, 872

ye te agna ındavo yā u nābhayah (yā urnunābhayah), 810

ye te agne medayo (medavo) ya indavah, 248

ye te aryaman, see ye te 'ryaman ye te panthano bahavo janayanah, 511 ye te 'ryaman (arya") bahavo deva-

yānāh, 511, 908 ye'tra pitarah bhūyāstha, 90

ye trışaptāh (trısaptāh) parıyanti, 986 ye tvā rātry (rātrīm) upāsate, 365 ye devā agnuetrāh purabandas

ye devā agninetrāh purahsadas 615

ye devā uparīṣado (uparīṣadas) 986

ye devāh purahsado (parah°) agninetrā ('gni°) , 615, 910

ye devā divibhāgā ye antarıkşabhāgā ('ntarı') pṛthivibhāgās (pṛthivi') , 524, 910 ye devā devasuva ('veh) stha , 977 ye devā manojātā (manu°) manoyujah (manu°, manojusah) , daksapıt-, 500, 719 aras (°tāras) ve devā mitrāvamnanetrā vottarāsadas (vottara°) ye devāh somanetrā uparisado (°sado) , 986 ye 'do rocane divah, 907 yena (yenā) rsayas (yenarsa*) tapasā satram (sattram) āsate (āyan), 390, 916, 919 yena turyena brahmanā brhaspatave 'pavathās tena mahyam pavasva, 802, 910 yena prajā achidrā yena bhūyas ca rātryām (carāty ayam, caraty ayam), 61, 244, 254, 354, 738, yena bhūriš carā divam, 61, 244, 254, 354, 738, 840 vena mahanaghnya ("nagnya) 1aghanam, 83 yena rūpena prajāpataye 'vapathās tena mahyam pavasva, 802, 910 , see yena rş° yenarşayah yena yahasi sahasram, 458 yena ériyam akrnutām, 237, 287, 420 yena sahasram vahasi, 458 yena striyam akrnutam (striyav akurutam), 237, 287, 420 , see yena 13° venā rsayas yenākṣā (yenā kṣām, yenākṣān, yenākşyāv) abhyaşıcyanta (abhyaşıncatam, °tām), 309, 330, 332, 835 yenā te pūrve pitarah paretāh, 452 yenāpāmṛśatam (°mṛṣatam) surām, 201, 289 venāvamīšatām surām, 201, 289 yenā samatsu sāsahah (°hıh, °hı), 381, 584yenā sahasram vahası, 458 yenendro abhivavrte (°dhe), 97 venendro havisā krtvī (krtī), 367 ye no dvisanty anu tan rabhasva, 222, 802 ye 'nneşu vıvıdhyantı, 907 ye pūrvāso ya uparāsa (ye aparāsa) Iyuh, 617

ye 'psu sadûnsı, see ye apsu şa° ye bhaksayanto na vasūny anrdhuh (anrhuh, anasuh), 122, 634 yebhir viśvam (vy aśvam) airayah, yebhyo na rte (narte) pavate dhāma kım cana, 919 yebhyo madhu pradhāvatı (pradhāv adhı), 98, 832 ye rätrım (°im) anutışthantı (°sthatha). ve 'vatesu serate. 808 ve vanaspatīnām, 808 ye vaneşu saşpıfijarāh, 32, 278, 294 ve vā nūnam suvrjanāsu vikşu (dikşu), 869 ye vāvateşu serate, 808 ve vā vanaspatīnr anu ("patīnām), 803 ve vrksesu šaspinjarāh (saspio), 32, 278, 294 ye sakvara rşabha ye svarajah, 359 ye sambare hariyo ye gayiştau (galstau), 889 yeşām apsu sadas (sadah) kṛtam. 964 yeşu va yatudhanah, 990 ye sajātāh samanasah (su°), 612 ye samanah samanasah, 612 ye sarpāh pārthivā ye antanksjā je , 314, 490 divyā ye 'sman abhyaghayantı, 909, 924 ye 'smin mahaty , see ye asmu yo agnih kravyavāhanah (kavya°), 353, 380 yo agnım hotāram avīthāh, 908 yo agnau rudro yo apsv antah, 909 yo adya senyo (saumyo) vadhah, 907 yo antaro mitramaho vanusjāt (anusvāt). 360 yo asmān abhyaghāyatı, 909, 924 yo asman dveştı, see yo 'sman vo asmı so asmı, 910 yo asya kauşthya jagatah, 315, 907 yo asyāh pṛthivyās tvaci, 907 yo gā udājad apa (api) hi valam (balam) vah, 210, 578 yo gopā apı (gopāyatı) tam huve, 180, 342 yo'gnim hotāram ayrthāh, 903

vo 'gnau rudro vo 'psv antah, 909 raksobāmīvacātanah, 386 vo devānām nāmadhā ("dha) eka eva rajani granther dhānām (dānam), 107. (eko astı), 493 401, 618 rajobhūmis tvam mām (tvam ām) vo'dva saumvo vadhah. 907 yo nah kadā cid abhidāsati druhā, 620 rodayasva ... 307 rajjuni granther dānam, 107, 401, 618 yo nah pitā janitā yo vidhātā (viratham sahasrabandhuram (°vandhudhartā), 350 yo nah svo (svo yo) aranah ('ranah). ram, hiranyayan°), 213 907 rathe aksesy rsabhasya (aksesu yrsa°) yo no agne nistvo vo 'nistvo . . . 808 vāje, 267, 359 yo no anti sapati tam etena jeşam, 910 ratheşv akşeşu vrşabharājāh, 267. 359 yo no dvesti tanûm rabhasya (dvesty ratho na väjem sanişyann (sanişann) anu tam ravasva), 222, 802 ayasit, 334 yo no mitrāvarunā abhidāsāt sapatnah radantam śuddham (sudam, śunam) (°varunāv abhidāsati), SSS uddharet, 286 yo mā kadā cid abhidāsati druhuh, 620 ramadhvam mā bibhīta mat (biyo me 'nti dure 'rātīyatī tam etena bhitana), 827 jeşam, 910 ramayata ("tā) marutah Syenam Jviyo maitasyā diśo abhidāsāt (°sād, nam (marutah pretam vijinam), 193. °sān) . 910 360, 442 yo rayivo (rayim vo) rayintamah, 307. rayim yena vanāmahai (che), 710 rayim devī dadhātu me, 105 yo rudro agnau yo apsu (rudro 'psu yo rayim no debi jīvase (dhehi yajniyam). 'gnau') ., 909 106 yo vām ratha rjurašmih satyadharmā. rayim me dāh (dhehi), 103 rayisthīno (°sthāno) rayim asmīsu yo vaisvanara uta visvadavyah (vaisdhehi. 986 vadevyah), 699 rayyī mā pašyats, 396 yo 'sāv ('sl) ādītye puruşah so 'sāv rayyā vah pasyāmi, 396 ('sā) aham 888 rasena sam asıkşmahi (agasmahi, aganyo 'smān (asmān) dvești yam . . ., 910 mahi, apṛkṣmahi), 634, 853, 874 yo'smi sa san yaje, 910 rājanye dundhubhāv āyetāyām, 888 yo 'sya kausthya (kaustha) lagatah, rājānah satyam kṛnvīnīh (gṛhnīnāḥ), 315, 907 yo'syāh pṛthivyā adhı tvaci, 907 rājānah samitāv (°tā) iva, 888 yo 'syese dvipado yas catuspadah, rājā me prāno 'mṛtam (amṛtam), 907. 907 rātrim-rātrim aprayāvam bharantah. yo'ham asmi sa san yaje, 910 117, 528 yau te pakṣāv ajarau patatrinau, 732, rātrum jinya, 528 888 rätrım dhenum . , 528 yau višvasya paribhū (višvasyādhipī) rātrim pīvasā, 529 babhūvathuh (°tuh), 91 rātriyai . ., see rātryai . . yau vīryair vīratamā šavisthā, 323, 849, rātri stomam na jigyuşe (°şī), 525, 695 rātrīm-rātrīm aprayāvam bharantah, rakşohanau (°nau väm) valagahanā 117, 528 (nāv) upadadhāmi . , 886 rātrim jinva, 528 rakşohāmitrān (°trān) apabādhamārātrīm dhenum . . , 528 nah, 924 rātrīm pīvesā, 528

rātrī stomam na jigyuşī, 525, 695 rätryai (rätriyai) kṛṣṇam pingākṣam. 791 rātryai (rātrīvai) tvā. 791 rātryai (rātriyai) mā pāhi, 791 rātryai (rātriyai) svāhā. 791 rādhānsīt (°sı) sampçūcānāv (°nā) , 545, 888 asam o rāyas poşam yajamāne dadhātu, 105 rāvas posam cikituse (°sī) dadhātu (dadātu), 105, 695 rāyas poşam audbhidam ("dyam), 319 rāyas posena mā pašyata, 396 rāyas posena vah pasyami, 396 rāyas poşo ni şīdatu, 720 rāyah syāma rathyo vayasvatah (vivasvatah), 255, 579 rāyo devī dadātu nah, 105 rästram duhäthäm iha revatibhih, 91 rışyapadim vışadatim, 666 rišvasveva parīšāsam, 666 rucito gharmah, 713 rudra yat te krayl (krivı, kravı, gırı°) , 47, 244, 255, 267, param nāma 573, 819 rudras tanticaro vrsā, 144 rudrasya maryā adhā (athā) svasvāh, rudrānām urvyāyām (ūrmyāyām) svā-., 228, 355, 564, 719 dıtvä adıtaye rudrānām omyāyām svādītyā , 228, 355, 564, 719 °bhrtya) samsriya (°yā. rudrāh prthivim, 457 rudro 'gnīt (agnīt), 910 rudro 'dhipatih (adhi"), 910 ruvad dhokṣā paprathānebhir evaih, 684, 840, 861, 875 , revati yajamāne prirevatı predhā , 747, 820 yam dhā revati ramadhvam ("tir amedhyam). 255, 837 revatīr yajūapatīm prīyadhāvišata. 747, 820 resinām tvā patmann ādhūnomi, 363 rešīsu, 363 reşmānam stupena (stū°), 563 rocasva devavitamah, 398, 853

rocitas tvam deva gharma devesy ası. rocito gharmo ruciva, 713 lājān āvapantikā, 151 lālilāys (lāle°) dhīmahı, 696 lekah salekah sulekas te viyantu, 49, 686, 796 lokam asmaı yazamanaya dehi (dhehi), lokam u (id) dve upa jāmī Iyatuh, 392, 627 vakratundāva dhīmahı, 866 vaksahsu (vaksassu) rukmā upašišrıvanah, 971 vagnunendram hvayata, 256, 346, 800 vankrīr ašvasya svadhītīh sam etī. 545 vajrıñ (vajrın) citrabhir ütibhih. 930 vatso jarāvu pratidhuk plyūsah, 381 vatso virājo visabho matīnām, 236, vadhūr jajāna (jigāya, mimāya) navagaj (navakri) janitri, 46, 634 vanakrakşam (°prakşam) udaprutam, vanarşade vat, 353, 632, 650 vanasade vet (vat), 353, 632, 650 vanaspatibhyah pary ābhṛtam (āvṛtam) sabah, 221 vanaspatinr oşadhi rāya eşe (rāye aśyāh), 292, 803 vanaspate rašanayā nīyūyā ("ya), 457 vanaspate 'va srjā (srja), 431, 446 vanā vananti dhrsatā ("dā, drsadā) rujantah, 60, 110 vanıştum (°şthum) asya mā rāvışta, vanışthor hıdayad (udarad) adhı, 244, 386, 643 vanuşvad deva dhimahı pracetasam, vangsade vet, 353, 632, 650 vaneşu cıtram vıbhvam (vibhuvam) viśe-viśe, 789 vandadvārā vandamānā vivasļu, 371, vandadvírāyendave, 229 vande dārum vandamāno vivakmi, 371, 833

vapayā dyāvāprtbivī prornuvāthām, varcoda agne 'si ("da ası), 100 91, 797 varcodā varīvodāh ("vodā dravinodāh) vaptā (vaptrā, vaptar) vapasi (°tı) keśaśmaśru (keśān), 357 varcodhā agne 'si ("dhā asi), 100 vayam rāstre jāgryāma (*mā, jāgrivarcodhā varıvodhāh, 104 yāma) purohitāh, 446, 674 varco mavi dhehi, 100, 103 vayam hi văm purutamăso ("damăso) varco me däh (dehi, dhäh, dhehi), 100, aśvins, 60 vayam ghā te apı şması (sması), 987 vardhanam purunissidhe ("nibsidhe). vayo ye bhûtvî (°tvā) patayanti 971 naktabhih, 598a varma (°mā) sivyadhvam bahula varano varayatai (°visvate), 606 prthuni, 460 varīvas (°vah) krnvan vijanasya rājā, varsāni cāksusāni, 328 varsābhyas tittirin (°rān). 598 varīvasya mahāmaha (*syā mahonām). varşās cākşuşyah, 328 442 varsimā . see varsma . . varuna dharmanam pate (dharmanam varşışthe adhi ('dhi) nāke, 907 adhipate), 494 varşman kşatrasya kakubhih (°bhi, varunasya rtasadanam ("syarta") asi, kakubbhih) sisriyanah (srayasva), 381, 400 varunasya rtasadany ("syarta") ası. varşmā (varşimā) ca me drāghimā 919 (drāghuyā, drāghyā, drāghmā) ca varunāya rājūe trayo lohitalalāmāh me, 240, 764, 805 (rohita*), 262 varşmä rathasya ni jihlşate (11hldate, varunāya rīšādase (vidase) 267 jihilate) divah, 853 varuneti šapāmahe ("hai, şayāmahe), vašāh stha, 489 289, 710, 867 vasatkārah, 489 varuno vārayāt, 606 vașat te vișnav (vișna) āsa ā krnomi, varutrī tvā. , see varūtrī tvā varutrīr avayan - (varūtrayas tvāvavasantena rtunā ("tenartunā) devāh, yan), 562 varutrīs tvā . , see varūtrīs tvā vasanto asyāsīd ('syāsīd) ājyam, 909 varūtrayo janayas tvā devīr višvavasavas cātisthan vasudhātaras ca, devyāvatīh pṛthīvyāh sadhasthe 'ngırasvat , 467, 562, 910 vasavas tvā pra bihantu (vih°) gāyavarūtrim (varutrīm, varūtrīm) tvastur trens chandasā, 212 varunasya nābhim, 528, 562 vasışthahanuh sıfigini kosyābhyām, varūtrī (varu°) tvā devī višvadevya-293, 347, 618, 804, 816 vatī pṛthivyāh sadhasthe angirasvat vasum gharmam divam ā rohatānu ., 467, 562, 910 (tışthatānu), 360 varūtrīs tvā (varutrīs tvā) devir visvasudeyāya (°dheyāya) vidhate vi vadevyāvatīh prthivyāh sadbasthe bhātı, 105 angirasvac . , 467, 562, 910, 958 vasupate vi ramaya, 479 varenyakratür ("tur) aham, 272, 360, vasuranvo (°ranyo) vibhūr ası, 248 383, 554, 600 vasuvane vasudheyasya vyantu (vıvarebhir varān abhı şu prasidatah yantu), 796 (°ta), 379 vasuš cetistho vasudhātamas ca, 828 varco asmāsu dhatta (dhehi), 103

vasuh sūnuh sahaso apsu rājā, 716

vasūni cārur (cārye, cāryo, cāryo) vi bhajāsi (bhrjāsi, bhajā sa) jīvan, 244, 579, 632, 825 vasoh kuvid vanāti nah, 804a vaso vasvoh (vasor vaso) purusprhah. 368 vasospate ni ramaya (rām°), 479 vasoh sūnuh sabaso apsu rājā, 716 vasto vayah, 216 vasneva (vasna iva) vikrināvahai, 991 vasvah kuvid vanāti nah. 804a vaha devatrā didhişo havinsi, 437, 440, 581 vahad divyābhir ūtibhih . , 165, 272, 272a, 324, 360 vahānsi sā sukrtām yatra lokah, 303a, 870 vahā devatrā dadhişo (didhişo) havīnsi, 437, 440, 581 vahāsi mā sukrtām yatra lokāh, 303a, vahişthebhir viharan yasi (pāhi) tantum, 214, 867 vahnih samtarano (sampārano) bhava, 180, 486 vān ma āsan (āsyan, āsye), 328 vānmanascaksuhšrotrajihvāghrānaretobuddhyākūtisamkalpā (Kütih samkalpā) me śudhyantām, 383. 818 vācam vişnum sarasvatīm, 156 vācam dhehi, 103 vācam asme niyacha devāyuvam, 51 vācam me jinva, 852 vācam me dāh, 103 vācam me pinva, 852 vācaspatīr no adya vājam svadatu, 51 vācaspatir vācam (vājam) nah svadatu (vācam adya svadātı nah, "te, "svadātu nah), 51 'chidrayā vācāchidrayā vācaspate devāvidham (devã dıvi vrdhan) hotrām airayat (°yant, erayasva, airayasva) svāhā, 711, 816 vācaspate vāco vīryeņa sambhītatamenāyaksase ("yaksyase, "yachase), vācaspate hydvidhe nāman (hinvidhe). 640

hedanam, 578, 617 vācā tvā hotrā. pañcabhir daivyair (devair) 324, 707 vācā mendriyāviša (vācām indr°), 693 vācā somam avanayāmi, 353, 830 vāce krauficah (kruficah), 724 vāco vidhṛtim ("tam) agnim prayujam svāhā, 587 vājajityāyai (°jityai) tvā, 813 vājam tvāgne . . ., 594 vājam arvatsu pavo aghnivāsu (aghny-Esu), 784 vājam asmin nidhehi devāyuvam. 51 vājaš ca prasavaš...vasuš (suvaš) ca.., 802 vājasya hi prasavo (°ve) namnamīti (nanna°), 413 vāji tvā sapatnasāham sam mārjmi (märsti), 594 vājinam šepena. 872 vājinam tvā vājin vājayatyšyai sam mārīmi, 131, 594 vājinam tvā vājedhyāyai (sapatnasāham) sam mārjmi (mārgmi), 131, vājinām vājo 'vatu bhakşo asmān, 903 vājinām bhakso avatu vājo asmān, 908 vājinīm tvā vājini vājayatyāyai sam mārjmi, 131 vājinīm tvā vājedhyāyai (sapatnasāhīm) sam mārjmi (mārgmi), 131 vājino vājajito vājam sastvānso (jigīvānso, sasīvānso vājam jigivānso) . . ., 537 vājo devān (devān) rtubhih kalpayāti 924 vājy aham vājinasyopahūta upabūtasya bhakşayāmi, 594 vātam vişnum sarasvatīm, 156 vātajavair balavadbhir manojavaih, 268, 511, 579 vātavān varşan bhīma rāvat svāhā, 467 vātājirsir balavadbhir manojavaih, 268, 511, 579 vātāpe pīva id bhava, 627 vātāvad varşam ugrar āvīt svāhā, 467

vācā cit prayatam (ca prayuti) deva-

mehanam), 49, 529

vi te bhinadmı takarım ("rim, tagarım, yātāvān varsann ugra rāvat svāhā, 467 vāmam pitrbhyo ya idam samerire (°Irire), 698 vāmī te samdrši višvam reto dbesīya (dhi°) . , 688 vāyava ārohanavāhāv (°hā) anadvāhau. 888 vāvava (°vah, °vas) stha, 977 vāyur dīksito 'ntarīksam diksā sā diksayatu (dikseta) , 745 antankşyaıh (antavāvur na Idita. rıkşaıh) pätu, 314, 490 vāyuş tān (tān, vāyus tān) agre pramumoktu devah, 924, 958 väyus te (väyus te) 'dhipatih, 958 vāyuş te (vāyus te) vājin yun, 958 vāyus tvāntariksāt pātu sūryo divah, vāyus tvābhipātu (vāyus tvā°) mahyā ., 958 svastvā vāvusavitrbhvām agomugbhyām payah, 162, 244, 491, 617, 716 vāyus t-, see vāyuş tvāyo ve (vihi) stokānām ("nām jusanah, sto°), 988 vāyosāvitra āgomugbhyām caruh, 162. 244, 491, 617, 716 vārsāharam sāma gūya, 512 vāšā stha. 489 vāsat, 489 väsantikäv (°kä) rtü abbikalpamänäh, vikirida (°dra, °da) vilohita, 168, 353, 675, 734 vikhyāya (vikšūya) cakşuşā tvam, 190 vigā (vī gā) indra vicaran spāšayasva. 831 vı ca nasan na ışo arātayah, 826 viciti svāhā, 866 vi cid aśnānā işayo arātayah, 826 viertāya (vierttāya) svābā, 401 vı jıhişva lokam krnu (jıhirşva lokan krdhi), 353 vijye vivye viksipet, 244 vijre viksipe vidhame, 244 vidvīr yāman vavardhayan (yāmann avar°), 360, 544 vı te krodham nayāması, 98

vidad gavyam saramā drdham ürvam (urvyam), 347 vidad yadi (yati, yadı) saramā rugņam (saramārunam) adreh, 63, 516 vidma te dhāma paramam guhā yat, 436, 440, 855 vidma (°mi) te svapna janitram, 436, vidmā te nāma paramam guhā jat, 436, 440, 855 vidyām yām u ca (uta) vidmasi, 156, vidvutam kaninakābhyām (kaninis), 595, 597 vidyutüm ıva süryah, 743 vidyutau kanānakābhyām, 595, 597 vidyun me asya devāh, 862 vidyur me asya devāh, 862 vidyullekheva bhūsvarā (hhāsurā), 739 vi dhūmam agne aruşam miyedhya (medhya), 747 vidhe krodbam navāmasi. 98 vi no rūstram unattu payasā svena, 139, vi päsam madhyamam erta (yrta). viprea ("cah, "cas) stha, 977 viprasya dhürayl kavılı, 189, 824 viprah sa dhārayā sutah, 189, 824 viprāso mānuşā yugā, 132 vipro babhūva saprathāh, 180, 235 vibhave svähä, 604, 789 vi bhanum visvadhatanat (visvatha"). vibhur ası pravähanah, 554 vibhur mātrā prabhuh pitrā, 554 vibhur vibhāvā suşakhā (sakhā ā) sakhīyate, 995 vibhuve svāhā, 604, 789 vibhūr asi pravāhanah, 554 vibhūr mātrā prabhūh pitrā, 554 vibhrājañ (°jah) jyotisā svah, 936 vibhrājamānah sarīrasya (salilasva) madhye (°yāt), 264 vibhve svāhā, 604, 789 vimā asi (vimāsi), 993

341, 386

vi mucyadhvam aghnyā (aghniyā) devavānāh. 784 viyantu devā haviso me asya, 796 vivantu devir ya rtur janinam, 796 viyantv ājyasya, 796 viyugbhir väya iha tā vi muñca 145. 379, 889 viratāh smah (sma bhoh), 379 virājah grustih (śnu°) sabharā asan nah, 57, 383, 865 viliptī yā (viliptyā) brhaspate, 791a vivadhat chandah, 516 vivarto 'stacatvarınsah, 516, 910 vivalam chandah, 805 vivasvān adıtır devajūtıs viyantu, 337, 686, 720, 818 vivasvān no abhayam krnotu, 699 viviktyai ksattāram, 139 viviti (vivittyai) svähä, 401, 866 vivityai (vivittyai) kşattāram, 139 vivistyai svähä, 401, 866 vivrttacakrā āsīnāh, 139, 235, 643, 861 viša ādevīr abhy ašnavāma, 470), see višvantu višantu tvām (tvā višalyo vānavān (°vān, bānavān. °vān) uta, 218, 925 višām vavarjuşīnām, 360 višām agnim atīthim suprayasam (°yāsam), 502 višām avarjuşīnām, 360 visām patir abhavad vājinīvān, 869 višo adevir abby acarantih, 470 višo yantre (°trī) nudamāne arātim, 695 višo-višah pravišivānsam Imahe, 808 višo višvā anu prabhuh (prabhu), 381, 889 viśrutayo yatha pathah, 30, 275 vi śloka etu (eti, śloka yanti) pathyeva sūreķ (sūrīh, sūrah. (patheva) sūrāh), 328, 596, 691 višloka višvadāvye tvā samjuhomi syāhā, 151, 835

visva ūdityā vasavas ca devāh (sarve),

viśvam satyam krnuhi vistam astu, 291

višvam bi (ha) ripram pravahanti

989

(°tu) devih, 578

višvakarma rsih, 918 visvakarman bhauyana mām didāsitha (manda āsītha), 511, 579, 840 višvakarmā rsih ("karmarsih), 918 višvakarmā vimanā ād vihāyāh (vimanā yo vyomā, vimame yo vihāyāh, manasā yad vihāyāh), 339 viśvacarsanih sahurih sahāvān (sahiyan), 248, 598 višvatohasta uta višvataspāt (°tah syāt), 867 višvantu (višvam tu) tvām āhutavaš (tvähutayah) . , 371, 825 višvapsnyā (°sniyā) višvatas parī, 791 višvam id dhitam (dhitam) anasuh (āśata), 545 višvarūpā šabalīr (šavaly) agniketuh, višvalopa višvadāvasya tvāsañ juhomi, 151, 835 višvavidam (°do) vācam avišvaminvām (aviśyavinnām), 236, 410 višvavyacā isayantī subhūtih ("tā), 599 višvasmāt sīm aghāyata uruşya, 379 višvasmād devakilbisāt, 216, 818 višvasmai bhūtāyādhvaro 'si (°dhvaro astu devāh, bhūtāya dhruvo 'stu [astu] devāh), 802, 836, 908 viśvasya te viśvāvato vṛṣṇiyāvatah tavāgne vāmīr anu samdṛśi viśvā retānsi dhişīya, 688 viśvasya devi mrcayasya (mrśa°) janmanah, 195 višvasyām viši pravivišivānsam (pravivišānam) īmahe, 808 viśvā agne abhiyujo vihatyā (°tya), 457 viśvā amīvāh pramuncan mānusībhih (°şebbyah), 357, 695, 783, 832 viśvā āśāh pramuñcan mānuşīr bhıyah, 357, 783, 832 viśvā āśā dakşınasat (°sāt, daksınatah, dakşınadhak), 499 viśväh pinvathah (°tha) svasarasya

dhenäh, 379

vam, 191

viśvāksam (viśvākhyam) viśvaśambhu-

viśvam hy asyam bhuvanam aviveśa.

viśvādityāh, 989 viśvā deva prtanā abhişya, 380 višvā dvesāńsi taratı svayugvabhıh (sayug°), 364 viśvādhiko (viśvā dhiyo) rudro maharşıh (°rşıh), 918 višvāny anyo bhuvanā jajāna, 862 viśvāny anyo bhuvanābhicaşte (°nā vicaste), 220, 808 viśvany aryo bhuvana jajana, 862 viśvanyo bhuvana vicaste, 220, 808 viśvābhyo mā nāstrābhyah (°bhyas, danstrābhyas) pāhi (pāta, parīpāhi), 964 viśyā mrdho abhimātīr jayema, 205, 375 viśvāvasum namasā girbhir Ide (iţţe), višvāvasur abhi tan no grnātu, 172 viśväś ca deva (devah) prtana abhisyah (°syak), 380 viśvā sprdho abhimātīr jayema, 205, višve devā udicvām tu abhisincantu śrevase, 512 viśve devā nātividhyanti sarve (śūrāh, sūrāh), 278, 285 viáve devā mama árnvantu vajūivāh (vaiñam), 321 viśvebhyas tvā devebhyah pravrhāmi jāgatena chandasā, 212 višve šumbhantu mainasah, 173 viśvesam devanam priyam patho 'pihi (apIhi), 910 visvair devai rātibhih samrarānah (devai rtubhih samvidānah), 627, 665 vişāne vi şya guşpıtam (gulphitam), vişe vişam aprkthāh (aprāg apı), 657, 843 vişkandham enam visrtam prajāsu, 986 vişthitāh (°tā) pṛthivīm anu, 381 vişna (vışnav) urukram° vişnum vācam sarasvatım, 156 vişnur aprītapā apyayyamānah, 355. vişnur upāvahrıyamānah, 117 vişnuh sipivişta üräv (ürā) asannah, 888

vişnus tryakşarena trini lokan (trin imāni lokān, trīn lokān) visnuh sambhrivamānah. 117 visnūvarunā (°nāv) abhišastipāvā (°pā vām), 826, 888 visnoh šipre sthah, 337 visnoh śnaptre (śnyaptre) sthah, 337 vişno (vişnoh, vişnos) stupo (stūpo) 'sı, 563, 977 vişno (vişnoh, vişnos) sthānam asi, 977 višvak satyam krnuhi cittam esām, 291 vi sakhyānı srjāmahe ("hai, visrjāvahai), 710 vı senābhir davamāno (bhava°) vi rādhasā, 177 viskandham enam vidhrtam prajāsu, visrutayo (vi sru°) yathā pathah, 30, vihāyaso 'dhi bhūmyām, 699 vidu (vilu) cid ārujatnubhih, 271 vidu chapathajambhanih, 272, 381 vidvir vāmann avardhavan, 360, 544 vīnāganakinah pūrvaih (°ganaginah purānair) . . ., 48 vīnāganakıno (°ganagino) devair vity arsa canisthavā (panistave), 86. 162 vīram hi vīravatah suševā, 123 viram janayişyathah (°tah), 91 viram dhatta (me datta, no datta) pitarah, 103 vīrasūr devakāmā syonā (°sūr devṛkāmā, "sūr jīvasūr devakāmā syonā, °sūr jīvasūr jīvapatnī), 633 vīrān nah pitaro dhatta, 103 vīrān mā no rudra bhāmīto (°mino) vadhih (ba°), 209, 871 vīrān me pitaro (tatāmahā, pratatāmahā) datta, 103 vīruc chapathayopanī, 272, 381 vīrenyah kratur indrah sušastih, 272, 360, 383, 600 vīrebhir adhī tan no grnānah, 172 vīrebhir aśvair maghavā bhavā (bhava) nah, 448

vīrebhir vīratamā šavisthā. 323. 849. vīryam kuhābhyām (gu°), 49 vīryebhir vīratami. savisthā (saci°). 323, 849, 866 vilu, see vidu . . . vivadham (°dhas) chandah, 516 vīvarto 'stācatvārinšah (astā°), 516, 910 vihi sūra (sūra) purodāšam ("lāšam). 271, 284 vīhi svām ābutim juşāno manasā. 836 vīhi svāhāhutim juşānah, 836 vrjite pari vrādhi nah, 360 vrtratūr no (no) abhayam sarma yansat, 949 vrtratūr no (no) vajūam ihopavāsat. vṛtrasya kanīnikāsi ("nakāsi), 235, 595. 640 vrtrasyāsi kanīnakah (kanīnikā), 235, 595, 640 vrtrāni vrtrahan ("han) jahi, 936 vrsajūtir no 'vrtah ('vitā), 640 vrsanam prtsu (prksu) sāsahim, 140 vrşanah samidhimahi, 501 vrsabham naryāpasam, 359 vrsabhāya gavayī, 359 vrsabhena gāvah (gāh), 359 vrsabhena tvastā, 359 vrsabho gaur vayo dadhuh, 359 vrsabho 'si svargah, 359 vrsānah samıdhīmahi, 501 vrsā dharmāni dadhişe (dadhrişe), 350 visā na kruddhah patayad rajassv (rajahsv) ā, 971 vṛṣā pavitre adhi sāno avye (avyaye), vrsā punāna āyuşu (āyūnşi), 304, 555 vīsāyamāno 'vīnīta (avīno) somam, vrsāva cakradad (°do) vane, 581 vrso acikradad vane, 581 vrstidyāvānam amṛtam svarvidam, 803, 820 vrstim dıvah pari srava, 200 viştim devânām amṛtam svarvidam, 803, 820 venubbāram girāv (girā) iva, 888

vedhām ašāsata šrīve, 230, 508 vešantābhyo dāšam, 708 vessárir (*árir) ası, 528 vairājī (°je) purusī, 695, 876 vaivasvato no abhayam kṛṇotu, 699 vaišantābhyo baindam, 708 vaišvānara uta višvadāvyah, 699 vaišvānarah pratnathā nākam ārubat (°ha), 401 vaišvānaram kṣaitrajityāya (kṣetra°) devāh, 707 vaišvānaram rta ā (rtāya) jātam agnım, 36, 342 vaišvanaraya matir navvasī (°se) šucib. 695 vaišvānaro angirasām ('neirasām, angirobhyah), 907 vaišvānaro adabdhas (no adabdhas, me 'dabdhas, 'dabdhas) tanupah, 907 vaihāyaso 'dhi bhūmyām, 699 vauşat (vauşal), 271 vyakrda vilobita, 168, 353, 675, 734 vy akhyan (aksan) mahiso divam (mahişah svah, °suvah), 190 vyacssvatīşayantī subhūtih, 599 salilasya (sarirasya) vyacyamānam madhye, 264 vyantu devā havişo me asya, 796 vyantu devir ya rtur janinam, 796 vyantu vayo 'ktam (ripto) rihānāh, 96, 796, 857 vyantv ājyasya, 796 vy amīvāh pramufican mūnuşūņām, 783, 832 vy asau yo asmān ('smān) dveşti yam ca vayam dvişmah, 910 vv astabhuā (aska°, aşka°, aşta°, askabhnād, astabhnād) rodasī visnav (vişna, vışnur) ete, 137, 889, 983 vy asya yonim prati reto grhāna. 116, 341, 354, 363, 819 vyāghram maūgīradāsa gauh, 49, 279, 824 vyāghro adhi vaiyāghre, 907 vyäghro vaiyäghre adbi ('dhi), 907 vy anad (anal) indrah pitanah svojah, vyanaših (°šī) pavase soma . , 5292

vyuksat krūram ud acantv āpah, 53 vv uchā duhitar divah, 724 vy usridho asro adrir bibheda, 618 vyrddhyā (vyrdhyā) apagalbham (apra°), 353 vyomā (°ma) saptadašah, 460 vy aucho duhitar divah, 724 vratam gacha gosthanam (gosthanam), 986 vratam raksantı vısvahā, 477, 511 vratānām vratapate (°patayo) vratam acārisam (acārsam), 754 vratāni (vratā nu) bibhrad vratapā adabdhah (adabhyah), 487, 627, 823 vratā raksante višvāhā, 511 vrīhīnām medha (medhah) sumanasyamanah, 380 vrešīnām tvā patmann ādhūnomi, 363 śam yor abhi sravantu (śra°) nah, 275 śam rātrī ("ih, "ih) prati dhīyatām, 381, 528 śansya paśūn me 'jugupas tān me pāhy eva. 548 sakalyam, 319, 490 sakma yat te goh, 47, 287 šakrāya sunavai (°ve) tvā, 705 <u>śamgayī</u> ("gavī, °gaye) ıīradānū (jīva°), 255, 266, 695 śacyā paśyanti sūrayah, 158, 287 śacyā harī dhanutarāv (°rā) atasta. 888 śandāva tvā. 289 sanderathas sandıkera ulükhalah, 244, 489, 544 šatam yasya subhvah (subhuvah) sākam īrate, 789 šatam yo nah šarado ajītān (ajījāt, ajīyāt, jījān), 192 śatam hemantāti ("tān) chatam u vasantān, 937 šataksaraš chandasānustubhena. 511. śatam jīvema śaradah sarvavīrāh (savīrāh. su°). 612 śatamūlā (°lāh) śatāñkurā (°rāh), 381 šatam pavitrā vitatā hy (vitatāny) äsu, 849 satam purbhir yaviştha pāhy anhasah (vavisthya), 315

śatena pāśair abbi dhebi varunainam (pāśair varunābhi dhehi), 845 śatotave 'bhimātisāhe (abhi"), 907 amitrahanam śatruhanam tvendram vairam . 712 satruhanam ası. tvaindram vairam śam te prusvāva šīvatām, 680, 876 śam te methi bhavatu śam yugasya trdma, 529, 650 šam te santv anūpyāh, 151 sam te hiranyam sam u santv (sam u śanty) apah. 277, 278, 802 śam tokaya tanuve (tanvai) syonah, 705, 793 śam nah (nas) karato aśvinā, 964 śam nah santv anupyāh, 151 śam no bhavantv āpa oşadhayah (apa osadhīh) sivāh, 498 śam no bhava hrda a pita indo (indro), 353 śabalı prajanam śacistha vratam (śavisthā vrajam) anugesam . 157. 866 śam agnir agnibhis (°bhih) karat, 966 śam adbhyah, 280 śamibhih śamyantu tvā, 528, 572 śam u te santv anūkyāh, 151 śam u prsthava (prsvava) śivatam, 680, 876 śam u santv anūpyāh, 151 śam ūdho romaśam hathah, 91, 276 šam padam magham rayīşine na kāmam (rayışanı na somah), 545, 579 śambhūr (°bhur) mayobhūr abhı mā vāhi svāhā, 554 śam methir bhavatu śam yugasya

tardma, 529, 650

ratām iha). 155

775

145

śamyāh prataratām (°tā) iva (praca-

śarad dhemantah suvite dadhāta ("tu),

śarad varşāh suvitam (sukrtam) no

śarabham te śug rchatu (te ksut),

astu (svite no dadhāta), 775

šatāksarachandasā jāgatena, 511. 819

śatāpāsthādya vişū (°sthā gha vişā)

parı no vrnaktu, 86, 198, 838, 868

śara vastad dhavisa varņah, 86. 198. 838, 868 éariram yaiñasamalam (yaiñah samalam) kusidam ... 383, 818 śariram me vicarsanam (vicaksanam, °na), 857 sarau parnam ıvā dadhat, 278 śardhāńsy agne ajarām (ajarasya) dhaksatah (dhaksyase), 332 sarman ("mans) te svāma trivarūtha udbhau. 932 śarma yachātha saprathah ('thāh). 460, 502 šarma varmedam ā bhara (varmaitad ā hara), 117 šarmā (°ma) saprathā āvīņe, 460, 502 śalmalir viddhyā (iddhyā), 360 śavasa hy asi śrutah (śritah), 626 šavisthā stha rūstradūh, 349 sasvatibhyah samübhyah, 491 šašvat parikupitena (°pilena), 878 śaśvad viśah (diśah) savitur daivyasya, 4ākalam, 319, 490 šākvarā vṛṣabhā ye svarājah, 359 śändikera ulūkhalah, 244, 489, 544 śāmā sarūpamkaraņī, 337 śūradena rtunā (°partunā) devāh, 919 śūrgah srjayah śayāṇḍakas te maitrāḥ, 315, 489 šāšvatībhyah samābhyah, 491 šiksā ņo (no) asmin puruhūta yāmani, śitibhrayo (°bhruyo) yasünām, 604 sıpıvişta ürā āsādyamānah, 888 sımāh (sımām) kravantu sımyantah, 278, 572 šimibhih (šimi°) šimyantu tvā, 528, 572 śırahpānıpādapārśvapṛṣṭhorūdarajañghasisnopasthapāyavo (°pṛṣṭhodarajangha") me sudhyantam, 475 sırah-sırah pratı süri (sıro devi pratı sūrir) vi cașțe, 529 śilpā vaiśvadevīh (°vyah), 598 šilpās trayo vaišvadevāh, 598 šīva ītasya . , see šīvā rutasya śivam prajābhyo 'hińsantam (ahińs') prthivyäh sadhasthäd (°sthe) agnım ('gnim)., 910

śivan agnin apsusado hayamahe, 285. 849, 924, 927 śiva no bhavata ("tha) jivase, 90 bivā rutasya (rudrasya, biva rtasya) bheşajî (°jā), 60, 355, 597, 684 śivű viśväha bhesaji (viśváhabhesaji, °ābā bhe°, °āha bheşajā), 477, 511, 598, 817 śivebhir arcibhis tvam (°bhis tvam), śivo asya nisangatih, 77, 93, 98 śivo me saptarşīn (sapta ṛṣīn) upa tisthasva (tistha), 919 āišīrāya vikakarān (vikarān, vikirān, vikikirān), 489, 573, 813 šišīte šrūge raksase (raksobhyo) vinikse (vinakse, viniksve), 370, 577 šišum padīnām harim adribudhuam (°buddham), 415 śiśū kridantau pari yāto adhvaram (arnavam, 'rpavam), 907 šīte vāte punann ıva (punarnıva), 833, 862 sukesu me harımanam, 30, 278 gukram vām anyad rajatam (yaj°) vām anvat, 244 śukram te anyad yajatam te anyat, 244 šukram na jyotir amṛtam dadhānā (°nāh), 381 šukraš ca rtapāš cātyanhāh, 919 śukraś ca śuciś ca graişmāv (°mā) rtū, 888 śukras te grahah (grahyah), 325 šukrām vayanty asurāya nirnijam, 579, šukrāya svāhā, 262 šukrā vi yanty asurāya nirnīje, 579, 828 suklāya svāhā, 262 śucanto agnim vavidhanta (vā°) indram, 469 śucir ankte (ante) śucibhir gobhir agnih, 418 sucih sukre ahany ojasinā (ahann ojasine, śukro ahany ojasye, śukre 'hany ojasinām), 907, 928 śutudri stomam sacatā paruşny ā (parusniy ā), 777 śuddhah pūta bhavata (°tha, bhav-

antu) yajniyasah, 90

śuddho mamaddhi somyah (°ya), 380 śraddhe kam indra carato vitarturam (vicar°), 156 sunam vähäh sunam narah (nārāh), 491 śramena lokāna tapasā piparti (biśunam ma istam śunam śāntam (śrānbharti), 112 tam) sunam krtam bhūyāt, 287, 353 śunām agram suvīrmah (subīransh), fravas ca me frutis ca me. 486 śravisthāh stha, 349 219, 593 śravo devasva sānasim (°sı), 421 śunddhi (śundhi) śiro māsyāyuh pra śravaś ca me śrutiś ca me. 486 moşīh, 173, 389, 418 sundhatām lokah pitrsadanah, 173 śriyam vasānaś carati svarocih (°cāh). sundhantām lokāh pitrsadanāh, 173 sundhi siro, see sunddhi ... śriye (śriyai) putrāya vedhavai (vettavai), 98, 705 áundhvur (°yūr) ası mārjāliyah, 554 sumbhantām lokāh pitrsadanāh, 173 śriyo vasanaś carati svarocib, 599 sumbham mukham mā na āyuh pra śrinana apsu mrnjata (vrnjate), 234 śritas tvam śrito 'ham, 677 mosth, 173 sumbhānas tanvam (°vām, tanuvam) śriś ca te laksmiś ca patnyży ("nyž) svām, 287, 420, 618 [aho°], 888 śruta rsim ("tarsim) ugram abhimātisśūdrāryāv (°ryā) aspyetām, 888 śūrāso ve tanūtyajah (tanu°), 554 ăham. 919 śrutakakso aram ("kaksāram) gave, 836 śūro na mitrāvarunā gaviştişu, 284 śūro nrsātā śavasaś (śra°) cakānah śrutam me mā pra hāsih, 353 (ca kāme), 181, 349, 828 śrutkarnāya kavaye vedyāya, 109, 230 śrnihi (śrnāhi) viśvatah prati (°tas śrudhi śruta śraddhivam (śraddheyam) pari), 598, 964 te vadāmi, 248, 692 śrnvanty (°tv) āpo adha ('dhah) ksarśrustī ("te) jātāsa indavah svarvidah. antih, 382, 907 śrnyanty apo dhisanaś ca devih ("sana śrestho ha (hi) vedas tapaso 'dhijātah. ca devi), 381 578 śrtas tvam śrto 'ham, 677 śronibhyam (śroni°) svaha, 529 śeşo (śepo) vājinena, 872 śrotram dehi (dhehi), 103 śaiśirāv (°rā) rtū abhikalpamānāh, 888 śrotrapah (°pa) śrotram me pahi śaiśirena rtunā ("nartunā) devāh. 919 (pātu), 980 śokāt pṛthivyā uta vā divas pari, 126 śrotram mayi (me) dhehi (dāh), 103 śocasya devayitamah ("vittamah), 398. śvātrāh pītā bhavata yūyam āpah, 287, 352 śocat prthivya uta va divas pari, 126 śvävrt tat, 277 śociskeśam (śocih°) purupriya, 962 śvitra adityanam, 195, 369 śaundikeya ulūkhalah, 244, 489, 544 śvitro raksıtā, 195, 369 śaunakam (°kim), 590 švetāya vaitahavyāya (vaidarvyāya, śyāmā sarūpamkaranī, 337 vaidarvāya, vaidārvāya) . 63, 315, šyenasya patram (pattram) na plihā śacibhih, 390 șad 1d yamă (udyamā) ţşayo devajā śyenasyeva dhrajato (dravato) añıtı, 627, 819 kasam pari, 109 şandāya tvā, 289 śycne paritto (parito) acarac ca vāte, şan morvīr anhasas (°sah) pāntu . , śyene väta uta yo 'carat parīttah, 404

śrad asmai naro vacase dadhātana, 704

şaştım (şaşthım) sahasrā navatim ca

kaurama, 87

sa ācāryam tapasā piparti (bibharti), sa idhāno vasus (vasuh) kavıh, 693, 967 sa ımam devah püşä, 996 sa ımām devo aryamā (adhvarah), 996 sa ımam devo varunah, 996 sa ımām no havyadātım jusānah, 996 sa îm pāhī ya rjīsī tarutrah (tarudrah). sa īm (i) mandrā suprayasah (mandrāsu prayasah, mandrā suprayasā stariman), 307, 374, 830, 839 sa u (uv) ekavińśavartanih, 774 sa ugrah sa hi (1) havyo babhūva, 386 sa edhāno vasus kavīh, 693, 967 sa eva jātah sa janışyamānah, 829 sam yajñapatır (yajamāna) asışā, 306 sam vāv apnastho (yā apnahstho) apaseva janān, 888 samvopayanto duritāni visvā, 113 samlobhayanto duritā padām, 113 samvatsara rtubhih samvidānah (°bhis cākļpānah, "bhis cākupānah), 39, 645 samvatsarasya tejasā (dhāyasā), 98, samvatsarāya parykymīm (°yārmīm), 244 samvrd ası, 306 samveśāyopaveśāya gāyatryai (°triyās) 'bhibhūtaye ('bhūtyai, 'bhṛtyai) svāhā, 644, 791 samsıtam kşatram pışnu (kşatram ajaram astu jişnuh, kşatram me jişnu), 381 samsıştam ubhayam kıtam (abhayam kratum), 609, 664 samsıştasu yutsv ındro gaņeşu, 612, 660, 826 samstup chandah, 306, 984 sam sravantu diśo mahih (mayı), 256 , see samsrāva° samsrayabhāgā samsraștă sa yudha ındro ganena, 612, 660, 826 samsrāvabhāgā (samsrava°, °bhāgāh, °gūs) sthesā (tavisā) bihantah, 96, 375, 486, 747, 977 samhitāsi visvarūpā (°pī, °pīh), 381, 597

sakhāvau saptapadāv abhūva (°padā babhūva), 207 sakhā sakhibhyo varīvah (varīvah) krnotu, 249, 541a sakhā saptapadī ("dā) bhava, 597 sakhāsi gāvatram chandah, 70 sakhāsı ("sı patvā) jagacchandāh. 70 sakhā suševo advayāh (°vuh), 620 sa gavatrva (*triva) tristubha sagme te goh, 47, 287 sa ghā no devah savītā sahāvā (savāva), 250, 269, 868 saghāsı jagatichandāh, 70 samkasuko vikasukah, 605 samkusuko vikusukah, 605 samkrośān prānaih ("krośaih prānān), sam grbhāva purū (puru) satā, 555 sam grāvabhir nasate (vas°) vīte adhvare, 853 samghoṣān (°goṣān) prānaih, 46, 292 sacāvahe (chai) yad avrkam purā cit, 710 sacetasāv (°sā) arepasau, 180, 376, sacetasau druhvano yau nudethe, 156, 305, 371, 634, 684 sacetasau saretasau, 180, 376 sacyutım jaghanacyutım, 874 sajātānām śraisthya ā dhehy enam, 612 sajātānām madhye śraisthyā ā dhehi sajūr abdo (abdā) ayavobhih ('yāvabhih, ayavabhih, ayavobhih), 471, 485. 910 sajūr devair vayonādhaih (vayu°), 719 sajūh sūra (sūrya) etašena, 318 sajoşasāv (°sā) aśvinā dansobhih, 888 salosa indra (indrah) sagano marudbhih, 380 salosā vīsabham patīm, 376 samjayan kşetrānı sahasāham ındra, 941 samıñānam nah (na) svebhyah (svebhih, svaih), 980 satatam tu śirābhis tu, 263, 306 satayasemam yajñam divi deveşu dhat-

tam, 364

satām šikyah (śak°) provācopanisat, 571 satāsatī prajāpatīh, 347 sa tū (sato) dhanam kārme na pra vansat, 723, 831 sato vah pitaro desma, 60 sattvānām pataye namah, 392, 494 satvam vadanty anv icha (anu yacha) etat, 738 satyam vrsan vrsed ası, 254, 830 satvam it tan na tvāvān anyo asti ('st1), 909 satyam pürvair (°vebhir) rşıblılı samvidānah (°bhis cākļpānah, °bhis cākupānah), 645 satvas ca rtapās (cartapās) cātyanhāh, 919 satyasatī prajāpatih, 347 satyasya dharmanas pati (pate), 695 satyā esām (etā) āśisah (csas) santu , 971 satyā tā (satyād ā) dharmanas patī (dharmanā, "nas parı), 65, 525, 837 satyanrte avapasyan ("yan, "yan) janānām, 936 satyaujasā drohanā (durhrnā, drhanā) yam nudethe, 156, 305, 371, 634, 654, 684 satrā dadhānam apratiskutam sayānsi (śravānsı bhūri), 349 sa tvam vrsan vrsed ası, 254, 830 sa tvam sanım suvimucă vimunca. 830, 871 satvanām pataye namah, 494 sa tvam asy amo 'ham, 723, 907 satvānām pataye namah, 392, 494 sa tvā manmanasām karotu (°sam krnotu), 494 sa tvā rāstrāya subhrtam bibhartu (pipartu), 112, 175, 639 sa dahan (sadanān) pradahan nv (v) agāh, 392, 829 sadā pašyantı sūrayah, 158, 287 sadā yācann aham girā (1yā), 134, 244 sa dāšuṣe kıratu bhūri vāmam, 306 sa dundubhe sajūr indrena devaih, 306 sado vah pitaro desma, 60

sado vanesu dadhişe (dadhrişe), 350

sadvahkrīš chandasā saha, 491, 962 sadyā no devah savītā savāya, 250, 269, 868 sa nah pito madhumān ā višeha (viveśa), 849 sa nah pṛthu (pṛthuh) śravāyyam, 381 sanim gäyatram navyänsam (naviyānsam), 786 sa nirudhyā nahuso (nahrso) yahvo agnih, 642 sa no tivesy a vame, 394 sa no dadātu tam (tām) ravim. 505 sa no divā sa risah (risas) pātu naktam. 964 sa no devesy ā yamat. 394 sa no dohatām suvīryam (suvīram), 323 sa no bodhi śrudhī (°dhi) havam, 518 sa no mayobhūh pito āvišasva (pitav āvic, pitav āvišeha, pitur āvivesa, pitevāvišasva), 849, 890 sa no rāstresu sudhītām dadhātu. 175. sa no rucam dhehy ahrniyamanah. 387. sam takṣā hanti cakrī vah (cakrinah), samtatam śirābhis (śil°) tu, 263, 306 sam te rāştram anaktu payasā ghrtena, 139, 618 sam tvā rnanti, 676, 992 sam tvä tataksuh (tataksnuh), 311 sam tvā rinanti, 676, 992 sam tvā šišanti (šis°), 292 samdānam arvantam padbīšam (°višam), 217 sam dāśuşe kiratu bhūrı vāmam, 306 sam dundubhe sajūr indrena devaih, sam devi (devī) devyorvašyā pašyasva (°vasyākhyāta), 525 sam devena (daivena, daivyena) savitrā, 317, 707 samdhātā samdhim (°dhir) maghavā

puruvasuh (puro", puru"), 551, 717,

samdhvānā ("dhuvānā) vātā abhi no

gmantu, 783

sanyan sanım suvimucă vi muñca, sapatnā vācam manasa (*sā) upāsatām. sapatnīr abhibhūvarī (°rīh), 381 saputrikāyām jāgratha, 90, 662 saptarşayah sapta dhāma privāni, 919 saptarşayo 'srjyanta, 919 saptarşīnām sukrtām yatra lokah, 919 saptarşîn jinva, 919, 936 sapta ca mānusīr imāh. 701 sapta ca vărunîr (vărunair) imah (ımān prajāh), 701 sapta yonir (yoninr) aprnasva (°sva) ghrtena, 446 sapta rājāno ya udābhişiktāh, 63 saptarşayah sapta dhāma priyānı, 919 saptarsayo 'srjyanta, 919 santarşın jinva, 919, 936 saptarşīnām sukrtām yatra lokah, 919 sa prathamah samkrtir visyakarma. 374 sapratha (°thah) sabhām me gopāya (pāhi, 'jugupah), 381 sa bibheda valam (balam) magham (madyam), 210, 868 sa budhnyā ("niyā) upamā asya visthäh, 784 sa budhnyād ("nād) āṣṭa januṣo 'bhy (°şābhy) agram, 325 sa bhakşamāno (bhikş°) amṛtasya cārunah, 583 sa bhūmim višvato (sarvato) vitvā (sarvata spṛtvā), 200, 375 sam agnis tapasāgata, 379 sam adbhyah, 280 sam arīr (arır) vidām (vidah), 529 sam arvanto raghudruvah (odrucah), 866 samavayantu sarvatah, 63 samānam keto abhisamrabhadhvam (ceto abhisamvisadhvam), 126 samānamūrdhnīr abhi (adhi) lokam ekam. 172 samīnā vā (va) ākūtām, 598 samānī va ākūtıh, 598 sa mā mṛta (vṛtat), 98, 225 samıngayati sarvatah, 536

sam it sravantı santo (°tā) na dhenāh, 142, 735, 830 samıd dıśām āśayā nah (āśayānah) svarvit (suvar°), 826 samıddhe agnāv (agnā) adhi māmabānah, 888 samiddho aguir vṛṣanāratir ("ṇā rathī, °nā rayır) dıvah, 93, 545, 877 samıdhah-samıdho 'gne-'gna (-samidho agna, "gnā) āivasva vvantu. 910 samidho agna ājyasya vyantu (viyantu), 796, 910 samidhyamānah prathamānu dharmā (prathamo nu dharmah), 835 sam ındra no (no) manasā neşi (neşa) gobhih, 584, 950 sam īm rebhāso asvaran, 307, 628 samingayati sarvatah, 536 samīcīnāsa āsate (āšata), 282 samudra ıväsı gahmanā (ganh°), 305 samudram na subhvah svā abhistavah. 384, 789 samudram na suhavam (suhuvam, subhuvas) tasthivānsam, 119, 384, 604, 789 samudrasya tvāvakayā (tvāvā°), 496 samudrād udajani vah (udacann iva) srucā, 53, 383, 401, 840 samudrāya šišumārah, 305, 551 samudrena (samudre na) sındhavo yādamānāh, 826 sam u rebhāso asvaran, 307, 628 samuhyo 'si viśvabharāh, 560 samūdham (samūlham) asya pānsure (°le), 261 sam ūdho romašam hatah, 91, 276 samūhyo 'si višvabharāh, 560 samūhyo 'sı vıśvavedā , 560 sam eta višvā (°ve) vacasā (ojasā) patim divah, 52, 804 sa me mukham pra mārkşyate (veksyat1), 235 samokasāv (°sā) arepasau, 180, 888 samokasau sacetasā arepasau, 180, 898 sampasyan panktīr (pantim) upatisthamānah, 418 sam pūṣā (pūṣā sam dhātā) sam brhaspatsh (dhātā), 720

samprea ("cah, "cas) stha ..., 977 sam posā sam brhaspatīh, 720 sampriyah pasubhir bhava (bhuvat). 602 samprıyam prajayā pasubhır bhuvat, 602 sam bāhubhyām dhamati (bharati, namatı, namate, °bhyām adhamat) sam patatraih (yajatraih), 157, 176, 853, 867 sammā ası (sammāsi), 993 sammışlo aruşo bhava (bhuvah), 602 samyak sravant: samto na dhenāh, 142, 735, 830 samvat te goh, 47, 287 samrājāv (°jā) asya bhuvanasya rājathah. 888 samrājāi švašīvām (švašruvām) bhava, sa yajñapatır asışa, 306 sa yathā tvam rucyā roco 'sy evāham rucisīva (rucvā rocasa evam aham rucyā rocisīya), 715 sa yo vrşā vrşnyebhih (°niyebhih) samokāh, 784 sarasvatī tvā maghavana abhişnak (abhīşnāt), 142, 545 sarasvatīm asvināv (°nā) indram agnun. 888 sarasvatī (°tīh) syapasah sadantu (sadantām), 381 sarasvatyā adhī manāv (mānā, manā, vanāva) acarkrsuh (acakro, carkṛdhi), 170, 225, 356 sarasvatyām adhi manāv acarkṛṣuh. 170, 225, 356 sarasvatyā (°tyāh) supippalah, 381 sarasvatyaı püşne 'gnaye (agnaye) svāhā, 910 sarasvatyai yasobhaginyai (vesabha°) gyāhā, 255 sarasvatyai vāco yantur yantriye (vāco yan turye turyam) dadhami, 840 sarāh patatrinīh sthana (stha), 381, 600 sarā patatrinī bhūtvā, 381, 600 sant sravanti santo na dhenah. 142.

735, 830

sarıram chandah, 264 sarirāya tvā vātāya svāhā, 264 sarırāva svāhā. 264 sarire tvā sadane sādayāmi, 264 sarūpavarsā ehi (sarūpa vṛṣann ā gahi), 650, 821 sarau parņam īvā dadhat, 278 sarnīkāya tvā, 651 sarpadevajanebhy ah svāhā, 198 sarvatah sarvasarvebhyah (sarva sarv°, sarva sarv°), 285sarvadevajanebhyah svāhā, 198 sarvam tam bhasmasā (masmasā) kuru, 242, 294, 632 sarvam ni svāpayā ("yāj) janam, 402 sarvam uktam anuvidur vasisthäh, 139, 627 sarvam manişāna, 829 sarvalokam ma ışāna, 829 sarvasmād devakilbisāt ("visāt, eva kılb°), 216, 402, 818 sarvah sarvā vi caratu prajānan, 354, 831 sarvān agnihr apsusado huve (huve vah), 285, 849, 924, 927 sarvāń apa yajāmasi, 201, 924 sarvān it tān anu vidur vasisthāh, IC' 627 sarvāns tān mrsmrsā (masmasā) kuri, 242, 294, 632 sarvā dāmāni (dhā°) muncatu, 107 sarvān ava yajāmahe, 201, 924 sarvān ni masmasākaram, 242, 294, 632 sarvān patho anrnā ā ksīvema (ksi°), 536 sarvān sa devāns tapasā piparti (bibhart1), 112 sarvābhvo abhayam ('bhayam) karat. sarvā vinudya samtrdyah, 170 sarvās ca rājabāudhavīh (°vaih, °vyah), 490, 701 sarve rādhyāh stha (rādhyās tu) putrāh, 96, 616 salılam chandah, 264 salılah salıgah sagaras te na adıtya havişo juşana vyantu syaha, 49, 686,

796

salılaya tvā (tvā vātāya svāhā), salılāva svāhā. 264 salıle tvä sadane sad ıyami, salıle sadane sīda, 264 sa vah sarvāh sam caratı prajānan. 354, 831 sa vijāyamānah sa janişyamānah, 829 savıtā jyotir ud ayan (ayan) ajasram, savıtā te hastam agrabhīt (agrabhīd asau, agrabīt), 116 savitā bhrtyām, 242, 634, 871 savitā manyām, 242, 634, 871 savītā hastam agrahīt (agrabhīt), 116 savitus tvā ("tus tvā) prasava . , 958 brhaspataye (vrh°) savitrorasūtā stuta, 215 indrenasme savitrā prasavitrā , 704 ("smai) (tvarbhu°. savitre rbhumate tvarbhū°) vibhumate (vibhū°) 549, 554, 916, 918 sa viśvācīr (°cī) abhi caşte ghṛtācīh (°c1), 357, 381 savrtā savrte savri jinva, 306 savrd asi, 306 sastup chandah, 306, 984 sasavān san (sam) stūyase jātavedah, sa supranīte (°ti) nrtamah svarād (°rāl) ası, 695 sa sūra ā (sūrye) janayañ jyotir irdram (indrah), 318 saha ojah, 731, 990 sahamānā sahasvatī (saras°), 269 sahamūrān anu daha kravyādah, 355, sahaś ca sahasyaś ca haimantikāv (°kā) rtū, 888 sahasah sūnav (sūna) āhuta, 889 sahasranithah (°nithah) padavih kavīnām, 952 sahasradhāra eva te sam asvaran, sahasradhāram vişabham divo duhuh (divoduham), 821

sahasradhāre 'va te sam asvaran, 989 sahasranīthah, sec sahasranīthah

sahasraposam subhage (°gā) rarānā. 466 sahasraposasyesise, 466 (°valıśā) sahasravalšā VI vavam ruhema, 760 sahasrašīrsā (°sāh) purusah, 381 sahasrasamam prasutena yantah, 233 sahasrasavaprasavena yantah, 233 sahasrasā (°sām) medhasātāv (°sātā) ıva tmanā, 888 sahasrasthūna āsāte (āśāte). 282 sahasrasya pratımāsı (°mā ası), 993 sahasrasya pramäsi (°mā asi), 993 sahasrasyonmäsi (°mä asi), 993 sahasrāksa medha ā (medhāya) cīyamänah, 342 sahasrākso amartyah ("āksāyāmartya), sahasrākso medhāya cīyamānah, 342 sahasrāposam subhage rarānā, 466 sahasrāposasyesise, 466 sahasrāpsāh prtanāsān (°ṣād) na yajfiah, 412 sahasriyo dyotatām (dipyatām, oriyo lyotatām) aprayuchan, 24, 159, 541 sa hi puru (puru) cid ojasā virukmatā, 555 sahojah, 731, 990 saho mayı dhehi (me dāh svāhā), 103 sahaujah, 731, 990 sā tvam asy amo 'ham (amo aham, amūham, āpy amo 'ham), 723, 907 sā dīkşītā sanavo vājam asme (vācam asmāt), 52 sādyaskrīš chandasā saha, 491, 962 sādhah (sādhu) kravantam avase, 609 sādhyebhyah kulungān (kulangān), 607 sādhyebhyaś carmamnam (°mnam), sā nah prajām pašūn pāhy araņīyamānah, 387, 665 sā nah prīyā supratūrtir maghonī, 749 sā nah sravann ütibhih sīda sasvat, sā nah sīte payasābhyāvavṛtsva, 849 sā nah supratūrtih priyā nah suhār nah priyavanir maghavanir antā ebi, 749

sā no dohatām suvīryam (suvīram), 323 sā prathamā samskrtir višvavārā. 374 sā prasūr dhenukā (°gā) bhava, 48, 620, 829 sā brahmajāyā vi dunoti rāstram, 107, 569 sā brāhmanasva rājanva, 870 sā mandasānā manasā šivena, 609 sāmāni cakrus tasarāny otave (oni vātave), 804 să me satvāšīr devān panyāt panyatarā (panyāt panyatarā), 165 sā rāstram ava dhūnute brahmaj vasva. 107, 569 savitro 'si canodhah (janadhayah), 54 sā šamtātı (°tā, °cī) mayas karad apa sridhah, 156, 598 sā samnaddhā sanuhi vājam emam (sunuhı bhāgadhevam), 52, 617 smantı păkam atı (adhı) dhīra eti (em1). 98 sindhoh śinśumārah (śiśū°), 305, 551 sımāh kravantu samyantih, 278, 572 sımāh samyantu samyantih, 278, 572 sIdantu manuso yathā, 227, 719 sīdanto vanuşo yathā, 227, 719 sīrāh patatrinī sthana, 381, 600 sīsam ca me trapu (°puś) ca me, 381 sīsena agnim adya hotāram avrnīta ayam sutāsutī yajamānah pacan paktih . . ., 310 sukarīrā svopašā. 41, 605, 731 sukurīrā svaupašā, 41, 605, 731 sukeşu te harımanam, 30, 278 sukham ca me sayanam ca me, 82 sukham meşāya meşyaı, 82, 705 sugam ca me sayanam ca me, 82 sugam ca me supatham ("thyam) ca sugantuh karma karanah karayan, 293, 384, 573, 609, 739, 824 sugam tvah karmah karanah karah karasyuh, 293, 384, 573, 609, 739, 824 sugandhım patıvedanam, 152, 627 sugandhım puştivardhanam (rayıpoşanam), 152, 627 sugam meşāya meşyaı (°ye), 82, 705

sugā vo devāh sadanā ("nam) akarma (krnomi, sadanāni santu), 741 sugā vo devās sadanedam astu. 741 sucaksā aham aksībhyām (aksi°) bhūyāsam, 528 sucaksāh soma uta sasrud astu. 145. 283. sujätänäm śraisthya ä dhehy enam, 612 sutarası tarase (sutarasıddhatarase) namah, 833 sutah sudaksa dhanya (dhaniya), 764 sutā mavā varadā vandamānā. 419 sudakşā dakşapıtarā (°pıtārā), 500 suditinādītvebhya suditir (sudîtir) ası, 545 sudevam ındre asvinā (ındrāvāsvinā), 342 sunāvam āruhevam, 817 sunītī svayašastaram (suvaš°), 741 suparnapakşāya dhīmahı, 200 suparno avyathir ("thi) bharat, 529a supānih (°nı) svangurıh, 980 supippalā oşadhīh kartanāsme (kartam asmaı, asme), 704 supippalā oşadhīh (°dhīs) kṛdhi, 966 suprasūr dhenukā bhava, 48, 620, 829 subandhum pativedanam, 152, 627 subāhuh svangurih, 980 subirana srja-srja šunaka, 219, 380, 593 subhagamkarani (subhagamkaranam) mama, 486, 820 subhūtakrta stha (°krtah subhūtam nah krnuta), 119, 569, 977 subhūtāya pipīhi (pīpihi), 545 sumitrah soma no (sumano) bhava, 714, 826 sumitrā (°trıyā, °tryā) na (na) āpa oşadhayah santu (°yo bhavantu). 315, 787, 950 sumnāya nunam imahe sakhibhyah, sumnāya sumninī sumne mā dhattam, sumnāyuvah ("yavas) sumnyāva sumnam (°nyam) dhatta, 315, 604 sumne sthah sumne mā dhattam, 315

sugavyam no vājī svašvyam ("viyam),

suyame me adya ghrtācī bhūyūstam svävrtau süpäyrtau, 552, 910 suyame me bhūyāstam, 552 sur abbivyakhyam, 190, 739 surayā mūtrāj janayantı (°ta) retah, 507 surayā somah suta āsuto madāya, 507 surāyā mūtrāj janayanta (°ti) retah, 507 surāyāh somah suta āsuto madāya, 507 suvah ., suvar , suvarga . , 779 (and see under syah etc.) suvarnapaksāya dhimahı, 200 suvarnastainyam avrātyam (avratyam), 490 , 779 **SUVAS** auvān nabhrād anghāre bambhāre 'star ahasta kṛśūno, 146, 405, 778, 809 suvānā devāsa ındavah. 794 suvano arsa pavitra a, 794 suvāno yāti kavikratuh, 794 suvitasva manāmahe (vanā°), 227 suvite mā dhāh, 775 suvīrābhis taratı vājakarmabhih (tırate vājabharmabhih), 152, 582 suvīrmah srja-srja, 219, 380, 593 sušami šamisva (šami°, šamnisva), 531 susimam somasatsaru, 180, 224, 696, 714, 874 susrtam manye tad rtam navlyah, 661 suśevam somapitsaru (sumatitsaru), 180, 224, 696, 714, 874 susrātam manye tad rtam naviyah, 661 suślokyłya svastaye, 724 susadam id gavām asti pra khuda, 67, 347, 986 suşamıddham varenyam, 986 susamiddho na ā vaha, 986 susamiddho varenyah, 986 suşumnah (°mnah) süryarasmıs candramā gandharvah, 954 susatyam id gavām asyasi pra khudasi, 67, 347, 986 susamıddham varenyam, 986 susamiddho na ā vaha, 986 susamiddho varenyah, 986 susaveha havāmahe, 299 susasyāh (susaspāh) kṛṣĩs kṛdhi, 867

suhaveha havāmahe, 299 suhutakrtah etha suhutam karisyatha ("tam akārsta), 119, 569, 977 sücibhih śamyantu (śim°, śamayantu) tva, 572 sūpasthā ası vānaspatyah, 325, 491, 737 sūpasthā devo vanaspatih, 325, 491, 737 sümnäya nünam Imahe sakhibhyah, 563 sūyame me 'dya stam svāvrtau sūpāvrtau, 552, 910 süyavasını manave (manuse, manuse) daśasyā (°ye, yaśasye), 161, 490 sūrāso na daršatāsah. 318 sūro na mitrāvaruņā gavistīsu, 284 sūro na rurukvāň ("vāh) chatātmā, 937 sūro na svayugvabhih (savu°), 364 suro rathasya naptyah (naptryah, naptriyah), 357, 791 sūryatvacasa (°sah, °sas) stha, 977 sürva nāvam āruksah. 715 sürvarasmım samäbhrtam, 118, 639 sūryasya caksur āruham (āroha), 715 sūryasya tapas tapa (tapah), 379 sūrvācandramasau vrkyābhyām (vrkkā°), 408 süryäñ áukram samābhrtam, 118, 639 sūryāvā ūdho 'dıtvā (adı'. adıter) upasthe, 909 sūryāso na daršatāsah, 318 sürye santam (sukram) samāhitam (samäbhrtam), 118, 639 sūrvo apo vi gāhate ('vagāhate), 578 sūryo ahobhir ('hobhir) anu tvāvatu, 907 divo (devo) dıvışadbhyah BŪTVO), 686 ("bhyo sūryo rūpam krņute dyor (dyaur) upasthe, 732 , see sŭryo aho sūryo 'hobhır srkāhastā (srkāvanto) nişafiginah, 48, srgavanto mşangınah, 48, 467 srdikāya tvā, 651 sedam priyena dhāmnā priyam sada āsīda (priyena nāma priye sadası sida), 855 sed u rājā kṣayatı (kṣetı) carşaninām, 745

semām devo aryamā (pūsā, varunah), somi ghosena yachatu (vaksatu), 184, 255 996 somena tvātanacmindrāva dadhi. 127 semām no havyadātım juşānah, 996 somaindrā babhrulalāmās tūparāh, 707. so adhvarā jātavedāh, 907 so adhvarān sa rtūn kalpayātı, 907 728 somo asmākam brāhmanānām rājā. 910 so asmān (asmān) adhipatin karotu, somo vaisnavo rājā (somo vaisnavas) 907, 924 angiraso (ango, angiraso vedo) so asmān pātu sarvatah, 909 so 'dhvarā karati jātavedāh, 907 somo 'smākam brāhmanānām rājā. 910 so 'dhyarān sa rtūn kalpayāti, 907 so 'smān adhipatīn krnotu, 907. 924 soma āyuşmān sa oşadhībhir (sausa°) so 'smān pātu, 909 āvusmān, 996 so 'ham vājam saneyam (sanāmy) soma u suvänah (svänah) sotrbhih, agne (agneh), 381 saujāmim, 28, 192 somah pati ravinām, 964 saumāpauşnāh šyāmalalāmās tūparāh. somam sa . rchatu yo maitasyai (°syā) diśo 'bhidāsatı, 910 somanetrebhyo devebhya uparısadsaumendrā babhrulalāmās tūparāh. bhyo (°sadbhyo) 707, 728 ., 986 somam te krināmy ūrjasvantam payassaumvās travah svitimgāh (siti°), 369 sauvāmım, 28, 192 vantam virvāvantam abhimātīsāham (vīryāvantam bahvargham śobhamāsauślokyāya svastaye, 724 stani mandras suprayakşuh, 374, 381, nam), 123, 467 somavikravın mamoa te 830, 839, 861 mahantam bahyarham bahu sobhastambhanas tanvam svam. 287, 420. mänam, 123 618 somaś caturaksaravāśrīvīr (°srivir) stavāno devyā kṛpā, 421, 824 nakşatrāni, 277 stutah (°ta) śravasyann avasopa madsomas patī rayīnām, 964 rık. 980 somasya drapsam (bhakşam) avrnîta stutā (°to) mayā varadā vedamātā, 419 pūṣā (śakrah), 153a stuto yası (yahı) yaşan anu. 299 somasya rājňah kulumgah, 607 stuto 'sı janadhāh, 54, 93, 375 somasyāham devayajyayā suretā (viśstuhi suram yajrınam apratikam (apravam) reto dhişiya (dhe°), 688 tīttam, °tītam), 138, 404 somah sutah puyate ajyamanah (suta stegān danstrābhyām, 374 rcyate püyamānah), 57, 634 stokā (°kāh, °kāś) ścotanti medasah. somah sutasya madhvah (sutah sa madhumān), 189, 824 stotā me goşakhā (gosa°) syāt, 986 somāpauşnāh syāmalalāmās tūparāh. stotāram id didhişeya (dadhise) radāvaso. 581 somāya kulungah (kulangah), 607 stotrbhyo dhrsnav ıvanah (īvā°), 538 somāya janıvide (jana°) svāhā, 588 stomatrayastrınse bhuvanasya patnı, somāya rājūe kulungah, 607 525, 818 somāya rājāe paridhātavā (°dātavā) stomaprsiho ghrtavan supratikah, 419 u, 105 stomas trayastrinše bhuvanasva patni. somāya vaca udyatam (ucyate), 158 525, 818 somārudrāv (°drā) iha su mṛdatam stomo yajňaš ca (yajňasya) radhyo nah, 888 havışmatā (°tah), 188, 826

staumi devāv (devā) asvinau nāthito 10havim1, 888 strīsūyam anyān sv ā dadhat (anyāsv üdadhat), 702 straisūyam anyatra dadhat, 702 sthirā cin namayisnavah, 857 spātāh prītā bhavata vūvam apah, 287. 352 snusā sapatnā ("nāh) švašuro 'yam astu ('ham asmı), 256, 980 spardhante dhiyah (divah) sürye na (sure na, survena) višah, 109, 255, 318, 826 spārhū yasya śriyo drśe, 198, 761 spārho deva nivutvatā, 198, 761 syonam patye (patibhyo) vahatum krnusva (krnu tvam), 842 syonā māvišaterā madah (°terammadah), 818 syonā (°nāh) syonena ghṛtena mā samuksata, 978, 980 syone kraudhvam surabhā (°bhāv) u loke, 886 srucă juhuta no (juhutană) havih, 827 srucă devam ghrtascută (%cyută), 336 svah , 779 syahpatır yadi vrdhe, 307, 831, 968 svam yonun gacha svāhā, 505 svam vonım ıhāsadah, 505 svagākārakīto mahyam, 466 svagā vo devāh sadanam akarma (°nāni santu), 741 svamkrto 'sı, 505 svatavasemam yajñam divi deveşu dhattam, 364 prthivisadbhyah svadhā pitrbhyah (prthivi°), 524 svadhā pitrbhyo 'ntarikşasadbhyah (antari°, 'ntarī'), 517, 910 svadhitis te (°tiş te) pitā, 958 svapnah svapnadhikarane (svapna syapnābhikaranena), 172, 980 svam ma (ma ıdam) ıştam svam , 287, 353 śrāntam (śrātam) svam ma ıştam astu sunam santam , 353 svayonım gacha svāhā, 505 svar. , 779

svar abhivyakhyam (°kśam), 190, svargāsi, 315 svargena lokena samprornuväthäm, 91, svarge (suvarge) loke prornuvāthām (prornv°, °nuvātām, samprorn°), 91, 779, 797 svargyāsı, 315 svar na gharmah svāhā, 949, 980 svar (suvar) na (na) jyotih (°tih svāhā). 949 svar (suvar) na (na) šukrah svāhā. 949 svar na (suvar na) sūrvah svāhā. 949 svar nārkah (suvar nārkah) svāhā, 949 svar devā (suvar devān) aganma (agama), 304 suvar na gharmah (°ma) svāhā, 949, 980 , sec svar na svarpatim vad im vrdhe, 307, 831, 968 svarmūrdhā vaiyašano vyašyann āntyo 'ntyo bhauvanah, 725 svarmaurdhnyāya svāhā, 725 svar yaj jyotir abhayam svasti, 254, 824 svarvaj jyotir abhayam svasti, 254, 824 svarvido abhi ga adrim uşnan (muşnan, ısnan), 401, 627 svarşām (suvar°) apsām (apsvām) vrjanasya gopām, 370, 780 svasāra āpo abhı gā utāsaran (udā°), 60, 829 svastida äghrnih (agh°) sarvavīrah, 473 svastı nah pathyäkrteşu (putrakıthesu) yonişu, 93, 618, 802 svastı rāye maruto dadhātana (°tu nah), 825 svas (suvas) te dadāmı (tvayı dadhamı), 104 svasty apsu vrjane svarvati (vrajane svarvatah), 658 svām yonım gacha svāhā, 505 svām yonım ıhāsadah, 505 svāmkīto sī, 505 svām cāgne tanvam (tanuvam) piprayasva (piprā°), 480 svā tanūr baladeyāya mehi (baladāvā na ehı), 248

svättam sad dhavir üpo devih svadantu, 371

svättam cit sadevam havyam äpo devih svadutamam, 371

svāduş (°duh) kilāyam madhumān utāyam, 967

svādhyam (°dhiyam) janayat südayac ca, 789

svādhyo (°dhiyo) manasā devayantah, 742, 789

svadhyo (°dhiyo) vidathe apsu jijanan (apsv ajijanan), 789

svāna bhrājānghāre bambhāre hasta suhasta kṛśāno, 146, 405, 778, 809

svāna bhrāt anghārir bambhārih, 146, 405, 778, 809

svānā devāsa indavah, 794

svānair yāti kavikratuh, 794 svāno arsa pavitra ā. 794

svām tanvam (tanuvam) varuno 'suşot

(asisret), 287, 355, 907 svän nabhräd anghäre bambhäre hasta

suhasta kṛśāno, 146, 405, 778, 809 svāyām tanū (tanūn) rtviye (rtvye) nādhamānām (nātha°, bādha°), 22,

76, 308, 784

svāruhā yasya śriyo drše, 198, 761 svāruho deva myutvatā, 198, 761

svāvešo anamīvo bhavā (bhuvā) nah, 602

svāha rşabham ("hā rş", "harş") indrāya..., 918

svähäkṛtasya sam u tṛpnuta ṛbhavah (tṛpnutarbh°, tṛnnutarbh°), 411, 919 svähäkṛtıbhyah (°tibhyah) preṣya, 529

svanakriiddyan ("tiddyan) preşya, 521 svaha tva vatāya vişļisanaye

svāhā tvā subhava ("vah, subho) sūryāya, 381, 749

svāhā tvā sūryasya vṛṣṭivanaye, ., \$57

svāhā pūsne šarase, 691

svīhī yajāam manasah (yajāamanasah), 819

svāhā rājesūyāh (°sūyāya citānāh, °svah), 326

svāhī sam agnis tapasā gafa (gatah), 379 svāhestībhyah ("tebhyah svāhā), 690 svīte mā dhāh, 775

svinnah snätvi (°tvä, snäto) maläd iva, 598a

sviştam no 'bhi vasyo nayantu, 587, 786, 909

sviştanı agne abhı tat praāhı (praīhi, tad graīhi), 153

svistim no abhi ('bhi) vasiyo (vasyo) nayantu, 587, 786, 909

hatal krimīnām kşudrakah (rājā), 96, 262, 386

hatas te atrınā krimih (kr°), 668

hatīh krimayah (kr°) sīśūtikāh sanilamakşikāh, 668

hatāghašansīv (°sā) ūbharadvasū, 888 hatāghašansāv (°sā) ūbhūrstām vasu vāryāni, 888

hatā mātā hatah pitā, 96, 386 hato dāsām satpatī, 91

hato viśvā apa dvisah, 91

hato vṛtrāny āryā (apratı), 91 hato hatamātā krimih, 96, 386

hatho dāsān satpatī, 91

hatho višvā apa dvişah, 91 hatho vitrāny āryā (aprati), 91

hanurhyam (hanu°) stenan bhagavah,

554

hanubhyām (hanū°) svīhā, 554 hayo dātra edhi vayo (mayo) mahjam pratigrahītre (°grhnate), 232, 657 hariknike (°klike) kim ichasi, 273

hariknike ("klike) kim ichasi, 273 harinasya raghusyadah ("syatah), 64 harivato giaham idhyāsam ("vato

graham rādhyāsam), 659 barısmasrum na varmanā dhanarcım, 573, 596, 835

harī ındra pratadvasū abhı svara, 95 harşamānāso dhṛṣitā (dhṛṣatā) marutvah, 122, 596

harşamānā hṛṣitāso marutvan, 122 havanasrun no rudreha bodhi, 488, 554

havir havışşu (havıhşu) vandyah, 618, 971

havis (havih) kṛnvantah parivatsarīnam ("nām, "rīyam), 967 haviṣmān ("mān) astu sūryah, 925

havyāyāsmai vodhave ("vai) jātavedah, 705 hastagrābhasya didhisoh (da°) tavedam (tvam etat), 581 hāvanasrūr no rudreha bodhı, 488, 554 hımkārāya svāhā, 386, 544 hunkītāya svāhā 386, 544 hitvā na ūrjam pra patāt patisthah ("padāt pathi"), 60, 96 hitvā (hitvī) širo jihvayā rārapac (vāvadae) carat, 267, 598a hinva (hinvā) me gātrā ("trāni) harivah, 436, 440 hinvāno mānuşā yugā (yujā), 132 hinvāno hetrbhir yatah (hitah), 256, 579 hıranyanābhah kausalyah, 699 hıranyapakşah sakunıh (°parna sakune), 198, 380, 588, 691 hıranyapāvāh pašum āsu (apsu) grbhnate (grh°), 116 hiranyam astrtam (asrutam) bhava, biranyayāt parī yoner nişadyā ("ya), huanyayāh ("yā) sucayo dhārapūtāh. 381 hiranyayad annayad dhehi (annam adhyehi, annamad dhehi) mahyam. 239, 347, 840 hiranyayarnah sakunah, 198, 380, 588 hıranyavāsir ışıraah svarşāh (suvar^o). hiranye 'smin samāhitāh ('bhṛtāh, °hrtāh), 118, 639 hırısmasrum närvänam dhanarcam, 573, 596, 835 hutam havir madhu havir indratame 'gnau (madhuhavır asındra' 'gnau svāhā), 910 hutah (hutas, huta) stokah, 977 huve nu sakram puruhūtam indram, brtsu kratum varunam (*no) vikşv (apsv. dikşv) agnım, 153a, 360, 579, hrdam na hi tvä nyrsanty ürmayah, 658

hrdisprk kratusprg varcodah (°dha ası), 103 hrdo astv antaram taj jujosat (tad yuyota), 193 hetayas tava bāhvoh, 792 hemantasısırāv (°rā) rtū (rtūnām), 888 hemantāya kakarān (kakārān), 489 hemantena rtună (°nartună) devāh, 919 he 'lavo he 'lavo, 712 haımahāş haımahāş, 124 haumahāz (°hā) idam hairanyanabhah kausalyah, 699 hailo-hailo, 712 hotā yaksat tvastāram acıştum ("tam) . 618 hotā yakşat sarasvatīm meşasya (yakşad ındram rşabhasya, yaksad brhaspatım chāgasya) śromtah (śonıtaś) . 353 hotā yaksad usāsānaktā nřňs (nřah) patibhyo , 965 hotā yakşan narāsansam nršastam nīnspranetram (nīnh°), 965 hotāram agnim antarā vierttāh, 866 hotārāv (°rā) indram ašvinā. 888 hotārāv (°rā) ındram prathamā suvācă, 888 hotā vistīmena (vistvī me) jarītar. 367, 835 hotā vedişad atithir duronasat (dū°). 568 hotrşadanam harıtam hiranyayam, 200 hotrsadanā harītāh suvarnāh, 200 hotrakānām (hotrkānām) camasādhvarvavah . 663 hotrāvidah (°vida, °vidha) stomatastāso arkaih, 108, 640, 972, 977 hradam na hi tvā nyrsanty ūrmayah, 658 hrādunībhvah ("nibhyah) svāhī, 528 hrādunīr dūsikābhih, 488, 528, 543 hriyai salpakah (salyakah), 867 hladike hladikavatı (hladuke hladu"), 622 hvayāmi šakram puruhūtam indram, 849